UNIT-IN-PLACE COSTS

INSTRUCTIONS for Converting Square Foot Costs into Whole Dollar Costs for an Entire Residence.

Step A: Select the proper class for the residence.

Step B: Select and list Unit-in-Place components for all construction areas of the residence. Tip: Work through the Unit-In-Place section page by page, first selecting a component, then marking down the corresponding class cost. For an example of how this step is done, see the following pages. If you are not sure of the exact specifications of the residence, refer to the Specification pages located in front of the Square Foot cost tables.

Step C: Convert Unit-in-Place costs into whole dollar costs. Pay special attention to the unit of measure when converting costs. For additional conversion help, see below or refer to the example on the following pages.

Step D: Total all whole dollar costs.

Step E: Divide the result of Step D by the ground area of your residence in square feet.

CONVERSION INSTRUCTIONS

In order to convert the various Unit-in-Place costs into whole dollar costs, use the following formulas:

UNIT-IN-PLACE SECTION	BASE UNIT OF MEASURE	CONVERSION FORMULA
Exterior wall	Sq. Ft. of Wall Area	Unit-in-Place Cost x Sq. Ft. of Wall Area = Whole Dollar Cost
Windows	Sq. Ft. of Window Area	Unit-in-Place Cost x Sq. Ft. of Window Area = Whole Dollar Cost
Roof	Sq. Ft. of Ground Area	Unit-in-Place Cost x Sq. Ft. of Ground Area = Whole Dollar Cost
Interior partitions and finish	Sq. Ft. of Partition Area	Unit-in-Place Cost x Sq. Ft. of Partition Area = Whole Dollar Cost
Floor finish	Sq. Ft. of Floor Area	Unit-in-Place Cost x Sq. Ft. of Floor Area = Whole Dollar Cost
Ceiling	Sq. Ft. of Ceiling Area	Unit-in-Place Cost x Sq. Ft. of Ceiling Area = Whole Dollar Cost
Excavation	Sq. Ft. of Ground Area	Unit-in-Place Cost x Sq. Ft. of Ground Area = Whole Dollar Cost
Basement walls, foundations and footings	Sq. Ft. of Wall Area	Unit-in-Place Cost x Sq. Ft. of Wall Area = Whole Dollar Cost
Basement floor	Sq. Ft. of Floor Area	Unit-in-Place Cost x Sq. Ft. of Floor Area = Whole Dollar Cost
Floor construction	Sq. Ft. of Floor Area	Unit-in-Place Cost x Sq. Ft. of Floor Area = Whole Dollar Cost
Heat and air conditioning	Sq. Ft. of Living Area	Unit-in-Place Cost x Sq. Ft. of Living Area = Whole Dollar Cost
Electric lighting system	Sq. Ft. of Living Area	Unit-in-Place Cost x Sq. Ft. of Living Area = Whole Dollar Cost

As a final note, when determining costs for exterior walls and interior partitions, originally assume no window or door openings to arrive at a total area for each unit. For example, an interior partition (wall) 8 feet high and 10 linear feet long with a door opening would be measured as 80 square feet of interior partition.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE EXAMPLE

CONVERTING UNIT-IN-PLACE COSTS INTO SQUARE FOOT COSTS FOR AN ENTIRE RESIDENCE.

Instructions for Steps (A) through (E) are located on the previous page.

Assume we have chosen a Class C, one-story residence with the following measurements:

STEP A

Dimensions: 40' X 25'
Square Feet of Ground: 1000
Square Feet of Living Area: 1000
Square Feet of Window: 125
Square Feet of Basement Wall: 1040
Square Feet of Exterior Wall: 1040
Square Feet of Partition: 896
Square Feet of Basement Floor: 1000
Linear Feet of Footing: 130
Interior Doors: 20
Linear Feet of Interior Trim: 164
Linear Feet of Closet Shelving: 24

STEP B Exterior Walls	**STEP C** Unit-in-Place Cost	Unit	Whole Dollar Cost	Subtotals
Wood frame with:				
Face brick veneer	$18.40	x 1040 s.f. wall =	$19,136.00	
Building paper	.38	x 1040 s.f. wall =	395.20	
1/2" insulation board	1.96	x 1040 s.f. wall =	2,038.40	
2" x 6" studs, 16" o.c.	3.82	x 1040 s.f. wall =	3,972.80	
6" batt insulation	1.49	x 1040 s.f. wall =	1,549.60	
1/2" drywall	2.32	x 1040 s.f. wall =	2,412.80	
Interior surface: painted, two coats	1.06	x 1040 s.f. wall =	1,102.40	
Two exterior doors (wood raised panel)	760.00	x 2 (cost each) =	1,520.00	
Aluminum storm and screen door	430.00	x 1 (cost each) =	430.00	$32,557.20
Wood double hung windows	28.35	x 125 s.f. wind. =	$3,543.75	
Aluminum storms and screens	11.98	x 125 s.f. wind. =	1,497.50	$5,041.25
Roof				
4/12 pitch				
235# asphalt shingles	2.69	x 1000 s.f. ground =	$2,690.00	
Felt	.39	x 1000 s.f. ground =	390.00	
1/2" plywood	2.11	x 1000 s.f. ground =	2,110.00	
2" x 6" rafters, 16" o.c.	3.27	x 1000 s.f. ground =	3,270.00	
1' overhang and soffit	2.00	x 1000 s.f. ground =	2,000.00	
Gutters and downspouts	1.28	x 1000 s.f. ground =	1,280.00	$11,740.00
Interior Partitions and Finish				
8' walls				
1/2" drywall, two sides	4.65	x 896 s.f. partition =	$4,166.40	
Painted, two coats, two sides	2.12	x 896 s.f. partition =	1,899.52	
2" x 4" studs, 16" o.c.	2.67	x 896 s.f. partition =	2,392.32	
Softwood trim	3.29	x 164 l.f. trim =	539.56	
Flush hollow core doors	450.00	x 20 (cost each) =	9,000.00	
Closet shelving	4.07	x 24 l.f. shelving =	97.68	$18,095.48
Floor Finish				
65% carpet with pad	5.03	x 1000 s.f. floor x 65% =	$3,269.50	
35% vinyl inlay	5.85	x 1000 s.f. floor x 35% =	2,047.50	
35% 5/8" underlayment	2.55	x 1000 s.f. floor x 35% =	892.50	$6,209.50

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STEP B		STEP C	Unit-in-Place Cost	Unit	Whole Dollar Cost	Subtotals
	Ceiling					
	1/2” drywall		3.20	x 1000 s.f. ceiling =	$3,200.00	
	Painted, two coats		1.89	x 1000 s.f. ceiling =	1,890.00	
	12” insulation		2.83	x 1000 s.f. ceiling =	2,830.00	
	2” x 8” Joists, 16” o.c.		2.98	x 1000 s.f. ceiling =	2,980.00	$10,900.00
	Excavation					
	8’ Basement		2.27	x 1000 s.f. ground =	$2,270.00	$2,270.00
	Basement Walls					
	8” concrete block		13.09	x 1040 s.f. wall =	$13,631.60.00	
	8” x 24” footings		26.52	x 130 l.f. footing =	3,447.60	
	Drain tile, two sides		18.93	x 130 l.f. footing =	2,460.90	
	Perimeter Insulation		2.17	x 1040 s.f. wall =	2,256.80	
	Waterproofing		1.78	x 1040 s.f. wall =	1,851.20	$23,648.10
	Basement Floor					
	4” gravel base		.96	x 1000 s.f. floor =	$960.00	
	4” concrete floor		5.08	x 1000 s.f. floor =	5,080.00	
	Vapor barrier		.35	x 1000 s.f. floor =	350.00	$6,390.00
	Floor Construction					
	Felt underlay		.62	x 1000 s.f. floor =	$620.00	
	3/4” plywood		2.60	x 1000 s.f. floor =	2,600.00	
	2” x 10” joists, 16” o.c.		3.78	x 1000 s.f. floor =	3,780.00	
	Bridging		.44	x 1000 s.f. floor =	440.00	
	8” steel I-beam		1.06	x 1000 s.f. floor =	1,060.00	
	3” diameter steel posts		.41	x 1000 s.f. floor =	410.00	$8,910.00
	Heating and Cooling					
	Gas-fired forced-air, with return ducts		5.78	x 1000 s.f. living =	$5,780.00	
	Block chimney, 16” x 22’ Ht.		243.60	x 22 Ht. of chimney =	5,359.20	$11,139.20
	Electric					
	200-ampere, 110/220-volt, Romex		9.91	x 1000 s.f. living =	$9,910.00	
	Unfinished Area, Non metallic		2.87	x 1000 s.f. unfin. area =	2,870.00	$12,780.00
	Plumbing					
	White fixtures:					
	One sink, countertop		906.00	x 1 (cost each) =	$906.00	
	One toilet		1,454.00	x 1 (cost each) =	1,454.00	
	One bathtub with shower		2,030.00	x 1 (cost each) =	2,030.00	
	Ceramic tile, tub alcove		800.00	x 1 (cost each) =	800.00	
	One two-compartment kitchen sink		1,385.00	x 1 (cost each) =	1,385.00	
	One two-compartment laundry tub		1,045.00	x 1 (cost each) =	1,045.00	
	One 40-gallon gas water heater		1,355.00	x 1 (cost each) =	1,355.00	$8,975.00
	Built-In Units					
	Wood veneer kitchen cabinets					
	16’ base with laminated plastic top		263.00	x 16 l.f. cabinet =	$4,208.00	
	10’ wall mounted, 30” high		178.00	x 10 l.f. cabinet =	1,780.00	
	6’ wall mounted, 18” high		151.00	x 6 l.f. cabinet =	906.00	
	Vanity cabinet		566.00	x 1 (cost each) =	566.00	
	Open-riser basement stairs		1,175.00	x 1 (cost each) =	1,175.00	$8,635.00
				Summary	STEP D	$167,290.73

STEP E		
	Total Whole Dollar Cost of Unit-in-Place Components:	$167,290.73
	Square Feet of Ground Area:	1,000
	Whole Dollar Cost/Square Feet of Ground Area:	$167.29

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
EXTERIOR WALLS						
Costs/Sq. Ft. of Wall Area						
MASONRY WALLS						
Block, concrete, 6”	10.86	11.35	11.89	13.13	13.98	15.09
8”	11.91	12.40	12.93	14.24	15.09	16.21
10”	13.46	14.12	14.83	16.59	17.72	19.18
12”	14.87	15.69	16.59	18.77	20.17	21.95
Block, reinforced, 6”	11.76	12.46	13.24	15.12	16.32	17.85
8”	12.71	13.57	14.52	16.82	18.29	20.15
10”	14.54	15.57	16.71	19.48	21.24	23.47
12”	16.23	17.42	18.73	21.94	23.98	26.55
Brick, common, 8”	27.39	29.22	31.24	36.16	39.28	43.25
12”	36.18	38.52	41.09	47.35	51.33	56.39
Brick, 6”, SCR modular	19.04	20.20	21.47	24.55	26.51	29.02
8”	21.61	22.85	24.20	27.50	29.61	32.30
Concrete, reinforced, 5” – 6”	20.15	22.02	24.10	29.25	32.54	36.68
8”	22.66	24.60	26.76	32.06	35.44	39.69
12”	26.63	28.84	31.30	37.32	41.15	45.99
Additives for block and concrete walls						
Synth. plaster on rigid insul. (EIFS)	8.94	9.86	10.88	13.44	15.08	17.15
Stay-in-place forming	0.72	0.94	1.22	2.09	2.76	3.69
SIDINGS						
Aluminum	3.31	3.87	4.53	6.30	7.50	9.06
Asphalt	2.34	2.53	2.75	3.27	3.61	4.03
Cement fiber, embossed	5.48	5.81	6.17	7.06	7.62	8.34
Siding or shingles, horizontal	3.79	4.05	4.34	5.04	5.48	6.04
Vinyl	4.75	5.05	5.37	6.16	6.66	7.29
Synth. plaster on rigid insul. (EIFS)	8.94	9.86	10.88	13.44	15.08	17.15
Wood						
Board and batten	3.56	4.17	4.90	6.86	8.19	9.91
Clapboard	4.84	5.40	6.02	7.60	8.62	9.91
Hardboard sheet, embossed	2.97	3.22	3.49	4.15	4.57	5.10
Siding or shingles, horizontal	3.31	3.57	3.87	4.59	5.05	5.63
Masonite, 1/8” tempered	2.78	2.97	3.19	3.69	4.02	4.44
Masonite, 1/4” tempered	3.00	3.22	3.47	4.05	4.44	4.92
Plywood, 3/8” textured	3.56	3.74	3.93	4.41	4.71	5.10
1/2” plain	2.82	2.97	3.14	3.54	3.80	4.13
5/8” textured	3.56	3.74	3.93	4.41	4.71	5.10
5/8” plain	2.82	2.97	3.14	3.54	3.80	4.13
Rustic or log siding, veneer	7.01	8.39	10.05	14.61	17.79	21.95
Half rounds with full corners	19.04	20.10	21.26	24.09	25.89	28.20
Full logs, 6” – 7” in diameter	17.94	19.34	20.88	24.67	27.07	30.11
8”	21.16	22.81	24.65	29.13	31.98	35.59
10”	25.38	27.36	29.57	34.95	38.38	42.71
Hand hewn or oversized logs	31.16	34.28	37.78	46.50	52.08	59.13
Shingle, cedar	4.12	4.43	4.78	5.63	6.16	6.84
Shake	4.68	4.99	5.32	6.13	6.64	7.29
VENEERS						
Face brick veneer	15.33	16.77	18.40	22.40	24.97	28.20
Select common brick veneer	13.42	14.72	16.18	19.79	22.10	25.02
Select reused brick veneer	14.67	16.05	17.59	21.39	23.82	26.88
Stone veneers						
Ashlar, granite	44.22	47.98	52.16	62.42	68.95	77.20
Split	38.44	41.27	44.39	52.00	56.84	62.96
Native stone	25.63	28.04	30.75	37.43	41.70	47.09
Permastone	12.75	13.98	15.37	18.80	21.00	23.77
Split rock	13.79	15.10	16.56	20.16	22.47	25.38

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
Costs/Sq. Ft. of Wall Area						
MISCELLANEOUS						
Glass panel	26.00	29.58	33.71	44.04	51.00	59.88
Local stone, rough cut, solid, 12”	62.03	68.16	75.07	91.53	102.41	116.14
Granite	64.67	73.01	82.56	106.21	122.08	142.20
Limestone	70.62	77.33	84.87	102.77	114.61	129.53
Add for each 6” variation in thickness	7.92	8.48	9.09	10.51	11.46	12.66
Rammed earth, soil cement, 24”	26.40	28.01	29.77	33.84	36.55	40.02
Add for each 6” variation in thickness	1.58	1.73	1.87	2.22	2.45	2.75
Sand. panels, cement fiber or Shotcrete	16.40	18.05	19.89	24.32	27.24	30.93
Stucco on baled straw	18.88	20.68	22.69	27.50	30.69	34.69
FRAMING (Frame including sills, plates and wood) studs						
2” x 4”, 12” o.c.	3.56	3.63	3.72	3.95	4.10	4.33
16” o.c.	2.50	2.64	2.79	3.16	3.39	3.69
24” o.c.	1.85	1.93	2.02	2.23	2.37	2.55
2” x 6”, 16” o.c.	3.63	3.72	3.82	4.07	4.25	4.49
24” o.c.	2.50	2.64	2.79	3.16	3.39	3.69
2” x 8”, 12” o.c.	6.37	6.59	6.83	7.42	7.82	8.34
16” o.c.	4.84	5.01	5.19	5.64	5.94	6.34
24” o.c.	3.05	3.15	3.27	3.57	3.77	4.03
Steel studs						
Light (to 25 gauge)						
4” – 16” o.c.	2.75	2.85	2.95	3.21	3.38	3.60
4” – 24” o.c.	2.25	2.34	2.43	2.65	2.80	3.00
6” – 16” o.c.	3.05	3.17	3.30	3.63	3.85	4.13
6” – 24” o.c.	2.75	2.81	2.87	3.04	3.15	3.32
Medium (to 20 gauge)						
4” – 16” o.c.	3.56	3.66	3.77	4.04	4.23	4.49
4” – 24” o.c.	2.82	2.94	3.07	3.40	3.60	3.88
6” – 16” o.c.	4.12	4.23	4.36	4.67	4.89	5.18
6” – 24” o.c.	3.56	3.64	3.74	3.99	4.16	4.40
Wood pole framing	1.06	1.26	----	----	----	----
INSULATION						
Insulation, 2-1/2”	0.81	0.87	0.93	1.08	1.18	1.30
3-1/2”	0.94	1.00	1.05	1.19	1.28	1.39
6”	1.34	1.41	1.49	1.69	1.81	1.97
FINISHES						
Paint on exterior, two coats	1.17	1.23	1.30	1.46	1.57	1.71
Three coats	1.61	1.69	1.78	2.01	2.15	2.33
On masonry, two coats	0.90	0.99	1.08	1.31	1.46	1.64
Three coats	1.26	1.37	1.50	1.81	2.01	2.27
Stain on exterior, two coats	1.09	1.16	1.25	1.47	1.60	1.77
Stucco, two coats on masonry	4.12	4.46	4.85	5.78	6.38	7.13
Three coats on metal lath	6.13	6.43	6.76	7.55	8.06	8.73
Sheathing						
Building paper	0.32	0.35	0.38	0.45	0.49	0.55
Insulation board, 1/2”	1.84	1.89	1.96	2.11	2.21	2.35
25/32”	2.15	2.22	2.29	2.47	2.59	2.75
Plywood, 3/8”	2.25	2.30	2.35	2.48	2.58	2.72
1/2”	2.33	2.38	2.43	2.57	2.66	2.80
5/8”	2.66	2.71	2.77	2.93	3.04	3.20

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
Costs/Sq. Ft. of Wall Area						
OSB (oriented strand board), 3/8”	2.09	2.15	2.21	2.37	2.48	2.63
1/2”	2.17	2.23	2.29	2.46	2.57	2.73
5/8”	2.47	2.54	2.62	2.80	2.93	3.11
Wood board, 1” x 6”	2.75	2.90	3.06	3.46	3.71	4.03
Interior finish of exterior walls						
Ceramic tile	12.31	14.67	17.52	25.31	30.72	37.78
Drywall, one side 3/8”	1.86	1.93	2.00	2.16	2.28	2.43
1/2”	2.18	2.25	2.32	2.51	2.63	2.80
5/8”	2.25	2.34	2.45	2.70	2.86	3.08
Furring, wood strips on masonry	1.44	1.58	1.74	2.14	2.40	2.73
Painting						
One coat	0.50	0.56	0.62	0.78	0.89	1.02
Two coats	0.85	0.95	1.06	1.34	1.52	1.74
Three coats	1.21	1.34	1.50	1.89	2.14	2.46
Plaster, two coats on gypsum	4.75	4.95	5.17	5.70	6.05	6.50
Three coats on gypsum	5.79	5.92	6.07	6.47	6.74	7.12
Two coats on masonry	4.12	4.29	4.48	4.94	5.24	5.63
Wall paper	1.84	2.09	2.38	3.11	3.60	4.22
Custom	4.26	4.87	5.58	7.42	8.63	10.18

EXTERIOR DOORS

Costs Each						
Entrance doors, cost each						
Aluminum storm and screen	315	370	430	590	700	840
Metal, hollow core	445	505	575	750	870	1,020
Insulated	545	615	700	910	1,050	1,225
Deluxe	520	590	675	890	1,035	1,215
Wood						
Flat panel	525	600	690	920	1,075	1,275
Raised panel	550	645	760	1,070	1,280	1,555
Dutch	690	790	900	1,195	1,390	1,635
French	720	830	960	1,295	1,520	1,810
Carved, stock	935	1,050	1,175	1,500	1,705	1,970
Custom, carved	6,660	7,770	9,085	12,570	14,930	17,975
Hardwood, solid core, flat panel	1,975	2,205	2,470	3,130	3,560	4,105
Raised panel	2,410	3,280	4,470	8,415	11,655	16,365
Sliding glass door, 6’ opening	970	1,060	1,155	1,395	1,545	1,735
Sliding insul. glass door, 6’ opening	1,425	1,575	1,745	2,170	2,440	2,780
Wood storm and screen	405	450	505	635	720	830
Garage Doors, cost/sq. ft. of garage door area						
Single						
Overhead						
Metal	14.67	16.15	17.81	21.94	24.58	27.92
Plastic	16.38	17.36	18.44	21.06	22.73	24.86
Wood	13.12	14.11	15.22	17.91	19.62	21.79
Redwood or select cedar	20.45	22.21	24.16	28.95	32.01	35.86
Sectional						
Metal	16.38	18.14	20.12	25.08	28.27	32.30
Plastic	18.04	19.31	20.70	24.11	26.27	29.02
Wood	14.67	15.91	17.28	20.66	22.80	25.51
Redwood or select cedar	23.92	26.53	29.48	36.86	41.62	47.63
Add for insulation	2.35	2.61	2.89	3.59	4.05	4.62

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
Garage doors, cost/sq. ft. of a garage door area						
Double						
Overhead						
Metal	10.04	11.49	13.18	17.55	20.44	24.14
Plastic	10.90	12.15	13.55	17.10	19.39	22.28
Wood	8.56	9.86	11.37	15.33	17.97	21.35
Redwood or select cedar	16.38	18.09	20.01	24.79	27.87	31.76
Sectional						
Metal	11.76	13.37	15.22	20.00	23.15	27.16
Plastic	12.61	13.96	15.49	19.30	21.76	24.86
Wood	10.04	11.49	13.18	17.55	20.44	24.14
Redwood or select cedar	21.00	23.22	25.73	31.97	35.99	41.06
Add for insulation	2.03	2.25	2.49	3.10	3.50	4.00
WINDOWS						
Costs/Sq. Ft. of Window Area						
Metal windows						
Double-hung	21.00	22.59	24.34	28.61	31.33	34.77
Casement	22.01	24.20	26.66	32.76	36.68	41.61
Slide-by	14.57	16.21	18.07	22.74	25.75	29.57
Picture, fixed	18.34	19.93	21.70	26.04	28.81	32.30
For double glazed, add 50%						
Vinyl-sash, windows						
Double-hung	25.21	27.11	29.21	34.34	37.60	41.72
Casement	26.41	29.04	31.99	39.31	44.01	49.93
Slide-by	17.49	19.45	21.68	27.28	30.91	35.48
Picture, fixed	22.01	23.91	26.04	31.25	34.57	38.76
For double glazed, add 50%						
Wood windows						
Double-hung, barn sash type	13.05	14.47	16.08	20.11	22.70	25.98
Double-hung	24.62	26.39	28.35	33.11	36.13	39.97
Casement	29.65	32.19	35.03	41.99	46.42	52.01
Slide-by	20.15	21.70	23.42	27.62	30.30	33.67
Picture, fixed	18.34	19.93	21.70	26.04	28.81	32.30
For double glazed, add 50%						
Aluminum storms and screens						
Double-hung or slide-by	10.41	11.15	11.98	13.90	15.16	16.78
Casement	11.11	11.88	12.72	14.67	15.98	17.64
Wood storms and screens						
Double-hung or slide-by	11.72	12.43	13.22	15.05	16.27	17.83
Casement	12.24	13.01	13.86	15.83	17.14	18.81
Bay Windows (cost/sq. ft. of wall area displaced)						
Wood, single-pane, awning	55.48	58.49	61.80	69.84	74.98	81.58
Casement	52.70	55.57	58.71	66.35	71.23	77.50
Double-hung	50.07	52.79	55.77	63.03	67.67	73.62
Insulated glass, wood, awning	83.21	90.02	97.58	116.10	127.88	142.76
Casement	79.05	85.52	92.70	110.30	121.49	135.62
Double-hung	75.10	81.25	88.07	104.78	115.42	128.84
Metal, awning	80.44	87.09	94.48	112.60	124.13	138.68
Casement	76.42	82.74	89.76	106.97	117.92	131.75
Double-hung	72.60	78.60	85.27	101.62	112.03	125.16
Vinyl, awning	91.54	98.37	105.93	124.37	136.09	150.92
Casement	81.69	88.30	95.64	113.62	125.06	139.50
Double-hung	77.60	83.89	90.86	107.94	118.81	132.52

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
ROOF (4” rise in 12” run)						
Costs/Sq. Ft. of Ground Area						
Roofing						
Asphalt singles, 210#	4.51	5.15	5.89	7.79	9.06	10.67
235#	1.97	2.13	2.30	2.73	3.00	3.34
290#	2.36	2.52	2.69	3.11	3.37	3.71
Built-up 2-ply and gravel	2.51	2.91	3.38	4.60	5.43	6.48
Built-up 3-ply and gravel	2.16	2.34	2.54	3.04	3.36	3.76
Cement fiber (Asbestos) shingles	2.47	2.70	2.95	3.57	3.97	4.47
Cement tile	6.04	6.71	7.47	9.37	10.60	12.15
Clay Spanish tile	7.16	8.60	10.35	15.19	18.59	23.05
Copper, flat or standing seam	14.12	15.69	17.47	21.94	24.83	28.47
Batten seam	15.38	17.08	19.01	23.86	26.98	30.93
Roll asphalt roofing	1.11	1.27	1.46	1.95	2.28	2.69
Slate 3/16” and 1/4”	8.81	9.85	11.04	14.03	15.97	18.43
Slate 3/8”	10.58	11.67	12.91	15.99	17.98	20.48
Terne, flat or standing seam	13.17	14.62	16.26	20.38	23.03	26.39
Batten seam	14.22	15.79	17.56	21.99	24.86	28.47
Wood shingle	4.03	4.47	4.98	6.23	7.05	8.07
Shake	4.37	4.86	5.41	6.80	7.70	8.84
Add for fire-resistant finish	0.66	0.75	0.85	1.10	1.26	1.47
Felt, 15#	0.33	0.36	0.39	0.46	0.50	0.55
Sheathing						
Plywood, 5/16”	1.57	1.63	1.70	1.86	1.97	2.11
3/8”	1.72	1.79	1.88	2.08	2.21	2.39
1/2”	1.91	2.00	2.11	2.36	2.52	2.73
5/8”	2.25	2.38	2.52	2.85	3.07	3.34
OSB (oriented strand board), 3/8”	1.64	1.70	1.77	1.94	2.05	2.19
1/2”	1.83	1.91	2.00	2.21	2.35	2.53
5/8”	2.17	2.28	2.41	2.70	2.90	3.14
Boards, 1” x 6” solid	2.79	3.01	3.25	3.83	4.20	4.66
Boards, 1” x 6” spaced	1.79	1.97	2.18	2.70	3.03	3.45
Rafters						
2” x 4”, trussed frame	3.39	3.58	3.77	4.23	4.54	4.94
2” x 4”, 12” o.c.	3.12	3.26	3.41	3.79	4.03	4.34
16” o.c.	2.51	2.63	2.75	3.05	3.25	3.50
24” o.c.	1.86	1.95	2.04	2.26	2.41	2.59
2” x 6”, 12” o.c.	3.71	3.87	4.06	4.50	4.79	5.16
16” o.c.	2.99	3.13	3.27	3.63	3.87	4.17
24” o.c.	2.26	2.36	2.47	2.74	2.92	3.15
2” x 8”, 12” o.c.	4.31	4.50	4.71	5.23	5.56	5.99
16” o.c.	3.50	3.66	3.83	4.25	4.52	4.87
24” o.c.	2.60	2.71	2.84	3.15	3.35	3.61
2” x 10”, 12” o.c.	5.44	5.68	5.95	6.60	7.02	7.57
16” o.c.	4.42	4.62	4.84	5.37	5.71	6.16
24” o.c.	3.32	3.47	3.63	4.03	4.29	4.62
DORMERS (Per linear foot, measured across face of dormer)						
Unfinished area dormer are for attics areas, finished areas are for finished upper floors.						
Unfinished areas, gable roof	115.00	129.75	146.50	186.50	210.50	237.50
Hip roof	120.75	136.25	154.00	196.25	221.50	250.00
Shed roof	100.00	113.00	127.75	163.50	184.75	209.00
Finished areas, gable roof	215.00	245.00	279.50	363.25	414.25	472.25
Hip roof	225.75	257.50	293.75	382.00	435.75	497.00
Shed roof	181.00	208.25	239.50	316.75	364.25	419.00

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
Costs/Sq. Ft. of Wall Area						
Skylights (per square foot of framed area)						
Flat, plain glass or plastic	54.25	57.25	60.50	68.40	73.45	79.95
Wire glass	59.30	62.70	66.45	75.50	81.30	88.70
Pitched, without vent, plain glass or plastic	59.80	63.60	67.75	77.90	84.30	92.55
Wire glass	63.80	69.25	75.35	90.25	99.70	111.70
Pitched, with vent, plain glass or plastic	61.30	67.30	74.05	90.75	101.50	115.00
Wire glass	66.85	73.85	81.80	101.55	114.25	130.30
Plastic domes, fixed, small (under 3 sq. ft.)	75.40	82.85	91.25	112.10	125.50	142.35
Large (over 3 sq. ft.)	56.30	61.65	67.65	82.50	92.05	104.05
Roof windows or vented domes,						
Small (under 3 sq. ft.)	136.70	148.30	161.25	193.00	213.20	238.70
Large (over 3 sq. ft.)	95.50	104.25	114.00	138.15	153.55	173.00
Add for blinds, small (under 3 sq. ft.)	11.30	12.15	13.10	15.40	16.85	18.70
Large (over 3 sq. ft.)	6.45	7.10	7.85	9.70	10.85	12.30
Add for screens, small (under 3 sq. ft.)	18.95	19.70	20.55	22.60	23.95	25.75
Large (over 3 sq. ft.)	15.20	15.80	16.45	18.15	19.20	20.65
Electric controls, each	658.30	681.90	707.75	772.10	814.40	870.55
Each 1’-0” overhang and soffit	1.73	1.86	2.00	2.33	2.55	2.82
Gutters and downspouts	1.07	1.17	1.28	1.53	1.70	1.90

Roof Pitch Adjustment

All roof costs above include an adjustment for a 4” rise in a 12” run. Use these multipliers to adjust for deviations.

Rise in Run	Multiplier
4” in 12”	1.00
5” in 12”	1.03
6” in 12”	1.07
8” in 12”	1.14
10” in 12”	1.24
12” in 12”	1.35
14” in 12”	1.47
16” in 12”	1.56

INTERIOR PARTITIONS AND FINISH						
Costs/Sq. Ft. of Partition Area						
Ceramic tile	12.31	14.67	17.52	25.31	30.72	37.78
Drywall, 5/8”, one side	2.25	2.34	2.45	2.70	2.86	3.08
Two sides	4.50	4.69	4.89	5.40	5.73	6.15
1/2”, one side	2.18	2.25	2.32	2.51	2.63	2.80
Two sides	4.36	4.50	4.65	5.02	5.27	5.61
3/8”, one side	1.86	1.93	2.00	2.16	2.28	2.43
Two sides	3.71	3.84	3.99	4.32	4.55	4.87
Paint, one coat, one side	0.50	0.56	0.62	0.78	0.89	1.02
One coat, two sides	1.01	1.12	1.25	1.57	1.77	2.04
Two coats, one side	0.85	0.95	1.06	1.34	1.52	1.74
Two coats, two sides	1.71	1.90	2.12	2.67	3.03	3.48
Three coats, one side	1.21	1.34	1.50	1.89	2.14	2.46
Three coats, two sides	2.41	2.69	3.00	3.78	4.29	4.93
Plaster, two coats, one side	4.07	4.42	4.81	5.73	6.34	7.08
Two sides	8.15	8.85	9.63	11.45	12.66	14.18

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
Costs/Sq. Ft. of Wall Area						
Plaster, three coats, one side	5.92	6.10	6.31	6.80	7.14	7.60
Two sides	11.83	12.21	12.63	13.58	14.27	15.21
Stained wood finish, two coats, one side	1.35	1.45	1.55	1.79	1.96	2.16
Three coats, one side	1.70	1.84	1.99	2.33	2.56	2.87
Stud framing						
2” x 4” wood, 16” o.c.	2.41	2.52	2.67	2.97	3.18	3.46
24” o.c.	1.75	1.83	1.90	2.09	2.20	2.38
4” steel, 16” o.c.	2.70	2.78	2.89	3.12	3.28	3.50
24” o.c.	2.22	2.29	2.38	2.59	2.74	2.92
Wall paper	1.83	2.07	2.35	3.07	3.54	4.15
Interior doors, cost each						
Flush doors	395	420	450	520	565	620
Panel doors	525	565	605	715	780	865
Closet shelving, cost per linear foot	3.32	3.67	4.07	5.03	5.67	6.48
Paneling, lauan	3.52	3.84	4.18	4.92	5.36	5.83
Birch	4.81	5.05	5.29	5.79	6.08	6.36
Oak	4.77	5.21	5.66	6.67	7.26	7.91
Walnut	5.89	6.41	6.97	8.21	8.94	9.73
Trim, hardwood, cost per linear foot	3.51	4.39	5.51	8.71	11.12	14.36
Softwood	2.58	2.91	3.29	4.22	4.84	5.63

FLOOR FINISH

Costs/Sq. Ft. of Floor Area						
Asphalt tile	2.90	3.23	3.60	4.53	5.13	5.89
Carpet	2.74	3.71	5.03	9.35	12.88	17.98
Custom	12.51	16.40	21.54	37.61	50.20	67.89
Ceramic tile	12.91	15.21	17.96	25.34	30.40	36.96
Custom	31.16	35.58	40.70	53.95	62.73	73.91
Felt underlay	0.41	0.46	0.51	0.65	0.74	0.85
Hardwood, 1/2”	11.61	13.19	15.01	19.70	22.79	26.72
25/32”	11.56	13.32	15.39	20.79	24.40	29.02
Linoleum	4.68	5.32	6.05	7.92	9.16	10.73
Marble	32.41	39.45	48.11	72.46	89.80	112.79
Parquet block	15.63	18.27	21.40	29.74	35.40	42.71
Rubber tile	4.93	6.06	7.47	11.46	14.34	18.18
Standing and seal for wood floor	2.64	2.89	3.15	3.72	4.06	4.44
Slate	20.20	22.68	25.50	32.67	37.34	43.25
Softwood	9.11	10.16	11.35	14.36	16.31	18.78
Terrazzo	13.72	15.84	18.32	24.83	29.18	34.77
Underlayment, 1/2” plywood	1.94	2.03	2.12	2.32	2.46	2.65
5/8” plywood	2.33	2.44	2.55	2.81	2.98	3.21
Vinyl composition tile	2.50	2.85	3.24	4.26	4.94	5.79
Vinyl inlay	3.79	4.70	5.85	9.16	11.58	14.84
Vinyl tile	4.04	5.00	6.20	9.66	12.17	15.55

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
CEILING						
Costs/Sq. Ft. of Wall Area						
Joists, 2” x 6”, 12” o.c.	2.99	3.10	3.23	3.53	3.73	3.99
16” o.c.	2.33	2.42	2.51	2.75	2.90	3.11
24” o.c.	1.61	1.67	1.74	1.90	2.00	2.14
2” x 8”, 12” o.c.	3.50	3.63	3.77	4.12	4.36	4.66
16” o.c.	2.77	2.87	2.98	3.26	3.44	3.69
24” o.c.	2.11	2.19	2.27	2.48	2.62	2.81
2” x 10”, 12” o.c.	4.42	4.59	4.77	5.21	5.50	5.89
16” o.c.	3.48	3.61	3.75	4.10	4.33	4.64
24” o.c.	2.42	2.50	2.60	2.85	3.01	3.22
2” x 12”, 12” o.c.	5.20	5.39	5.60	6.13	6.47	6.93
16” o.c.	4.06	4.21	4.38	4.79	5.05	5.41
24” o.c.	2.85	2.95	3.07	3.36	3.55	3.79
Plaster, two coats	4.19	4.64	5.13	6.35	7.14	8.16
Three coats	5.60	6.15	6.76	8.24	9.22	10.45
Acoustic tile	2.82	3.30	3.86	5.35	6.36	7.67
Drywall, 3/8”	2.57	2.79	3.04	3.65	4.04	4.53
1/2”	2.70	2.94	3.20	3.84	4.25	4.76
Furring						
Metal	1.94	2.24	2.59	3.51	4.13	4.92
Wood	1.16	1.34	1.56	2.13	2.51	3.00
Hardwood	6.47	7.41	8.49	11.30	13.17	15.55
Coffered/vaulted panel with molding	11.36	14.43	18.38	30.17	39.04	51.19
Paint, one coat flat	0.81	0.98	1.18	1.74	2.13	2.65
Two coats flat	1.39	1.62	1.89	2.56	3.04	3.63
Wood, boards or T&G, softwood	3.79	4.36	5.02	6.75	7.91	9.38
Insulation, 4”	1.03	1.08	1.13	1.27	1.35	1.47
6”	1.42	1.49	1.58	1.78	1.91	2.08
8”	1.81	1.91	2.02	2.28	2.45	2.66
10”	2.19	2.31	2.44	2.76	2.96	3.22
12”	2.54	2.68	2.83	3.19	3.42	3.72

EXCAVATION						
Costs/Sq. Ft. of Ground Area						
Basement, excavation, 10’-0” deep	2.39	2.60	2.84	3.43	3.80	4.28
9’-0”	2.15	2.34	2.56	3.09	3.42	3.85
8’-0”	1.91	2.08	2.27	2.74	3.04	3.42
7’-4”	1.74	1.90	2.07	2.50	2.78	3.12
7’-0”	1.67	1.82	1.99	2.40	2.66	3.00
Crawl space excavation, 4’-0” deep	0.95	1.04	1.14	1.37	1.52	1.71
2’-0”	0.48	0.52	0.57	0.69	0.76	0.86
Pier pits	0.60	0.65	0.71	0.86	0.95	1.07
Trench excavation, 4’ -0” deep	2.37	2.47	2.58	2.84	3.01	3.23
2’-0”	1.41	1.47	1.54	1.71	1.82	1.96

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
BASEMENT WALLS/FOUNDATIONS AND FOOTINGS						
Costs/Sq. Ft. of Wall Area						
Basement walls						
Block, concrete, 8" thick.	12.56	12.81	13.09	13.83	14.36	15.11
10".	13.96	14.37	14.82	15.95	16.71	17.75
12".	15.23	15.78	16.39	17.90	18.89	20.20
Poured concrete, 6" thick.	0.74	0.92	1.15	1.81	2.29	2.93
8".	18.44	18.81	19.22	20.33	21.12	22.23
10".	20.05	20.50	21.00	22.33	23.25	24.53
12".	20.85	21.48	22.17	23.92	25.08	26.66
Add for stay-in-place forming.	22.51	23.11	23.77	25.47	26.62	28.20
Treated wood, 2" x 4" studs.	8.04	8.32	8.62	9.38	9.88	10.54
2" x 6".	9.41	9.66	9.93	10.64	11.12	11.78
Footings, cost per linear foot						
8" x 16".	21.24	22.14	23.12	25.52	27.09	29.13
8" x 18".	22.36	23.30	24.33	26.87	28.51	30.66
8" x 20".	23.10	24.04	25.06	27.59	29.23	31.39
8" x 24".	24.57	25.50	26.52	29.03	30.68	32.85
10" x 20".	25.68	26.65	27.71	30.34	32.06	34.33
10" x 24".	28.26	29.26	30.36	33.09	34.89	37.28
12" x 24".	31.66	32.72	33.89	36.82	38.75	41.34
Drain tile, cost per linear foot, one side.	9.62	9.98	10.38	11.37	12.01	12.87
two sides.	16.83	17.83	18.93	21.60	23.30	25.48
Perimeter insulation, cost/sq. ft..	1.55	1.83	2.17	3.09	3.72	4.54
Piers, block, cost per linear foot.	19.82	20.86	21.99	24.75	26.51	28.77
Sill plate, cost per linear foot.	3.06	3.48	3.97	5.23	6.06	7.12
Waterproofing, cost per sq. ft. of wall.	0.98	1.32	1.78	3.28	4.49	6.23
BASEMENT FLOOR						
Costs/Sq. Ft. of Floor Area						
Concrete floor, 2" thick, raked finish.	3.32	3.39	3.47	3.66	3.80	4.00
3".	3.94	4.05	4.15	4.39	4.58	4.84
3" thick, trowel finish.	4.15	4.26	4.39	4.68	4.90	5.20
4".	4.86	4.96	5.08	5.34	5.56	5.85
5".	5.71	5.81	5.95	6.24	6.48	6.81
6".	6.51	6.63	6.76	7.07	7.33	7.70
Gravel base, 4".	0.90	0.93	0.96	1.02	1.08	1.15
6".	1.29	1.33	1.39	1.51	1.60	1.71
Terrazzo on 3" concrete.	17.99	19.88	22.00	27.10	30.48	34.75
Vapor barrier.	0.30	0.32	0.35	0.39	0.42	0.46
Wire mesh reinforcing.	0.58	0.65	0.74	0.94	1.08	1.24
FLOOR CONSTRUCTION						
Costs/Sq. Ft. of Floor Area						
Subfloor						
Common board, 1" x 6".	2.41	2.55	2.70	3.07	3.30	3.60
Plywood, 3/8".	1.63	1.70	1.78	1.98	2.10	2.27
1/2".	1.91	1.99	2.08	2.30	2.44	2.63
3/4".	2.37	2.48	2.60	2.88	3.07	3.31
Felt underlay.	0.53	0.57	0.62	0.73	0.80	0.89

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
Costs/Sq. Ft. of Wall Area						
Wood joists, 2” x 6”, 12” o.c.	2.66	2.78	2.91	3.23	3.44	3.71
16” o.c.	2.42	2.53	2.65	2.94	3.13	3.37
24” o.c.	1.61	1.69	1.76	1.96	2.08	2.25
2” x 8”, 12” o.c.	3.12	3.26	3.42	3.81	4.06	4.38
16” o.c.	2.83	2.97	3.11	3.46	3.69	3.99
24” o.c.	1.89	1.98	2.07	2.31	2.46	2.65
2” x 10”, 12” o.c.	3.66	3.90	4.16	4.79	5.20	5.71
16” o.c.	3.33	3.54	3.78	4.36	4.72	5.19
24” o.c.	2.22	2.36	2.52	2.90	3.15	3.46
2” x 12”, 12” o.c.	4.39	4.67	4.97	5.72	6.19	6.79
16” o.c.	3.99	4.24	4.52	5.20	5.63	6.18
24” o.c.	2.66	2.83	3.01	3.46	3.75	4.11
Bridging	0.41	0.42	0.44	0.48	0.50	0.55
Steel I-beam, 6”	0.91	0.94	0.97	1.04	1.08	1.14
8”	1.02	1.03	1.06	1.12	1.18	1.25
10”	1.25	1.28	1.31	1.40	1.45	1.54
Wood beams	0.62	0.62	0.64	0.66	0.69	0.72
Steel posts, 3” diameter	0.38	0.39	0.41	0.45	0.46	0.49
4” diameter	0.46	0.46	0.48	0.50	0.53	0.56
Wood posts	0.30	0.30	0.32	0.35	0.36	0.37
Slab on grade, concrete, 4” thick	5.06	5.23	5.42	5.85	6.15	6.57
5”	5.68	5.87	6.06	6.52	6.84	7.29
6”	6.32	6.51	6.71	7.19	7.53	8.01
Gravel base, 4”	0.90	0.93	0.96	1.02	1.08	1.15
6”	1.29	1.33	1.39	1.51	1.60	1.71
Sleepers, 1” x 2”	1.03	1.22	1.42	1.97	2.36	2.85
Insulation additive for crawl space	0.75	0.93	1.13	1.70	2.10	2.65
Vapor barrier, polyethylene	0.27	0.29	0.32	0.38	0.41	0.46

HEATING AND AIR CONDITIONING

Costs/Sq. Ft. of Living Area						
Heating systems						
Forced warm air, with return ducts	4.75	5.24	5.78	7.12	7.99	9.08
Without return ducts	3.77	4.23	4.77	6.11	6.98	8.11
Forced hot water/steam	8.22	9.02	9.92	12.15	13.58	15.38
Electric wall heaters, baseboard type	4.25	4.65	5.11	6.22	6.94	7.84
Electric ceiling, radiant	3.87	4.18	4.52	5.36	5.90	6.57
Electric wall heaters	2.06	2.21	2.38	2.79	3.04	3.37
Radiant (in-floor) heating	8.28	9.20	10.25	12.87	14.56	16.70
Space heaters	1.93	2.19	2.48	3.24	3.74	4.37
Wall or floor furnace, no ducts	2.32	2.48	2.65	3.06	3.32	3.66
Heating and cooling combined systems						
Forced air, same ducts	11.31	12.33	13.46	16.27	18.06	20.31
Heat pump	8.82	9.80	10.90	13.66	15.44	17.68
Wood burner integrated with furnace, add	2,103	2,429	2,755	3,672	4,284	5,076
Exterior furnace	7,395	8,809	10,549	15,264	18,432	22,680
Cooling only with separate ducts	7.83	8.54	9.34	11.30	12.55	14.13
Solar for space and hot water system (costs per sq. ft. of collector area)						
Fluid system	139.50	152.50	166.50	201.50	223.50	252.00
Other collectors	70.00	75.50	82.00	98.00	108.00	120.50
Air system	135.50	147.00	159.50	190.50	210.50	235.50

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
Costs/Sq. Ft. of Wall Area						
Storage wall, concrete, cost/sq. ft. area	22.13	23.06	24.07	26.38	27.98	30.08
Block	14.11	14.82	15.59	17.37	18.58	20.13
Floor, pavers	12.34	14.01	15.94	20.72	23.95	28.05
Quarry tile	14.21	16.47	19.11	25.92	30.54	36.55
Tanks, storage, LP gas, 125 gallons	1,300	1,325	1,350	1,425	1,500	1,575
250 gallons	1,725	1,750	1,800	1,900	1,975	2,075
500 gallons	2,475	2,525	2,575	2,725	2,850	3,000
1,000 gallons	4,400	4,475	4,575	4,850	5,025	5,300
Fuel oil, 275 gallons	1,250	1,325	1,375	1,525	1,625	1,750

Costs are for gas-fired systems. For oil-fired, add 7% plus storage tank.

Note: The assessor should analyze whether the added cost of oil heat contributes to the value.

ELECTRIC LIGHTING SYSTEMS

Costs/Sq. Ft. of Wall Area						
60-amp. system, Romex	5.70	6.23	6.82	8.27	9.19	10.36
BX	6.69	7.31	8.00	9.70	10.79	12.15
Conduit	7.90	8.63	9.44	11.45	12.73	14.34
100-amp. system	6.87	7.51	8.22	9.96	11.08	12.48
BX	8.11	8.86	9.69	11.75	13.07	14.73
Conduit	9.56	10.44	11.42	13.85	15.40	17.36
150-amp. system	7.58	8.28	9.06	10.99	12.22	13.77
BX	8.94	9.76	10.68	12.95	14.40	16.23
Conduit	10.55	11.52	12.61	15.29	17.00	19.16
200-amp. system	8.29	9.06	9.91	12.01	13.36	15.06
BX	9.77	10.67	11.67	14.16	15.74	17.74
Conduit	11.55	12.61	13.80	16.73	18.61	20.97
Unfinished Area:						
Nonmetallic	2.33	2.58	2.87	3.58	4.03	4.62
BX	2.80	3.10	3.42	4.26	4.80	5.48
Conduit	4.12	4.53	4.98	6.12	6.86	7.78

Garage lighting, $315 to $1,015 per garage.

PLUMBING

Costs Each						
Bathtub, no shower, white	1,095	1,385	1,755	2,850	3,670	4,790
Colored	1,315	1,625	2,010	3,120	3,930	5,010
Fiberglass	1,030	1,285	1,605	2,530	3,210	4,130
With shower, white	1,295	1,620	2,030	3,225	4,105	5,295
Colored	1,515	1,860	2,285	3,490	4,355	5,515
Fiberglass	2,040	2,360	2,740	3,735	4,400	5,255
Sink, countertop, white	619	743	906	1,343	1,656	2,060
Colored	770	915	1,090	1,575	1,915	2,350
Wall hung, white	805	960	1,140	1,645	1,990	2,440
Colored	985	1,140	1,320	1,795	2,120	2,530
Shower stall, ceramic tile	1,745	1,975	2,235	2,895	3,330	3,885
Fiberglass	998	1,134	1,297	2,641	3,032	3,534
Toilet, white	1,024	1,219	1,454	2,093	2,536	3,130
Colored	1,325	1,550	1,825	2,555	3,050	3,695
Electric, incinerator type	3,415	3,620	3,845	4,385	4,730	5,175
Composting	3,695	4,010	4,360	5,220	5,770	6,460
Ceramic tile, tub alcove	670	730	800	970	1,080	1,215
Wainscoting, per room	2,005	2,190	2,395	2,910	3,235	3,645
Marble, tub alcove	3,690	4,444	5,351	7,819	9,576	11,887
Wainscoting, per room	12,369	14,399	16,791	22,968	27,216	32,688

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
Costs Each						
Kitchen sink, one compartment, white	845	930	1,025	1,265	1,420	1,615
Colored	930	1,015	1,115	1,355	1,510	1,705
Steel	970	1,065	1,165	1,425	1,590	1,795
Two compartments, white	1,035	1,195	1,385	1,880	2,210	2,635
Colored	1,085	1,255	1,455	1,980	2,330	2,785
Steel	940	1,125	1,345	1,955	2,375	2,930
Laundry tub, one compartment	625	715	820	1,100	1,285	1,520
Two compartments	780	900	1,045	1,425	1,680	2,005
Water heater, gas, 30-gallon	1,115	1,190	1,270	1,460	1,585	1,740
40-gallon	1,175	1,260	1,355	1,580	1,725	1,905
50-gallon	1,255	1,360	1,475	1,755	1,930	2,155
Electric, 30-gallon	1,005	1,070	1,140	1,315	1,425	1,565
40-gallon	1,060	1,135	1,220	1,420	1,550	1,715
52-gallon	1,230	1,330	1,445	1,720	1,895	2,115
80-gallon	1,845	1,965	2,090	2,405	2,600	2,855
Solar with 100-gallon tank	6,885	7,625	8,455	10,540	11,885	13,580
Floor drain	555	640	740	1,005	1,185	1,415
Rough-in	575	635	705	875	985	1,130
Sump pump	700	780	865	1,095	1,240	1,425

WATER AND WASTE DISPOSAL						
Costs Each						
Municipal connections, including trench, pipe, tap and fees (40-foot setback)	2,282	2,575	2,901	3,716	4,271	4,955
Well system, 50 feet deep	2,425	2,510	2,608	2,836	2,999	3,195
100 feet	5,346	5,477	5,640	6,064	6,357	6,748
150 feet	7,889	8,117	8,346	8,965	9,389	9,943
200 feet	9,715	10,073	10,432	11,377	11,997	12,812
Septic system, 1000-sq. ft. bed						
1000-gallon tank	4,068	4,342	4,642	5,379	5,835	6,422
1500-gallon tank	6,455	6,813	7,205	8,150	8,769	9,519
2000-gallon tank	8,179	8,704	9,226	10,562	11,377	12,453
Septic system, mound type, 1000-sq. ft. bed						
1000-gallon tank	5,125	5,475	5,850	6,750	7,325	8,075
1500-gallon tank	8,125	8,575	9,075	10,275	11,050	12,050
2000-gallon tank	10,325	10,950	11,650	13,300	14,375	15,725
Grinder pump system, add	8,000	9,200	10,625	14,350	16,850	20,050

BUILT-IN UNITS						
Costs as Shown						
Kitchen cabinet, cost per linear foot						
Base, with laminated plastic counter top						
Softwood	147	179	218	328	407	511
Hardwood	272	307	348	451	519	606
Hardwood veneer	185	220	263	379	460	566
Laminated plastic veneer	162	195	235	346	424	527
Ceramic tile counter top, add	44	48	53	64	71	80
Linoleum counter top, deduct	12	14	16	21	25	29
Marble or granite counter top, add	155	173	194	246	279	322
Solid plastic counter top, add	118	115	111	106	105	105

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
Costs as Shown						
Wall mounted, 18”						
Softwood	89	99	109	135	152	173
Hardwood	181	191	203	230	248	271
Hardwood veneer	136	143	151	170	183	198
Laminated plastic veneer	112	121	130	153	167	185
Wall mounted, 30”						
Softwood	107	117	130	160	180	204
Hardwood	213	225	238	269	289	314
Hardwood veneer	160	168	178	201	216	235
Laminated plastic veneer	125	135	147	175	192	214
China cabinet, 80” high, corner type	1,102	1,204	1,320	1,591	1,764	1,987
Medicine cabinet, cost each	276	334	406	605	749	936
Vanity cabinet, cost each	348	442	566	936	1,224	1,620
Fireplace, cost each						
Inside chimney, one-story	4,425	5,025	5,725	7,425	8,425	9,600
Two-story	5,575	6,300	7,125	9,100	10,300	11,650
Add for second fireplace, same stack	3,750	4,200	4,675	5,800	6,450	7,200
Two-sided fireplace	6,425	7,250	8,200	10,500	11,875	13,450
Outside chimney, one-story	5,350	6,125	6,975	9,125	10,425	11,900
Two-story	6,650	7,550	8,575	11,075	12,575	14,300
Add for second fireplace, same stack	3,750	4,200	4,675	5,800	6,450	7,200
Prefabricated fireplace	2,000	2,375	2,825	4,000	4,750	5,650
Pellet or corn cob stoves	3,925	4,375	4,850	6,025	6,700	7,450
Heat-circulating device	550	625	750	1,000	1,150	1,325
Direct vented (no chimney) gas fireplace	2,250	2,700	3,250	4,700	5,650	6,800
Chimney, inside, furnace, cost per lin. ft.						
Common brick with liner, 16” x 16”	209.53	236.35	266.80	342.00	392.40	456.48
16” x 20”	236.35	266.08	300.15	384.48	440.64	511.92
Concrete block with liner, 16” x 16”	170.38	190.68	213.15	267.84	304.56	351.36
16” x 20”	196.48	218.95	243.60	303.84	344.16	395.28
Metal, single-wall	46.40	51.40	56.99	70.49	79.42	90.65
Double-wall	53.72	59.74	66.63	83.16	94.10	108.00
Triple-wall	72.50	80.26	89.03	110.16	124.13	141.84
Custom fireplace, cost each						
Inside chimney, one-story	13,800	15,025	16,350	19,400	21,125	23,000
Two-story	16,350	17,700	19,150	22,450	24,300	26,300
Add for second fireplace, same stack	6,900	7,525	8,175	9,700	10,550	11,500
Two-sided fireplace	17,950	19,525	21,275	25,225	27,450	29,900
Outside chimney, one-story	17,700	19,425	21,325	25,650	28,150	30,900
Two-story	21,150	23,175	25,375	30,450	33,350	36,525
Add for second fireplace, same stack	6,900	7,525	8,175	9,700	10,550	11,500
Direct vented (no chimney) gas fireplaces	5,700	6,450	7,275	9,300	10,525	11,900
Stairs, second floor, with balustrade	1,850	2,250	2,725	4,025	4,875	5,900
Partial balustrade	1,575	1,925	2,375	3,550	4,350	5,300
Custom stairs, curved or floating	23,900	30,675	39,400	64,925	83,350	107,000
Attic	1,610	1,740	1,885	2,225	2,455	2,736
Attic, disappearing, manual	800	1,000	1,225	1,900	2,350	2,900
Motorized	15,200	15,825	16,450	17,825	18,550	19,300
Basement, open riser	900	1,025	1,175	1,525	1,725	1,975
Closed riser	1,525	1,750	2,025	2,675	3,075	3,525
Range, drop-in, each						
With standard oven	913	1,056	1,232	1,656	1,917	2,223
With self-cleaning oven	1,187	1,408	1,676	2,367	2,810	3,338
Custom	4,500	5,050	5,675	7,150	8,025	9,000
Cooktop, countertop, four burners	482	606	756	1,180	1,480	1,845
With self-venting grille (Jenn Air)	725	900	1,100	1,650	2,025	2,500

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
Costs as Shown						
Oven, built-in	861	1,063	1,304	1,976	2,432	2,993
Double	1,425	1,750	2,125	3,175	3,875	4,725
Microwave	215	300	411	789	1,095	1,519
Microwave combination	2,075	2,325	2,600	3,250	3,625	4,050
Custom double-wall	2,575	3,375	4,425	7,575	9,925	13,000
Refrigerator/freezer, built-in	675	900	1,200	2,075	2,750	3,650
Deluxe	3,600	4,300	5,100	7,250	8,650	10,300
Icemaker	750	850	975	1,250	1,425	1,650
Dishwasher, built-in	502	613	756	1,141	1,402	1,721
Deluxe	1,625	1,825	2,050	2,575	2,900	3,250
Garbage disposal	176	209	254	352	424	502
Deluxe, heavy duty	475	550	600	750	850	925
Heater, bathroom, without fan	163	189	209	274	306	352
With fan	235	267	306	391	443	509
Hood, range, unvented	222	267	319	463	554	672
Vented	398	469	554	776	913	1,076
Custom, stainless steel or copper	2,575	3,275	4,175	6,775	8,625	11,000
Hot tub, with whirlpool, built-in	5,666	6,370	7,179	9,232	10,575	12,271
Intercom system, master station	587	665	756	985	1,121	1,278
Satellite	124	137	156	183	202	222
Jacuzzi tub	5,666	6,742	8,033	11,547	13,985	17,167
Sauna with heater and controls	4,140	5,164	6,448	10,047	12,544	15,661
Skylight, costs per square foot	100	100	100	150	150	175
Smoke detector, each	175	200	225	275	300	325
Trash compactor	711	782	861	1,043	1,148	1,265
Vacuum, central system	2,282	2,406	2,536	2,823	2,980	3,136
Vent fan, bathroom	150	175	225	325	375	450
Kitchen	150	175	225	325	375	450
Attic	725	805	899	1,117	1,238	1,375
Whole house	1,494	1,610	1,733	2,016	2,153	2,326
Water softener, automatic, 25,000-grain	2,204	2,256	2,302	2,406	2,458	2,510
50,000-grain	2,550	2,625	2,675	2,800	2,850	2,925
75,000-grain	2,650	2,725	2,800	2,925	3,000	3,100
100,000-grain	2,750	2,825	2,900	3,075	3,150	3,250
Manual, 25,000-grain	1,369	1,434	1,500	1,663	1,760	1,923
50,000-grain	1,775	1,825	1,900	2,025	2,100	2,175
75,000-grain	1,875	1,975	2,050	2,250	2,350	2,450
125,000-grain	2,200	2,275	2,375	2,575	2,700	2,800
Wet bar	925	1,000	1,075	1,250	1,350	1,475
Deluxe	1,825	2,200	2,625	3,775	4,500	5,400
Wood-burning stove, freestanding	1,900	2,250	2,700	3,800	4,525	5,400
Fireplace insert	1,950	2,325	2,775	3,950	4,700	5,600

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

UNIT-IN-PLACE COSTS	D	CD	C	BC	B	A
Costs as Shown						
SECURITY ALARM SYSTEMS						
Audio/video entry systems	3,515	4,150	4,900	6,930	8,325	10,130
Home automation systems	3,415	3,860	4,370	5,675	6,525	7,610
Residential security systems, wireless	1,075	1,410	1,850	3,220	4,295	5,805
Hard-wired	2,990	3,550	4,225	6,060	7,325	8,980
Sensors						
Point-area detectors (per opening)						
Alarm glass (wired)	160	180	205	265	305	355
Screen (burglarproof, wired)	160	200	255	410	525	680
Photoelectric, beam interrupt	690	790	910	1,225	1,430	1,695
Field of view changes	20	25	40	80	120	175
Stress detectors, floor	220	250	285	380	440	520
Pressure mat	160	200	255	410	525	680
Trip or pull switches (wire trap)	20	25	30	50	65	85
Switch sensors, magnetic, (each)	170	190	215	280	320	370
Mercury	170	190	215	280	320	370
Self-contained (battery)	85	95	105	135	150	175
Vibration detectors	90	110	125	180	210	255
Volume detectors						
Motion detectors, infrared	110	150	205	385	535	750
Microwave	180	225	285	455	580	750
Ultrasonic	180	225	285	455	580	750
Self-contained (battery)	180	220	275	425	535	680
Sound detectors, sensing units	180	225	285	455	580	750
Remote monitoring	1,465	1,945	2,580	4,605	6,210	8,485
Annunciators						
Alarms, local, residential						
Bells	160	180	205	265	305	355
Buzzers	20	20	25	30	35	40
Horns	75	100	125	215	285	380
Sirens	75	100	125	215	285	380
Lights	160	180	205	265	305	355
Control units (transmission/display)						
Control panel	590	645	710	870	975	1,105
Remote annunciator	325	390	465	680	830	1,025
Add for: electrical switch locks	235	295	375	610	785	1,025
Remote transmitters, each	85	90	95	110	120	130
Stand-by power, battery	35	55	75	160	235	345

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LAND IMPROVEMENTS	D	CD	C	BC	B	A
DRIVEWAYS AND WALKS						
Costs/Sq. Ft.						
Asphalt paving	2.88	3.09	3.31	3.85	4.20	4.63
Sealer, two coats	3.18	3.42	3.70	4.37	4.80	5.34
Concrete, plain, 3-1/2” thick	6.24	6.66	7.13	8.27	9.00	9.92
4”	6.43	6.90	7.41	8.66	9.46	10.47
Reinforced, 4”	7.01	7.80	8.69	10.91	12.35	14.17
5”	7.41	8.26	9.24	11.68	13.27	15.28
Crushed rock	2.26	2.34	2.43	2.65	2.80	2.99
TERRACE OR PATIO						
Costs/Sq. Ft.						
Brick	16.23	17.62	19.17	22.98	25.41	28.47
Concrete patio blocks	13.92	15.18	16.58	20.03	22.24	25.02
Flagstone	18.19	20.11	22.29	27.70	31.19	35.59
WOOD DECKS						
Costs/Sq. Ft.						
(includes decking, railings, girder, joists, posts, and footings)						
Pressure-treated wood, 12 sq. ft.	48.97	49.94	50.99	53.92	56.01	58.94
25 sq. ft.	42.58	43.42	44.34	46.88	48.70	51.25
50 sq. ft.	31.43	32.08	32.86	34.82	36.25	38.21
100 sq. ft.	22.75	23.34	23.93	25.43	26.54	28.04
200 sq. ft.	18.52	18.91	19.36	20.67	21.52	22.69
500 sq. ft.	13.50	13.82	14.15	15.00	15.65	16.50
Regular (pine or similar), 12 sq. ft.	39.12	39.90	40.82	43.16	44.79	47.14
25 sq. ft.	34.03	34.69	35.47	37.49	38.99	41.01
50 sq. ft.	25.10	25.69	26.28	27.84	28.95	30.51
100 sq. ft.	18.19	18.65	19.10	20.34	21.19	22.43
200 sq. ft.	14.80	15.13	15.52	16.50	17.21	18.13
500 sq. ft.	10.76	11.02	11.28	12.00	12.52	13.24
Redwood or cedar, 12 sq. ft.	57.44	58.61	59.98	63.57	66.05	69.63
25 sq. ft.	45.90	46.88	47.99	50.86	52.88	55.68
50 sq. ft.	34.88	35.66	36.58	38.99	40.62	42.90
100 sq. ft.	26.99	27.64	28.36	30.19	31.49	33.25
200 sq. ft.	22.36	22.89	23.54	25.10	26.15	27.64
500 sq. ft.	16.82	17.28	17.73	18.97	19.76	20.93
Vinyl, 12 sq. ft.	60.31	62.46	64.94	70.94	74.85	80.07
25 sq. ft.	52.81	53.92	55.16	58.48	60.77	64.03
50 sq. ft.	40.10	41.01	42.12	44.79	46.68	49.36
100 sq. ft.	31.04	31.75	32.60	34.75	36.19	38.27
200 sq. ft.	25.69	26.34	27.06	28.82	30.06	31.82
500 sq. ft.	19.36	19.89	20.41	21.78	22.75	24.06
Wood polymer composite, 12 sq. ft.	50.92	51.90	53.07	56.07	58.29	61.29
25 sq. ft.	44.27	45.12	46.10	48.77	50.66	53.33
50 sq. ft.	32.67	33.38	34.16	36.25	37.69	39.71
100 sq. ft.	23.67	24.25	24.84	26.47	27.58	29.14
200 sq. ft.	19.23	19.69	20.15	21.45	22.36	23.60
500 sq. ft.	14.02	14.34	14.74	15.65	16.30	17.15

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LAND IMPROVEMENTS	D	CD	C	BC	B	A
RETAINING WALLS						
Costs/Sq. Ft. of Wall Area (includes footings)						
Block, reinforced, 6”	13.87	15.54	17.44	22.25	25.39	29.35
8”	15.38	17.31	19.53	25.16	28.84	33.51
Block w/ pilaster, reinforced, 8”	16.15	18.18	20.50	26.42	30.28	35.18
Brick, 8” thick	25.78	28.68	31.98	40.25	45.60	52.36
12” thick	33.03	36.96	41.44	52.74	60.09	69.38
Precast, 8” nonretaining	10.03	10.98	12.04	14.66	16.34	18.45
Retaining	16.42	17.86	19.48	23.45	25.98	29.17
LANDSCAPING						
Costs as Shown						
Soil preparation, per sq. ft.						
Fine grading	0.32	0.38	0.44	0.61	0.72	0.84
Mulching	0.36	0.44	0.60	0.77	0.92	1.11
Top dressing or bedding	3.56	3.79	4.25	4.54	4.82	5.12
Lawns, per sq. ft., seeding	0.44	0.49	0.58	0.70	0.78	0.87
Sodded	0.81	0.97	1.37	1.63	1.93	2.30
Ground cover, per sq. ft.						
Gravel/wood chip	2.60	2.83	3.38	3.63	3.95	4.29
Spreading plants	0.84	1.02	1.51	1.85	2.24	2.72
Edging redwood, per lin. ft.	3.55	3.94	4.80	5.40	6.00	6.66
Shrubs and hedges, each, small	21.15	23.45	28.25	31.75	35.25	39.00
Medium	50.50	57.00	72.50	81.50	91.50	103.00
Large	157.00	175.00	225.00	242.00	269.00	300.00
Trees, each						
Small, 15-gallon, 20” box	144	180	271	344	425	525
Medium, 24” to 36” box	615	720	995	1,170	1,370	1,610
Large, 42” box and larger	1,560	1,850	2,725	3,125	3,725	4,425
FENCES						
Cost/Lin. Ft.						
Vinyl fencing						
Spaced slat panels						
6’	33.42	37.33	41.79	53.02	60.32	69.53
4’ – 5’	31.91	35.33	39.20	48.87	55.10	62.96
Basketweave, 5’	46.48	50.53	55.04	66.14	73.21	82.13
Solid board panels						
6’	35.93	39.91	44.43	55.74	63.05	72.27
4’ – 5’	33.17	36.80	40.91	51.21	57.86	66.25
Add for lattice top	7.04	7.58	8.18	9.65	10.59	11.77
Picket, 36” – 48” high	22.36	24.71	27.35	33.94	38.18	43.53
Lattice, framed 24” – 50” high	12.31	13.81	15.53	19.87	22.70	26.28
Two rails, 36” – 48” high	15.58	16.67	17.87	20.80	22.66	25.02
Three rails, 60” high	19.90	20.95	22.10	24.91	26.71	29.02
Four rails, 60” high	20.85	22.24	23.77	27.49	29.85	32.85
Lattice, arbor, per sq. ft.	6.69	7.60	8.64	11.32	13.09	15.33
Trellis (no frame)	1.61	1.77	1.95	2.40	2.69	3.06

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LAND IMPROVEMENTS	D	CD	C	BC	B	A
Costs/Lin. Ft.						
Wood fencing						
Solid board, horizontal or vertical, 6’.	29.15	31.36	33.82	39.82	43.63	48.45
5’.	26.63	28.52	30.60	35.67	38.89	42.98
Split redwood/grape stake, 6’.	28.89	31.28	33.94	40.45	44.59	49.82
5’.	27.14	29.09	31.24	36.50	39.84	44.07
Basketweave, 6’.	34.42	36.71	39.23	45.36	49.25	54.20
5’.	33.42	35.44	37.67	43.08	46.52	50.92
Wood picket, 12” to 24”.	15.73	17.11	18.66	22.45	24.87	27.92
30” – 40”.	20.85	22.33	23.96	27.94	30.47	33.67
Split, two-rail, 24” to 36” high.	14.47	15.43	16.48	19.03	20.66	22.72
Three-rail, 36” to 48” high.	16.03	17.11	18.31	21.21	23.06	25.40
Four-rail, 42” to 54” high.	19.50	20.91	22.47	26.28	28.69	31.76
Wooden gates, per sq. ft..	15.63	16.81	18.13	21.34	23.37	25.95
Paint, per sq. ft., per coat.	0.58	0.62	0.66	0.77	0.84	0.92
CHAIN LINK FENCES						
Costs/Sq. Ft.						
Mesh, 2”, #9 wire.	3.81	3.87	3.93	4.12	4.26	4.47
#11 wire.	3.27	3.32	3.37	3.54	3.66	3.83
Add for rails.	3.13	3.18	3.24	3.41	3.53	3.70
Add for three-strand barbed wire.	4.06	4.15	4.25	4.52	4.71	4.97
Gates, 3’ wide.	370	397	428	501	548	608
5’ wide.	481	546	620	810	935	1,094
10’ wide.	799	886	984	1,229	1,388	1,588
15’ wide.	1,000	1,115	1,246	1,575	1,789	2,059
METAL FENCES AND GRILLS						
Costs/Sq. Ft.						
Hand-forged wrought iron.	10.10	12.15	14.65	21.20	25.50	30.75
Modular, steel or aluminum.	14.62	17.05	19.91	27.50	32.63	39.24
LAWN SPRINKLERS						
Costs/Sq. Ft.						
Conventional.	0.92	1.01	1.28	1.37	1.52	1.69
Rainbird or Rain Jet systems.	0.60	0.63	0.71	0.76	0.80	0.84
For automatic control, add per station.	225.00	235.00	246.00	268.00	280.00	292.00
SWIMMING POOLS						
Costs/Sq. Ft. Surface Area (including filter, diving board, steps, and ladder)						
Gunite pool						
Surface area: 200 sq. ft..	131.55	138.95	147.15	167.00	179.65	195.85
400 sq. ft..	90.20	94.95	100.15	112.85	120.95	131.40
600 sq. ft..	68.70	73.40	78.60	91.25	99.30	109.50
800 sq. ft..	57.05	60.75	64.80	74.70	80.95	88.95
Poured concrete pool, in ground						
Surface area: 200 sq. ft..	151.25	163.10	176.25	208.40	228.80	254.65
400 sq. ft..	103.75	111.45	120.00	140.85	154.05	170.80
600 sq. ft..	79.00	86.15	94.15	113.90	126.45	142.35
800 sq. ft..	71.30	76.40	82.05	95.85	104.60	115.65

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LAND IMPROVEMENTS	D	CD	C	BC	B	A
Costs/Sq. Ft. Surface Area (including filter, steps, and ladder)						
Fiberglass pool, in ground						
Surface area: 200 sq. ft..	111.80	118.15	125.05	141.95	152.70	166.50
400 sq. ft..	76.65	80.70	85.15	95.90	102.80	111.70
600 sq. ft..	58.35	62.40	66.80	77.55	84.40	93.10
800 sq. ft..	48.50	51.60	55.05	63.50	68.85	75.60
Plastic-lined pool, in ground						
Surface area: 200 sq. ft..	108.55	112.15	116.10	125.95	132.50	141.25
400 sq. ft..	71.35	73.25	75.40	80.80	84.50	89.50
600 sq. ft..	56.80	58.10	59.60	63.50	66.20	69.90
800 sq. ft..	47.00	47.95	49.05	52.00	54.05	56.95
Pool accessories						
Deduct for lack of filter.	970	1,076	1,197	1,498	1,693	1,938
Add for diving board.	905	1,015	1,142	1,464	1,673	1,938
Add for heater.	2,000	2,408	2,904	4,279	5,245	6,515
Chlorinator.	181	283	443	1,099	1,749	2,820
Hydrosweep.	1,005	1,305	1,697	2,907	3,842	5,147
Attached whirlpool bath (portable type, including hot tubs).	9,849	10,982	12,269	15,508	17,606	20,258
Separate whirlpool bath, (4–10 persons).	13,367	15,906	18,966	27,304	33,083	40,625
GAZEBOS						
Typical cost each (8' to 20' wood units including minimal foundation but excluding floors)						
Standard.	4,950	6,950	9,400	16,100	20,600	26,000
Deluxe.	23,100	27,300	32,300	45,000	53,000	62,750
BOAT DOCKS						
Costs/Sq. Ft. (including fenders and railings)						
Decking, light posts, 2”.	42.00	44.25	48.50	51.50	54.00	56.50
Light piling, 3”.	48.25	51.50	55.50	63.50	68.00	73.00
SHEDS						
Costs/Sq. Ft. (excluding permanent foundation or slab and electrical. Includes entry doors with some windows in better qualities). Exterior wall height is 8'. For loft/barn (gambrel), add 10 to 15%.						
Wood frame, 40 sq. ft..	33.28	37.38	42.06	53.93	61.67	71.46
100 sq. ft..	24.45	27.46	30.90	39.62	45.30	52.50
200 sq. ft..	20.91	23.48	26.42	33.88	38.74	44.90
300 sq. ft..	20.03	22.50	25.32	32.46	37.12	43.02
400 sq. ft..	19.15	21.50	24.20	31.02	35.48	41.11
Metal prefabricated, 40, sq. ft..	18.90	22.37	26.52	37.77	45.51	55.58
100 sq. ft..	13.88	16.43	19.49	27.75	33.44	40.83
200 sq. ft..	11.87	14.05	16.66	23.73	28.59	34.92
300 sq. ft..	11.38	13.46	15.97	22.74	27.40	33.46
400 sq. ft..	10.87	12.87	15.26	21.73	26.18	31.98

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREEN ADDITIONS

CONCRETE

Concrete can contribute Green credits by being a regional material or by being recycled. Concrete within the building envelope needs to come from within 500 miles and contain post-consumer recycled material. The specific credit is dependent on the amount of the recycled content.

Costs Each

Insulated concrete, Form-in-place, Expanded polystyrene,	
Straight, 9-1/4”x 48”x 16”, 4” core	$47.50
Corner, 9-1/4”x 60”x 16”, 4” core	57.00
Angle, 9-1/4”x 52”x 16”, 4” core	55.00
Insulated concrete, Form-in-place, Expanded polystyrene,	
Straight, 11-1/4”x 48”x 16”, 6” core	47.75
Corner, 11-1/4”x 56”x 16”, 6” core	56.00
Angle, 11-1/4”x 44”x 16”, 6” core	51.00
Tee, 11-1/4”x 44”x 16”, 6” core	55.00
Insulated concrete, Form-in-place, Expanded polystyrene,	
Straight, 13-1/4”x 48”x 16”, 8” core	50.00
Corner, 13-1/4”x 60”x 16”, 8” core	59.00
Angle, 13-1/4”x 60”x 16”, 8” core	57.00
Tee, 13-1/4”x 44”x 16”, 8” core	57.00

Costs/Sq. Ft.

Insulated concrete, Form-in-place, Reinforced, Expanded polystyrene form,	
3,000 psi, 4” thick core	18.30
3,000 psi, 6” thick core	20.45
4,000 psi, 8” thick core	23.05
Concrete countertop, Cast-in place, Recycled materials,	
1-1/2” thick	24.60
2” thick	33.00
Concrete countertop, Pre-cast, Various recycled materials,	
1-1/2” thick	250.00
Glass Chips, Various recycled materials,	
1-1/4” thick	304.00
Paper Fiber, Various recycled materials,	
1-1/8” thick	363.00
Concrete slab on grade, Cast-in-place, With welded wire fabric, Recycled content, 3,000 psi,	
4” thick	5.73
5” thick	7.22
6” thick	8.00
Concrete slab, Elevated, Cast-in-place, Recycled content, Reinforced, 3,000 psi,	
4” thick	20.10
5” thick	21.65
6” thick	22.80
Concrete slab, Elevated, Cast-in-place, Recycled content, Reinforced, 4,500 psi,	
4” thick	22.50
5” thick	23.90
6” thick	25.75
7” thick	27.00
8” thick	28.75
10” thick	31.25
12” thick	34.00

Costs/Sq. Ft.

Foundation wall, Cast-in-place, With damp proofing, Recycled content, 3,000 psi, Reinforced,	
6” thick	$25.00
8” thick	27.00
10” thick	29.75
12” thick	31.75

Costs/Sq. Ft.

Concrete wall, Cast-in-place, Recycled content, 3,000 psi, Reinforced,	
6” thick	25.00
8” thick	26.75
10” thick	29.50
12” thick	31.50

Costs/V.L.F.

Concrete column, Cast-in-place, Recycled content, 4,500 psi, Reinforced,	
6” x 6”	58.00
8” x 8”	73.50
10” x 10”	89.50
12” x 12”	103.00
Concrete column, Cast-in-place, Recycled content, 4,500 psi, Reinforced,	
6” dia.	49.00
8” dia.	52.00
10” dia.	58.00
12” dia.	61.00

Costs/Sq. Ft.

Wall, Adobe brick,	
8” thick	33.75
12” thick	45.75
Concrete masonry block - 4”x8”x16”	11.05
Reinforced Lightweight	12.30
Concrete masonry block - 6”x8”x16”	13.05
Reinforced Lightweight	15.60
Concrete masonry block - 8”x8”x16”	15.15
Reinforced Lightweight	16.65
Concrete masonry block - 12”x8”x16”	21.80
Reinforced Lightweight	24.50
Concrete masonry block - 24”x8”x16”	43.75
Reinforced lightweight	48.50
Glass block, With reinforcement,	
6”x 6”x 4” wide	89.50
8”x 8”x 4” wide	54.00
12”x 12”x 4” wide	47.75
Glass block, Reflective, With reinforcement,	
6”x 6”x 4” wide	59.00
8”x 8”x 4” wide	40.50
12”x 12”x 4” wide	47.75

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WOOD, PLASTIC, & COMPOSITES

WOOD: Wood components can contribute Green credits by meeting the Construction Waste Management, Material Reuse, Regional Materials, and Certified Wood requirements. Material needs to be diverted from disposal in landfills through recycle and/or salvage and the material needs to have been salvaged, refurbished, or reused within 500 miles. Fifty percent of the wood-based materials and products must be certified in accordance with the Forest Stewardship Councils Principles and Criteria.

PLASTIC: Plastic components can contribute Green credits by meeting the Regional Materials and Recycled Content requirements. Plastic needs to contain post-consumer recycled material and come from within 500 miles.

COMPOSITES: Composite components can contribute Green credits by meeting the Construction Waste Management, Regional Materials, and Recycled Content requirements. Composite material needs to be diverted from disposal in landfills through recycle and/or salvage and must contain post-consumer recycled material within 500 miles.

The specific credit for Wood, Plastic, and Composites is dependent on the amount of the recycled content.

Costs/Sq. Ft.

Wall panel, Structural insulated panel (SIP), OSB both sides,	
4’ x 8’ x 4-1/2” thick.	$11.70
4’ x 8’ x 6-1/2” thick.	12.95
4’ x 8’ x 8-1/4” thick.	14.35
4’ x 8’ x 10-1/8” thick.	15.95
Roof panel, Structural insulated panel (SIP), OSB both sides,	
4’ x 8’ x 4-1/2” thick.	11.75
4’ x 8’ x 6-1/2” thick.	13.05
4’ x 8’ x 8-1/4” thick.	14.50
4’ x 8’ x 10-1/8” thick.	16.20

Costs/Lin. Ft.

Engineered I-Joist, Recycled content, Southern pine,	
1-1/2”x 9-1/2”.	5.62
1-1/2” x 11-7/8”.	6.17
1-1/2” x 14”.	7.05
1-3/4” x 9-1/2”.	6.14
1-3/4” x 11-7/8”.	6.91
1-3/4” x 14”.	7.95
1-3/4” x 16”.	7.58
2-5/16” x 11-7/8”.	9.47
2-5/16” x 14”.	10.50
2-5/16” x 16”.	11.00

Costs/Sq. Ft.

Floor framing, SFI certified, Engineered laminated veneer lumber,	
1-3/4”x 7-1/4” joist, 16” o.c..	$8.99
1-3/4”x 7-1/4” joist, 24” o.c..	6.90
1-3/4”x 9-1/2” joist, 16” o.c..	10.80
1-3/4”x 9-1/2” joist, 24” o.c..	8.25
1-3/4”x 11-7/8” joist, 16” o.c..	11.55
1-3/4”x 11-7/8” joist, 24” o.c..	9.06
3-1/2”x 9-1/2” joist, 16” o.c..	20.10
3-1/2”x 9-1/2” joist, 24” o.c..	15.15
3-1/2”x 11-7/8” joist, 16” o.c..	25.50
3-1/2”x 11-7/8” joist, 24” o.c..	19.35
5-1/4”x 9-1/2” joist, 16” o.c..	34.75
5-1/4”x 9-1/2” joist, 24” o.c..	26.25
5-1/4”x 11-7/8” joist, 16” o.c..	38.50
5-1/4”x 11-7/8” joist, 24” o.c..	29.00

Costs/Sq. Ft.

Roof framing, SFI certified, Engineered laminated veneer lumber,	
1-3/4”x 7-1/4” rafter, 16” o.c..	9.10
1-3/4”x 7-1/4” rafter, 24” o.c..	6.98
1-3/4”x 9-1/2” rafter, 16” o.c..	10.90
1-3/4”x 9-1/2” rafter, 24” o.c..	8.34
1-3/4”x 11-7/8” rafter, 16” o.c..	12.05
1-3/4”x 11-7/8” rafter, 24” o.c..	9.16
3-1/2”x 9-1/2” joist, 16” o.c..	20.20
3-1/2”x 9-1/2” joist, 24” o.c..	15.25
3-1/2”x 11-7/8” joist, 16” o.c..	25.75
3-1/2”x 11-7/8” joist, 24” o.c..	19.40
5-1/4”x 9-1/2” joist, 16” o.c..	35.00
5-1/4”x 9-1/2” joist, 24” o.c..	26.25
5-1/4”x 11-7/8” joist, 16” o.c..	38.50
5-1/4”x 11-7/8” joist, 24” o.c..	29.00

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREEN ADDITIONS

THERMAL & MOISTURE PROTECTION INSULATION

Thermal protection affects the thermal and acoustical comfort of building occupants. It also has significant impact on the amount of energy used to cool and heat the building. By controlling moisture at the building envelope, the longevity, and therefore the sustainability, of the building will be increased. Proper moisture protection at the building envelope, is also an important step in controlling and preventing the growth of mold, which affects the indoor air quality of buildings. Materials must contain recycled content and future recyclability, have low embodied energy which reduces the initial energy investment of the product, not contain CFCs, HCFCs or other ozone depleting substances, nor contain formaldehyde, no VOCs, and no off-gassing for promoting indoor air quality.

Costs/Sq. Ft.

Radiant barrier, 97% reflectivity, Double-sided, Aluminum foil, Poly mesh reinforced,	
48” wide	$0.42
16” to 24” wide	0.48
Laser perforated, 97% reflectivity,	
48” wide	0.46
16” to 24” wide	0.53
Heavy weight, 98% reflectivity, Double-sided, Aluminum,	
48” wide	0.48
16” to 24” wide	0.58
Double bubble sided, 98% reflectivity,	
48” wide	0.82
16” to 24” wide	0.91
Reflective roof coating, Rubberized, Water-based,	
White	0.88
Asphalt/aluminum, Silver	0.77
Polyester fabric, With primer and seal, Acrylic,	
Clear	1.58
Ice/water shield flashing at roof edge	1.73

GREEN ROOF SYSTEM

Costs Each

Plant tray, Modular, Plastic, Polystyrene,	
8” x 8” x 2-1/2”	6.57
8” x 12” x 2-1/2”	7.07
22” x 11” x 2-1/2”	15.60
13” x 15” x 3-1/2”	17.65
Recycled content, Coconut coir fiber,	
11” x 21”	22.50

Costs/Sq. Ft.

Plant tray, Barrier, Root barrier, Bio degradable fabric, Trifluralin,	
24’ x 100’	7.08
Plant tray, Screen, Weed barrier, Moisture retention fabric, Micro-perforated film,	
6’ x 250’	7.03

Costs/Sq. Ft.

Plant Growing Media, Hoisted up to 5 story,	
Clay, 2” thick	$1.52
Clay, 4” thick	3.03
Clay, 6” thick	4.37
Clay, 8” thick	5.82
Recycled content, 2” thick	2.13
Recycled content, 4” thick	4.25
Recycled content, 6” thick	6.33
Recycled content, 8” thick	8.45
Sand and Gravel, 2” thick	1.07
Sand and Gravel, 4” thick	2.13
Sand and Gravel, 6” thick	2.98
Sand and Gravel, 8” thick	3.97

Costs/Lin. Ft.

Plant tray, Edge restraint, Treated lumber, Wood,	
4” x 4”	5.10
4” x 6”	5.77

Costs/Sq. Ft.

Roof paver, Walkway pads, Recycled rubber tire,	
19-1/2” x 19-1/2”	10.20
Walkway squares, Recycled rubber,	
16” x 16” x 1” thick	11.25
Insulation, Batt, Foil-faced, Non-rigid, Walls, or Floor,	
3-1/2” Thick, R11	1.16
Insulation, Blanket, Unfaced, Non-rigid, Walls, or Ceiling,	
3-1/2”, R11	1.25
Insulation, Blown-in, Wall, Cellulose,	
3.5” thick, R-13	1.45
Insulation, Blown-in, Wall, Fiberglass,	
3.5” thick, R-9	1.58
Insulation, Blown-in, Ceiling, Cellulose,	
6” thick, R-22	1.13
Insulation, Blown-in, Ceiling, Fiberglass,	
6” thick, R-13	0.93
Insulation, Roof, Straw, Wire tied, 2-wire, Rice,	
4.0 Lbs./Cu. Ft., 15” thick	0.80
Insulation, Wall, Straw, Wire tied, 2-wire, Rice,	
4.0 Lbs./Cu. Ft., 15” thick	0.60

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREEN ADDITIONS

DOOR & WINDOW OPENINGS

Openings can contribute Green credits by meeting the Minimum Energy Performance, Daylight & Views, Material Reuse and Regional Material requirements. Openings are considered part of the building envelope system design and can contribute to the Minimum Energy Performance. The Daylight requirement specifies a minimum glazing factor for a specific percentage of all regularly occupied areas. The Views requirement specifies direct line of sight for a specific percentage of all regularly occupied areas. To meet the Material Reuse requirements the material needs to have been salvaged, refurbished or reused. The Regional Material credit requires all materials to be extracted, processed and manufactured within 500 miles of the building site. Opening components must also be NFRC certified and contribute to the reduction in energy to be considered Green.

Costs Each

Skylight, Solar tube kit, With 4' flexible tube, Acrylic dome,	
10" diameter.	$680.00
14" diameter.	770.00
21" diameter.	1010.00
Skylight, Solar tube kit, With 4' rigid tube and fresnel diffuser, Acrylic dome,	
10" diameter.	730.00
14" diameter.	945.00
Skylight, Solar tube kit, With 6' rigid tube and fresnel ceiling diffuser,	
Acrylic dome, 21" diameter.	1250.00

Costs/Lin. Ft.

Weatherstripping, Door, Vinyl gasket.	4.61
Weatherstripping, Window, Rubber,	
3/4" wide, 7/16" thick.	4.11

Costs/Sq. Ft.

Translucent wall panel, With aluminium frame, Triple wall, 48" wide x 5/8" thick polycarbonate panels, Clear,	
8' high.	34.25
48" wide x 5/8" thick polycarbonate panels, White,	
8' high.	35.00
6-wall, 48" wide x 1" thick polycarbonate panels,	
Clear, 8' high.	39.00
6-wall, 48" wide x 1" thick polycarbonate panels,	
White, 8' high.	40.00
Skyroof, Atrium, Curb mounted, Single pitch, With aluminum frame, 5/8" clear triple wall polycarbonate,	
8'-0" wide.	47.75
5/8" white triple wall polycarbonate, 8'-0" wide.	48.50
1" clear 6-wall polycarbonate, 8'-0" wide.	53.00
1" white 6-wall polycarbonate, 8'-0" wide.	54.00
Skyroof, Atrium, Curb mounted, Double pitch, With aluminum frame, 5/8" clear triple wall polycarbonate,	
16'-0" wide.	49.00
5/8" white triple wall polycarbonate, 8'-0" wide.	50.00
1" clear 6-wall polycarbonate, 8'-0" wide.	55.00
1" white 6-wall polycarbonate, 8'-0" wide.	57.00

FINISHES

Finishes can contribute Green credits by meeting the Low-Emitting Materials for Carpet, Adhesives & Solvents, Paints & Coatings and Regional Material requirements. The Low-Emitting Materials requirement limits the amount of VOC's that can be out gassed for specific product and the use of urea-formaldehyde resins. The Regional Material credit requires all materials to be extracted, processed and manufactured within 500 miles of the building site. Opening components must also be NFRC certified and contribute to the reduction in energy to be considered Green.

Costs/Sq. Ft.

Sealer, Concrete floor, Semi-transparent, Acrylic, Colored,	
Semi-gloss finish, 2 coats, Spray.	$1.35
Paint, Floor, Interior, Concrete, Low VOC, 1 coat finish,	
Sprayed.	0.48
Paint, Floor, Interior, Metal, Low VOC, Primer and finish	
coat, Sprayed.	0.97
Paint, Wall, Interior, Low VOC latex paint, Average,	
Brush/Roller/Spray, 2 Finish coats, Flatwall.	0.71
2 finish coats, Semi-gloss enamel.	0.76
Paint, Ceiling, Interior, Low VOC latex paint, Average,	
Brush/Roller/Spray, 2 Finish coats, Flatwall.	0.71
2 finish coats, Semi-gloss enamel.	0.76
Paint, Wall, Interior, Zero VOC latex paint, Average, Brush/	
Roller/Spray, Primer and Finish coat, Flatwall.	0.76
Primer and Finish coat, Semi-gloss enamel.	0.82
Paint, Ceiling, Interior, Zero VOC latex paint, Average,	
Brush /Roller/Spray, Primer and Finish coat,	
Flatwall.	0.82
Primer and Finish coat, Semi-gloss enamel.	0.87
Wood finish, Low VOC, Polyurethane, Clear,	
1 coat, Brushed.	1.08
Wood finish, Low VOC, Lacquer, Clear,	
3 coat, Brushed.	2.10
Metal stud framing, Recycled Content, Non-load bearing, Galvanized, 25 Ga,	
1-5/8" wide, 16" o.c..	2.71
1-5/8" wide, 24" o.c..	2.02
2-1/2" wide, 16" o.c..	3.19
2-1/2" wide, 24" o.c..	2.43
4" wide, 16" o.c..	33.75
4" wide, 24" o.c..	2.85
6" wide, 16" o.c..	3.73
6" wide, 24" o.c..	2.84

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREEN ADDITIONS

SPECIALTIES

This area is very broad and encompasses many items. Material or building components typically addressed in this section would be specialty items such as Green Power generation equipment, rainwater harvesting, signage, bathroom hand dryers and site features to control heat island effects.

Costs Each

Pellet stove, Freestanding, With glass door and 3" direct vent,
- 40,000 Btu, Heavy steel, 24"x 21"x 20" H. . . . $5250.00
- 45,000 Btu, Heavy steel, 22"x 27"x 29" H. . . . 5800.00

With ceramic glass door, 50,000 Btu, Heavy steel,
- 26"x 31"x 33-1/4" H. 6850.00

Fireplace insert, Wood burning, With cast iron glass door, blower and 6" dia. flue liner,
- 69,600 BTU, Steel, Black finish. 3400.00

With steel glass bay door and blower,
- 70,000 BTU, Steel, Black finish. 6200.00

Exit sign, Door mounted, Photoluminescent,
- Rigid plastic, 4" x 6" x 1/8" thick. 39.25

Exit egress sign, With directional graphic, Photoluminescent,
- Rigid plastic, 8" x 4-1/2" x 5/8" thick. 58.00

Egress stair signage, Wall mounted, Projecting, Double sided, With graphic, Aluminum, Photoluminescent,
- 6" x 5" x 3-1/2" projection. 63.00

Exit sign, Photoluminescent,
- 15" x 8-1/2" x 1" thick. 128.00

With directional arrows, 15" x 8-1/2" x 1" thick. . . . 147.00

8" lettering, Plastic, 17" x 10" x 1/2" thick. 201.00

With directional arrows, Metal frame,
- 15-1/4" x 8-1/4" x 1" thick. 236.00

8" lettering, Plastic, 17" x 10" x 1/2" thick. 290.00

100 ft visibility, With directional arrows,
- 16" x 8-5/8" x 1/2" thick. 324.00

Ceiling mounted, Double sided, With directional arrows, Metal frame, Photoluminescent,
- 15-1/4" x 8-1/4" x 1" thick. 432.00

GLAZING/WINDOW SHADING

Costs Each

Awning, Fixed, Aluminum, Baked enamel finish,
- 2' projection, 3' wide. 620.00

Costs/Sq. Ft.

Awning, Retractable, Manual, Standard vinyl,
- 8' projection, Up to 10' wide. 39.00

Costs Each

Awning, Fixed, Aluminum, Baked enamel finish,
- 3' projection, 6' wide. 795.00

Costs/Sq. Ft.

Custom acrylic fabric, 8' projection,
- Up to 10' wide. 41.25

Awning, Retractable, Motorized, Standard vinyl,
- 8' projection, Up to 10' wide. 47.75

Custom acrylic fabric, 8' projection,
- Up to 10' wide. 50.00

SPECIAL CONSTRUCTION

Costs Each

Solar hydronic panel, Residential, Roof mounted, With 50 gal tank, photovoltaic pump and piping, Flat lexan/anodized aluminum frame panel,
- 20" x 144". $1900.00

Solar hydronic panel, Flat roof tilt mounted, With 52 gal steel tank, single heat exchanger, pump and piping, Flat glass/anodized aluminum frame panel,
- 88" x 96". 6350.00

Solar panel array. Photovoltaic, Grid-tied system, Flush mounted rack, Sloped roof,
- 2 kWH capacity. 10700.00

Solar panel array. Photovoltaic, Grid-tied system, Flush mounted rack, Sloped roof,
- 4 kWH capacity. 19600.00

Solar water heater, System including, Collectors / Tank / Controller / Pump / Valves / Piping / Insulation / etc.,
- 120 gallon. 14900.00

Solar water heater, System including, Collectors / Tank / Controller / Pump / Valves / Piping / Insulation / etc.,
- 80 gallon. 11700.00

Solar panel array. Photovoltaic, Grid-tied system, Flush mounted rack, Sloped roof,
- 6 kWH capacity. 26200.00

Solar panel array. Photovoltaic, Grid-tied system, Flush mounted rack, Sloped roof,
- 8 kWH capacity. 33300.00

Solar panel array. Photovoltaic, Grid-tied system, Low tilt (30deg) mounted rack, Flat roof,
- 10 kWh capacity. 50250.00

Solar panel array. Photovoltaic, Grid-tied system, Low tilt (30deg) mounted rack, Flat roof,
- 15 kWh capacity. 72000.00

Solar panel array. Photovoltaic, Grid-tied system, Low tilt (30deg) mounted rack, Flat roof,
- 50 kWh capacity. 201000.00

Solar panel array. Photovoltaic, Grid-tied system, Low tilt (30deg) mounted rack, Flat roof,
- 75 kWh capacity. 293000.00

Roofing, Solar photovoltaic, Tile, Slate, Grid-tied system,
- 2kWh capacity 25400.00

Roofing, Solar photovoltaic, Shingles, Grid-tied system,
- 2kWh capacity. 15900.00

Roofing, Solar photovoltaic, Shingles, Grid-tied system,
- 4kWh capacity. 30200.00

Wind turbine generator, Off-grid, With 33' guyed pole,
- 9' rotor blade, 24/36/48 VDC, 1.0 Kwatt 26500.00

Grid-tied, With inverter and 45' tower, 12' rotor blade,
- 120/240V, 1.8 Kwatt. 36900.00

Electric backup power storage, With inverter and steel enclosure, 8-200aH 6V batteries,
- 120VAC, 9.6 KwH. 13800.00

Electric backup power storage, Add-on with steel enclosure,
- 8-200aH 6V batteries, 240VAC, 9.6 KwH. 5800.00

Wind turbine generator, Grid-tied, With inverter and
- 60' tower, 12' rotor blade, 120/240V,
- 2.4 Kwatt. 79750.00

Electric backup power storage, With inverter and steel enclosure, 4-200aH 6V batteries,
- 120VAC, 4.8 KwH. 11900.00
- 12-200aH 6V batteries, 120VAC, 14.4 KwH. . . . 14400.00
- 12-200aH 6V batteries, 240VAC, 14.4 KwH. . . . 8950.00

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

PLUMBING & FIXTURES

Plumbing has a very broad impact on Green credits primarily covering the efficient management, use and reuse of water and energy use. Typically, items covered may include Water Efficient Landscaping, Innovative Waste Water Technologies, Water Use Reduction, Minimum Energy Performance, Recycled Content, On-site Renewable Energy and Fundamental Refrigerant Management.

Costs Each

Reverse Osmosis/Deionization water purification system,	
3 stage, 24 gpd	$250.00
3 stage, 36 gpd	255.00
3 stage, 50 gpd	265.00
3 stage, 75 gpd	270.00
3 stage, 100 gpd	358.00
4 stage, 75 gpd	447.00
5 stage, 50 gpd	590.00
5 stage, 75 gpd	605.00
6 stage, 50 gpd	635.00
6 stage, 75 gpd	645.00
Greywater system, For water closet, With pump and filter,	
5-1/2 gallon tank, 12VDC	790.00
Greywater tank, Residential, Up to 3 persons,	
39 gallons, 22-1/2" dia. x 46"H	5350.00
Up to 6 persons, 66 gallon tank,	
22-1/2" dia. x 60"H	5950.00
Up to 9 persons, 92 gallon tank,	
30-1/2" dia. x 53"H	6750.00
Up to 12 persons, 119 gallon tank,	
30-1/2" dia. x 60"H	7200.00
Atmospheric water system, Generator,	
110v 50Hz, 3.17 gallon capacity	2130.00
3.6 gallon capacity	2500.00
Faucet aerator, Kitchen, 2 spray setting, With pause valve,	
Chrome finish, 1.5 GPM	26.25
Showerhead, Shutoff valve, Brass, Chrome finish	30.00

Costs/Lin. Ft.

Insulation, Pipe, Fiberglass, P/c with ssl,	
1/2"o.d. x 1/2"wall	7.26
3/4"o.d. x 1/2"wall	8.04
1"o.d. x 1/2"wall	8.37
1-1/4"o.d. x 1/2"wall	8.78
1-1/2"o.d. x 1/2"wall	9.24
2"o.d. x 1/2"wall	9.82
2-1/2"o.d. x 1/2"wall	10.70
1/2"o.d. x 1"wall	7.69
3/4"o.d. x 1"wall	8.68
1"o.d. x 1"wall	9.22
1-1/4"o.d. x 1"wall	10.50
1-1/2"o.d. x 1"wall	11.55
2"o.d. x 1"wall	12.35
2-1/2"o.d. x 1"wall	13.20
1/2"o.d. x 1-1/2"wall	10.35
3/4"o.d. x 1-1/2"wall	11.50
1"o.d. x 1-1/2"wall	12.00
1-1/4"o.d. x 1-1/2"wall	12.65
1-1/2"o.d. x 1-1/2"wall	13.35

Costs/Lin. Ft.

Insulation, Pipe, Fiberglass, P/c with ssl,	
2"o.d. x 1-1/2"wall	$14.10
2-1/2"o.d. x 1-1/2"wall	14.80
1/2"o.d. x 2"wall	12.95
3/4"o.d. x 2"wall	14.20
1"o.d. x 2"wall	14.85
1-1/4"o.d. x 2"wall	15.48
1-1/2"o.d. x 2"wall	16.47
2"o.d. x 2"wall	17.54
2-1/2"o.d. x 2"wall	18.60
Insulation, Pipe, Rubber, Closed cell foam,	
3/8"o.d. x 3/8"wall	6.73
1/2"o.d. x 3/8"wal	7.14
5/8"o.d. x 3/8"wall	7.44
3/4"o.d. x 3/8"wall	7.63
7/8"o.d. x 3/8"wall	7.91
1-1/8"o.d. x 3/8"wall	8.33
1-3/8"o.d. x 3/8"wall	8.70
1-5/8"o.d. x 3/8"wall	9.33
2-1/8"o.d. x 3/8"wall	10.35
3/8"o.d. x 1/2"wall	7.60
1/2"o.d. x 1/2"wall	8.00
5/8"o.d. x 1/2"wall	8.28
3/4"o.d. x 1/2"wall	8.43
7/8"o.d. x 1/2"wall	8.68
1-1/8"o.d. x 1/2"wall	9.16
1-3/8"o.d. x 1/2"wall	9.63
1-5/8"o.d. x 1/2"wall	10.30
2-1/8"o.d. x 1/2"wall	11.75
2-3/8"o.d. x 1/2"wall	13.00
2-5/8"o.d. x 1/2"wall	13.85
3-1/8"o.d. x 1/2"wall	15.40
3-1/2"o.d. x 1/2"wall	16.15
4-1/8"o.d. x 1/2"wall	19.65
4-1/2.d. x 1/2"wall	20.70
5/8"o.d. x 3/4"wall	9.34
7/8"o.d. x 3/4"wall	10.20
1-1/8"o.d. x 3/4"wall	11.60
1-3/8"o.d. x 3/4"wall	12.45
1-5/8"o.d. x 3/4"wall	14.60
2-1/8"o.d. x 3/4"wall	16.70
5/8"o.d. x 1"wall	12.50
7/8"o.d. x 1"wall	14.85
1-1/8"o.d. x 1"wall	16.65
1-3/8"o.d. x 1"wall	18.30
1-5/8"o.d. x 1"wall	19.95
2-1/8"o.d. x 1"wall	23.15
Pipe fitting cover, Insulated, Pvc, Ips, 90 degree elbow, #2,	
3/8"o.d. x 1/2"wall	10.80
1/2"o.d. x 1/2"wall	11.10
3"o.d. x 1/2"wall	17.45
3-1/2"o.d. x 1/2"wall	18.60
4"o.d. x 1/2"wall	20.45

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

Costs Each

Pipe fitting cover, Insulated, Pvc, Ips, 45 degree elbow, #2,

3/8”o.d. x 1/2”wall	$10.80
1/2”o.d. x 1/2”wall	11.10
3”o.d. x 1/2”wall	17.45
3-1/2”o.d. x 1/2”wall	18.60
4”o.d. x 1/2”wall	20.45

Pipe fitting cover, Insulated, Pvc, Ips, 45 or 90 degree elbow, #4,

3/4”o.d. x 1/2”wall	11.50
1”o.d. x 1/2”wall	11.75
1-1/4”o.d. x 1/2”wall	12.25
1-1/2”o.d. x 1/2”wall	12.70
2”o.d. x 1/2”wall	14.00
2-1/2”o.d. x 1/2”wall	15.60
5”o.d. x 1/2”wall	29.00
6”o.d. x 1/2”wall	34.75
7”o.d. x 1/2”wall	39.50
8”o.d. x 1/2”wall	50.00
9”o.d. x 1/2”wall	57.00
10”o.d. x 1/2”wall	63.00
11”o.d. x 1/2”wall	78.50

Pipe fitting cover, Insulated, Pvc, Ips, Tee, #2,

3/8”o.d. x 1/2”wall	16.15
1/2”o.d. x 1/2”wall	16.40
3/4”o.d. x 1/2”wall	17.30
1”o.d. x 1/2”wall	17.70
1-1/4”o.d. x 1/2”wall	19.10
1-1/2”o.d. x 1/2”wall	19.50
2”o.d. x 1/2”wall	21.25
2-1/2”o.d. x 1/2”wall	23.55
3”o.d. x 1/2”wall	25.75
3-1/2”o.d. x 1/2”wall	27.75
4”o.d. x 1/2”wall	32.00
5”o.d. x 1/2”wall	41.50
6”o.d. x 1/2”wall	66.00
7”o.d. x 1/2”wall	71.50
8”o.d. x 1/2”wall	91.50
9”o.d. x 1/2”wall	98.00
10”o.d. x 1/2”wall	108.00
11”o.d. x 1/2”wall	123.00

Pipe fitting cover, Insulated, Pvc, Ips, Mechanical groove, 90 degree elbow,

2”o.d.	34.00
2-1/2”o.d.	35.50
3”o.d.	42.50
4”o.d.	51.00
5”o.d.	60.00
6”o.d.	74.50
8”o.d.	93.50
10”o.d.	123.00
12”o.d.	196.00

Costs Each

Pipe fitting cover, Insulated, Pvc, Ips, Mechanical groove, 45 degree elbow, #9,

2”o.d.	$32.75
2-1/2”o.d.	33.50
3”o.d.	41.25
4”o.d.	50.00
5”o.d.	58.00
6”o.d.	70.50
8”o.d.	89.50
10”o.d.	113.00
12”o.d.	162.00

Pipe fitting cover, Insulated, Pvc, Ips, Mechanical groove, Tee,

2”o.d.	54.00
2-1/2”o.d.	58.00
3”o.d.	65.00
4”o.d.	88.50
5”o.d.	98.00
6”o.d.	123.00
8”o.d.	142.00
10”o.d.	182.00
12”o.d.	226.00

Costs/Lin. Ft.

Pipe cover, Jacket, Pvc, Ips, Cc with ssl,

1”o.d.	7.95
2”o.d.	8.86
3”o.d.	9.81
4”o.d.	11.15
1-1/2”o.d.	8.40
2-1/2”o.d.	9.22
3-1/2”o.d.	10.40
4-1/2”o.d.	11.75
4-3/4”o.d.	12.45
5-1/2”o.d.	12.75
5-3/4”o.d.	13.25
6-1/2”o.d.	14.00
6-3/4”o.d.	14.85
7-1/4”o.d.	15.90
8-1/2”o.d.	16.50
8-3/4”o.d.	17.30

Pipe cover, Jacket, Aluminum, Ips, Cc with ssl, Smooth, 16mil,

1-1/2”o.d.	8.43
2”o.d.	9.07
2-1/2”o.d.	9.55
3”o.d.	10.05
3-1/2”o.d.	10.65
4”o.d.	11.25
4-1/2”o.d.	12.05
5-1/2”o.d.	13.05
7”o.d.	14.55
8”o.d.	15.55
9”o.d.	16.70
10”o.d.	17.75
11”o.d.	18.85

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

Costs/Lin. Ft.

Pipe cover, Jacket, Aluminum, Ips, Cc with ssl, Smooth, 16mil,	
12”o.d.	$20.10
13”o.d.	21.25
15”o.d.	22.85
15-1/2”o.d.	23.85
Pipe cover, Jacket, Aluminum, Ips, Cc with ssl, Stucco embossed, 16mil,	
1-1/2”o.d.	8.49
2”o.d.	9.17
2-1/2”o.d.	9.59
3”o.d.	10.20
3-1/2”o.d.	10.75
4”o.d.	11.40
4-1/2”o.d.	12.20
5-1/2”o.d.	13.25
7”o.d.	14.75
8”o.d.	15.80
9”o.d.	17.00
10”o.d.	18.05
11”o.d.	19.15
12”o.d.	20.45
13”o.d.	21.60
15”o.d.	23.20
15-1/2”o.d.	24.25
Pipe cover, Jacket, Aluminum, Ips, Cc with ssl, Smooth, 20mil,	
1-1/2”o.d.	8.91
2”o.d.	9.63
2-1/2”o.d.	10.15
3”o.d.	10.75
3-1/2”o.d.	11.40
4”o.d.	12.10
4-1/2”o.d.	13.00
5-1/2”o.d.	14.20
7”o.d.	15.80
8”o.d.	16.95
9”o.d.	18.20
10”o.d.	19.45
11”o.d.	20.60
12”o.d.	22.10
13”o.d.	23.35
15”o.d.	25.00
15-1/2”o.d.	26.25
Pipe cover, Jacket, Aluminum, Ips, Cc with ssl, Stucco embossed, 20mil,	
1-1/2”o.d.	8.99
2”o.d.	9.76
2-1/2”o.d.	10.30
3”o.d.	10.90
3-1/2”o.d.	11.55
4”o.d.	12.25
4-1/2”o.d.	13.20
5-1/2”o.d.	14.40
7”o.d.	16.00

Costs/Lin. Ft.

Pipe cover, Jacket, Aluminum, Ips, Cc with ssl, Stucco embossed, 20mil,	
8”o.d.	$17.20
9”o.d.	18.50
10”o.d.	19.80
11”o.d.	20.95
12”o.d.	22.45
13”o.d.	23.75
15”o.d.	25.50
15-1/2”o.d.	26.75

Costs Each

Pipe fitting cover, Insulated, Aluminum, Ips, 90 degree elbow,	
1-1/2”o.d.	16.25
2”o.d.	17.25
2-1/2”o.d.	18.95
3”o.d.	19.70
3-1/2”o.d.	21.70
4”o.d.	24.05
4-1/2”o.d.	27.75
5-1/2”o.d.	35.75
7”o.d.	39.75
8”o.d.	43.25
9”o.d.	54.00
10”o.d.	55.00
11”o.d.	64.00
12”o.d.	81.50
13”o.d.	84.50
13-1/2”o.d.	98.00
14"o.d.	103.00
Pipe fitting cover, Insulated, Aluminum, Ips, 45 degree elbow,	
1-1/2”o.d.	16.00
2”o.d.	16.95
2-1/2”o.d.	17.80
3”o.d.	19.35
3-1/2”o.d.	20.25
4”o.d.	21.45
4-1/2”o.d.	23.95
5-1/2”o.d.	30.25
7”o.d.	33.25
8”o.d.	38.50
9”o.d.	43.75
10”o.d.	51.00
11”o.d.	57.00
12”o.d.	64.00
13”o.d.	70.50
13-1/2”o.d.	87.50
14"o.d.	94.50
Pipe fitting cover, Insulated, Aluminum, Ips, Tee,	
1-1/2”o.d.	46.50
2”o.d.	47.00
2-1/2”o.d.	47.50
3”o.d.	48.00
3-1/2”o.d.	48.50
4”o.d.	49.00
4-1/2”o.d.	51.00

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

PLUMBING & FIXTURES (CONT.)

Costs Each

Pipe fitting cover, Insulated, Aluminum, Ips, Tee,

5-1/2”o.d..	$58.00
7”o.d..	61.00
8”o.d..	63.00
9”o.d..	70.50
10”o.d..	72.50
11”o.d..	74.50
12”o.d..	77.50
13”o.d..	80.50
13-1/2”o.d..	91.50
14"o.d..	93.50

Costs/Lin. Ft.

Insulation, Pipe, Polyethylene, P/c with ssl,

3/8”o.d. x 3/8”wall.	6.16
1/2”o.d. x 3/8”wal.	6.48
3/4”o.d. x 3/8”wall.	6.90
1”o.d. x 3/8”wall.	7.36
1-3/4”o.d. x 3/8”wall.	8.79
1/4”o.d. x 1/2”wall.	6.67
3/8”o.d. x 1/2”wall.	6.98
1/2”o.d. x 1/2”wall.	7.39
3/4”o.d. x 1/2”wall.	7.85
1”o.d. x 1/2”wall.	8.30
1-3/4”o.d. x 1/2”wall.	8.89
1-1/4”o.d. x 1/2”wall.	10.10
2”o.d. x 1/2”wall.	10.55
2-1/4”o.d. x 1/2”wall.	11.30
2-3/4”o.d. x 1/2”wall.	12.80
3/8”o.d. x 3/4”wall.	8.09
1/2”o.d. x 3/4”wall.	8.68
3/4”o.d. x 3/4”wall.	9.54
1”o.d. x 3/4”wall.	10.30
1-1/4”o.d. x 3/4”wall.	11.90
1-3/4”o.d. x 3/4”wall.	13.90

Pipe Insulation - Fiberglass Wrap,

1/2” pipe.	5.44
3/4” pipe.	5.79
1” pipe.	6.14
1-1/2” pipe.	6.68

HVAC

This area focuses on the efficient use of energy for habitant comfort as it pertains to climate control of a building. Typically items covered may include Minimum Energy Performance, On-site Renewable Energy and Fundamental Refrigerant Management.

Costs Each

High efficiency gas furnace, Forced air,

With single stage burner, 92% AFUE, 45 MBH.	$2575.00
With 2 stage burner, 95% AFUE,70 MBH.	2750.00
With 2 stage burner, Variable speed blower, 95% AFUE, 115 MBH.	4575.00

Costs Each

Heat pump, Geothermal, Forced air, Heat and cooling,

2.5 tons.	8200.00
3 tons.	8350.00
4 tons.	9000.00
5 tons.	9550.00

Heat pump, Geothermal, Hydronic, Heat and cooling,

2.5 tons.	10100.00
3 tons.	10300.00
4 tons.	12100.00
5 tons.	13600.00
6 tons.	16300.00

Heat pump, Geothermal, Hybrid, Hydronic and forced air, Heating and cooling,

3 tons.	14900.00
4 tons.	16800.00
5 tons.	18400.00
6 tons.	21000.00

Geothermal, Horizontal ground loop system, With tubing and heat transfer fluid,

3 tons.	8450.00
4 tons.	10500.00
5 tons.	12900.00
6 tons.	14700.00

Costs/Sq. Ft.

Radiant floor, Sub-floor, With heat transfer plates, Circulating pump, Brass manifolds,

3/4” id BPex tubing at 8’’ o.c..	9.16

With aluminum covered grooved OSB panels,

1/2” id BPex tubing at 8’’ o.c..	10.75

Embedded, Light weight concrete,

3/4” id BPex tubing, 12’’ o.c..	10.75

4” concrete, 2” polystyrene insulation,

3/4” id BPex tubing, 12’’ o.c..	13.80

Costs Each

Heat recovery ventilator, 4 port, 56 Max CFM,

18-1/2”x 17-1/4”x 10-1/2”.	1420.00

4 port, 160 Max CFM, 3 speed,

28”x 17-1/2”x 25-1/2”.	2140.00

4 port, 240 Max CFM, 3 speed,

28”x 20-1/2”x 25-1/2”.	3575.00

Combination exhaust fan, With 2- 18W compact fluorescent bulbs, Ceiling mounted, Low profile housing,

80 CFM, 25 Watts, 13” x 13”.	275.00
80 CFM, 25 Watts.	304.00
110 CFM, 36 Watts.	329.00

Combination exhaust fan, With 26W compact fluorescent bulb, Ceiling mounted, Perimeter grill,

110 CFM, 13” x 13”.	373.00
150 CFM.	491.00

Fan, Exhaust, Ceiling mounted, Wall timer, Low profile housing, With 2- 18W compact fluorescent bulbs,

80 CFM, 25 Watts, 13” x 13”.	339.00

Fan, Exhaust, Ceiling mounted, Humidity sensor,

130CFM, 90 Watts.	265.00

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREEN ADDITIONS

HVAC (CONT.)

Costs Each

Attic fan, Roof mounted, Solar powered, With thermostat switch,
- 10 watt, 850 CFM. $820.00
- 1200 CFM, 20 Watts. 1170.00

Attic fan, Gable mounted, Solar powered, With thermostat switch,
- 10 watt, 850 CFM. 765.00
- 1275 CFM, 20 Watts. 1100.00

ELECTRICAL LIGHTING

Costs Each

Floodlight, Exterior solar powered, Motion/Photo-cell activated, With photovoltaic panel and 4V battery, 2 - 3W LED conical heads, Cast aluminum housing,
- 8” x 9” x 6-3/4”H. $157.00

6V battery, Plastic housing, 80 LED,
- 7-7/8” x 7-3/4” x 8-5/8”H. 211.00

6V battery, Plastic housing, 30 watt,
- 8”x 7-3/4”x 9”H. 265.00

Light fixture, Wall mounted, Automatic dusk-to-dawn, With photovoltaic module and battery, 8 LEDs, Aluminum housing, Beveled glass,
- 6-7/8”x 13”H. 280.00

Light fixture, Ceiling mounted, Vandal resistant, Motion sensor, With photovoltaic module and battery, 11 watt compact fluorescent, Aluminum housing,
- 8”x 8”x 8”H. 1030.00

EXTERIOR IMPROVEMENTS

Exterior improvements are items typically independent of the building itself, such as equipment associated with Public Transportation Access, Bicycle Storage, Restoration of Habitat, Stormwater Quantity & Quality Control, Non-Roof heat Island Effect and Water Efficient Landscaping.

PERMEABLE/POROUS PAVING

Costs/Sq. Ft.

Paving, Reclaimed Brick, With 2” sand bed,
- 4”x 8”x 2-1/4”. 18.05
- Herringbone pattern. 21.85

Paving, Reclaimed, Granite, With 2” sand bed, Random,
- 4”x 6” to 6”x 10”. 25.00
- Herringbone pattern. 29.00

Permeable pavers, interlocking, 2”gravel base and fill,
- precast concrete. 17.30
- L-shaped, precast concrete. 15.65
- Turf block, 8 open cells, precast concrete. 12.30

DRIP IRRIGATION

Costs Each

Drip irrigation, Micro sprayer kit,
- Small lawn, Up to 450 sf. $187.00
- Medium lawn, Up to 675 sf. 260.00
- Large lawn, Up to 900 sf. 388.00

System timer, Hose end, Electronic,
- Single station. 48.50
- Digital dial, Dual station. 71.50
- Digital programmable, Multi station. 80.50

IRRIGATION WEATHER SENSOR

Costs Each

Irrigation control, Rain/Freeze sensor,
- Wireless. 137.00

Rain/solar/freeze sensor, Automatic seasonal
- adjustment, With 40 ft wiring. 147.00

Sensor, Mini weather station, Automatic seasonal
- adjustment. 304.00

RAINWATER HARVESTING SYSTEM

Costs Each

Rain barrel, Brass spigot,
- 54 gallon. 383.00

Rain barrel, Recycled wood, Brass hose bib,
- 55 gallon. 780.00

Stained,
- 55 gallon. 1070.00

Rainwater storage tank, Recycled plastic, Modular,
- 50 gallon. 845.00

PLANT PREP-MULCH

Costs/Sq. Ft.

Mulch, Straw, Hand spread, 1” deep. 2.00
- Bark, Mixed hardwood. 6.49
- Bark, Pine mini nuggets. 7.95
- Bark, Aromatic red cedar. 9.76

GROUND COVER AND VINES (NO PREP)

Costs Each

Ground Cover, Standard pot,
- Euonymus fortunei. 6.54
- Vinca major. 13.45
- Kamtschaticum. 12.45

Xeriscape, Drought resistant, Potted, Plant ready, Sedum,
- 2” pot. 6.34
- 4” pot. 8.33
- 1 gallon. 11.05
- 24 plug tray. 118.00

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREEN ADDITIONS

EXTERIOR IMPROVEMENTS

SHRUBS AND TREES

Costs Each

Tree, Evergreen, Potted,	
DeGroot's spire, 5 gal, 1-2' tall.	$128.00
DeGroot's spire, 10 gal, 2-3' tall.	206.00
Fir, 15 gal, 4-5' tall.	260.00
Fir, 5-6' tall.	550.00
Fir, 6-7' tall.	745.00
Juniper spartan, 15 gal, 4-5' tall.	403.00
Pine, Austrian, 15 gal, 4-5' tall.	275.00
Pine, Austrian, 5-6' tall.	339.00
Pine, Austrian, 6-7' tall.	595.00
Adler, 15 gal, 2-3' tall.	309.00
Ash autumn purple, 15 gal, 2-3' tall.	270.00
Ash marshall, 15 gal, 2-3' tall.	250.00
Hawthorn, 15 gal, 2-3' tall.	290.00
Maple, 15 gal, 2-3' tall.	290.00
Oak, 15 gal, 4-5' tall.	319.00
Willow weeping, 15 gal, 4-5' tall.	280.00

PLANTING ACCESSORIES

Costs Each

Planter box, Recycled plastic, White, 12" long.	295.00
Cedar, 17" long.	373.00
Planter box, Recycled plastic lumber,	
Small, 19" x 19" x 17".	300.00
Large, 24" x 24" x 19".	373.00

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.