JAILS - CORRECTIONAL FACILITIES



GOOD CLASS A-B



GOOD CLASS C

OCCUPANCY DESCRIPTION: These are buildings used for the detention of people either awaiting trial or for convicted offenders serving sentences for law violations. They include a complete plant, from minimum to maximum security facilities, commensurate with the level. Divided into individual cells, most jails are built of steel frame, reinforced concrete or masonry.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with and jail hardware.

NOT INCLUDED IN COSTS: Sprinklers, parking equipment or balconies.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 639.50	Best brick, stone, architectural concrete, good ornamentation	Plaster, vinyl wall coverings, acoustic tile, terrazzo, vinyl tile	Best lighting and plumbing, maximum security	Hot and chilled water (zoned)
	Good	470.50	Concrete, limestone, granite, some ornamentation	Plaster or drywall, ceramic tile, acoustic tile, and asphalt tile	Good lighting, plumbing and security	Warm and cool air (zoned)
	Average	351.50	Concrete, limestone, granite, little ornamentation	Painted concrete, some plaster, acoustic tile, and asphalt tile	Adequate lighting and plumbing	Heat pump system
C	Excellent	522.00	Face brick, stone, architectural concrete, good ornamentation	Plaster or drywall, ceramic tile, acoustic tile and vinyl	Best lighting and security, good plumbing	Hot and chilled water (zoned)
	Good	384.50	Heavy stone or brick masonry, some ornamentation	Plaster and acoustic tile, vinyl and ceramic floors	Good lighting and plumbing	Warm and cool air (zoned)
	Average	289.50	Block or brick, concrete, some ornamentation on front	Painted walls, few partitions, some acoustic and vinyl composition	Adequate lighting and plumbing	Heat pump system
	Low cost	217.50	Block, tilt-up, very plain	Unfinished walls and floors, low-cost ceilings	Minimum jail plumbing and lighting, minimum security	Hot water
D	Excellent	484.50	Best siding, EIFS, face brick or stone veneer, good entrance	Plaster or drywall, ceramic tile, acoustic tile and vinyl	Best lighting and security, good plumbing for detention housing	Warm and cool air (zoned)
	Good	363.50	Brick veneer, best stucco or siding with good trim	Plaster and acoustic tile, vinyl and ceramic floors	Good lighting and plumbing	Heat pump system
	Average	268.50	Brick veneer, good stucco or siding with brick trim	Drywall, few partitions, slabs, some acoustic and vinyl composition	Adequate lighting and plumbing for camp-dormitory type	Package A.C.
S	Average	266.00	Pre-engineered sandwich panels, metal liner	Metal walls, acoustic tile or liner panel ceiling, slabs, some asphalt tile	Adequate lighting and plumbing for camp-dormitory type	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

JAILS - CORRECTIONAL FACILITIES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 68,000 to $ 112,000.

ELEVATOR STOPS: For basements stops, add $9,400 to $14,400 per stop.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99
75,000	3.39	4.20	5.22	6.46
100,000	3.27	4.01	4.96	6.13

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$2,950 to $3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	200	250	300	400	500	600	700	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
3,000	-----	.975	1.018	1.061	1.105	1.191	-----	-----	-----	-----	-----	-----	-----	-----	**3,000**
5,000	-----	-----	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	.926	.942	.975	1.007	1.040	1.072	1.105	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	1.105	1.155	-----	-----	**10,000**
14,000	-----	-----	-----	-----	.900	.920	.938	.956	.975	.993	1.030	1.067	1.105	1.140	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.910	.923	.936	.949	.975	1.000	1.027	1.052	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.897	.908	.918	.928	.948	.969	.990	1.011	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.897	.906	.915	.932	.949	.965	.983	**30,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	.928	**50,000**
75,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.873	.879	.885	.892	.900	**75,000**
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.866	.871	.876	.881	.887	**100,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

JAILS - POLICE STATIONS



EXCELLENT CLASS A-B



GOOD CLASS C

OCCUPANCY DESCRIPTION: Police stations are basically law enforcement facilities with a limited number of jail cells. Secured entry facilities consistent with the quality are included.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit and jail hardware.

NOT INCLUDED IN COSTS: Sprinklers, parking equipment or balconies.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 429.50	Best brick, stone, architectural concrete, good lobby	Plaster, vinyl wall coverings, acoustic tile, terrazzo, vinyl tile, good detail	Best lighting, plumbing and security, major command center	Hot and chilled water (zoned)
	Good	324.50	Best block, concrete, masonry and glass, some ornamentation	Plaster or drywall, ceramic tile, acoustic tile, carpet and asphalt tile	Good lighting, plumbing, security for law enforcement center	Warm and cool air (zoned)
	Average	258.50	Brick, precast concrete, good block, some trim	Plaster or drywall, ceramic tile, acoustic tile, and asphalt tile, good concrete	Good lighting, plumbing, security and sallyport, good holding facility	Warm and cool air (zoned)
	Low cost	201.50	Precast concrete, block, very plain	Painted concrete, some plaster, acoustic tile, and asphalt tile, slab	Adequate lighting and plumbing, some extras, holding cells	Heat pump system
C	Excellent	363.50	Face brick, stone, architectural concrete, glass, good lobby	Plaster, paneling, carpet and terrazzo, suspended ceilings, best administrative	Good lighting, plumbing, security for law enforcement center	Warm and cool air (zoned)
	Good	275.00	Heavy stone or brick masonry, some ornamentation	Plaster and acoustic tile, vinyl and ceramic floors, good slab	Good lighting, plumbing, security and sallyport, good holding facility	Heat pump system
	Average	206.00	Block or brick, concrete, some ornamentation on front	Painted walls, few partitions, some acoustic and vinyl composition, slab	Adequate lighting and plumbing, some extras, holding cells	Package A.C.
	Low cost	153.50	Block, tilt-up, very plain	Unfinished walls and floors, low-cost ceilings and floors in public areas	Minimum plumbing and lighting, minimum administrative and cells	Forced air
D	Excellent	347.00	Face brick or stone veneer, metal and glass, good lobby	Plaster, paneling, carpet and terrazzo, suspended ceilings, best administrative	Good lighting, plumbing, security for law enforcement center	Warm and cool air (zoned)
	Good	263.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, vinyl composition, carpet, good slab	Good lighting, plumbing, security and sallyport, good holding facility	Heat pump system
	Average	197.00	Wood frame or pipe columns, good stucco or siding with some trim	Painted walls, acoustic tile or drywall ceilings, some asphalt tile, slab	Adequate lighting and plumbing, some extras, holding cells	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

JAILS - POLICE STATIONS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 68,000 to $ 112,000.

ELEVATOR STOPS: For basements stops, add $9,400 to $14,400 per stop.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99
75,000	3.39	4.20	5.22	6.46
100,000	3.27	4.01	4.96	6.13

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$2,950 to $3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.; over 30, add .4% (4/10%) for each additional story.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	200	250	300	400	500	600	700	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
3,000	-----	.975	1.018	1.061	1.105	1.191	-----	-----	-----	-----	-----	-----	-----	-----	**3,000**
5,000	-----	-----	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	.926	.942	.975	1.007	1.040	1.072	1.105	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	1.105	1.155	-----	-----	**10,000**
14,000	-----	-----	-----	-----	.900	.920	.938	.956	.975	.993	1.030	1.067	1.105	1.140	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.910	.923	.936	.949	.975	1.000	1.027	1.052	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.897	.908	.918	.928	.948	.969	.990	1.011	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.897	.906	.915	.932	.949	.965	.983	**30,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	.928	**50,000**
75,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.873	.879	.885	.892	.900	**75,000**
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.866	.871	.876	.881	.887	**100,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

KENNELS



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: This occupancy is predominantly for the boarding of small animals, and has limited examination and treatment facilities. The better qualities include the large animal control facilities and the high cost pet hotels and salons.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit, cages and enclosed runs.

NOT INCLUDED IN COSTS: Sprinklers, canopies or outdoor runs.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$333.50	Face brick, stone or concrete, metal and glass, good lobby and trim	Plaster, carpet, glazed and epoxy finishes, indoor exercise facilities	Good electrical and plumbing, best pet hotel and salon	Warm and cool air (zoned)
	Very good	261.00	Face brick, block or concrete, good entrance and trim	Plaster, ceramic, glazed and epoxy finishes, indoor exercise facilities	Good lighting and plumbing, lab, better animal control facility	Warm and cool air (zoned)
	Good	189.50	Face brick, ornamental block, good trim and fenestration	Plaster or drywall, vinyl, good masonry kennels, large animal control type facility	Good lighting and plumbing, good locker, shower and restrooms	Package A.C.
	Average	141.00	Brick, partially finished interior, some trim	Plaster or drywall, some vinyl comp., cages & runs, low cost animal control type facility	Adequate lighting and plumbing, few extras, small restroom	Forced air
	Low cost	97.00	Block or tilt-up, plain entry	Drywall, small office, grooming, minimum cages and runs	Minimum lighting and plumbing	Wall furnace
	Cheap	68.50	Cheap block	Unfinished, workroom and runs only	Minimum services, good drains	None
D	Excellent	314.00	Good masonry veneer, metal and glass, best siding, EIFS, good lobby	Plaster, carpet, glazed and epoxy finishes, indoor exercise facilities	Good electrical and plumbing, best pet hotel and salon	Warm and cool air (zoned)
	Very good	245.50	Face brick or stone veneer, good entrance and trim	Plaster, ceramic, glazed and epoxy finishes, indoor exercise facilities	Good lighting and plumbing, lab, better animal control facility	Warm and cool air (zoned)
	Good	179.00	Good brick veneer, siding or stucco trim and fenestration	Plaster or drywall, vinyl, good masonry kennels, large animal control type facility	Good lighting and plumbing, good locker, shower, and restrooms	Package A.C.
	Average	132.00	Stucco or siding, brick trim or low-cost brick veneer	Plaster or drywall, some vinyl comp., cages & runs, low-cost animal control type facility	Adequate lighting and plumbing, few extras, small restroom	Forced air
	Low cost	90.50	Stucco or siding, finished interior	Drywall, small office, grooming, minimum cages and runs	Minimum lighting and plumbing	Wall furnace
	Cheap	63.50	Plywood or low-cost boards	Unfinished, workroom and runs only	Minimum services, good drains	None
D POLE	Average	125.50	Pole frame, metal siding, brick trim, insulated, finished interior, lobby	Drywall, some vinyl comp., cages and runs, low-cost animal control facility	Adequate lighting and plumbing, few extras, small restroom	Forced air
	Low cost	84.00	Pole frame, metal siding, plain entry	Drywall, small office, grooming, minimum cages and runs	Minimum lighting and plumbing	Wall furnace
	Cheap	57.50	Metal on light pole frame	Unfinished, workroom and runs only	Minimum services, good drains	None
S	Good	175.50	Insulated sandwich panels, good trim and fenestration	Plaster or drywall, vinyl, good masonry kennels, large animal control type facility	Good lighting and plumbing, good locker, shower, and restrooms	Package A.C.
	Average	129.50	Insulated sandwich panels or metal with finished interior, lobby	Drywall, vinyl composition, cages and runs, low-cost animal control type facility	Adequate lighting and plumbing, few extras, small restroom	Forced air
	Low cost	87.00	Metal on light frame, plain entry	Drywall, small office, grooming, minimum cages and runs	Minimum lighting and plumbing	Wall furnace
	Cheap	60.00	Steel siding and frame	Unfinished, workroom and runs only	Minimum services, good drains	None
CDS	Finished basement	83.50	Reinforced concrete or block, slab floor, painted, epoxy walls	Few partitions, some acoustic tile, VCT, average cages included	Adequate lighting and plumbing, work and storage rooms	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

KENNELS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

KENNEL CAGES AND RUNS: Costs of kennel caging are included in the base kennel building costs, with a typical range of $424 to $1,200 each allocated on gross building area is listed below. For outdoor runs, see Section UIP 16.

	Sq. Ft. Costs		
Good	$ 13.25	–	$ 16.00
Average	15.95	–	18.60
Low cost (Minimum)	19.35	–	21.55

CANOPIES:

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 39.00	$ 49.00	$ 60.00	$ 75.50
Light false-mansard	21.50	26.75	33.00	41.25
Steel frame	47.75	60.00	76.50	96.50
Light false-mansard	26.25	33.00	41.75	53.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.65	$ 8.65	$ 11.27	$ 14.66
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$ 2,950 to $ 3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$ 2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	14	1.046
9	.928	15	1.069
10	.953	16	1.092
11	.977	18	1.138
12	1.000 (base)	20	1.184
13	1.023		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	700	800	1000	1200	1400	Sq. Ft./Story
1,000	1.168	1.235	1.299	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	1.007	1.040	1.072	1.105	1.168	1.235	1.364	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	-----	.936	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	.932	.952	.975	1.018	1.061	1.105	1.146	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	-----	.926	.942	.975	1.007	1.040	1.072	1.105	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	1.105	1.155	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.910	.932	.952	.975	.997	1.018	1.061	1.105	1.146	**12,000**
14,000	-----	-----	-----	-----	-----	.900	.920	.938	.956	.975	.993	1.030	1.067	1.105	**14,000**
18,000	-----	-----	-----	-----	-----	-----	.903	.918	.932	.946	.960	.990	1.018	1.046	**18,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.910	.923	.936	.949	.975	1.000	1.027	**20,000**
25,000	-----	-----	-----	-----	-----	-----	-----	.897	.908	.918	.928	.948	.969	.990	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	-----	.897	.906	.915	.932	.949	.965	**30,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LABORATORIES



GOOD CLASS C

OCCUPANCY DESCRIPTION: Laboratories include commercial, research and development facilities exclusive of lab equipment. Interiors will have clean surfaces with good enamels, vinyls and glazed tiles and conductive flooring consistent with the level of quality. Costs include laboratory plumbing, electrical and cabinetry, but not fume hoods. The better qualities are highly ornamented with good offices, testing and research areas and numerous work stations.



AVERAGE CLASS C

Laboratories have higher requirements for heating, cooling and ventilation. Costs are included under complete H.V.A.C. systems.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, parking, balconies or laboratory equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$594.00	Stone, best brick, metal and glass, highly ornamental	Plaster, glazed finishes, enamel, tile, many workstations, support facilities	*Best lab plumbing and lighting, many extras	Complete H.V.A.C.
	Good	452.00	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl, good testing and research	*Good fluorescent fixtures, good lab stations and plumbing	Complete H.V.A.C.
	Average	343.00	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, VCT, carpet, good labs and support	*Adequate lighting and plumbing, some extra features	Complete H.V.A.C.
	Low cost	261.00	Brick, precast concrete, block, little trim	Low-cost finishes, acoustic tile, VCT, plain labs, production and offices	*Minimum lab lighting and plumbing, few extras	Complete H.V.A.C.
A-B	Lab basement	210.00	Reinforced concrete, plaster interior	R&D finish, administrative and technical facilities	Adequate lighting and plumbing for R&D facilities	Complete H.V.A.C.
C	Excellent	435.00	Steel frame, face brick, metal panels, tile, highly ornamental	Plaster, glazed finishes, enamel, tile, carpet, vinyl, good support facilities	*Best lab stations and plumbing, good lighting and outlets	Complete H.V.A.C.
	Good	337.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, vinyl or carpet, good research & development	Good fluorescent fixtures, lab stations and plumbing	Complete H.V.A.C.
	Average	264.00	Steel frame or bearing walls, brick, block, or concrete, some trim	Plaster or drywall, acoustic tile, VCT, adequate labs, support facilities	Adequate lighting, plumbing and workstations	Complete H.V.A.C.
	Low cost	207.50	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall, VCT, plain labs and offices	Minimum lab lighting and plumbing	Complete H.V.A.C.
D	Excellent	420.50	Steel or wood frame, brick or stone veneer, metal and glass, ornamental	Plaster, glazed finishes, enamel, tile, carpet, vinyl, good support facilities	*Best lab stations and plumbing, good lighting and outlets	Complete H.V.A.C.
	Good	325.00	Steel or glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, vinyl or carpet, good research & development	Good fluorescent fixtures, lab stations and plumbing	Complete H.V.A.C.
	Average	254.00	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, VCT, adequate labs, support facilities	Adequate lighting, plumbing and workstations	Complete H.V.A.C.
	Low cost	199.00	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, vinyl comp., plain labs, production and offices	Minimum lab lighting and plumbing	Complete H.V.A.C.
S	Good	327.00	Pre-engineered, good sandwich panels, some brick or stone	Plaster or drywall, acoustic tile, vinyl or carpet, good research & development	Good fluorescent fixtures, lab stations and plumbing	Complete H.V.A.C.
	Average	256.00	Pre-engineered, sandwich panels, some trim	Plaster or drywall, acoustic tile, VCT, adequate labs, support facilities	Adequate lighting, plumbing and workstations	Complete H.V.A.C.
	Low cost	201.00	Pre-engineered, finished interior, insulation	Drywall, acoustic tile, vinyl comp., plain labs, production and offices	Minimum lab lighting and plumbing	Complete H.V.A.C.
CDS†	Lab basement	154.50	Reinforced concrete, plaster or drywall interior	R&D finish, administrative and technical facilities	Adequate lighting and plumbing for R&D facilities	Complete H.V.A.C.

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.61 per square foot.
For Lab basements with Complete H.V.A.C., default is Low-quality.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LABORATORIES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Excellent	$ 5.92
Good	4.67
Average	3.77
Low cost	3.05

Classes C/D	Sq. Ft. Costs
Excellent	$ 5.92

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,700 to $14,600 per stop.

A small freight elevator with simple call system and push-button control, four-passenger cab and two or three stops, costs $66,500 to $109,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.16	$ 5.51	$ 7.28	$ 9.63
10,000	3.78	4.95	6.48	8.49
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
50,000	2.96	3.79	4.89	6.27
80,000	2.75	3.49	4.47	5.72
100,000	2.67	3.39	4.32	5.51
200,000	2.40	3.04	3.84	4.85
400,000	2.17	2.73	3.39	4.23

DOCK HEIGHT FLOORS: Add $2.39 to $9.03 per square foot to base cost of first floor.

For loading docks, see Page CAL 398.

2

LABORATORY HEATING, COOLING AND AIR CONDITIONING

The basement costs include low-quality complete H.V.A.C. These costs are averages of total installed cost of the entire heating or cooling installation including its prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated costs.

Classes A/B	Sq. Ft. Costs	Classes C/D/S	Sq. Ft. Costs
Excellent	$104.00	Excellent	$ 88.00
Good	80.50	Good	67.50
Average	61.50	Average	51.00
Low cost	46.50	Low cost	39.25

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.885	20	1.133
10	.921	22	1.181
12	.960	24	1.231
14	1.000 (base)	26	1.281
16	1.041	28	1.331
18	1.086	30	1.382

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	300	400	500	600	800	1000	1200	1400	1600	1800	2000	2200	2400	3000	Sq. Ft./Story
5,000	1.083	1.168	1.252	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	.996	1.040	1.083	1.168	-----	-----	-----	-----	-----	-----	-----	-----	-----	10,000
14,000	-----	.945	.977	1.008	1.071	1.132	-----	-----	-----	-----	-----	-----	-----	-----	14,000
20,000	-----	-----	.926	.949	.996	1.040	1.083	-----	-----	-----	-----	-----	-----	-----	20,000
25,000	-----	-----	.907	.924	.959	.996	1.032	1.066	-----	-----	-----	-----	-----	-----	25,000
30,000	-----	-----	-----	.907	.935	.965	.995	1.025	-----	-----	-----	-----	-----	-----	30,000
40,000	-----	-----	-----	-----	.907	.926	.949	.972	.995	1.019	-----	-----	-----	-----	40,000
50,000	-----	-----	-----	-----	.891	.907	.924	.942	.959	.977	.996	1.015	-----	-----	50,000
80,000	-----	-----	-----	-----	-----	.875	.887	.898	.907	.916	.926	.937	.949	.984	80,000
100,000	-----	-----	-----	-----	-----	.863	.872	.882	.891	.899	.907	.916	.924	.950	100,000
200,000	-----	-----	-----	-----	-----	-----	.846	.850	.855	.859	.863	.868	.873	.887	200,000
400,000	-----	-----	-----	-----	-----	-----	-----	-----	.835	.838	.841	.843	.846	.853	400,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LAUNDRIES/DRY CLEANERS



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These structures are designed for full-service laundry cleaning, including typical retail storefront and laundry work space commensurate with the quality level. Better qual ities have an area for a small amount of in house cleaning.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: The cost do not reflect the cost of a dry cleaning plant.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 157.50	Brick, stucco on block, best tilt-up, good front	Good store finish, carpet or vinyl, standard unfinished work area	Good lighting and outlets, adequate plumbing	Package A.C.
	Average	115.50	Brick, block, tilt-up, plain front, some ornamentation	Acoustic tile, vinyl composition in sales area, sealed concrete	Adequate store lighting, outlets and plumbing	Evaporative cooling
D	Good	147.50	Good stucco or siding, brick veneer, good front, ornamentation	Good store finish, carpet or vinyl, standard unfinished work area	Good lighting and outlets, adequate plumbing	Package A.C.
	Average	106.50	Stucco or siding, plain front	Finished sales, plain work area	Adequate lighting and plumbing	Evaporative cooling
S	Average	104.00	Metal panels, little ornamentation, plain front	Acoustic tile, vinyl composition in sales area, sealed concrete	Adequate store lighting, outlets and plumbing	Evaporative cooling
CDS	Storage basement	49.00	Painted interior	Painted ceiling and floors, few partitions	Exposed lighting, few outlets, drains	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LAUNDRIES/DRY CLEANERS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 36.25	$ 45.00	$ 56.00	$ 69.50
Light false-mansard	18.10	22.55	28.00	34.75
Steel frame	46.25	59.00	75.00	96.00
Light false-mansard	23.10	29.50	37.50	48.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$10.10	$13.05
2,000	5.43	6.95	8.88	11.35
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$2,300 to $3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	14	1.042
10	.957	15	1.064
11	.979	16	1.085
12	1.000 (base)	18	1.127
13	1.021	20	1.170

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	175	200	225	250	275	300	350	400	450	500	Sq. Ft./Story
500	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	500
1,000	1.079	1.183	1.283	1.376	1.470	1.566	1.660	1.753	-----	-----	-----	-----	-----	-----	1,000
1,500	.969	1.042	1.115	1.183	1.256	1.322	1.384	1.445	1.506	1.566	-----	-----	-----	-----	1,500
2,000	.912	.969	1.025	1.079	1.130	1.183	1.233	1.283	1.330	1.376	1.470	-----	-----	-----	2,000
2,500	.878	.924	.969	1.011	1.054	1.097	1.140	1.183	1.227	1.270	1.351	1.420	-----	-----	2,500
3,000	.854	.892	.931	.969	1.005	1.042	1.079	1.115	1.149	1.183	1.256	1.322	1.380	-----	3,000
3,500	-----	.873	.907	.941	.973	1.006	1.038	1.070	1.101	1.131	1.194	1.253	1.300	-----	3,500
4,000	-----	.854	.883	.912	.941	.969	.997	1.025	1.052	1.079	1.131	1.183	1.232	1.280	4,000
5,000	-----	-----	.854	.878	.901	.924	.947	.969	.990	1.011	1.054	1.097	1.140	1.183	5,000
6,000	-----	-----	-----	-----	.873	.892	.912	.931	.950	.969	1.005	1.042	1.079	1.115	6,000
7,000	-----	-----	-----	-----	-----	.870	.887	.904	.921	.937	.969	1.000	1.030	1.060	7,000
8,000	-----	-----	-----	-----	-----	-----	-----	.883	.898	.912	.941	.969	.997	1.025	8,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LAUNDROMATS



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: Structures built to hold automatic self-service washers, dryers and dry cleaning machines. Generally, these are large, open buildings with very little interior partitioning and with some countertop area. Floors are commonly resilient tile with ceilings of acoustical tile. Interiors are plain, with either painted plaster or drywall.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Plumbing and electrical facilities to operate washers and dryers.

NOT INCLUDED IN COSTS: Sprinklers, furnishings, laundry or cleaning machinery.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. Ft.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Average	$ 119.50	Brick, block, tilt-up, plain storefront	Plaster or drywall, acoustic tile, vinyl composition tile	Adequate lighting, outlets and plumbing	Space heaters
D	Average	109.50	Stucco or siding, plain storefront	Plaster, acoustic tile, little ornamentation, vinyl composition	Necessary electrical and plumbing outlets	Space heaters
D POLE	Average	103.00	Pole frame, metal panels, lined, plain front, little ornamentation	Acoustic tile, vinyl composition	Necessary electrical and plumbing outlets	Space heaters
S	Average	107.00	Insulated panels, little ornamentation, plain front	Acoustic tile, vinyl composition	Necessary electrical and plumbing outlets	Space heaters
CDS	Storage basement	49.00	Painted interior	Painted ceiling and floors, few partitions	Exposed lighting, few outlets, drains	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LAUNDROMATS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs. For laundry equipment see UIP 12, page 6.

1

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 36.25	$ 45.00	$ 56.00	$ 69.50
Light false-mansard	18.10	22.55	28.00	34.75
Steel frame	46.25	59.00	75.00	96.00
Light false-mansard	23.10	29.50	37.50	48.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	14	1.042
10	.957	15	1.064
11	.979	16	1.085
12	1.000 (base)	18	1.127
13	1.021	20	1.170

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	175	200	225	250	275	300	350	400	450	500	Sq. Ft./Story
500	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	500
1,000	1.079	1.183	1.283	1.376	1.470	1.566	1.660	1.753	-----	-----	-----	-----	-----	-----	1,000
1,500	.969	1.042	1.115	1.183	1.256	1.322	1.384	1.445	1.506	1.566	-----	-----	-----	-----	1,500
2,000	.912	.969	1.025	1.079	1.130	1.183	1.233	1.283	1.330	1.376	1.470	-----	-----	-----	2,000
2,500	.878	.924	.969	1.011	1.054	1.097	1.140	1.183	1.227	1.270	1.351	1.420	-----	-----	2,500
3,000	.854	.892	.931	.969	1.005	1.042	1.079	1.115	1.149	1.183	1.256	1.322	1.380	-----	3,000
3,500	-----	.873	.907	.941	.973	1.006	1.038	1.070	1.101	1.131	1.194	1.253	1.300	-----	3,500
4,000	-----	.854	.883	.912	.941	.969	.997	1.025	1.052	1.079	1.131	1.183	1.232	1.280	4,000
5,000	-----	-----	.854	.878	.901	.924	.947	.969	.990	1.011	1.054	1.097	1.140	1.183	5,000
6,000	-----	-----	-----	-----	.873	.892	.912	.931	.950	.969	1.005	1.042	1.079	1.115	6,000
7,000	-----	-----	-----	-----	-----	.870	.887	.904	.921	.937	.969	1.000	1.030	1.060	7,000
8,000	-----	-----	-----	-----	-----	-----	-----	.883	.898	.912	.941	.969	.997	1.025	8,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LIBRARIES - COLLEGE



EXCELLENT CLASS A-B



GOOD CLASS C

OCCUPANCY DESCRIPTION: This occupancy refers to structures used to provide books and services to meet the reading and research needs of colleges. Variations can be found in the design due primarily to the amount of service programs and the amount of students and faculty serviced by the center.

Typically, the college libraries can be subdivided into a number of different sections. Each library may not have all segments due to its design characteristics and services offered.

Commonly, there are control areas, staff work areas, reading areas, collection areas and restrooms in most libraries.

The better quality libraries may have, in addition to the sections specified, study cubicles, conference/meeting rooms, audiovisual facilities and various processing, cataloging and exhibiting areas for specialized studies, research or special collections.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Cabinets, counters, reader tables, book stacks and seating.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 479.00	Special architecture, metal and glass, marble, face brick, stone	Acoustical design, glazed finishes, enamel, vinyl, good media stations	*High-level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Good	374.00	Face brick, metal and glass, limestone, architectural concrete	Plaster or drywall, acoustic tile, carpet, vinyl and ceramic tiles	*High-level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Average	275.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or vinyl composition	*High-level lighting, TV circuits, adequate plumbing	Warm and cool air (zoned)
	Low cost	214.50	Brick, precast concrete, good block, some trim	Plaster or drywall, acoustic tile, hardwood or vinyl composition	Good lighting, adequate wiring and plumbing	Warm and cool air (zoned)
A-B	Finished basement	195.00	Finished interior, good waterproofing	Few partitions, acoustic tile, vinyl composition floors	High-level lighting, adequate wiring and plumbing	Warm and cool air (zoned)
	Mezzanine	119.00	Not included	Few partitions, plaster soffit	High-level lighting	In bldg. cost
C	Excellent	369.50	Special architecture, metal and glass, face brick, stone, concrete	Plaster, glazed finishes, enamel, carpet, vinyl, terrazzo or tile	High-level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Good	270.50	Face brick, metal and glass, limestone, architectural concrete	Plaster or drywall, acoustic tile, carpet, vinyl composition	High-level lighting, TV circuits, good plumbing	Warm and cool air (zoned)
	Average	209.50	Good brick, ornamental block, metal and glass, some trim	Plaster or drywall, acoustic tile, vinyl composition, some carpet	Good lighting, adequate wiring and plumbing	Heat pump system
	Low cost	153.50	Brick, block, tilt-up panels, little ornamentation	Painted walls, acoustic tile or drywall ceilings, asphalt tile, few extras	Adequate lighting, wiring and plumbing	Package A.C.
D	Excellent	359.00	Special architecture, best masonry veneer, metal and glass	Plaster, enamel, glazed or vinyl finishes, carpet, vinyl and tile	High-level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Good	261.50	Brick veneer, metal and glass, EIFS, good entrance and ornamentation	Plaster or drywall, acoustic tile, carpet, vinyl composition	High-level lighting, TV circuits, good plumbing	Warm and cool air (zoned)
	Average	200.50	Brick veneer, good stucco or siding with brick trim	Plaster or drywall, acoustic tile, vinyl composition, some carpet	Good lighting, adequate wiring and plumbing	Heat pump system
	Low cost	147.00	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, few extras	Adequate lighting, wiring and plumbing	Package A.C.
S	Good	255.50	Pre-engineered, good sandwich panels, some brick or stone trim	Plaster or drywall, acoustic tile, carpet, vinyl composition	High-level lighting, TV circuits, good plumbing	Warm and cool air (zoned)
	Average	196.00	Pre-engineered, sandwich panels, some ornamentation	Drywall, acoustic tile, vinyl composition, some carpet	Good lighting, adequate wiring and plumbing	Heat pump system
	Low cost	141.50	Pre-engineered, finished interior, insulation, little trim	Drywall, acoustic tile ceilings, asphalt tile, few extras	Adequate lighting, wiring and plumbing	Package A.C.
CDS	Finished basement	130.50	Finished interior, good waterproofing	Few partitions, acoustic tile, vinyl composition tile	High-level lighting, adequate wiring and plumbing	Forced air
	Mezzanine	87.00	Not included	Few partitions, plaster soffit	High-level lighting	In bldg. cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.59 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LIBRARIES - COLLEGE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Excellent	$ 8.89
Good	5.79
Average	3.72

LIBRARY EQUIPMENT: Typical cost of fixtures including book-stacks, cabinets, counters, reader tables, seating, etc., excluding extremes.

LOW	AVG.	GOOD	EXCL.
$19.20	$26.50	$37.00	$ 51.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LIBRARIES - MEDIA CENTER (K-12)



GOOD CLASS A-B

OCCUPANCY DESCRIPTION: This occupancy refers to structures used to provide books and services to meet the reading and media resource needs of elementary and secondary schools. Variations can be found in the design due primarily to the amount of service programs and the amount of students serviced by the center.

Typically, the school libraries can be subdivided into a number of different sections. Each resource center may not have all segments due to its design characteristics and services offered.

Commonly, there are: control, staff work, reading and collection areas. The better quality libraries may have, in addition to the sections specified: study cubicles, conference/meeting rooms, multi-media facilities and various processing, cataloging and exhibiting or presentation areas.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Cabinets, counters, reader tables, book stacks and seating.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 342.00	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet, vinyl and ceramic tile	High-level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Average	253.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or carpet	High-level lighting, good plumbing and media resource wiring	Warm and cool air (zoned)
	Low cost	199.50	Brick, precast concrete, block, very plain	Low-cost finishes, acoustic tile, hardwood or vinyl composition	Good lighting, adequate plumbing and media wiring	Heat pump system
C	Excellent	324.50	Steel frame, face brick, metal panels, tile, highly ornamental	Plaster, glazed finishes, enamel, carpet, vinyl and ceramic tile	High-level lighting, audio-visual wiring, good plumbing	Warm and cool air (zoned)
	Good	253.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, hardwood or carpet	High-level lighting, good plumbing and media resource wiring	Heat pump system
	Average	188.00	Steel frame or bearing walls, brick, block or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Good lighting, adequate plumbing and media wiring	Package A.C.
	Low cost	146.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Adequate lighting, plumbing and interactive wiring	Forced air
D	Excellent	316.50	Steel or wood frame, brick or stone veneer, metal and glass, ornamental	Plaster, enamel, glazed or vinyl finishes, carpet, vinyl and tile	High-level lighting, audio-visual wiring, good plumbing	Warm and cool air (zoned)
	Good	245.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, hardwood or carpet	High-level lighting, good plumbing and media resource wiring	Heat pump system
	Average	180.50	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Good lighting, adequate plumbing and media wiring	Package A.C.
	Low cost	138.50	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, linoleum or wood floors	Adequate lighting, plumbing and interactive wiring	Forced air
D POLE	Average	174.50	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, vinyl composition	Good lighting, adequate plumbing and media wiring	Package A.C.
	Low cost	132.50	Pole frame, good metal panels, finished inside, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Adequate lighting, plumbing and interactive wiring	Forced air
S	Good	241.50	Pre-engineered, good sandwich panels, some brick or stone trim	Drywall, acoustic tile, carpet, vinyl composition	High-level lighting, good plumbing and media resource wiring	Heat pump system
	Average	177.00	Pre-engineered, sandwich panels, some trim	Drywall, acoustic tile, vinyl composition	Good lighting, adequate plumbing and media wiring	Package A.C.
	Low cost	134.00	Pre-engineered, finished interior, insulation	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Adequate lighting, plumbing and interactive wiring	Forced air

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LIBRARIES - MEDIA CENTERS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

LIBRARY EQUIPMENT: Typical cost of fixtures including book-stacks, cabinets, counters, reader tables, seating, etc., excluding extremes.

LOW	AVG.	GOOD	EXCL.
$19.20	$26.50	$37.00	$ 51.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LIBRARIES - PUBLIC



EXCELLENT CLASS C

OCCUPANCY DESCRIPTION: This occupancy refers to structures used to provide books and services to meet the reading and research needs of a community. Variations can be found in the design, due primarily to the amount of service programs and the amount of people serviced by the library.

Typically, libraries can be subdivided into a number of different sections. Each library may not have all segments due to its design characteristics and services offered.

Commonly there are: control areas, staff work areas, reading areas, collection areas and restrooms in most libraries. The better quality libraries may have, in addition to the sections specified, study cubicles, conference/meeting rooms, audiovisual facilities and various processing, cataloging and exhibiting areas.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, parking or balconies.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 418.50	Special architecture, metal and glass, marble, face brick, stone	Plaster, carpeting, vinyl, typical large city library	*High-level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Average	309.00	Face brick, metal and glass, limestone, architectural concrete	Plaster or drywall, terrazzo and vinyl tile, typical main library	*High-level lighting, TV circuits, adequate plumbing	Warm and cool air (zoned)
B	Good	381.50	Special architecture, metal and glass, face brick, stone, concrete	Plaster, carpeting, vinyl, typical large city library	*High-level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Average	281.50	Face brick, metal and glass, limestone, architectural concrete	Plaster or drywall, terrazzo and vinyl tile, typical main library	*High-level lighting, TV circuits, adequate plumbing	Warm and cool air (zoned)
A-B	Finished Basement	209.00	Finished interior, good waterproofing	Few partitions, acoustic tile, vinyl composition floors	High-level lighting, adequate plumbing	Warm and cool air (zoned)
	Mezzanine	118.00	Not included	Few partitions, plaster soffit	High-level lighting	In bldg. cost
C	Excellent	469.50	Special architecture, metal and glass, face brick, stone, concrete	Best plaster, carpeting, vinyl, best large city library, sustainable construction	High-level lighting, best cabling systems, good plumbing	Hot and chilled water (zoned)
	Very good	373.00	Good architecture, metal and glass, face brick, stone, concrete	Best plaster, carpeting, vinyl, typical large city library	High-level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Good	280.50	Face brick, metal and glass, limestone, architectural concrete	Plaster or drywall, vinyl composition, typical small city	High-level lighting, good plumbing	Warm and cool air (zoned)
	Average	207.00	Good brick, ornamental block, metal and glass, some trim	Plaster or drywall, vinyl composition, typical neighborhood branch	Good lighting, adequate plumbing	Package A.C.
	Low cost	156.00	Brick, block, tilt-up, little ornamentation	Painted masonry, few partitions, acoustic tile, asphalt tile	Adequate lighting and plumbing	Forced air
D	Excellent	434.00	Special architecture, best masonry veneer, metal and glass	Best plaster, carpeting, vinyl, best large city library, sustainable construction	High level lighting, best cabling systems, good plumbing	Warm and cool air (zoned)
	Very good	340.00	Good architecture, best masonry veneer, metal and glass	Best plaster, carpeting, vinyl, typical large city library	High level lighting, audio-visual wiring, good plumbing	Warm and cool air (zoned)
	Good	268.50	Brick veneer, metal and glass, EIFS, good entrance and ornamentation	Plaster or drywall, vinyl composition, typical branch library	High level lighting, good plumbing	Warm and cool air (zoned)
	Average	197.00	Brick veneer, good stucco or siding with brick trim	Drywall, acoustic and asphalt tile, typical small branch library	Good lighting, adequate plumbing	Package A.C.
	Low cost	147.00	Stucco or siding, little trim, residential type windows	Drywall, asphalt tile, few extras	Adequate lighting and plumbing	Forced air
D POLE	Low cost	136.00	Pole frame, metal siding, fully lined and insulated	Drywall, asphalt tile, few extras	Adequate lighting and plumbing	Forced air
S	Good	258.50	Sandwich panels, brick veneer and good fenestration	Drywall or plaster walls and ceiling, branch library	High-level lighting, good plumbing	Warm and cool air (zoned)
	Average	189.50	Metal panels, gypsum or metal interior, insulated, some trim	Drywall, acoustic and asphalt tile, typical small branch library	Good lighting, adequate plumbing	Package A.C.
	Low cost	141.50	Metal panels, light insulation, plywood or gypsum interior	Drywall, asphalt tile, few extras	Adequate lighting and plumbing	Forced air
CDS†	Finished Basement	130.00	Finished interior, good waterproofing	Few partitions, acoustic tile, vinyl composition tile	High-level lighting, adequate plumbing	Forced air
	Mezzanine	85.50	Not included	Few partitions, acoustic tile	High-level lighting	In bldg. cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.54 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LIBRARIES - PUBLIC

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Good	$ 5.78
Average	3.38

ELEVATOR STOPS: For basements stops, add $9,400 to $14,400 per stop.

A small passenger elevator with simple call system and push button control, four passenger cab and two or three stops, costs $68,000 to $112,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99
75,000	3.39	4.20	5.22	6.46
100,000	3.27	4.01	4.96	6.13

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 41.00	$ 53.00	$ 69.00
Steel	29.75	40.50	55.00	75.50
Wood	25.25	33.75	45.00	60.00
Add for ornate finishes, balustrades	27.50	34.00	41.75	51.00
Add for roofs or awnings	15.20	20.15	26.75	35.75

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$2,950 to $3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	200	250	300	400	500	600	700	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
3,000	-----	.975	1.018	1.061	1.105	1.191	-----	-----	-----	-----	-----	-----	-----	-----	**3,000**
5,000	-----	-----	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	.926	.942	.975	1.007	1.040	1.072	1.105	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	1.105	1.155	-----	-----	**10,000**
14,000	-----	-----	-----	-----	.900	.920	.938	.956	.975	.993	1.030	1.067	1.105	1.140	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.910	.923	.936	.949	.975	1.000	1.027	1.052	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.897	.908	.918	.928	.948	.969	.990	1.011	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.897	.906	.915	.932	.949	.965	.983	**30,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	.928	**50,000**
75,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.873	.879	.885	.892	.900	**75,000**
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.866	.871	.876	.881	.887	**100,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LODGES



FAIR CLASS D

OCCUPANCY DESCRIPTION: Lodges are generally of rustic design with multiple sleeping units and lobby with some additional plumbing and kitchen facilities for the additional number of unrelated guests. The better qualities will include large formal dining and meeting rooms with one or more baths per guest room.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Fireplaces, elevators, balconies or porches, sprinklers, furnishings or service equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 288.00	Best adobe, cut stone, heavy roof structure, shakes, tile, slate	Plaster, ornamental detail, fine carpet, stone, parquet or plank	Some special fixtures, more than one bath per guestroom	Warm and cool air (zoned)
	Very good	244.00	Good adobe, stone, shakes or concrete tile roof on good structure	Very good plaster and detail, good-quality carpet or hardwood	Top quality standard fixtures, electrical and plumbing	Heat pump system
	Good	209.00	Local stone, brick or good block and stucco, shakes or wood shingles	Good plaster or drywall, some ornamentation, carpet or hardwood	Good lighting and outlets, one full bathroom per guestroom	Package A.C.
	Average	148.00	Brick or block, local field stone, wood or good asphalt shingle, elastomeric	Plaster or drywall, hardwood, vinyl composition, average carpet	Adequate lighting/plumbing for each sleeping room	Forced air
	Fair	126.50	Block or brick, standard sash, asphalt shingle or built-up roof	Drywall or tinted plaster, carpet, vinyl composition tile, good softwood	Adequate standard lighting and plumbing	Electric baseboard
	Low cost	104.00	Block or brick, asphalt shingle roof, few windows	Drywall, exposed block, vinyl composition tile, cheap hardwood	Minimum standard lighting and plumbing, cheap fixtures	Wall furnace
	Cheap	83.50	Cheap block or brick, composition roof, low-cost sash	Painted block, few partitions, asphalt tile on slab or softwood	Minimum, common baths	Electric wall heaters
D	Excellent	286.50	Half-timber, stone trim, rustic log, heavy rafters, slate, shakes	Plaster, ornamental detail, fine carpet, stone, parquet or plank	Some special fixtures, more than one bath per guestroom	Warm and cool air (zoned)
	Very good	241.50	Select logs, best siding, brick or stone trim, good shakes	Very good plaster and detail, good quality carpet or hardwood	Top quality standard fixtures, electrical and plumbing	Heat pump system
	Good	205.00	Good siding or log, light shakes or good shingles	Good plaster or drywall, some ornamentation, carpet or hardwood	Good lighting and outlets, one full bath per guestroom	Package A.C.
	Average	143.50	Log, stucco or siding, some trim, wood or good asphalt shingles	Plaster or drywall, hardwood, carpet, vinyl composition	Adequate lighting/plumbing for each sleeping room	Forced air
	Fair	121.00	Stucco or siding, standard sash, asphalt shingles or built-up rock	Drywall or plaster, carpet, vinyl composition tile, good softwood	Adequate standard lighting and plumbing	Electric baseboard
	Low cost	99.00	Low-cost log or siding, asphalt shingle roof, few windows	Drywall/tinted plaster, vinyl composition tile, cheap hardwood	Minimum standard lighting and plumbing, cheap fixtures	Wall furnace
	Cheap	79.00	Box frame or light studs, low-cost boards/siding, windows, comp. roof	Drywall, cheap ceiling or none, softwood or asphalt tile on slab	Minimum, common baths	Electric wall heaters
CD	Utility basement	34.25	Unfinished	Unfinished interior, few partitions	Minimum lighting and plumbing	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LODGES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Lodges with basements, add 40% to extend the foundation to the basement level. Custom oversized units can run 100% to 200% more.

TYPE	COST RANGE
One-story	$3,675 – $ 11,800
Two-stories	4,655 – 14,170
Three-stories	5,635 – 16,540

ELEVATORS: A small passenger or freight elevator with simple call system and push-button control, and two or three stops, costs $60,750 to $98,250. For detailed costs, see Section UIP 8

ELEVATOR STOPS: For basement stops, add $8,450 to $13,500 per stop.

SWIMMING POOLS: Swimming pools, complete, cost $ 90.00 to $129.00 per square foot. For detailed costs, see Section UIP 16.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 4.51	$ 5.78	$ 7.38	$ 9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL
Concrete	$ 31.75	$ 40.25	$ 51.00	$ 65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $ 2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$ 298 to $ 449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.91	11	1.03
8	.94	12	1.06
9	.97	13	1.09
10	1.000 (base)	14	1.12

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	250	300	350	400	450	500	550	600	700	800	900	1000	1100	1200	Sq. Ft./Story
4,000	0.989	1.021	1.052	1.083	1.113	1.143	1.175	1.206	1.268	1.329	-----	-----	-----	-----	4,000
6,000	0.938	0.959	0.980	1.000	1.021	1.042	1.063	1.083	1.123	1.165	1.206	1.247	1.288	1.329	6,000
8,000	0.913	0.929	0.944	0.959	0.974	0.989	1.005	1.021	1.052	1.083	1.113	1.143	1.175	1.206	8,000
10,000	-----	0.910	0.922	0.935	0.947	0.959	0.972	0.984	1.009	1.034	1.059	1.083	1.108	1.133	10,000
12,000	-----	-----	0.907	0.917	0.928	0.938	0.949	0.959	0.980	1.000	1.021	1.042	1.063	1.083	12,000
16,000	-----	-----	-----	0.898	0.906	0.913	0.921	0.929	0.944	0.959	0.974	0.989	1.005	1.021	16,000
20,000	-----	-----	-----	-----	-----	0.898	0.904	0.910	0.922	0.935	0.947	0.959	0.972	0.984	20,000
24,000	-----	-----	-----	-----	-----	0.886	0.891	0.896	0.907	0.917	0.928	0.938	0.949	0.959	24,000
28,000	-----	-----	-----	-----	-----	-----	-----	0.888	0.898	0.906	0.915	0.924	0.933	0.942	28,000
32,000	-----	-----	-----	-----	-----	-----	-----	0.882	0.889	0.898	0.906	0.913	0.921	0.928	32,000
36,000	-----	-----	-----	-----	-----	-----	-----	0.877	0.883	0.890	0.897	0.904	0.911	0.917	36,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	0.879	0.885	0.892	0.898	0.904	0.910	40,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LODGES – INNS AND COTTAGES



GOOD/EXCELLENT CLASS D



AVERAGE CLASS D

OCCUPANCY DESCRIPTION: Bed and breakfast inns are residential-type buildings designed for transient boarding and are more family style in character than lodges.

Guest cottages or cabins are individual sleeping bungalows without kitchen facilities. The lowest quality are camp facilities without plumbing, while the best resort types will contain luxury bathroom suites.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Fireplaces, built-in appliances, balconies or porches, sprinklers, furnishings or service equipment.

Costs given are for one-story units. For two-story units, deduct 4%; three-story, deduct 5%.

BED AND BREAKFAST INNS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 253.50	Fine masonry and windows, special architecture and trim	Fine interior detail, ceramic tile, carpet, paneling, fine hardwood	Good fixtures, many outlets, one full bath per bedroom	Heat pump system
	Good	192.00	Face brick, stucco, stone trim, good windows and architecture	Plaster or drywall, paneling, carpet or hardwood and sheet vinyl	Individual baths, large kitchen, good electrical fixtures	Package A.C.
	Average	140.50	Brick or block, some trim and entrance ornamentation	Plaster or drywall carpet, hardwood, vinyl composition, good dining area	Adequate lighting/plumbing, one bath per two bedrooms	Forced air
	Low cost	105.50	Concrete block and stucco, very plain, residential sash	Drywall, some carpet, asphalt tile, limited common area	Minimum quantity and quality, small residential kitchen	Electric baseboard
D	Excellent	249.00	Face brick or stone veneer, fine windows, special architecture	Fine interior detail, ceramic tile, carpet, paneling, fine hardwood	Good fixtures, many outlets, one full bath per bedroom	Heat pump system
	Good	185.00	Brick veneer, best stucco or siding, good windows and architecture	Plaster or drywall, paneling, carpet or hardwood and sheet vinyl	Individual baths, large kitchen, good electrical fixtures	Package A.C.
	Average	133.00	Brick veneer, good stucco or siding, some trim and entry ornament	Drywall, carpet, hardwood, vinyl composition, good dining area	Adequate lighting/plumbing, one bath per two bedrooms	Forced air
	Low cost	99.00	Stucco or siding, very plain, residential sash	Drywall, some carpet, asphalt tile, limited common area	Minimum quantity and quality, small residential kitchen	Electric baseboard

GUEST COTTAGES

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 265.00	Face brick, stone, best windows, heavy roof, tile, slate, metal	Plaster, paint, paper, paneling, fine hardwood, vinyl, carpet	Best lighting and plumbing, one bath per sleeping room	Package A.C.
	Good	204.00	Adobe, brick, some trim or good stucco, good roof and fenestration	Plaster or gypsum board, paint, paper, hardwood, vinyl composition, carpet	Good lighting and plumbing, one bath, some extras	Package A.C.
	Average	151.50	Brick, stucco on block, little trim, wood or good composition shingles	Gypsum board and paint, hardwood, vinyl composition, carpet	Adequate lighting and plumbing, one bath, standard fixtures	Forced air
	Fair	131.50	Block or brick, cheap fieldstone, asphalt shingles or built-up rock	Drywall, carpet, vinyl composition tile, few partitions	Standard bathroom fixtures	Electric baseboard
	Low cost	111.50	Block or cheap brick, low-cost roof and sash	Gypsum board and paint, asphalt tile, cheap hardwood	Minimum standard lighting and plumbing, low-cost fixtures	Wall furnace
D	Excellent	257.00	Best brick veneer, good stone trim, heavy roof, tile, slate, metal	Plaster, paint, paper, paneling, fine hardwood, vinyl, carpet	Best lighting and plumbing, one bath per sleeping room	Package A.C.
	Good	196.00	Siding, log or brick veneer, some ornamentation, good fenestration	Plaster or gypsum board, paint, paper, hardwood, vinyl composition, carpet	Good lighting and plumbing, one bath, some extras	Package A.C.
	Average	145.00	Stucco or siding, some trim, wood or good composition shingles	Plaster or drywall, hardwood, carpet, vinyl composition	Adequate lighting and plumbing, one bath, standard fixtures	Forced air
	Fair	125.00	Stucco or siding, standard sash, asphalt shingles or built-up	Drywall, carpet, vinyl composition tile, few partitions	Adequate standard lighting and bathroom fixtures	Electric baseboard
	Low cost	105.50	Stucco or siding, asphalt shingle roof, few windows	Drywall, vinyl composition tile, cheap hardwood	Minimum standard lighting and plumbing, low-cost fixtures	Wall furnace
	Cheap	66.00	Box frame or light studs, screening or cheap siding, windows, comp. roof	Drywall, cheap ceiling or none, softwood or asphalt tile on slab	Minimum electrical, no plumbing, seasonal use	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

LODGES – INNS AND COTTAGES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

KITCHENETTES: For units having kitchenettes or built-in kitchen units, add the following per unit:

Excellent (stove, refrigerator, sink & cabinet unit)	$ 7,500
Good	5,500
Average (cabinets and sink)	4,100
Low-Cost	3,050

BUILT-IN APPLIANCES: For individual listing, see Segregated costs, Section SEG 2.

	LOW	AVG	GOOD	EXCL
Allowance (if not itemized)	$1,820	$4,150	$7,550	$12,800

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Lodges with basements, add 40% to extend the foundation to the basement level. Custom oversized units can run 100% to 200% more.

TYPE	COST RANGE
One-story	$ 3,675 – $ 11,800
Two-stories	4,655 – 14,170
Three-stories	5,635 – 16,540

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
500	$ 5.34	$ 6.91	$ 8.94	$ 11.55
1,000	4.67	5.96	7.62	9.74
2,000	4.85	6.24	8.01	10.27
4,000	4.36	5.56	7.08	8.99
6,000	4.12	5.22	6.61	8.35

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL
Concrete	$ 31.75	$ 40.25	$ 51.00	$ 65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

CARPORTS: For complete listing of built-in, attached or detached garages, see Garages – Residential cost pages.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $ 2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$ 298 to $ 449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	11	1.09
8	1.000 (base)	12	1.12
9	1.03	13	1.15
10	1.06	14	1.18

4

AVERAGE FLOOR AREA PER UNIT

BED AND BREAKFAST INNS				GUEST COTTAGES			
Sq. Ft.	Multiplier	Sq. Ft.	Multiplier	Sq. Ft.	Multiplier	Sq. Ft.	Multiplier
800	1.08	2,800	0.92	100	1.21	900	0.93
1,000	1.05	3,200	0.91	200	1.11	1,000	0.92
1,200	1.03	3,600	0.89	300	1.06	1,200	0.90
1,400	1.01	4,000	0.88	400	1.03	1,400	0.89
1,600	0.99	4,400	0.87	500	1.00		
1,800	0.98	4,800	0.86	600	0.98		
2,000	0.96	5,200	0.85	700	0.96		
2,400	0.94	5,600	0.84	800	0.95		

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.