MAINTENANCE (STORAGE) BUILDING



AVERAGE CLASS D POLE

OCCUPANCY DESCRIPTION: This weatherproof storage structure is designed for closed storage and light maintenance of miscellaneous school ground equipment. The masonry buildings have brick or block with heavy roof framing and windows on the better qualities.

The frame structures are constructed with either wood or steel framed walls. The exterior covers are typically stucco, wood siding or metal siding. Floors at the lower qualities may be unfinished while the better qualities have sealed floors and walls with some finished shop area and cabinets.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, lockers, therapy or recreational equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 111.00	Decorative concrete block, brick, wood rafters, overhead doors	Sealed walls, concrete floor, some shop area and cabinets	Good lighting and outlets, water service	Space heaters
	Average	75.50	Concrete block, composition shingles, barred windows	Unfinished, concrete or asphalt floor	Adequate electrical and outlets	None
D	Good	100.50	Heavy wood frame, siding or stucco, overhead doors	Wainscot, concrete floor, some shop area and cabinets	Good lighting and outlets, water service	Space heaters
	Average	64.50	Open wood frame, exposed siding, barred windows	Some wainscot, concrete or asphalt floor	Adequate electrical and outlets	None
D POLE	Good	90.50	Good pole frame, colored siding, overhead doors	Wainscot, concrete floor, some shop area and cabinets	Good lighting and outlets, water service	Space heaters
	Average	57.00	Pre-engineered pole frame, metal siding, barred windows	Some wainscot, concrete or asphalt floor	Adequate electrical and outlets	None
S	Good	95.00	Good frame, colored siding, overhead doors	Wainscot, concrete floor, some shop area and cabinets	Good lighting and outlets, water service	Space heaters
	Average	61.00	Pre-engineered frame, metal siding, barred windows	Some wainscot, concrete or asphalt floor	Adequate electrical and outlets	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MAINTENANCE (STORAGE) BUILDING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 **SPRINKLERS:** Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2 **HEATING AND COOLING**

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3 **HEIGHT REFINEMENTS**

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	**12,000**
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	**16,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	**20,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MARKETS



AVERAGE CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: Retail food stores that often handle limited lines of other merchandise. Items which are generally classed as real property are included in the costs, i.e., built-in refrigerators, cold rooms and ancillary cooling equipment. Other items found in this occupancy which are classed as personal property or trade fixtures, are not included in the costs. In this occupancy, 75% to 80% of the total store is devoted to space for display, with the remainder of the floor space being utilized for storage, prepackaging areas and coolers.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in refrigerators and freezers, cold rooms and cooling equipment.

NOT INCLUDED IN COSTS: Elevators, sprinklers, display cases, freezers and coolers, furnishings or other trade fixtures.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 161.50	Brick, concrete, metal and glass, small front	Plaster or drywall, acoustic tile, few partitions, vinyl composition	Adequate market lighting and plumbing	Warm and cool air (zoned)
A-B	Storage basement	79.00	Painted interior	Painted floor and ceiling	Exposed lighting, restrooms	Space heaters
	Parking basement	84.00	Unfinished interior	Unfinished (service booth)	Exposed lighting, drains	Ventilation
	Storage mezzanine	42.25	In-store cost	Painted soffit, unfinished floor	Minimum, exposed lighting	(in store cost)
C	Excellent	193.00	Individual design, heavy frame, ornamental front	Plaster, good acoustic tile, good terrazzo, rubber tile, carpet	Special lighting, good fixtures and plumbing throughout	Warm and cool air (zoned)
	Good	158.50	Brick, good tilt-up, heavy steel or Glulam frame	Plaster, acoustic tile, rubber or vinyl composition, terrazzo	Good lighting, plumbing for butchers, snack bar, etc.	Warm and cool air (zoned)
	Average	125.50	Brick, block, tilt-up, Glulam, medium steel, or pilasters	Plaster or drywall, acoustic tile, few partitions, vinyl composition	Adequate lighting and plumbing, few extra services	Package A.C.
	Low cost	94.00	Cheap brick, block, tilt-up, pilasters or light frame	Painted walls, part acoustic tile, exposed rafters, minimum partitions	Minimum food store lighting and plumbing	Forced air
D	Excellent	180.00	Best veneer or siding, highly ornamental front	Plaster, good acoustic tile, good terrazzo, rubber tile, carpet	Special lighting, good fixtures and plumbing throughout	Warm and cool air (zoned)
	Good	147.50	Brick veneer or good siding, good frame and front	Plaster, acoustic tile, rubber or vinyl composition, terrazzo	Good lighting, plumbing for butchers, snack bar, etc.	Warm and cool air (zoned)
	Average	116.50	Good stucco or siding, some trim, metal and glass front	Plaster or drywall, acoustic tile, vinyl composition, small office	Adequate market lighting and outlets, small restrooms	Package A.C.
	Low cost	87.00	Siding or stucco, small front	Some finish, very few partitions	Minimum lighting and plumbing	Forced air
D POLE	Average	112.50	Pole frame, good metal panels, finished inside, little trim	Plaster or drywall, acoustic tile, few partitions, vinyl composition	Adequate lighting and plumbing, few extra services	Package A.C.
	Low cost	82.50	Pole frame, metal siding, small front	Painted walls, part acoustic tile, exposed rafters, minimum partitions	Minimum food store lighting and plumbing	Forced air
S	Good	148.00	Insulated sandwich panels, pre-engineered frame, good front	Plaster, acoustic tile, rubber or vinyl composition, terrazzo	Good lighting, plumbing for butchers, snack bar, etc.	Warm and cool air (zoned)
	Average	115.00	Sandwich panels, some trim	Few partitions, acoustic, vinyl tile	Adequate lighting and plumbing	Package A.C.
	Low cost	84.00	Metal panels, small front	Some finish, very few partitions	Minimum lighting and plumbing	Forced air
CDS	Storage basement	49.50	Painted interior	Painted ceiling and floors, few partitions	Exposed lighting, few outlets, drains	Space heaters
	Storage mezzanine	31.00	In-store cost	Drywall soffit, wood floor, light storage	Minimum lighting, no and plumbing	In-store cost

MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MARKETS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small freight elevator with simple call system and push-button control, and two or three stops, costs $66,500 to $109,000. For detailed costs, see Section UIP 8.

For loading docks, see Page CAL 398.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$10.10	$13.05
2,000	5.43	6.95	8.88	11.35
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19
80,000	3.05	3.77	4.63	5.68

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$2.56

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.957	16	1.085
12	1.000 (base)	18	1.127
13	1.021	20	1.170
14	1.042	22	1.213
15	1.064	24	1.255

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Average Floor Area Sq. Ft./Story
1,000	1.183	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	.969	1.079	1.183	1.283	1.376	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	.878	.924	.969	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**5,000**
7,000	-----	-----	.870	.904	.937	1.000	1.060	1.121	1.183	-----	-----	-----	-----	-----	**7,000**
10,000	-----	-----	-----	-----	.878	.925	.969	1.011	1.054	1.097	1.140	1.183	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.892	.931	.969	1.005	1.042	1.079	1.117	1.183	-----	**12,000**
14,000	-----	-----	-----	-----	-----	.870	.904	.937	.969	1.000	1.030	1.060	1.121	-----	**14,000**
18,000	-----	-----	-----	-----	-----	-----	.866	.892	.917	.943	.969	.992	1.040	-----	**18,000**
20,000	-----	-----	-----	-----	-----	-----	.854	.878	.901	.924	.948	.969	1.011	-----	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.925	.969	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.878	.913	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	**50,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MARKETS – CONVENIENCE



AVERAGE CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: These are small food stores with limited interior facilities. They are designed for the quick purchase of standard staple items in small quantities. They have extensive shelving but few facilities. The storage area is relatively small. The better qualities include small specialty or gourmet food shops.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in refrigerators and freezers, cold rooms and cooling equipment.

NOT INCLUDED IN COSTS: Sprinklers, display cases, freezers and coolers or other trade fixtures.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 166.00	Brick or concrete, usually part of a building	Typical chain store, acoustic tile, vinyl composition	Adequate lighting outlets, adequate plumbing	Warm and cool air (zoned)
	Storage basement	79.00	Painted interior	Painted ceiling and floors, few partitions	Exposed lighting, few outlets, drains	Space heaters
C	Excellent	191.00	Individual design, highly ornamental exterior	Plaster, acoustic tile, terrazzo, carpet or vinyl, good trim	Special lighting, good fixtures and plumbing	Package A.C.
	Good	161.50	Brick, best block, stucco, good store front and ornamentation	Typically better chain stores, good acoustic, vinyl tile & carpet	Good lighting and outlets, restrooms, standard fixtures	Package A.C.
	Average	127.00	Brick or block, some mansard, parapet ornamentation	Typical chain store, acoustic tile, vinyl comp., some snack prep. area	Adequate lighting and outlets, small employees' restroom	Forced air
	Low cost	102.50	Minimum block or cheap brick	Painted exterior walls, minimum finish	Minimum code throughout	Space heaters
D	Excellent	181.00	Individual design, highly ornamental exterior	Plaster, acoustic tile, terrazzo, carpet or vinyl, good trim	Special lighting, good fixtures and plumbing	Package A.C.
	Good	151.50	Brick veneer or good siding, good frame and front	Typically better chain stores, good acoustic, vinyl tile & carpet	Good lighting and outlets, restrooms, standard fixtures	Package A.C.
	Average	119.50	Stucco or siding, some mansard, parapet ornamentation	Typical chain store, acoustic tile, vinyl comp., some snack prep. area	Adequate lighting and outlets, small employees' restroom	Forced air
	Low cost	95.00	Stucco or siding, small front	Drywall, few partitions	Minimum code throughout	Space heaters
D POLE	Low cost	91.00	Pole frame, metal, lined, small low-cost front	Minimum finish and partitions	Minimum code throughout, minimum display wiring	Space heaters
S	Excellent	184.00	Best metal panels, trim, good entrance	Drywall or plaster, acoustic tile, good finishes and trim	Special lighting, good fixtures and plumbing	Package A.C.
	Good	152.50	Insulated sandwich panels, good front & ornamentation	Typically better chain stores, good acoustic, vinyl tile and carpet	Good lighting and outlets, restrooms, standard fixtures	Package A.C.
	Average	118.00	Good panels, small front, mansard, some ornamentation	Typical chain store, acoustic tile, vinyl comp., some snack prep. area	Adequate lighting and outlets, small employees' restroom	Forced air
	Low cost	93.50	Steel siding, partly finished interior	Minimum finish and partitions	Minimum code throughout	Space heaters
CDS	Storage basement	49.00	Painted interior	Painted ceiling and floors, few partitions	Exposed lighting, few outlets, drains	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MARKETS – CONVENIENCE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 **For gasoline pumps and canopies, see UIP 14.**

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
500	$ 6.67	$ 8.71	$ 11.41	$ 14.89
1,000	6.02	7.78	10.10	13.05
1,500	5.66	7.28	9.35	12.00
2,000	5.43	6.95	8.88	11.35
2,500	5.25	6.69	8.55	10.92
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40

2 **HEATING AND COOLING**

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$2,300 to $3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3 **HEIGHT REFINEMENTS**

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	13	1.021
10	.957	14	1.042
11	.979	15	1.064
12	1.000 (base)	16	1.085

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	175	200	225	250	275	300	350	400	450	500	Sq. Ft./Story
500	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
1,000	1.079	1.183	1.283	1.376	1.470	1.566	1.660	1.753	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.969	1.042	1.115	1.183	1.256	1.322	1.384	1.445	1.506	1.566	-----	-----	-----	-----	**1,500**
2,000	.912	.969	1.025	1.079	1.130	1.183	1.233	1.283	1.330	1.376	1.470	-----	-----	-----	**2,000**
2,500	.878	.924	.969	1.011	1.054	1.097	1.140	1.183	1.227	1.270	1.351	1.420	-----	-----	**2,500**
3,000	.854	.892	.931	.969	1.005	1.042	1.079	1.115	1.149	1.183	1.256	1.322	1.380	-----	**3,000**
3,500	-----	.873	.907	.941	.973	1.006	1.038	1.070	1.101	1.131	1.194	1.253	1.300	-----	**3,500**
4,000	-----	.854	.883	.912	.941	.969	.997	1.025	1.052	1.079	1.131	1.183	1.232	1.280	**4,000**
5,000	-----	-----	.854	.878	.901	.924	.947	.969	.990	1.011	1.054	1.097	1.140	1.183	**5,000**
6,000	-----	-----	-----	-----	.873	.892	.912	.931	.950	.969	1.005	1.042	1.079	1.115	**6,000**
7,000	-----	-----	-----	-----	-----	.870	.887	.904	.921	.937	.969	1.000	1.030	1.060	**7,000**
8,000	-----	-----	-----	-----	-----	-----	-----	.883	.898	.912	.941	.969	.997	1.025	**8,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MARKETS – MINI-MARTS



AVERAGE CLASS C CONVENIENCE



GOOD CLASS C CONVENIENCE

OCCUPANCY DESCRIPTION: Mini-mart food stores are small convenience outlets that cater primarily to a transient trade for self service snack foods and beverages. The better stores will have public restrooms and limited hot or deli food preparation and service areas. Lower qualities are minimum code throughout.

Dairy sales buildings are drive up store buildings designed for sale and limited storage of dairy products. The cost for the built in refrigerators is included, while the fixtures and special equipment which might be needed for operation are not included. They may have storefront entrances with plaster walls, acoustic tile ceilings and a resilient floor finish. They also have typical store lighting and restrooms, and generally have high capacity electrical service.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in refrigerators.

NOT INCLUDED IN COSTS: Sprinklers, free standing refrigerators, display cases, special fixtures or equipment, fronts, freezers, coolers and other trade fixtures.

MINI-MART CONVENIENCE STORES

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 291.00	Decorative block, brick, good glass entrance	Good drywall, acoustic tile, good pavers, limited food prep. area	Good lighting, good fixtures and plumbing, tiled restrooms	Package A.C.
	Good	249.00	Brick, best block, stucco, good front and ornamentation	Good acoustic, ceramic tile, security partitioning, some snack prep. area	Good lighting and outlets, public restrooms, standard fixtures	Package A.C.
	Average	213.00	Brick or block, some mansard, parapet ornamentation	Typical food booth, acoustic tile, vinyl composition, adequate support	Adequate lighting and outlets, small employees' restroom	Package A.C.
	Low cost	182.50	Minimum block, small front	Minimum finish and partitions	Minimum code throughout	Package A.C.
D	Good	238.00	Brick veneer or good siding, good frame and front	Good acoustic, ceramic tile, security partitioning, some snack prep. area	Good lighting and outlets, public restrooms, standard fixtures	Package A.C.
	Average	204.00	Stucco or siding, some mansard, parapet ornamentation	Typical food booth, acoustic tile, vinyl composition, adequate support	Adequate lighting and outlets, small employees' restroom	Package A.C.
	Low cost	174.50	Stucco or siding, small front	Minimum finish and partitions	Minimum code throughout	Package A.C.
D POLE	Low cost	174.50	Pole frame, metal, lined, low-cost sash and fascia	Minimum finish and partitions, acoustic tile, vinyl composition	Minimum code, display wiring and plumbing	Package A.C.
S†	Excellent	287.00	Best metal panels, trim, good glass entrance	Good drywall, acoustic tile, good pavers, limited food prep. area	Good lighting, good fixtures and plumbing, tiled restrooms	Package A.C.
	Good	250.00	Good enameled prefinished steel, good front, masonry trim	Good acoustic, ceramic tile, security partitioning, some snack prep. area	Good lighting and outlets, public restrooms, standard fixtures	Package A.C.
	Average	217.00	Good panels, small front, some trim or mansard	Typical food booth, acoustic tile, vinyl composition, adequate support	Adequate lighting and outlets, small employees' restroom	Package A.C.
	Low cost	188.50	Metal panels, glass, lined interior	Minimum booth finish and partitions	Minimum code throughout	Package A.C.

†**NOTE:** For complete prefabricated food booths, see Garages – Service Stations, Page CAL 64.

MINI-MART DAIRY SALES

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Average	$137.50	Brick, concrete block, store or drive-up front	Plaster, acoustic tile, asphalt tile, built-in refrigerated storage	Store lighting and plumbing, restroom	Package A.C.
D	Average	127.50	Stucco or siding, store or drive-up front	Plaster, acoustic tile, asphalt tile, built-in refrigerated storage	Store lighting and plumbing, restroom	Package A.C.
S	Average	126.50	Good colored steel panels, drive-up front	Acoustic tile, vinyl composition, built-in refrigerated storage	Store lighting and plumbing, restroom	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MARKETS – MINI-MARTS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 **For gasoline pumps, see UIP 14.**

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 36.25	$ 45.00	$ 56.00	$ 69.50
Light false-mansard	18.10	22.55	28.00	34.75
Steel frame	46.25	59.00	75.00	96.00
Light false-mansard	23.10	29.50	37.50	48.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
500	$ 6.67	$ 8.71	$ 11.41	$ 14.89
1,000	6.02	7.78	10.10	13.05
1,500	5.66	7.28	9.35	12.00
2,000	5.43	6.95	8.88	11.35
2,500	5.25	6.69	8.55	10.92
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62

2 **HEATING AND COOLING**

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3 **HEIGHT REFINEMENTS**

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	13	1.021
10	.957	14	1.042
11	.979	15	1.064
12	1.000 (base)	16	1.085

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	175	200	225	250	275	300	350	400	450	500	Sq. Ft./Story
500	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
1,000	1.079	1.183	1.283	1.376	1.470	1.566	1.660	1.753	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.969	1.042	1.115	1.183	1.256	1.322	1.384	1.445	1.506	1.566	-----	-----	-----	-----	**1,500**
2,000	.912	.969	1.025	1.079	1.130	1.183	1.233	1.283	1.330	1.376	1.470	-----	-----	-----	**2,000**
2,500	.878	.924	.969	1.011	1.054	1.097	1.140	1.183	1.227	1.270	1.351	1.420	-----	-----	**2,500**
3,000	.854	.892	.931	.969	1.005	1.042	1.079	1.115	1.149	1.183	1.256	1.322	1.380	-----	**3,000**
3,500	-----	.873	.907	.941	.973	1.006	1.038	1.070	1.101	1.131	1.194	1.253	1.300	-----	**3,500**
4,000	-----	.854	.883	.912	.941	.969	.997	1.025	1.052	1.079	1.131	1.183	1.232	1.280	**4,000**
5,000	-----	-----	.854	.878	.901	.924	.947	.969	.990	1.011	1.054	1.097	1.140	1.183	**5,000**
6,000	-----	-----	-----	-----	.873	.892	.912	.931	.950	.969	1.005	1.042	1.079	1.115	**6,000**
7,000	-----	-----	-----	-----	-----	.870	.887	.904	.921	.937	.969	1.000	1.030	1.060	**7,000**
8,000	-----	-----	-----	-----	-----	-----	-----	.883	.898	.912	.941	.969	.997	1.025	**8,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MARKETS – ROADSIDE



GOOD CLASS D



GOOD CLASS D

OCCUPANCY DESCRIPTION: Roadside or farmers' markets are typically rural structures from the open stand to the enclosed, full retail market barn with refrigerated storage. They are designed for the quick purchase of fresh produce and a few standard staple items in small quantities. They have little display and storage space. The better qualities will have separate storage and office areas that are relatively small. These better qualities include suitable plumbing, electrical and built-in cooler storage.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in coolers in the better qualities.

NOT INCLUDED IN COSTS: Sprinklers, free-standing refrigerators, display cases, fronts, freezers, coolers and other trade fixtures.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 139.00	Decorative block, concrete, good roof and roll-up doors	Open sales, good preparation, storage and office	Adequate market lighting, restroom and cold storage	Package A.C.
	Good	84.50	Concrete block, tilt-up, large doorways	Open sales, sealed slab, small storage and cold box	Minimum store lighting and plumbing	Space heaters
	Average	55.00	Low-cost block, tilt-up, gated front, very plain	Open sales area, concrete slab, some partitions, dry storage	Minimum electrical and plumbing	Space heaters
D	Excellent	128.00	Heavy frame, arch or gambrel roof, roll-up doors	Open sales, good preparation, storage and office	Adequate market lighting, restroom and cold storage	Package A.C.
	Good	75.50	Exposed frame, good board siding, trim, large doorways	Open sales, sealed slab, small storage and cold box	Minimum store lighting and plumbing	Space heaters
	Average	48.00	Wood frame, board and batten, gated front, some trim	Open sales area, concrete slab, some partitions, dry storage	Minimum electrical and plumbing	Space heaters
	Low cost	27.50	Plywood or siding, open framing, some trim	Open interior, some slab or wood, gravel	Minimum electrical, hose bib	None
	Cheap	17.00	Box frame, plywood or boards, shed roof, very plain	Open interior, unfinished, seasonal use only	None	None
DPOLE	Excellent	122.50	Heavy pole frame and truss, good siding and roll-up doors	Open sales, good preparation, storage and office	Adequate market lighting, restroom and cold storage	Package A.C.
	Good	70.50	Exposed pole frame, metal siding, large doorways	Open sales, sealed slab, small storage and cold box	Minimum store lighting and plumbing	Space heaters
	Average	44.00	Pole frame, metal utility building, gated front	Open sales area, concrete slab, some partitions, dry storage	Minimum electrical and plumbing	Space heaters
	Low cost	24.50	Pole frame, metal siding, open front, shutter doors	Open interior, some slab or wood, gravel	Minimum electrical, hose bib	None
	Cheap	15.00	Light pole frame, metal siding, shed roof, open front	Open interior, unfinished, seasonal use only	None	None
S	Excellent	126.50	Metal sandwich panels, open frame, good roll-up doors	Open sales, good preparation, storage and office	Adequate market lighting, restroom and cold storage	Package A.C.
	Good	74.50	Exposed steel frame, metal siding, large doorways	Open sales, sealed slab, small storage and cold box	Minimum store lighting and plumbing	Space heaters
	Average	47.50	Steel frame, metal utility building, gated front	Open sales area, concrete slab, some partitions, dry storage	Minimum electrical and plumbing	Space heaters
	Low cost	27.00	Steel frame, metal siding, open front, shutter doors	Open interior, some slab or wood, gravel	Minimum electrical, hose bib	None
CDS	Storage basement	49.00	Painted interior	Painted ceiling and floors, few partitions	Exposed lighting, few outlets, drains	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MARKETS – ROADSIDE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

DOCK-HEIGHT FLOORS: add the cost per square foot to the base cost of the first floor.

Elevated on compacted fill: $5.08 to $10.15 per square foot. For cut and balance, use proportional cost.

Elevated on posts and piers with cross bracing, beams and skirting: $14.35 to $21.85 per square foot.

Loading platforms cost $19.85 to $25.75 per square foot; add $505 for steps.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
500	$ 6.67	$ 8.71	$11.41	$ 14.89
1,000	6.02	7.78	10.10	13.05
1,500	5.66	7.28	9.35	12.00
2,000	5.43	6.95	8.88	11.35
2,500	5.25	6.69	8.55	10.92
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$2,300 to $3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	13	1.021
10	.957	14	1.042
11	.979	15	1.064
12	1.000 (base)	16	1.085

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	175	200	225	250	275	300	350	400	450	500	Sq. Ft./Story
500	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
1,000	1.079	1.183	1.283	1.376	1.470	1.566	1.660	1.753	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.969	1.042	1.115	1.183	1.256	1.322	1.384	1.445	1.506	1.566	-----	-----	-----	-----	**1,500**
2,000	.912	.969	1.025	1.079	1.130	1.183	1.233	1.283	1.330	1.376	1.470	-----	-----	-----	**2,000**
2,500	.878	.924	.969	1.011	1.054	1.097	1.140	1.183	1.227	1.270	1.351	1.420	-----	-----	**2,500**
3,000	.854	.892	.931	.969	1.005	1.042	1.079	1.115	1.149	1.183	1.256	1.322	1.380	-----	**3,000**
3,500	-----	.873	.907	.941	.973	1.006	1.038	1.070	1.101	1.131	1.194	1.253	1.300	-----	**3,500**
4,000	-----	.854	.883	.912	.941	.969	.997	1.025	1.052	1.079	1.131	1.183	1.232	1.280	**4,000**
5,000	-----	-----	.854	.878	.901	.924	.947	.969	.990	1.011	1.054	1.097	1.140	1.183	**5,000**
6,000	-----	-----	-----	-----	.873	.892	.912	.931	.950	.969	1.005	1.042	1.079	1.115	**6,000**
7,000	-----	-----	-----	-----	-----	.870	.887	.904	.921	.937	.969	1.000	1.030	1.060	**7,000**
8,000	-----	-----	-----	-----	-----	-----	-----	.883	.898	.912	.941	.969	.997	1.025	**8,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MARKETS - SUPERMARKET



AVERAGE CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: These are large self service retail food stores that often handle several lines of other merchandise. Items that are generally classed as real property are included in the costs, i.e., built-in refrigerators, cold rooms and ancillary cooling equipment. Other items found in this occupancy which are classed as personal property or trade fixtures are not included in the costs.

In this occupancy, 75% to 80% of the total store is devoted to space for display with the remainder of the floor space being utilized for storage, pre-packaging areas and coolers.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in refrigerators and freezers, cold rooms and cooling equipment.

NOT INCLUDED IN COSTS: Elevators, sprinklers, display cases, freezers and coolers, furnishings or other trade fixtures.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 183.50	Brick, metal and glass, heavy frame, decorative front	Plaster, acoustic tile, rubber or vinyl composition, terrazzo, pavers	Good lighting, plumbing for butchers, snack bar, bakery, etc.	Warm and cool air (zoned)
	Average	160.50	Brick, concrete, metal and glass, small front	Plaster or drywall, acoustic tile, few partitions, vinyl composition	Adequate market lighting and plumbing, some extras	Warm and cool air (zoned)
	Storage Basement	79.00	Painted interior	Painted floor and ceiling	Exposed lighting, restrooms	Space Heaters
C	Excellent	183.50	Individual design, heavy frame, ornamental front	Plaster, good acoustic tile, good terrazzo, rubber tile, carpet	Special lighting, good fixtures and plumbing throughout departments	Warm and cool air (zoned)
	Good	156.00	Brick, good tilt-up, decorative block, heavy steel or Glulam frame	Plaster, acoustic tile, rubber or vinyl composition, terrazzo	Good lighting, plumbing for butchers, snack bar, bakery, etc.	Warm and cool air (zoned)
	Average	126.50	Brick, block, tilt-up, Glulam, medium steel, metal and glass front	Plaster or drywall, acoustic tile, some partitions, vinyl composition	Adequate lighting and plumbing, few extra services	Package A.C.
	Low cost	108.00	Cheap brick, block, tilt-up, vinyl composition light frame	Painted walls, acoustic tile, minimum chain store	Adequate food store lighting and plumbing	Package A.C.
D	Excellent	172.50	Best veneer or siding, highly ornamental front	Plaster, good acoustic tile, good terrazzo, rubber tile, carpet	Special lighting, good fixtures and plumbing throughout departments	Warm and cool air (zoned)
	Good	145.00	Brick veneer or good siding, good frame and front	Plaster, acoustic tile, rubber or vinyl composition, terrazzo	Good lighting, plumbing for butchers, snack bar, bakery, etc.	Warm and cool air (zoned)
	Average	118.00	Good stucco or siding, some trim, metal and glass front	Plaster or drywall, acoustic tile, vinyl composition, some partitions	Adequate market lighting and outlets, small restrooms, few extras	Package A.C.
S	Good	146.00	Insulated sandwich panels, good frame and front	Plaster, acoustic tile, rubber or vinyl composition, terrazzo	Good lighting, plumbing for butchers, snack bar, bakery, etc.	Warm and cool air (zoned)
	Average	117.00	Sandwich panels, pre-engineered frame, glass front	Plaster or drywall, acoustic tile, few partitions, vinyl composition	Adequate lighting and plumbing, few extra services	Package A.C.
	Low cost	97.50	Steel panels, partly finished interior, small front	Painted walls, acoustic tile, vinyl composition, minimum chain store	Adequate food store lighting and plumbing	Package A.C.
CDS	Storage basement	49.00	Painted interior	Painted ceiling and floors, few partitions	Exposed lighting, few outlets, drains	Space heaters

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $ 8.60 per square foot to the basement cost.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MARKETS - SUPERMARKET

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 36.25	$ 45.00	$ 56.00	$ 69.50
Light false-mansard	18.10	22.55	28.00	34.75
Steel frame	46.25	59.00	75.00	96.00
Light false-mansard	23.10	29.50	37.50	48.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
500	$ 6.67	$ 8.71	$ 11.41	$ 14.89
1,000	6.02	7.78	10.10	13.05
1,500	5.66	7.28	9.35	12.00
2,000	5.43	6.95	8.88	11.35
2,500	5.25	6.69	8.55	10.92
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$2,300 to $3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	13	1.021
10	.957	14	1.042
11	.979	15	1.064
12	1.000 (base)	16	1.085

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Average Floor Area Sq. Ft./Story
1,000	1.183	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	.969	1.079	1.183	1.283	1.376	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	.878	.924	.969	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**5,000**
7,000	-----	-----	.870	.904	.937	1.000	1.060	1.121	1.183	-----	-----	-----	-----	-----	**7,000**
10,000	-----	-----	-----	-----	.878	.925	.969	1.011	1.054	1.097	1.140	1.183	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.892	.931	.969	1.005	1.042	1.079	1.117	1.183	-----	**12,000**
14,000	-----	-----	-----	-----	-----	.870	.904	.937	.969	1.000	1.030	1.060	1.121	-----	**14,000**
18,000	-----	-----	-----	-----	-----	-----	.866	.892	.917	.943	.969	.992	1.040	-----	**18,000**
20,000	-----	-----	-----	-----	-----	-----	.854	.878	.901	.924	.948	.969	1.011	-----	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.925	.969	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.878	.913	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	**50,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MEDICAL – DENTAL CLINICS



GOOD CLASS C



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These are small stand-alone medical clinic buildings designed for dental services, with examination and outpatient treatment. They include a reception/lobby area as well as individual rooms.

Floor finishes are carpet or resilient flooring. Ceilings are acoustic tile and may be on a suspended system. Most utilize high-intensity fluorescent lighting, with the better qualities also having X-ray capa bilities and built-in cabinetry.

Individual treatment rooms have plumbing and sinks. Restrooms are adequate to service the number of personnel working in the building.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit, X-ray rooms, and built-in cabinetry.

NOT INCLUDED IN COSTS: Dental chairs, X-ray equipment, autoclaves, office equipment, permanent examination lights and other dental equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 364.50	Face brick, glass panels, stone, top quality	Best plaster, paneling, carpet and vinyl tile, high-cost waiting areas	Luminous ceilings, power and X-ray outlets, best plumbing	Warm and cool air (zoned)
	Good	281.50	Face brick, concrete or metal panels, ornamentation	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	Good fluorescent lighting, X-ray, lab, dark rooms, good plumbing	Heat pump system
	Average	214.00	Brick, block, concrete panels, some trim	Plaster, drywall partitions, acoustic tile, vinyl composition, carpet	Adequate lighting, power and plumbing, X-ray, air piping	Package A.C.
	Low cost	163.00	Brick or block, tilt-up, no trim	Paint, cheap partitions, acoustic tile, asphalt tile, small lobby	Minimum lighting and outlets, adequate plumbing, few extras	Forced air
D	Excellent	349.50	Face brick veneer, best siding, good ornamentation	Best plaster, paneling, carpet and vinyl tile, high-cost waiting areas	Luminous ceilings, power and X-ray outlets, best plumbing	Warm and cool air (zoned)
	Good	269.50	Brick veneer, good stucco or siding with good trim	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	Good fluorescent lighting, X-ray, lab, dark rooms, good plumbing	Heat pump system
	Average	205.00	Brick veneer, stucco or siding, little trim	Plaster, drywall partitions, acoustic tile, vinyl composition, carpet	Adequate lighting, power and plumbing, X-ray, air piping	Package A.C.
	Low cost	155.00	Stucco or siding, very plain	Paint, cheap partitions, acoustic tile, asphalt tile, small lobby	Minimum lighting and outlets, adequate plumbing, few extras	Forced air
D POLE	Average	191.50	Pole frame, insulated metal panels, some ornamentation	Drywall partitions, acoustic tile, vinyl composition, carpet	Adequate lighting, power and plumbing, X-ray, air piping	Package A.C.
	Low cost	143.00	Pole frame, finished interior, insulation, little trim	Paint, cheap partitions, acoustic tile, asphalt tile, small lobby	Minimum lighting and outlets, adequate plumbing, few extras	Forced air
S	Good	261.50	Pre-engineered, good sandwich panels, some brick or stone trim	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	Good fluorescent lighting, X-ray, lab, dark rooms, good plumbing	Heat pump system
	Average	196.50	Pre-engineered, sandwich panels, some ornamentation	Drywall partitions, acoustic tile, vinyl composition, carpet	Adequate lighting, power and plumbing, X-ray, air piping	Package A.C.
	Low cost	146.50	Pre-engineered, finished interior, insulation, little trim	Paint, cheap partitions, acoustic tile, asphalt tile, small lobby	Minimum lighting and outlets, adequate plumbing, few extras	Forced air
CDS	Finished basement	120.00	Plaster or drywall interior	Adequate dental office finish, acoustic tile, vinyl composition	Adequate medical office lighting and plumbing	Forced air
	Utility basement	48.50	Painted interior	Paint only, few partitions	Minimum lighting, drains	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MEDICAL – DENTAL CLINICS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 68,000 to $ 112,000.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 41.00	$ 53.00	$ 69.00
Steel	29.75	40.50	55.00	75.50
Wood	25.25	33.75	45.00	60.00
Add for ornate finishes, balustrades	27.50	34.00	41.75	51.00
Add for roofs or awnings	15.20	20.15	26.75	35.75

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99
75,000	3.39	4.20	5.22	6.46
100,000	3.27	4.01	4.96	6.13

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$ 2,950 to $ 3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$ 2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.299	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	1.007	1.040	1.072	1.105	1.168	1.235	1.364	-----	-----	-----	-----	-----	-----	-----	2,000
4,000	-----	-----	.958	.975	1.007	1.040	1.105	1.168	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	.936	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	5,000
8,000	-----	-----	-----	-----	.926	.942	.975	1.007	1.040	1.105	-----	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.052	1.105	1.155	-----	-----	10,000
14,000	-----	-----	-----	-----	-----	.900	.920	.938	.956	.993	1.030	1.067	1.105	1.140	14,000
20,000	-----	-----	-----	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	20,000
30,000	-----	-----	-----	-----	-----	-----	-----	-----	.897	.915	.932	.949	.965	.983	30,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.897	.910	.923	.936	.949	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	.928	50,000
75,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.873	.879	.885	.892	.900	75,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MEDICAL – OFFICE BUILDING



GOOD CLASS C



GOOD CLASS D

OCCUPANCY DESCRIPTION: These are buildings designed for medical and/or dental services with outpatient treatment. They include a reception/lobby area as well as individual examination rooms.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit, X-ray rooms, and built-in cabinetry. Elevators are included where designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, X-ray equipment, autoclaves, permanent examination lights or other medical equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$ 463.00	Best metal, brick or block backup, solar glass	Acoustic plaster, good veneers, vinyl wall coverings, carpet, vinyl	*Luminous ceilings, power and X-ray outlets, best plumbing	Hot and chilled water (zoned)
	Good	376.00	Good metal and solar glass, face brick, concrete and glass	Good plaster or drywall, acoustic tile, carpeting, vinyl composition	*High-intensity lighting, X-ray outlets, good plumbing, lab	Hot and chilled water (zoned)
	Average	290.00	Metal and glass, brick or concrete panels	Plaster or drywall, acoustic tile, vinyl composition floors	*Adequate lighting, power, and plumbing, X-ray rooms	Warm and cool air (zoned)
	Low cost	220.00	Brick, concrete block, very plain, small lobby	Low-cost finishes and partitions, acoustic tile, asphalt tile	*Minimum lighting and plumbing, few extras	Package A.C.
B	Excellent	424.00	Best metal, brick or block backup, solar glass	Acoustic plaster, good veneers, vinyl wall coverings, carpet, vinyl	*Luminous ceilings, power and X-ray outlets, best plumbing	Hot and chilled water (zoned)
	Good	344.00	Good metal and glass, good brick, concrete panels	Good plaster or drywall, acoustic tile, carpeting and vinyl composition	*High-intensity lighting, X-ray outlets, good plumbing, lab	Hot and chilled water (zoned)
	Average	264.00	Metal and glass, brick or concrete panels	Drywall or plaster, acoustic tile, vinyl composition floors	*Adequate lighting, power, and plumbing, X-ray rooms	Warm and cool air (zoned)
	Low cost	198.50	Brick, concrete block, lift slab, very plain, small lobby	Low-cost finishes and partitions, acoustic tile, asphalt tile	*Minimum lighting and plumbing, few extras	Package A.C.
A-B	Finished basement	217.00	Plaster interior	Average medical office finish, acoustic tile, vinyl composition	Adequate medical office lighting and plumbing	Warm and cool air (zoned)
	Stor. bsmt.	85.50	Painted interior	Partitions for storage and heating	Minimum lighting/plumbing	Space heaters
	Pkg. bsmt.	92.00	Unfinished interior	Unfinished, small service area	Minimum lighting/plumbing	Ventilation
	Office mezz.	121.00	Not included	Enclosed, medical office finish, plaster soffit	Average medical office lighting and plumbing	In building cost
	Open mezz.	68.50	Not included	Carpet and vinyl composition, plaster soffit	Average lighting and plumbing	In building cost
C	Excellent	367.00	Steel frame, masonry and glass, ornamentation, top quality	Acoustic plaster, paneling, carpet and vinyl tile, many soundproof rooms	*Fluorescent panels, air piping, X-ray rooms, good plumbing	Hot and chilled water (zoned)
	Good	279.50	Steel frame, masonry, best concrete panels, ornamentation	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	*Good fluorescent lighting, X-ray rooms, good plumbing, lab	Warm and cool air (zoned)
	Average	210.00	Steel or concrete frame or bearing walls, some trim	Plaster, drywall partitions, acoustic tile, vinyl composition	*Adequate lighting and outlets, adequate plumbing, lab	Package A.C.
	Low cost	158.50	Masonry bearing walls, light rafters, very plain	Paint, cheap partitions, acoustic tile, asphalt tile	Minimum lighting and outlets, adequate plumbing	Forced air
D	Excellent	331.50	Studs or steel columns, bar or web joists, brick or stone veneer, EIFS	Best plaster, paneling, carpet and vinyl tile, many soundproof rooms	*Fluorescent panels, air piping, X-ray rooms, good plumbing	Warm and cool air (zoned)
	Good	266.00	Best stucco on good frame, good brick or stone trim	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	*Good fluorescent lighting, X-ray rooms, good plumbing, lab	Warm and cool air (zoned)
	Average	200.00	Stucco or wood siding on wood or steel studs, some trim	Drywall, acoustic tile, low-cost carpet or vinyl composition	*Adequate lighting and outlets, adequate plumbing	Package A.C.
	Low cost	151.50	Light stucco or siding on wood or steel studs, very plain	Drywall, cheap partitions, acoustic tile, asphalt tile	Minimum lighting and outlets, adequate plumbing	Forced air
D POLE	Low cost	139.50	Pole frame, good metal panels, finished inside, little trim	Low-cost finishes and partitions, acoustic tile, asphalt tile	Minimum lighting and plumbing, few extras	Forced air
S	Good	258.50	Good sandwich panels and fenestration, some brick or stone	Good plaster or drywall, acoustic tile, carpeting and vinyl	*High-intensity lighting, X-ray outlets, good plumbing, lab	Warm and cool air (zoned)
	Average	187.50	Insulated wall or sandwich panels, adequate fenestration	Drywall or plaster, acoustic tile, vinyl composition floors	Adequate lighting, power, and plumbing, X-ray rooms	Package A.C.
	Low cost	143.00	Steel or aluminum on light frame, finished interior, some insulation	Low-cost finishes and partitions, acoustic tile, asphalt tile	Minimum lighting and plumbing, few extras	Forced air
CDS†	Finished basement	137.00	Plaster or drywall interior	Average medical office finish, acoustic tile, vinyl composition	Adequate medical office lighting and plumbing	Forced air
	Stor. bsmt.	48.50	Painted interior	Paint only, few partitions	Minimum lighting, drains	None
	Pkg. bsmt.	60.50	Unfinished interior	Finished ceiling, concrete floor	Minimum lighting, drains	Ventilation
	Office mezz.	87.00	Not included	Enclosed, medical office finish, acoustic tile soffit	Average medical office lighting and plumbing	In building cost
	Open mezz.	48.00	Not included	Open, finished floors and soffit	Average lighting, no plumbing	In building cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.54 per square foot.

MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MEDICAL – OFFICE BUILDING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Classes C/D	Sq. Ft. Costs
Excellent	$ 17.95	Excellent	$ 9.24
Good	12.30	Good	5.67
Average	8.43	Average	3.46
Low cost	5.78		

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,400 to $14,400 per stop.

A small passenger elevator with simple call system and push button control, four passenger cab and two or three stops, costs $68,000 to $112,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99
75,000	3.39	4.20	5.22	6.46
100,000	3.27	4.01	4.96	6.13

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 41.00	$ 53.00	$ 69.00
Steel	29.75	40.50	55.00	75.50
Wood	25.25	33.75	45.00	60.00
Add for ornate finishes, balustrades	27.50	34.00	41.75	51.00
Add for roofs or awnings	15.20	20.15	26.75	35.75

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$ 2,950 to $ 3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$ 2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.299	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	1.007	1.040	1.072	1.105	1.168	1.235	1.364	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	-----	-----	.958	.975	1.007	1.040	1.105	1.168	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.936	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.926	.942	.975	1.007	1.040	1.105	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.052	1.105	1.155	-----	-----	**10,000**
14,000	-----	-----	-----	-----	-----	.900	.920	.938	.956	.993	1.030	1.067	1.105	1.140	**14,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	-----	.897	.915	.932	.949	.965	.983	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.897	.910	.923	.936	.949	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	.928	**50,000**
75,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.873	.879	.885	.892	.900	**75,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MEDICAL – URGENT CARE FACILITIES



GOOD CLASS C



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These are buildings designed for urgent care, emergency first aid and medical treatment. Typically, they do not have facilities for surgery, although the better qualities may have some small surgical capabilities. Floor coverings are either ceramic tile or some type of resilient floor finish throughout the structure. Lighting and plumbing are adequate for emergency first aid use.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit, and office space suitable for this type of occupancy.

NOT INCLUDED IN COSTS: Elevators, sprinklers, medical equipment, surgery facilities and emergency power facilities.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 263.50	Brick, metal and glass, some ornamentation	Plaster or drywall, good enamel or vinyl walls, ceramic, vinyl, rubber tile	Good lighting and plumbing, first aid and overnight care	Warm and cool air (zoned)
	Average	219.50	Brick, precast panels, metal and glass, little trim	Drywall or plaster, acoustic tile, vinyl composition, some ceramic pavers	Adequate lighting and plumbing for emergency first aid and care	Warm and cool air (zoned)
A-B	Storage basement	85.50	Painted interior	Partitions for storage and heating	Minimum lighting/plumbing	Space heaters
C	Excellent	267.00	Face brick, stone, good ornamentation	Best plaster, paneling, carpet and vinyl tile, good reception areas	Luminous ceilings, power and X-ray outlets, good plumbing	Warm and cool air (zoned)
	Good	201.50	Brick or block, good fenestration, some trim	Drywall or plaster, acoustic tile, vinyl composition, some ceramic pavers	Good lighting and plumbing, first aid and overnight care	Package A.C.
	Average	156.50	Brick, block, tilt-up, very plain finish	Drywall or plaster, acoustic tile, vinyl composition tile	Adequate lighting and plumbing for emergency first aid	Forced air
D	Excellent	253.50	Face brick or stone veneer, good ornamentation	Best plaster, paneling, carpet and vinyl tile, good reception areas	Luminous ceilings, power and X-ray outlets, good plumbing	Warm and cool air (zoned)
	Good	191.50	Brick veneer, or best stucco or siding	Drywall or plaster, acoustic tile, ceramic tile, vinyl composition	Good lighting and plumbing, first aid and overnight care	Package A.C.
	Average	147.50	Stucco or siding, very plain	Drywall, acoustic tile, vinyl composition	Adequate lighting and plumbing	Forced air
S	Average	143.00	Metal siding, finished interior	Drywall, acoustic tile, vinyl composition tile	Adequate lighting and plumbing for emergency first aid	Forced air
CDS	Storage basement	48.50	Painted interior	Paint only, few partitions	Minimum lighting, drains	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MEDICAL – URGENT CARE FACILITIES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 68,000 to $ 112,000.

For elevators over three stories and service elevators see UIP 8.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.65	$ 8.65	$ 11.27	$ 14.66
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$ 2,950 to $ 3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$ 2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	700	800	1000	1200	1400	Sq. Ft./Story
1,000	1.168	1.235	1.299	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	1.007	1.040	1.072	1.105	1.168	1.235	1.364	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	-----	.936	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	.932	.952	.975	1.018	1.061	1.105	1.146	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	-----	.926	.942	.975	1.007	1.040	1.072	1.105	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	1.105	1.155	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.910	.932	.952	.975	.997	1.018	1.061	1.105	1.146	**12,000**
14,000	-----	-----	-----	-----	-----	.900	.920	.938	.956	.975	.993	1.030	1.067	1.105	**14,000**
18,000	-----	-----	-----	-----	-----	-----	.903	.918	.932	.946	.960	.990	1.018	1.046	**18,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.910	.923	.936	.949	.975	1.000	1.027	**20,000**
25,000	-----	-----	-----	-----	-----	-----	-----	.897	.908	.918	.928	.948	.969	.990	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	-----	.897	.906	.915	.932	.949	.965	**30,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MORTUARIES (FUNERAL HOMES)



GOOD CLASS C



AVERAGE CLASS S

OCCUPANCY DESCRIPTION: These buildings include chapels, stained glass windows and laboratories commensurate with overall quality. Depending on the class of construction, they may also include incinerators. Most have combined heating and cooling systems. Plaster and drywall are used on the interior, with hardwood, carpet or resilient flooring. Adequate plumbing and lighting are used throughout.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, or mortuary equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 330.00	Ashlar and face brick, metal and glass, good architecture	Plaster, quality carpet, hardwood, slate, good detail and millwork	Good electrical/plumbing fixtures, tiled restrooms, lab	Warm and cool air (zoned)
	Average	264.50	Face brick, stone time, austere front and entrance	Plaster or drywall, hardwood, carpet, good finishes and detail	Adequate lighting/plumbing, laboratory, incinerator	Warm and cool air (zoned)
A-B	Finished basement	127.50	Finished interior	Plaster, some ceramic tile, preparation and storage rooms	Adequate lighting/plumbing utility outlets and fixtures	Forced air
	Unfin/Util	71.00	Painted interior	Utility and storage areas	Utility lighting and plumbing	None
C	Excellent	427.00	Stone, face brick, highly ornamental	Plaster, terrazzo, carpet, hardwood, good detail and millwork	Good electrical/plumbing fixtures, tiled restrooms, lab	Warm and cool air (zoned)
	Good	330.00	Face brick, some trim, good exterior detail	Plaster or drywall, hardwood or carpet, good decor	Good electrical/plumbing, tiled restrooms, lab	Heat pump system
	Average	264.50	Brick or block, some trim, good entrance and drive	Exposed block, plaster or drywall, carpet, acoustic ceiling, hardwood	Adequate lighting/plumbing, laboratory	Package A.C.
	Low cost	205.00	Block or low-cost brick	Plain, minimum service functions	Minimum lighting/plumbing	Forced air
D	Excellent	297.00	Stone or face brick veneer, highly ornamental	Plaster, terrazzo, carpet, hardwood, good detail and millwork	Good electrical/plumbing fixtures, tiled restrooms, lab	Warm and cool air (zoned)
	Good	220.50	Best stucco or siding with brick trim, brick veneer	Plaster or drywall, hardwood or carpet, good detail and decor	Good electrical/plumbing fixtures, tiled restrooms, lab	Heat pump system
	Average	164.00	Stucco or siding, some trim, good entrance and drive	Plaster or drywall, carpet, hardwood, vinyl composition, acoustic ceiling	Adequate lighting/plumbing, laboratory	Package A.C.
	Low cost	119.50	Stucco or siding, very plain	Plain, minimum service functions	Minimum lighting/plumbing	Forced air
D POLE	Low cost	105.50	Pole frame, metal siding, finished inside, very plain	Plain, minimum service functions	Minimum lighting/plumbing, small lab	Forced air
S	Average	148.50	Insulated sandwich panels	Drywall, carpet, vinyl composition	Adequate lighting/plumbing, laboratory	Package A.C.
	Low cost	105.50	Single wall, finished interior	Plain, minimum service functions	Minimum lighting/plumbing	Forced air
CDS	Finished basement	81.00	Finished interior	Plaster or drywall, some ceramic tile, preparation and storage rooms	Adequate lighting/plumbing utility outlets and fixtures	Electric wall heaters
	Unfin/Util	44.25	Unfinished interior	Unfinished floor and ceiling	Minimum lighting/plumbing	None

For parking garages, see residential garages, Page CAL 85.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MORTUARIES (FUNERAL HOMES)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push-button control, and two or three stops, costs $64,750 to $106,000

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Mortuaries with basements, add 40% to extend the foundation to the basement level. Custom oversized units can run 100% to 200% more.

TYPE	COST RANGE
One-story	$3,850 – $12,400
Two-stories	4,890 – 14,890

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 5.14	$ 6.63	$ 8.55	$ 11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
50,000	3.36	4.20	5.24	6.50

CANOPIES: This is the cantilevered portion of a building that extends over an entrance. The distance when selecting rank.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 38.00	$ 47.00	$ 58.00	$ 71.50
Light false mansard	19.05	23.55	29.00	35.75
Steel frame	44.50	56.00	70.00	87.50
Light false mansard	22.35	28.00	35.00	43.75

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
	$ 10.50	Package A.C. (short ductwork)	$ 21.90	Central refrigeration (zoned)	$ 16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector	20.75	Heat pump system	25.50	Pkg. refrig.	$2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers.	$331 to $535 per MCFM capacity
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 3.18

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	11	1.027
9	.973	12	1.055
10	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	150	200	250	300	350	400	450	500	550	600	650	700	750	800	Sq. Ft./Story
2,000	1.020	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	.970	1.000	1.042	1.083	1.123	1.165	1.206	1.247	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	.959	.989	1.021	1.052	1.083	1.113	1.043	1.175	1.206	-----	-----	-----	-----	4,000
5,000	-----	.935	.959	.984	1.009	1.034	1.059	1.083	1.108	1.133	-----	-----	-----	-----	5,000
6,000	-----	-----	.938	.959	.980	1.000	1.021	1.042	1.063	1.083	1.103	-----	-----	-----	6,000
8,000	-----	-----	-----	.929	.944	.959	.974	.989	1.005	1.021	1.037	1.052	-----	-----	8,000
10,000	-----	-----	-----	.910	.922	.935	.947	.959	.972	.984	.997	1.009	1.022	1.034	10,000
12,000	-----	-----	-----	-----	.907	.917	.928	.938	.949	.959	.970	.980	.990	1.000	12,000
14,000	-----	-----	-----	-----	-----	.906	.915	.924	.933	.942	.951	.959	.968	.977	14,000
16,000	-----	-----	-----	-----	-----	.898	.906	.913	.921	.929	.937	.944	.952	.959	16,000
18,000	-----	-----	-----	-----	-----	-----	.897	.904	.911	.917	.925	.932	.939	.945	18,000
20,000	-----	-----	-----	-----	-----	-----	-----	.898	.904	.910	.916	.922	.929	.935	20,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS



AVERAGE CLASS D



FAIR CLASS D

OCCUPANCY DESCRIPTION: Buildings which are three or fewer stories with sleeping units and without kitchens. A motel includes offices, lobby, coffee shop or restaurant, and meeting rooms commensurate with the size and the quality of the facility. These structures are either masonry or wood frame construction. Interiors are of plaster or drywall with wall coverings. Paneling and wallpaper are included in the common areas and sleeping rooms in the better qualities. Bath areas have resilient or ceramic tile floors and some ceramic tile on walls and counters.

Floor coverings in the common areas are, in most cases, carpet with some resilient flooring found in the storage and work areas. Front elevations have some glass or storefront type entries.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Bathroom plumbing and suitable heating and cooling.

NOT INCLUDED IN COSTS: Elevators, balconies, sprinklers, furnishings, or service equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 241.50	Face brick, stone, metal and glass panels, highly decorative	Plaster & vinyl finishes, good carpet, built-in luxury items, good support services.	Good lighting, many outlets, good plumbing, TV and FM circuits	Hot and chilled water (zoned)
	Good	179.50	Brick and stone trim, large glass areas, typical large chain motel	Plaster/drywall and paint, good carpet, some built-in extras, support services	Good standard lighting and plumbing fixtures, TV circuits	Warm and cool air (zoned)
	Average	130.50	Common brick or block, little ornamentation, commercial style	Painted block, drywall, few extras, carpet, vinyl composition, no food services	Adequate lighting and plumbing, TV circuits, average fixtures	Indiv. thru-wall heat pumps
	Fair	113.50	Block or brick, standard front, small lobby, vending area	Drywall, carpet, vinyl composition, minimum suites, no food services	Standard fixtures, guest laundry, small lobby, restrooms	Indiv. thru-wall heat pumps
	Low cost	94.50	Concrete block, residential sash	Painted walls, carpet, asphalt tile	Minimum code, low-cost fixtures	Wall furnace
	Cheap	79.00	Cheap block, no trim	Minimum finish, very plain	Minimum code throughout	Electric wall heater
D	Excellent	237.00	Face brick, stone veneer, metal and glass panels, highly decorative	Plaster & vinyl finishes, good carpet, built-in luxury items, good support services	Good lighting, many outlets, good plumbing, TV and FM circuits	Hot and chilled water (zoned)
	Good	176.00	Brick and stone trim, large glass areas, typical large chain motel	Plaster/drywall and paint, good carpet, some built-in extras, support services	Good standard lighting and plumbing fixtures, TV circuits	Warm and cool air (zoned)
	Average	127.00	Siding or stucco, standard front, small lobby, vending area	Drywall, carpet, vinyl composition, minimum suites, no food services	Standard fixtures, guest laundry, small lobby, restrooms	Indiv. thru-wall heat pumps
	Fair	111.00	Good stucco and siding, little ornamentation, commercial style	Drywall or plaster, few extras, carpet, vinyl composition, no food services	Adequate lighting and plumbing, TV circuits, average fixtures	Indiv. thru-wall heat pumps
	Low cost	92.00	Siding or stucco, residential sash	Drywall, carpet, asphalt tile	Minimum code, low-cost fixtures	Wall furnace
	Cheap	77.00	Cheap siding, no trim	Minimum finish, very plain	Minimum code throughout	Electric wall heater
S	Average	123.50	Insulated panels, some ornamentation	Drywall, carpet and vinyl composition, no food services	Adequate lighting and plumbing	Indiv. thru-wall heat pumps
CDS	Finished basement	73.00	Plaster or drywall interior	Plaster/drywall, vinyl composition, finished ceiling, service functions	Adequate lighting and plumbing, utility outlets and fixtures	Space heaters
	Utility basement	37.25	Unfinished	Unfinished, no ceiling, few partitions	Minimum lighting and plumbing	None
	Open mezzanine	37.00	Not included	Open, finished floors and soffit	Adequate lighting, no plumbing	In bldg. cost

For semi-basement rooms, use 85% of comparable above ground units.

MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

KITCHENETTES: For units having kitchenettes or built-in kitchen units, add the following per unit:

Excellent (stove, refrigerator, sink & cabinet unit)	$7,500
Good	5,500
Average (cabinets and sink)	4,100
Low-Cost	3,050

ELEVATORS: A small passenger or freight elevator with simple call system and push-button control, and two or three stops, costs $60,750 to $98,250
For detailed costs, see Section UIP 8

ELEVATOR STOPS: For basement stops, add $8,450 to $13,500 per stop.

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG	GOOD	EXCL
Wood frame	$33.50	$41.50	$51.00	$64.00
Light false-mansard	16.75	20.80	25.50	32.00
Steel frame	41.50	52.50	67.00	84.50
Light false-mansard	20.80	26.25	33.50	42.25

SWIMMING POOLS: Swimming pools, complete, cost $75.00 to $110.00 square foot. For detailed costs, see Section UIP 16.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$4.51	$5.78	$7.38	$9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$31.75	$40.25	$51.00	$65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$7.33	Package A.C. (short ductwork)	$14.95	Central refrigeration (zoned)	$13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$298 to $449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	11	1.06
8	.97	12	1.09
9	1.000 (base)	13	1.12
10	1.03	14	1.15

4

Total Area Sq. Ft.	NUMBER OF UNITS*																	Total Area Sq. Ft.
	Basement	4	8	12	16	20	24	28	32	36	40	45	50	60	70	80	100	
1,500	1.194	0.999	1.088	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	1.158	0.963	1.049	1.103	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	1.109	-----	0.997	1.048	1.086	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	1.076	-----	0.961	1.010	1.047	1.076	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	-----	0.934	0.982	1.018	1.046	1.070	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
6,000	1.031	-----	-----	0.959	0.994	1.022	1.045	1.066	1.084	-----	-----	-----	-----	-----	-----	-----	-----	6,000
8,000	1.000	-----	-----	-----	0.957	0.984	1.007	1.026	1.044	1.059	1.073	-----	-----	-----	-----	-----	-----	8,000
10,000	0.977	-----	-----	-----	0.929	0.955	0.977	0.996	1.013	1.028	1.042	1.057	1.071	-----	-----	-----	-----	10,000
12,000	0.958	-----	-----	-----	-----	0.932	0.954	0.973	0.989	1.004	1.017	1.032	1.046	1.070	-----	-----	-----	12,000
14,000	0.943	-----	-----	-----	-----	-----	0.935	0.953	0.969	0.984	0.997	1.011	1.025	1.049	1.069	-----	-----	14,000
16,000	0.929	-----	-----	-----	-----	-----	-----	0.936	0.952	0.966	0.979	0.994	1.007	1.030	1.050	1.068	-----	16,000
20,000	0.908	-----	-----	-----	-----	-----	-----	-----	0.925	0.938	0.951	0.965	0.978	1.001	1.020	1.037	1.067	20,000
24,000	0.890	-----	-----	-----	-----	-----	-----	-----	-----	0.915	0.927	0.941	0.954	0.976	0.995	1.012	1.041	24,000
28,000	0.876	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.906	0.920	0.932	0.954	0.973	0.990	1.018	28,000
32,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.890	0.903	0.916	0.937	0.956	0.972	1.000	32,000
36,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.889	0.901	0.922	0.941	0.957	0.984	36,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.876	0.888	0.909	0.927	0.943	0.970	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.862	0.882	0.899	0.915	0.941	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.860	0.877	0.892	0.917	60,000
70,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.859	0.874	0.898	70,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.858	0.882	80,000

***For larger number of units, enter table with 100 units and 100 times the average area per unit.**
For instance, a building with 120 units and 325 square feed per unit, use 100 units and 32,000 Sq. Ft. for a multiplier of 1.00.

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS – (ALTERNATE METHOD)
CLASSES C, D and S

OCCUPANCY DESCRIPTION:

Shell, Motel
This occupancy, together with occupancy Interior Space, Motel, allows you to individually price the shell and the tenant improvement costs for an apartment. This provides an alternative to occupancy Motel, which includes both the shell and tenant improvement costs.

These shells are motels with three or fewer stories for multiple dwelling units. The light residential framed structures are built of class C, D, and S construction.

Shell structures have good finished offices, lobby, and some coffee shop or restaurant and meeting rooms commensurate with the size and the quality of the facility. These shell structures include common area finishes only, which are about 3% - 16%. Interior build-out costs can be added using occupancy Interior Build-out.

Interior Build-out, Motel
This occupancy, together with occupancy Shell, Motel, allows you to individually price the shell and the tenant improvement costs for a multiple residence. This provides an alternative to occupancy Motel, which includes both the shell and tenant improvement costs.

The lower qualities typically have low-cost partitions and floor covers. The better qualities have plaster and vinyl finishes, good detailing in molding and trim, high cost floor finishes, and built-ins. Some of the special refinements found in the better qualities include television and FM circuits.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.
NOT INCLUDED IN COSTS: Elevators, balconies, sprinklers, furnishings or fireplaces. Office facilities not included in room costs.

SHELL MOTELS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 113.00	Face brick, stone, metal and glass panels, highly decorative	Good core lobby, good carpet, good support services	Luminous lobby ceiling, good core lighting, many service fixtures	None
	Good	87.50	Brick and stone trim, large glass areas, typical better chain motel	Good core lobby, good carpet, support services	Some good core lighting & plumbing fixtures	None
	Average	68.00	Common brick or block, little ornamentation, commercial style	Core lobby, few extras, carpet, vinyl composition, hospitality room	Adequate core lighting & plumbing	None
	Fair	60.00	Block or brick, standard front	Small core lobby, carpet, vinyl composition, no food services, small vending area	Rough-ins, standard fixtures, guest laundry, small lobby restrooms	None
	Low cost	52.50	Concrete block	Small office, carpet, vinyl composition tile	Rough electrical and plumbing, low-cost fixtures	None
	Cheap	45.00	Cheap block, no trim	Minimum finish, very plain, minimal core services	Rough electrical and plumbing	None
D	Excellent	108.50	Face brick, stone veneer, metal and glass panels, highly decorative	Good core lobby, good carpet, good support services	Luminous lobby ceiling, good core lighting, many service fixtures	None
	Good	84.00	Brick and stone trim, large glass areas, typical better chain motel	Good core lobby, good carpet, support services	Some good core lighting & plumbing fixtures	None
	Average	65.00	Good stucco and siding, little ornamentation, commercial style	Core lobby, few extras, carpet, vinyl composition, hospitality room	Adequate core lighting & plumbing	None
	Fair	56.50	Siding or stucco, standard front	Small core lobby, carpet, vinyl composition, no food services, small vending area	Rough-ins, standard fixtures, guest laundry, small lobby restrooms	None
	Low cost	50.00	Siding or stucco	Small office, carpet, vinyl composition tile	Rough electrical and plumbing, low-cost fixtures	None
	Cheap	42.00	Cheap siding, no trim	Minimum finish, very plain, minimal core services	Rough electrical and plumbing	None
S	Average	62.50	Sandwich panels, pre-engineered frame, adequate fenestration	Painted block, drywall or plaster, few extras, carpet, vinyl composition	Rough electrical and plumbing	None

INTERIOR BUILD-OUT
(SQUARE FEET OF BUILD-OUT-FINISH)

TYPE	COST/ SQ.FT.	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
Excellent	$ 128.00	Plaster & vinyl finishes, good carpet, built-in luxury items	Good lighting, many outlets, good plumbing, TV and FM circuits	Hot and chilled water
Good	91.50	Plaster/drywall and paint, good carpet, some built-in extras	Some good suites, lighting & plumbing fixtures, TV circuits	Warm and cool air
Average	61.50	Painted block, drywall or plaster, few extras, carpet, vinyl composition	Adequate lighting & plumbing, TV circuits, some good fixtures	Individual thru-wall heat pumps
Fair	53.50	Drywall, carpet, vinyl composition, minimum suites	Standard fixtures, guest laundry, small lobby restrooms	Individual thru-wall heat pumps
Low cost	41.50	Painted walls, carpet, vinyl composition tile, budget rooms	Minimum code, low-cost fixtures	Wall furnace
Cheap	34.00	Minimum finish, very plain	Minimum code throughout	Electric wall heater

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS – ALTERNATE METHOD

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

KITCHENETTES: For units having kitchenettes or built-in kitchen units, add the following per unit:

Excellent (stove, refrigerator, sink & cabinet unit)	$7,500
Good	5,500
Average (cabinets and sink)	4,100
Low-Cost	3,050

ELEVATORS: A small passenger or freight elevator with simple call system and push-button control, and two or three stops, costs $60,750 to $98,250
For detailed costs, see Section UIP 8

ELEVATOR STOPS: For basement stops, add $8,450 to $13,500 per stop.

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG	GOOD	EXCL
Wood frame	$33.50	$41.50	$51.00	$64.00
Light false-mansard	16.75	20.80	25.50	32.00
Steel frame	41.50	52.50	67.00	84.50
Light false-mansard	20.80	26.25	33.50	42.25

SWIMMING POOLS: Swimming pools, complete, cost $75.00 to $110.00 square foot. For detailed costs, see Section UIP 16.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$4.51	$5.78	$7.38	$9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$31.75	$40.25	$51.00	$65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$7.33	Package A.C. (short ductwork)	$14.95	Central refrigeration (zoned)	$13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$298 to $449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825 per ton of rated capacity.		**VENTILATION ONLY**	
Wall or floor furnace	3.42			Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	11	1.06
8	.97	12	1.09
9	1.000 (base)	13	1.12
10	1.03	14	1.15

4

Total Area	NUMBER OF GUEST ROOM UNITS*																		Total Area
Sq. Ft.	Basement	4	8	12	16	20	24	28	32	36	40	45	50	60	70	80	100	Sq. Ft.
1,500	1.194	0.999	1.088	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	1.158	0.963	1.049	1.103	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	1.109	-----	0.997	1.048	1.086	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	1.076	-----	0.961	1.010	1.047	1.076	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	-----	0.934	0.982	1.018	1.046	1.070	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
6,000	1.031	-----	-----	0.959	0.994	1.022	1.045	1.066	1.084	-----	-----	-----	-----	-----	-----	-----	-----	6,000
8,000	1.000	-----	-----	-----	0.957	0.984	1.007	1.026	1.044	1.059	1.073	-----	-----	-----	-----	-----	-----	8,000
10,000	0.977	-----	-----	-----	0.929	0.955	0.977	0.996	1.013	1.028	1.042	1.057	1.071	-----	-----	-----	-----	10,000
12,000	0.958	-----	-----	-----	-----	0.932	0.954	0.973	0.989	1.004	1.017	1.032	1.046	1.070	-----	-----	-----	12,000
14,000	0.943	-----	-----	-----	-----	-----	0.935	0.953	0.969	0.984	0.997	1.011	1.025	1.049	1.069	-----	-----	14,000
16,000	0.929	-----	-----	-----	-----	-----	-----	0.936	0.952	0.966	0.979	0.994	1.007	1.030	1.050	1.068	-----	16,000
20,000	0.908	-----	-----	-----	-----	-----	-----	-----	0.925	0.938	0.951	0.965	0.978	1.001	1.020	1.037	1.067	20,000
24,000	0.890	-----	-----	-----	-----	-----	-----	-----	-----	0.915	0.927	0.941	0.954	0.976	0.995	1.012	1.041	24,000
28,000	0.876	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.906	0.920	0.932	0.954	0.973	0.990	1.018	28,000
32,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.890	0.903	0.916	0.937	0.956	0.972	1.000	32,000
36,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.889	0.901	0.922	0.941	0.957	0.984	36,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.876	0.888	0.909	0.927	0.943	0.970	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.862	0.882	0.899	0.915	0.941	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.860	0.877	0.892	0.917	60,000
70,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.859	0.874	0.898	70,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.858	0.882	80,000

*For larger number of units, enter table with 100 units and 100 times the average area per unit.
For instance, a building with 120 units and 325 square feed per unit, use 100 units and 32,000 Sq. Ft. for a multiplier of 1.00.

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS – ALTERNATE METHOD



LOW COST CLASS C

OCCUPANCY DESCRIPTION: Office/apartment costs are to be used in conjunction with the motel room or independently as typically encountered in mobile home parks, mini-warehouse developments, etc. Basic office lobby and living quarters commensurate with the quality level are included.

Motel room costs are for the guest sleeping rooms only.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, balconies, sprinklers, furnishings or fireplaces. Office facilities not included in room costs.

NOTE: This method is presented as an alternative to the normal method which includes average office-lobby-apartment, dining and meeting space and guest sleeping room costs commensurate with the occupancy type and quality level. Listed below are typical office apartment and separate sleeping room space costs which can be added together for a complete facility cost. Restaurant costs, convention/conference centers and clubhouses must be added separately. Guest room costs given below are for double row (back to back) units. Add 8% for single row (side by side) units. Costs are for two-story guestroom units. For one-story units, add 4%; three-story, deduct 1%.

OFFICE APARTMENTS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 260.50	Face brick, stone, metal and glass panels, highly decorative lobby	Plaster and vinyl finishes, good carpet and common area items	Good lighting, many outlets, good plumbing, public restrooms	Warm and cool air (zoned)
	Good	189.00	Brick and stone trim, large glass areas, good lobby entry	Plaster/drywall and paint, good carpet, some built-in extras	Good standard lighting and apartment plumbing fixtures	Package A.C.
	Average	134.00	Common brick or block, little ornamentation, commercial front	Painted block, drywall, few extras, carpet, vinyl comp. tile, adequate apartment	Adequate lighting and plumbing, average residence fixtures	Forced air
	Low cost	94.00	Block or cheap brick, low-cost roof, sash and office entrance	Gypsum board and paint, asphalt tile, low-cost cabinets, living quarters	Minimum, low-cost fixtures and residence plumbing	Wall furnace
	Cheap	78.00	Inexpensive block, small entry, little glass or trim	Registration office only, low-cost counters, vinyl composition	Minimum office lighting, outlets and plumbing	Electric wall heater
D	Excellent	256.50	Face brick, stone veneer, metal and glass panels, highly decorative lobby	Plaster and vinyl finishes, good carpet and common area items	Good lighting, many outlets, good plumbing, public restrooms	Warm and cool air (zoned)
	Good	185.50	Brick and stone trim, large glass areas, good lobby entry	Plaster/drywall and paint, good carpet, some built-in extras	Good standard lighting and apartment plumbing fixtures	Package A.C.
	Average	130.50	Good stucco and siding, little ornamentation, commercial front	Drywall or plaster, few extras, carpet, vinyl composition, adequate apartment	Adequate lighting and plumbing, average residence fixtures	Forced air
	Low cost	91.00	Siding or stucco, low-cost roof, sash and office entrance	Gypsum board and paint, asphalt tile, low-cost cabinets, living quarters	Minimum, low-cost fixtures and residence plumbing	Wall furnace
	Cheap	75.50	Stucco or siding, plain small entry, little glass or trim	Registration office only, low-cost counters, vinyl composition	Minimum office lighting, outlets and plumbing	Electric wall heater
S	Average	128.00	Insulated panels, some ornamentation, commercial front	Drywall, carpet and vinyl composition, few extras, adequate apartment	Adequate lighting and plumbing, average residence fixtures	Forced air

MOTEL GUEST ROOMS

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 231.00	Face brick, stone, metal and glass panels, highly decorative	Plaster and vinyl finishes, good carpet and built-in luxury items	Good lighting, many outlets, good plumbing, TV and FM circuits	Hot and chilled water (zoned)
	Good	174.00	Brick and stone trim, large window areas, typical large chain motel	Plaster/drywall and paint, good carpet, some built-in extras	Good standard lighting and plumbing fixtures, TV circuits	Warm and cool air (zoned)
	Average	128.50	Common brick or block, little ornamentation, commercial style	Painted block, drywall, few extras, carpet, vinyl composition	Adequate lighting and plumbing, TV circuits, average fixtures	Indiv. thru-wall heat pumps
	Low cost	94.50	Concrete block, residential sash	Painted walls, carpet, asphalt tile	Minimum code, low-cost fixtures	Wall furnace
	Cheap	79.00	Cheap block, no trim	Minimum finish, very plain	Minimum code throughout	Electric wall heater
D	Excellent	226.50	Face brick, stone veneer, metal and glass panels, highly decorative	Plaster and vinyl finishes, good carpet and built-in luxury items	Good lighting, many outlets, good plumbing, TV and FM circuits	Hot and chilled water (zoned)
	Good	170.50	Brick and stone trim, large window areas, typical large chain motel	Plaster/drywall and paint, good carpet, some built-in extras	Good standard lighting and plumbing fixtures, TV circuits	Warm and cool air (zoned)
	Average	125.00	Good stucco and siding, little ornamentation, commercial style	Drywall or plaster, few extras, carpet, vinyl composition	Adequate lighting and plumbing, TV circuits, average fixtures	Indiv. thru-wall heat pumps
	Low cost	92.00	Siding or stucco, residential sash	Drywall, carpet, asphalt tile	Minimum code, low-cost fixtures	Wall furnace
	Cheap	77.00	Cheap siding, no trim	Minimum finish, very plain	Minimum code throughout	Electric wall heater
S	Average	121.50	Insulated panels, some ornamentation	Drywall, carpet and vinyl composition	Adequate lighting and plumbing, TV circuits, average fixtures	Indiv. thru-wall heat pumps

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS – ALTERNATE METHOD

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

KITCHENETTES: For units having kitchenettes or built-in kitchen units, add the following per unit:

Excellent (stove, refrigerator, sink & cabinet unit)	$7,500
Good	5,500
Average (cabinets and sink)	4,100
Low-Cost	3,050

ELEVATORS: A small passenger or freight elevator with simple call system and push-button control, and two or three stops, costs $60,750 to $98,250
For detailed costs, see Section UIP 8

ELEVATOR STOPS: For basement stops, add $8,450 to $13,500 per stop.

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG	GOOD	EXCL
Wood frame	$33.50	$41.50	$51.00	$64.00
Light false-mansard	16.75	20.80	25.50	32.00
Steel frame	41.50	52.50	67.00	84.50
Light false-mansard	20.80	26.25	33.50	42.25

SWIMMING POOLS: Swimming pools, complete, cost $75.00 to $110.00 square foot. For detailed costs, see Section UIP 16.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$4.51	$5.78	$7.38	$9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$31.75	$40.25	$51.00	$65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$7.33	Package A.C. (short ductwork)	$14.95	Central refrigeration (zoned)	$13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$298 to $449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825 per ton of rated capacity.		**VENTILATION ONLY**	
Wall or floor furnace	3.42			Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	11	1.06
8	.97	12	1.09
9	1.000 (base)	13	1.12
10	1.03	14	1.15

4

Total Area	NUMBER OF GUEST ROOM UNITS*												Total Area	Independent
Sq. Ft.	8	12	16	20	24	28	32	36	40	50	80	100	Sq. Ft.	Offices
1,500	1.088	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	100	1.20
2,000	1.049	1.103	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	200	1.11
4,000	0.961	1.010	1.047	1.076	-----	-----	-----	-----	-----	-----	-----	-----	300	1.06
6,000	-----	0.959	0.994	1.022	1.045	1.066	1.084	-----	-----	-----	-----	-----	400	1.03
8,000	-----	-----	0.957	0.984	1.007	1.026	1.044	1.059	1.073	-----	-----	-----	500	1.00
10,000	-----	-----	0.929	0.955	0.977	0.996	1.013	1.028	1.042	1.071	-----	-----	600	0.98
12,000	-----	-----	-----	0.932	0.954	0.973	0.989	1.004	1.017	1.046	-----	-----	700	0.96
14,000	-----	-----	-----	-----	0.935	0.953	0.969	0.984	0.997	1.025	-----	-----	800	0.95
20,000	-----	-----	-----	-----	-----	-----	0.925	0.938	0.951	0.978	1.037	1.067	900	0.93
24,000	-----	-----	-----	-----	-----	-----	-----	0.915	0.927	0.954	1.012	1.041	1,000	0.92
32,000	-----	-----	-----	-----	-----	-----	-----	-----	0.890	0.916	0.972	1.000	1,200	0.90
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.888	0.943	0.970	1,400	0.89

*For larger numbers of units, enter table with 100 units and 100 times the average area per unit.
For instance, a building with 120 units and 325 square feet per unit, use 100 units and 32,000 Sq. Ft. for a multiplier of 1.00.

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS – EXTENDED STAY



GOOD CLASS D



GOOD CLASS D

OCCUPANCY DESCRIPTION: These buildings are three stories or fewer with sleeping units and kitchen facilities, including offices, laundry, lobby, and some recreation space commensurate with the size and the quality of the facility. Restaurants, clubhouses, convention halls, etc., connected with an extended stay motel, should be priced separately.

These structures are built of either masonry or wood or wood frame construction. Low end budget facilities are single rooms with low-cost finishes throughout and include a minimal kitchenette area. Better qualities are all suite sleeping rooms with good kitchens, and include paneling and wallpaper in the common areas.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Allowance for lobby area and interior hall access to dwelling units. Elevators are included where designated with an asterisk (*).

NOT INCLUDED IN COSTS: Appliances, elevators, sprinklers, fireplaces, canopies, balconies, swimming pools, yard improvements and any developers' or soft costs related to a type of ownership such as condominium.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 193.50	Face brick, stone trim, some decoration, good chain motel	Plastic and vinyl, good lobby and support and recreation services	Good lighting, communication outlets, good plumb., kitchen area	Warm and cool air
	Good	155.50	Brick and stone trim, good glass areas, typical upscale motel	Plaster/drywall and vinyl, good carpet, some built-in extras, all suites	Good lighting and plumbing, wet bar, kitchen, TV circuits	Package A.C.
	Average	123.00	Common brick or block, little ornamentation, good lobby	Painted block, drywall, few extras, carpet, VCT, mixed offsets and suites	Adequate lighting and plumbing, TV circuits, average kitchen	Indiv. thru-wall heat pumps
	Fair	111.00	Block or brick, standard to better economy motel	Drywall, carpet, vinyl composition, interior corridor, offset food area	Standard fixtures and kitchenette space	Indiv. thru-wall heat pumps
	Low cost	100.50	Block or cheap brick, low-cost roof, small office, budget type	Gypsum board & paint, VCT, carpet, low-cost cabinets, single rooms	Minimum, low-cost fixtures, minimum kitchenette area	Indiv. thru-wall heat pumps
D	Excellent	187.50	Face brick veneer, stone trim, some decoration, good chain motel	Plaster and vinyl, good lobby and support and recreation services	Good lighting, communication outlets, good plumb., kitchen area	Warm and cool air
	Good	152.00	Brick veneer, EIFS, good glass areas, typical upscale motel	Plaster/drywall and vinyl, good carpet, some built-in extras, all suites	Good lighting and plumbing, wet bar, kitchen, TV circuits	Package A.C.
	Average	119.50	Good stucco and siding, little ornamentation, good lobby	Drywall or plaster, few extras, carpet, vinyl comp., mixed offsets and suites	Adequate lighting and plumbing, TV circuits, average kitchen	Indiv. thru-wall heat pumps
	Fair	108.00	Siding or stucco, standard to better economy motel	Drywall, carpet, vinyl composition, interior corridor, offset food area	Standard fixtures and kitchenette space	Indiv. thru-wall heat pumps
	Low cost	98.50	Low-cost siding, roof, small office, budget type	Drywall and paint, VCT, carpet, low-cost cabinets, single rooms	Minimum low-cost fixtures, minimum kitchenette area	Indiv. thru-wall heat pumps

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS – EXTENDED STAY

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

KITCHENETTES: For units having kitchenettes or built-in kitchen units, add the following per unit:

Excellent (stove, refrigerator, sink & cabinet unit)	$7,500
Good	5,500
Average (cabinets and sink)	4,100
Low-Cost	3,050

ELEVATORS: A small passenger or freight elevator with simple call system and push-button control, and two or three stops, costs $60,750 to $ 98,250
For detailed costs, see Section UIP 8

ELEVATOR STOPS: For basement stops, add $ 8,450 to $13,500 per stop.

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG	GOOD	EXCL
Wood frame	$33.50	$41.50	$51.00	$ 64.00
Light false-mansard	16.75	20.80	25.50	32.00
Steel frame	41.50	52.50	67.00	84.50
Light false-mansard	20.80	26.25	33.50	42.25

SWIMMING POOLS: Swimming pools, complete, cost $ 75.00 to $ 110.00 square foot. For detailed costs, see Section UIP 16.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 4.51	$ 5.78	$ 7.38	$ 9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 40.25	$ 51.00	$ 65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $ 2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$ 298 to $ 449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $ 2,825 per ton of rated capacity.		**VENTILATION ONLY**	
Wall or floor furnace	3.42			Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	11	1.06
8	.97	12	1.09
9	1.000 (base)	13	1.12
10	1.03	14	1.15

4

Total Area	NUMBER OF UNITS																	Total Area
Sq. Ft.	Basement	4	8	12	16	20	24	28	32	36	40	45	50	60	70	80	100	Sq. Ft.
1,500	1.194	0.999	1.088	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	1.158	0.963	1.049	1.103	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	1.109	-----	0.997	1.048	1.086	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	1.076	-----	0.961	1.010	1.047	1.076	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	-----	0.934	0.982	1.018	1.046	1.070	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
6,000	1.031	-----	-----	0.959	0.994	1.022	1.045	1.066	1.084	-----	-----	-----	-----	-----	-----	-----	-----	6,000
8,000	1.000	-----	-----	-----	0.957	0.984	1.007	1.026	1.044	1.059	1.073	-----	-----	-----	-----	-----	-----	8,000
10,000	0.977	-----	-----	-----	0.929	0.955	0.977	0.996	1.013	1.028	1.042	1.057	1.071	-----	-----	-----	-----	10,000
12,000	0.958	-----	-----	-----	-----	0.932	0.954	0.973	0.989	1.004	1.017	1.032	1.046	1.070	-----	-----	-----	12,000
14,000	0.943	-----	-----	-----	-----	-----	0.935	0.953	0.969	0.984	0.997	1.011	1.025	1.049	1.069	-----	-----	14,000
16,000	0.929	-----	-----	-----	-----	-----	-----	0.936	0.952	0.966	0.979	0.994	1.007	1.030	1.050	1.068	-----	16,000
20,000	0.908	-----	-----	-----	-----	-----	-----	-----	0.925	0.938	0.951	0.965	0.978	1.001	1.020	1.037	1.067	20,000
24,000	0.890	-----	-----	-----	-----	-----	-----	-----	-----	0.915	0.927	0.941	0.954	0.976	0.995	1.012	1.041	24,000
28,000	0.876	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.906	0.920	0.932	0.954	0.973	0.990	1.018	28,000
32,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.890	0.903	0.916	0.937	0.956	0.972	1.000	32,000
36,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.889	0.901	0.922	0.941	0.957	0.984	36,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.876	0.888	0.909	0.927	0.943	0.970	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.862	0.882	0.899	0.915	0.941	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.860	0.877	0.892	0.917	60,000
70,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.859	0.874	0.898	70,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.858	0.882	80,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS – EXTENDED STAY (ALTERNATE METHOD)

OCCUPANCY DESCRIPTION: Shell, This occupancy, together with occupancy Interior Build-out, Motel - Extended Stay, allows you to individually price the shell and the tenant improvement costs for an apartment (in separate sections of the report). This provides an alternative to occupancy Extended Stay - Motel, which includes both the shell and tenant improvement costs.

These shells are extended-stay motel with three or fewer stories for multiple dwelling units. The light residential framed structures are built of class C and D construction. Each dwelling unit consists of its own separate living area, bath, and kitchen facility.

Better shell structures have good finished lobbies, recreation and service areas, interior hall access to dwelling units and some type of stairway for fire exit. These shell structures include common area finishes only, which are about 3% - 16%. Interior build-out costs can be added using occupancy Interior Space, Motel - Extended Stay in an additional section.

Interior Build-out,
This occupancy, together with occupancy Shell, Motel - Extended Stay, allows you to individually price the shell and the tenant improvement costs for a multiple residence (in separate sections of the report). This provides an alternative to occupancy Motel- Extended Stay, which includes both the shell and tenant improvement costs.

The lower qualities typically have low-cost partitions, floor covers and a kitchenette area. The better qualities have plaster and vinyl finishes, good detailing in molding and trim, high cost floor finishes, built-ins, and kitchen area. Some of the special refinements found in the better qualities include television and FM circuits and communication outlets.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Allowance for lobby area and interior hall access to dwelling units. Elevators are included where designated with an asterisk (*).

NOT INCLUDED IN COSTS: Appliances, elevators, sprinklers, fireplaces, canopies, balconies, swimming pools, yard improvements and any developers' or soft costs related to a type of ownership such as condominium.

SHELL EXTENDED STAY - MOTELS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 106.00	Face brick, stone trim, some decoration, good chain motel	Good lobby and support/recreation services, good carpet	Luminous lobby ceiling, good core lighting, many service fixtures	None
	Good	87.50	Brick and stone trim, good glass areas, typical upscale motel	Good lobby and support services, good carpet	Some good core lighting & plumbing fixtures	None
	Average	72.00	Common brick or block, little ornamentation	Good lobby, few extras, carpet, VCT	Adequate core lighting & plumbing	None
	Fair	65.50	Block or brick, standard to better economy motel	Small office and interior corridor, carpet, vinyl composition	Rough-ins, standard fixtures, guest laundry, small lobby restrooms	None
	Low cost	59.50	Block or cheap brick, low-cost roof, budget type	Small office, VCT, carpet	Rough electrical and plumbing, low-cost fixtures	None
D	Excellent	100.00	Face brick veneer, stone trim, some decoration, good chain motel	Good lobby and support/recreation services, good carpet	Luminous lobby ceiling, good core lighting, many service fixtures	None
	Good	82.50	Brick veneer, EIFS, good glass areas, typical upscale motel	Good lobby and support services, good carpet	Some good core lighting & plumbing fixtures	None
	Average	68.50	Good stucco and siding, little ornamentation	Good lobby, few extras, carpet, VCT	Adequate core lighting & plumbing	None
	Fair	62.00	Siding or stucco, standard to better economy motel	Small office and interior corridor, carpet, vinyl composition	Rough-ins, standard fixtures, guest laundry, small lobby restrooms	None
	Low cost	56.50	Low-cost siding, roof, budget type	Minimum finish, very plain	Rough electrical and plumbing, low-cost fixtures	None

INTERIOR BUILD-OUT

(SQUARE FEET OF BUILD-OUT-FINISH)

TYPE	COST/ SQ.FT.	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
Excellent	$ 87.00	Plaster and vinyl, good carpet, some built-in luxury items, all suites	Good lighting, communication outlets, good plumb., kitchen area	Warm and cool air
Good	68.00	Plaster/drywall and vinyl, good carpet, some built-in extras, all suites	Good lighting & plumbing, wet bar, kitchen, TV circuits	Package AC
Average	50.50	Painted block, drywall or plaster, few extras, carpet, VCT, mixed offsets and suites	Adequate lighting & plumbing, TV circuits, average kitchen	Individual thru-wall heat pumps
Low cost	45.50	Drywall, carpet, vinyl composition, interior corridor, offset food area	Standard fixtures and kitchenette space	Individual thru-wall heat pumps
Cheap	41.50	Gypsum board & paint, VCT, carpet, low-cost cabinets, single rooms	Minimum, low-cost fixtures, minimum kitchenette area	Individual thru-wall heat pumps

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS – EXTENDED STAY (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

KITCHENETTES: For units having kitchenettes or built-in kitchen units, add the following per unit:

Excellent (stove, refrigerator, sink & cabinet unit)	$7,500
Good	5,500
Average (cabinets and sink)	4,100
Low-Cost	3,050

ELEVATORS: A small passenger or freight elevator with simple call system and push-button control, and two or three stops, costs $60,750 to $98,250
For detailed costs, see Section UIP 8

ELEVATOR STOPS: For basement stops, add $8,450 to $13,500 per stop.

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG	GOOD	EXCL
Wood frame	$33.50	$41.50	$51.00	$64.00
Light false-mansard	16.75	20.80	25.50	32.00
Steel frame	41.50	52.50	67.00	84.50
Light false-mansard	20.80	26.25	33.50	42.25

SWIMMING POOLS: Swimming pools, complete, cost $75.00 to $110.00 square foot. For detailed costs, see Section UIP 16.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$4.51	$5.78	$7.38	$9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$31.75	$40.25	$51.00	$65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$7.33	Package A.C. (short ductwork)	$14.95	Central refrigeration (zoned)	$13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$298 to $449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825 per ton of rated capacity.		**VENTILATION ONLY**	
Wall or floor furnace	3.42			Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	11	1.06
8	.97	12	1.09
9	1.000 (base)	13	1.12
10	1.03	14	1.15

4

Total Area Sq. Ft.	NUMBER OF UNITS																	Total Area Sq. Ft.
	Basement	4	8	12	16	20	24	28	32	36	40	45	50	60	70	80	100	
1,500	1.194	0.999	1.088	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	1.158	0.963	1.049	1.103	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	1.109	-----	0.997	1.048	1.086	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	1.076	-----	0.961	1.010	1.047	1.076	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	-----	0.934	0.982	1.018	1.046	1.070	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
6,000	1.031	-----	-----	0.959	0.994	1.022	1.045	1.066	1.084	-----	-----	-----	-----	-----	-----	-----	-----	6,000
8,000	1.000	-----	-----	-----	0.957	0.984	1.007	1.026	1.044	1.059	1.073	-----	-----	-----	-----	-----	-----	8,000
10,000	0.977	-----	-----	-----	0.929	0.955	0.977	0.996	1.013	1.028	1.042	1.057	1.071	-----	-----	-----	-----	10,000
12,000	0.958	-----	-----	-----	-----	0.932	0.954	0.973	0.989	1.004	1.017	1.032	1.046	1.070	-----	-----	-----	12,000
14,000	0.943	-----	-----	-----	-----	-----	0.935	0.953	0.969	0.984	0.997	1.011	1.025	1.049	1.069	-----	-----	14,000
16,000	0.929	-----	-----	-----	-----	-----	-----	0.936	0.952	0.966	0.979	0.994	1.007	1.030	1.050	1.068	-----	16,000
20,000	0.908	-----	-----	-----	-----	-----	-----	-----	0.925	0.938	0.951	0.965	0.978	1.001	1.020	1.037	1.067	20,000
24,000	0.890	-----	-----	-----	-----	-----	-----	-----	-----	0.915	0.927	0.941	0.954	0.976	0.995	1.012	1.041	24,000
28,000	0.876	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.906	0.920	0.932	0.954	0.973	0.990	1.018	28,000
32,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.890	0.903	0.916	0.937	0.956	0.972	1.000	32,000
36,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.889	0.901	0.922	0.941	0.957	0.984	36,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.876	0.888	0.909	0.927	0.943	0.970	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.862	0.882	0.899	0.915	0.941	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.860	0.877	0.892	0.917	60,000
70,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.859	0.874	0.898	70,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.858	0.882	80,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS – RECREATIONAL (POOL) ENCLOSURES



GOOD CLASS D



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These structures are designed specifically to shelter swimming facilities from the elements. The lowest quality pre-engineered structures are light, residential, patio type enclosures only, while the better qualities are typical of hotel/motel-type facilities with ancillary restrooms, exercise or lounge finishes commensurate with the quality level.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers or pool costs.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 114.00	Face brick or block, good fenestration or good skylights, operable windows	Good flooring, lounge area, add for pool and spa	Good lighting, large tiled restrooms, some extras, sauna	Space heaters
	Average	76.50	Ornamental block, brick, good knee wall or fenestration, shingles	Concrete deck, few partitions, add for pool and spa	Adequate lighting and water service, small restrooms	Space heaters
	Low cost	47.50	Block or tilt-up, light frame, very plain, composition or metal roof	Light slab area, low-cost finishes, add for pool	Minimum lighting, no restrooms	None
D	Good	106.00	Masonry veneer, good fenestration or good skylights, operable windows	Good flooring, lounge area, add for pool and spa	Good lighting, large tiled restrooms, some extras, sauna	Space heaters
	Average	70.50	Brick veneer, good siding, good knee wall or fenestration, shingles	Concrete deck, few partitions, add for pool and spa	Adequate lighting and water service, small restrooms	Space heaters
	Low cost	42.00	Stucco or siding, light frame, very plain, composition or metal roof	Light slab area, low-cost finishes, add for pool	Minimum lighting, no restrooms	None
D POLE	Low cost	37.00	Post frame, low-cost metal panels, plastic, screens or knee wall	Light slab area, low-cost finishes, add for pool	Minimum lighting, no restrooms	None
S	Good	101.50	Sandwich panels, good fenestration or good skylights, operable windows	Good flooring, lounge area, add for pool and spa	Good lighting, large tiled restrooms, some extras, sauna	Space heaters
	Average	65.00	Good panels, knee wall or good glazing, insulated roof panels	Concrete deck, few partitions, add for pool and spa	Adequate lighting and water service, small restrooms	Space heaters
	Low cost	37.50	Pre-engineered, low-cost panels, plastic, screens or knee wall	Light slab area, low-cost finishes, add for pool	Minimum lighting, no restrooms	None
	Cheap	23.50	Screen enclosure only, light frame	Some concrete, add for pool	Minimum service	None

NOTE: Air-inflated (bubble) building costs are found in Section UIP 17.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MOTELS – RECREATIONAL (POOL) ENCLOSURES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

KITCHENETTES: For units having kitchenettes or built-in kitchen units, add the following per unit:

Excellent (stove, refrigerator, sink & cabinet unit)	$ 7,500
Good	5,500
Average (cabinets and sink)	4,100
Low-Cost	3,050

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 5.73	$ 7.43	$ 9.62	$ 12.45
3,000	5.14	6.63	8.55	11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
15,000	4.03	5.09	6.44	8.15
20,000	3.87	4.87	6.10	7.69

SWIMMING POOLS: Swimming pools, complete, cost $90.00 to $129.00 per square foot. For detailed costs, see Section UIP 16.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork)	$ 21.90	Central refrigeration (zoned)	$ 16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector	20.75	Heat pump system	25.50	Pkg. refrig.	$2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers.	$331 to $535 per MCFM capacity
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 3.18

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	14	1.114
9	.973	16	1.175
10	1.000 (base)	18	1.240
12	1.055	20	1.309

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	150	200	250	300	350	400	450	500	550	600	650	700	750	800	Sq. Ft./Story
1,000	1.150	1.310	1.370	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	1.020	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	.970	1.000	1.042	1.083	1.123	1.165	1.206	1.247	1.288	-----	-----	-----	-----	-----	3,000
4,000	.930	.959	.989	1.021	1.052	1.083	1.113	1.143	1.175	1.206	1.237	1.268	-----	-----	4,000
5,000	-----	.935	.959	.984	1.009	1.034	1.059	1.083	1.108	1.133	1.157	1.181	-----	-----	5,000
7,000	-----	-----	.924	.942	.959	.977	.994	1.011	1.029	1.047	1.065	1.083	1.101	1.118	7,000
10,000	-----	-----	-----	-----	.922	.935	.947	.939	.972	.984	.997	1.009	1.022	1.034	10,000
12,000	-----	-----	-----	-----	.907	.917	.928	.938	.949	.959	.970	.980	.990	1.000	12,000
14,000	-----	-----	-----	-----	-----	.906	.915	.924	.933	.942	.951	.959	.968	.977	14,000
18,000	-----	-----	-----	-----	-----	-----	.897	.904	.911	.917	.925	.932	.939	.945	18,000
22,000	-----	-----	-----	-----	-----	-----	-----	.892	.898	.903	.909	.915	.920	.926	22,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES



AVERAGE CLASS D



AVERAGE CLASS D

OCCUPANCY DESCRIPTION: These structures are three stories or fewer, with each unit having a kitchen and at least one bath. They are designed for permanent occupancy or semi-permanent. The best qualities have combined heating and cooling systems. They also have plaster, paneling, good detailing in molding and trim, and high cost floor finishes. The structures commonly are solid masonry or wood frame walls (Classes C and D). Some of the special refinements found in the better qualities include intercoms, television jacks and antenna and at least one bath per bedroom. The lower qualities typically have one bath or a bath and one-half for each unit, regardless of the number of bedrooms. The typical story height for these structures is 9 feet.

NOTE: The assessor will frequently encounter three story multiple residences where the bottom floor is partially below ground level and partially above. This type of building should be priced as a two story plus basement.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Intercoms and master antenna/cable services as indicated.

NOT INCLUDED IN COSTS: Elevators, sprinklers, balconies, fireplaces, built-in appliances, furnishings or equipment. Garages or carports can be found on the Garages – Residential cost page.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 202.00	Face brick, concrete/metal panels, best roof structure and roofing	Good plaster and paint, paneling, fine detail, hardwood, carpet	Good fixtures, many outlets, central TV antenna, intercoms	Warm and cool air (zoned)
	Good	151.00	Good brick/stucco on block, good trim, roof structure and roofing	Good plaster or drywall, hardwood, carpet, vinyl composition	Good lighting, one bath per bedroom, TV antenna	Package A.C.
	Average	110.50	Brick or block, some trim, asphalt shingle or built-up roof	Plaster/drywall, paint, hardwood, carpet, vinyl composition	Adequate lighting/plumbing, phone and TV jacks	Forced air
	Fair	95.50	Block/brick, standard sash, little trim, shingle or built-up roof	Drywall or plaster, carpet, vinyl composition tile	Adequate standard lighting and plumbing per good codes	Electric baseboard
	Low cost	80.00	Low-cost brick or block, very plain, minimum fenestration	Painted block, drywall partitions, low-cost carpet or asphalt tile	Minimum lighting/plumbing per code	Wall furnace
D MASONRY VENEER	Excellent	201.00	Face brick, stone veneer, good wood or steel frame and roof structure	Good plaster, paint, paneling, fine detail, hardwood, carpet	Good fixtures, many outlets, central TV antenna, intercoms	Warm and cool air (zoned)
	Good	149.50	Good brick veneer and fenestration, good roof structure and roofing	Good plaster and drywall, painted, hardwood, vinyl composition, carpet	Good lighting, one bath per bedroom, TV antenna	Package A.C.
	Average	109.00	Brick veneer, some ornamentation, average code construction	Plaster or drywall, hardwood, vinyl composition, carpet	Adequate lighting/plumbing, phone and TV jacks	Forced air
	Fair	94.00	Brick veneer, little trim, standard sash, asphalt shingle or built-up roof	Drywall or plaster, carpet, vinyl composition tile	Adequate standard lighting and plumbing per good codes	Electric baseboard
	Low cost	79.00	Low-cost brick, block veneer, very plain, minimum fenestration	Drywall and paint, asphalt tile and low-cost carpet	Minimum lighting/plumbing per code	Wall furnace
D	Excellent	196.50	Best stucco or siding, brick and stone trim, heavy basic structure	Good plaster, paint, paneling, fine detail, hardwood, carpet	Good fixtures, many outlets, central TV antenna, intercoms	Warm and cool air (zoned)
	Good	145.50	Good stucco or siding, some brick or stone trim, good roof	Good plaster or drywall, painted, hardwood, vinyl composition, carpet	Good lighting, one bath per bedroom, TV antenna	Package A.C.
	Average	105.50	Stucco/siding, some ornamentation, average code construction	Plaster or drywall, hardwood, vinyl composition, carpet	Adequate lighting/plumbing, phone and TV jacks	Forced air
	Fair	91.50	Stucco or siding, standard sash, asphalt shingles/built-up roof	Drywall or plaster, carpet, vinyl composition tile	Adequate standard lighting and plumbing per good codes	Electric baseboard
	Low cost	76.00	Low-cost stucco or siding, very plain, minimum fenestration	Drywall and paint, asphalt tile and low-cost carpet	Minimum lighting/plumbing per code	Wall furnace
S	Good	141.50	Good sandwich panels on pre-engineered frame, good fenestration	Gypsum board and plastics, carpet and vinyl composition	Good lighting, one bath per bedroom, TV antenna	Package A.C.
	Average	103.00	Sandwich panels, pre-engineered frame, adequate fenestration	Gypsum board, vinyl composition, carpet	Adequate lighting/plumbing, phone and TV jacks	Forced air
CDS†	Finished basement	48.75	Finished interior, add for saunas, pools, bars and equipment	Gypsum board ceiling, vinyl composition tile, or sheet vinyl	Adequate lighting/plumbing	None
	Unfin. bsmnt	34.50	Few partitions, little or no finish	Unfinished ceiling, slab, storage only	Minimum lighting/plumbing	None
	Finished mezzanine	70.00	Not included	Drywall, vinyl, some tile, carpet, VCT, finished loft	Adequate lighting and plumbing, extra outlets and fixtures	In building cost
	Open mezzanine	44.75	Not included	Finished floors, few partitions, open sleeping loft	Average lighting, no plumbing	In building cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $ 8.62 per square foot.
For basement apartments, use 80% of comparable above ground units. For semi-basement apartments, use 90%.
For parking basements, see CAL 210.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated costs, Section SEG 2.

	LOW	AVG	GOOD	EXCL
Allowance (if not itemized)	$1,820	$4,150	$7,550	$12,800

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Multiples with basements, add 40% to extend the foundation to the basement level. Custom oversized units can run 100% to 200% more.

TYPE	COST RANGE
One-story	$ 3,675 – $ 11,800
Two-stories	4,655 – 14,170
Three-stories	5,635 – 16,540

ELEVATORS: A small passenger or freight elevator with simple call system and push-button control, and two or three stops, costs $60,750 to $ 98,250

For detailed costs, see Section UIP 8
For basement elevator stops add $ 8,450 to $ 13,500 per stop.

CARPORTS: For complete listing of built-in, attached or detached garages, see Garages – Residential cost pages.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 4.51	$ 5.78	$ 7.38	$ 9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
40,000	3.08	3.81	4.71	5.84
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 40.25	$ 51.00	$ 65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $ 2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$298 to $ 449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	10	1.03
8	.97	11	1.06
9	1.000 (base)	12	1.16

4

Total Area Sq. Ft.	NUMBER OF UNITS*														Total Area Sq. Ft.
	Basement	4	8	12	16	20	24	28	32	36	40	50	80	100	
4,000	1.076	0.977	1.050	1.129	1.214	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	0.947	1.004	1.063	1.127	1.194	-----	-----	-----	-----	-----	-----	-----	-----	5,000
6,000	1.031	0.927	0.973	1.021	1.072	1.125	1.239	-----	-----	-----	-----	-----	-----	-----	6,000
8,000	1.000	0.903	0.936	0.971	1.007	1.044	1.123	1.207	-----	-----	-----	-----	-----	-----	8,000
10,000	0.977	0.888	0.914	0.941	0.969	0.998	1.057	1.121	-----	-----	-----	-----	-----	-----	10,000
12,000	0.958	-----	0.899	0.921	0.944	0.967	1.015	1.066	1.203	-----	-----	-----	-----	-----	12,000
16,000	0.930	-----	0.879	0.895	0.912	0.928	0.963	0.999	1.095	1.199	-----	-----	-----	-----	16,000
20,000	0.908	-----	-----	0.878	0.891	0.904	0.931	0.959	1.032	1.111	1.196	-----	-----	-----	20,000
25,000	0.887	-----	-----	-----	0.874	0.884	0.906	0.927	0.984	1.043	1.107	1.174	-----	-----	25,000
30,000	0.870	-----	-----	-----	-----	0.870	0.887	0.905	0.951	0.999	1.050	1.103	1.218	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	0.866	0.879	0.912	0.947	0.983	1.020	1.099	1.184	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	0.862	0.888	0.915	0.943	0.972	1.032	1.095	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	0.871	0.893	0.916	0.939	0.987	1.038	60,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	0.849	0.865	0.882	0.898	0.933	0.969	80,000
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.846	0.859	0.872	0.899	0.927	100,000

*For larger numbers of units, enter table with 100 units and 100 times the average area per unit.
For instance, a building with 120 units and 400 square feet per unit, use 100 units and 40,000 Sq. Ft. for a multiplier of 1.184.
Do not use basement factors with basement apartment living units.

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES (ALTERNATE METHOD)

OCCUPANCY DESCRIPTION: Shell, This occupancy, together with occupancy Interior Space, Multiple Residence, allows you to individually price the shell and the tenant improvement costs for a multiple residence. This provides an alternative to occupancy Multiple Residence, which includes both the shell and tenant improvement costs.

These shells are low-rise or garden apartments with three or fewer stories for multiple dwelling units. The light residential framed structures are built of class C, D, and S construction. Each dwelling unit consists of its own separate living area, bath, and kitchen facility.

Better shell structures have good finished lobbies, recreation and service areas, interior hall access to dwelling units and some type of stairway for fire exit. These shell structures include common area finishes only, which are about 3% - 16%. Interior build-out costs can be added using Build-out Interior Space, Multiple Residence in an additional section.

Although multiple residences built as condominiums sometimes are required by building and zoning codes to have certain items not required for rental units, basically, “condominium” is a type of ownership and not a type of construction and the multiple residence costs are valid.

INTERIOR SPACE: This occupancy, together with occupancy Shell, Multiple Residence, allows you to individually price the shell and the tenant improvement costs for a multiple residence (in separate sections of the report). This provides an alternative to occupancy Multiple Residence, which includes both the shell and tenant improvement costs.

The lower qualities typically have low-cost partitions, floor covers, minimal cabinetry, open kitchen offset and one bath or a bath and one-half for each unit, regardless of the number of bedrooms. The better qualities have plaster, paneling, good detailing in molding and trim, high cost floor finishes, and full kitchen and dining rooms. Some of the special refinements found in the better qualities include intercoms, television jacks and antennas, and at least one bath per bedroom.

INCLUDED IN COSTS: Architects’ fees, and contractors’ overhead and profit. Intercoms and master antenna/cable services as indicated.

NOT INCLUDED IN COSTS: Elevators, sprinklers, balconies, fireplaces, built-in appliances, furnishings or equipment. Garages or carports can be found on the Garages – Residential cost page.

SHELL MULTIPLE RESIDENCE BUILDINGS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 89.00	Face brick, concrete/metal panels, good roof structure and roofing	Core lobby and service finishes, good stone, terrazzo, carpet	Luminous lobby ceiling, good core lighting, service fixtures	None
	Good	68.50	Good brick/stucco on block, good trim, roof structure and roofing	Core finish only, some carpet, terrazzo, vinyl, adequate lobby	Rough-ins, some good core ceiling and service fixtures	None
	Average	54.00	Brick or block, some trim, asphalt shingle or built-up roof	Some entry, service areas and halls, plain finishes	Rough electrical and plumbing, some service outlets, fixtures	None
	Fair	47.50	Block/brick, standard sash, little trim, shingle or built-up roof	Bare floor structures, no separate service areas	Rough electrical and plumbing	None
D MASONRY VENEER	Excellent	84.50	Face brick, stone veneer, good wood or steel frame & roof structure	Core lobby and service finishes, good stone, terrazzo, carpet	Luminous lobby ceiling, good core lighting, service fixtures	None
	Good	65.00	Good brick veneer and fenestration, good roof structure and roofing	Core finish only, some carpet, terrazzo, vinyl, adequate lobby	Rough-ins, some good core ceiling and service fixtures	None
	Average	50.50	Brick veneer, some ornamentation, average code construction	Some entry, service areas and halls, plain finishes	Rough electrical and plumbing, some service outlets, fixtures	None
	Fair	44.50	Brick veneer, little trim, standard sash, asphalt shingle/built-up roof	Bare floor structures, no separate service areas	Rough electrical and plumbing	None
D	Excellent	82.00	Best stucco, EIFS or siding, brick and stone trim, heavy basic structure	Core lobby and service finishes, good stone, terrazzo, carpet	Luminous lobby ceiling, good core lighting, service fixtures	None
	Good	63.50	Good stucco, EIFS or siding, some brick or stone trim, good roof	Core finish only, some carpet, terrazzo, vinyl, adequate lobby	Rough-ins, some good core ceiling and service fixtures	None
	Average	49.00	Stucco/siding, EIFS, some ornamentation, average code construction	Some entry, service areas and halls, plain finishes	Rough electrical and plumbing, some service outlets, fixtures	None
	Fair	43.00	Stucco or siding, standard sash, asphalt shingles/built-up rock	Bare floor structures, no separate service areas	Rough electrical and plumbing	None
S	Good	60.50	Good sandwich panels on pre-engineered frame, good fenestration	Core finish only, some carpet, terrazzo, vinyl, adequate lobby	Rough-ins, some good core ceiling and service fixtures	None
	Average	47.00	Sandwich panels, pre-engineered frame, adequate fenestration	Some entry, service areas and halls, plain finishes	Rough electrical and plumbing, some service outlets, fixtures	None

INTERIOR BUILD-OUT

(SQUARE FEET OF BUILD-OUT FINISH)

TYPE	COST/ SQ.FT.	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
Excellent	$ 113.00	High-cost partitions and wall and floor finishes, large dining area, kitchen, good master bedroom and bath, good cabinetry, closets, some extras	Good fixtures, many outlets, some extras, TV jacks	Warm and cool air
Good	82.00	Plaster or drywall, good partitions, paneling, carpet, tile or vinyl, good room sizes, some good cabinetry and shelving	Good lighting, one bath per bedroom, TV jacks	Package A.C.
Average	56.50	Average drywall, vinyl composition, carpet, adequate shelving, counters, small dining area and kitchen, adequate bedrooms and bath	Adequate lighting/plumbing, phone and TV jacks	Forced air
Fair	48.00	Low-cost partitions, paint, vinyl composition, low-cost carpet, minimal counters and shelving, open kitchen offset	Adequate standard lighting and plumbing per good codes	Electric baseboard

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated costs, Section SEG 2.

	LOW	AVG	GOOD	EXCL
Allowance (if not itemized)	$1,820	$ 4,150	$7,550	$ 12,800

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Multiples with basements, add 40% to extend the foundation to the basement level. Custom oversized units can run 100% to 200% more.

TYPE	COST RANGE
One-story	$ 3,675 – $ 11,800
Two-stories	4,655 – 14,170
Three-stories	5,635 – 16,540

ELEVATORS: A small passenger or freight elevator with simple call system and push-button control, and two or three stops, costs $60,750 to $ 98,250

For detailed costs, see Section UIP 8
For basement elevator stops add $ 8,450 to $ 13,500 per stop.

CARPORTS: For complete listing of built-in, attached or detached garages, see Garages – Residential cost pages.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 4.51	$ 5.78	$ 7.38	$ 9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
40,000	3.08	3.81	4.71	5.84
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 40.25	$ 51.00	$ 65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$ 2,320 to $ 2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers. $298 to $ 449 per MCFM capacity	
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	10	1.03
8	.97	11	1.06
9	1.000 (base)	12	1.16

4

Total Area Sq. Ft.	NUMBER OF UNITS*														Total Area Sq. Ft.
	Basement	4	8	12	16	20	24	28	32	36	40	50	80	100	
4,000	1.076	0.977	1.050	1.129	1.214	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	0.947	1.004	1.063	1.127	1.194	-----	-----	-----	-----	-----	-----	-----	-----	5,000
6,000	1.031	0.927	0.973	1.021	1.072	1.125	1.239	-----	-----	-----	-----	-----	-----	-----	6,000
8,000	1.000	0.903	0.936	0.971	1.007	1.044	1.123	1.207	-----	-----	-----	-----	-----	-----	8,000
10,000	0.977	0.888	0.914	0.941	0.969	0.998	1.057	1.121	-----	-----	-----	-----	-----	-----	10,000
12,000	0.958	-----	0.899	0.921	0.944	0.967	1.015	1.066	1.203	-----	-----	-----	-----	-----	12,000
16,000	0.930	-----	0.879	0.895	0.912	0.928	0.963	0.999	1.095	1.199	-----	-----	-----	-----	16,000
20,000	0.908	-----	-----	0.878	0.891	0.904	0.931	0.959	1.032	1.111	1.196	-----	-----	-----	20,000
25,000	0.887	-----	-----	-----	0.874	0.884	0.906	0.927	0.984	1.043	1.107	1.174	-----	-----	25,000
30,000	0.870	-----	-----	-----	-----	0.870	0.887	0.905	0.951	0.999	1.050	1.103	1.218	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	0.866	0.879	0.912	0.947	0.983	1.020	1.099	1.184	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	0.862	0.888	0.915	0.943	0.972	1.032	1.095	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	0.871	0.893	0.916	0.939	0.987	1.038	60,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	0.849	0.865	0.882	0.898	0.933	0.969	80,000
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.846	0.859	0.872	0.899	0.927	100,000

*For larger numbers of units, enter table with 100 units and 100 times the average area per unit.
For instance, a building with 120 units and 400 square feet per unit, use 100 units and 40,000 Sq. Ft. for a multiplier of 1.184.
Do not use basement factors with basement apartment living units.

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – ELDERLY ASSISTED LIVING



GOOD CLASS D

OCCUPANCY DESCRIPTION: These structures are three stories or fewer where each studio, one or two bedroom suite has limited individual kitchen and bath facilities and a mix of common support areas, like kitchen and dining areas, associated with congregate housing for the elderly. The better qualities have good lounges, craft and game areas, beauty parlor and therapy rooms. They also have plaster, paneling, good detailing in molding and trim and high cost floor finishes.

The structures commonly are solid masonry or wood frame walls. Some of the special refinements found include task lighting, railings, intercoms, television jacks and antennas, and emergency call systems.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Intercoms and master antenna/cable services as indicated.

Elevators are included where designated with an asterisk (*).

NOT INCLUDED IN COSTS: Fireplaces, built-in appliances, balconies, furnishings, and kitchen, laundry, therapy or recreation equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 205.50	Face brick, concrete/metal panels, good roof structure and roofing	Good plaster, paper, paneling, good detail, some special care	*Good lighting, alarm system, some special plumbing fixtures	Warm and cool air
	Good	168.00	Good brick/stucco on block, good trim, roof structure and roofing	Good plaster or drywall, painted, hardwood, carpet, vinyl composition	*Good lighting/plumbing, some extras, emergency call system	Heat pump system
	Average	139.00	Brick or block, some trim, asphalt shingle or built-up roof	Plaster/drywall, hardwood, carpet, vinyl composition	*Adequate lighting/plumbing, few extra activity facilities	Package A.C.
	Fair	118.50	Block or brick, standard sash, asphalt shingle roof	Drywall or plaster, carpet, vinyl composition tile	*Adequate lighting and plumbing, alarm, minimum extra facilities	Forced air
D MASONRY VENEER	Excellent	204.00	Face brick, stone veneer, good wood or steel frame and roof	Good plaster, paper, paneling, good detail, some special care	*Good lighting, alarm system, some special plumbing fixtures	Warm and cool air
	Good	167.00	Good brick veneer and fenestration, good roof structure and roofing	Good plaster or drywall, painted, hardwood, vinyl composition, carpet	*Good lighting/plumbing, some extras, emergency call system	Heat pump system
	Average	137.50	Brick veneer, some ornamentation, average code construction	Plaster or drywall, hardwood, vinyl composition, carpet	*Adequate lighting/plumbing, few extra activity facilities	Package A.C.
	Fair	119.00	Brick veneer, little trim, standard sash, asphalt shingle	Drywall or plaster, carpet, vinyl composition tile	*Adequate lighting and plumbing, alarm, minimum extra facilities	Forced air
D	Excellent	199.00	Best stucco, EIFS or siding, brick and stone trim, heavy basic structure	Good plaster, paper, paneling, good detail, some special care	*Good lighting, alarm system, some special plumbing fixtures	Warm and cool air
	Good	162.50	Good stucco/siding, EIFS, some brick or stone trim, good roof	Good plaster or drywall, painted, hardwood, vinyl composition, carpet	*Good lighting/plumbing, some extras, emergency call system	Heat pump system
	Average	134.50	Stucco, EIFS or siding, some trim, average code construction	Plaster or drywall, hardwood, vinyl composition, carpet	*Adequate lighting/plumbing, few extra activity facilities	Package A.C.
	Fair	116.00	Stucco or siding, standard sash, asphalt shingles or built-up rock	Drywall or plaster, carpet, vinyl composition tile	*Adequate lighting and plumbing, alarm, minimum extra facilities	Forced air
	Low cost	106.00	Low-cost stucco or siding, very plain, minimum fenestration	Drywall and paint, asphalt tile and low-cost carpet, minimum detail	*Minimum lighting/plumbing, call system, per code	Indiv. thru-wall heat pumps
S	Good	131.00	Good sandwich panels on pre-engineered frame, good fenestration	Gypsum board and plastics, carpet and vinyl composition	*Good lighting/plumbing, some extras, emergency call system	Heat pump system
	Average	103.50	Sandwich panels, adequate fenestration	Drywall, carpet, vinyl composition	*Adequate lighting/plumbing, few extra activity facilities	Package A.C.
CDS†	Finished	69.00	Finished interior	Plaster or drywall, activity, therapy and housekeeping rooms	Adequate lighting/plumbing, high-voltage outlets	Forced air
	Average parking	41.00	Unfinished interior	Plaster/drywall ceiling, concrete floor, striping, stops	Adequate lighting, floor drains, sprinklers not included	Ventilation
	Low cost parking	32.75	Partially exposed, some ornamentation, unfinished interior	Finished ceiling, concrete slab, striping, stops	Minimum lighting, drains, sprinklers not included	None

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $ 8.62 per square foot.
For basement apartments, use 80% of comparable above ground units. For semi-basement apartments, use 90%.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – ELDERLY ASSISTED LIVING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated costs, Section SEG 2.

	LOW	AVG	GOOD	EXCL
Allowance (if not itemized)	$1,820	$ 4,150	$7,550	$ 12,800

ELEVATORS: Buildings whose base cost include elevators are marked with an (*). If the building under construction has no elevators, deduct the following from the base costs so marked. For detailed costs see Section UIP 8.

Classes C/D/S

	Sq. Ft. Costs
Excellent	$ 2.96
Good	2.53
Average	2.10
Fair	1.92
Low	1.75

For basement elevator stops add $ 8,450 to $ 13,500 per stop.

CARPORTS: For complete listing of built-in, attached or detached garages, see Garages – Residential cost pages.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 4.51	$ 5.78	$ 7.38	$ 9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
40,000	3.08	3.81	4.71	5.84
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 40.25	$ 51.00	$ 65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$ 2,320 to $2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers. $298 to $449 per MCFM capacity	
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	10	1.03
8	.97	11	1.06
9	1.000 (base)	12	1.16

4

Total Area Sq. Ft.	NUMBER OF UNITS*														Total Area Sq. Ft.
	Basement	4	6	8	10	12	16	20	30	40	50	60	80	100	
4,000	1.076	0.977	1.050	1.129	1.214	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	0.947	1.004	1.063	1.127	1.194	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	0.977	0.888	0.914	0.941	0.969	0.998	1.057	1.121	-----	-----	-----	-----	-----	-----	10,000
12,000	0.958	-----	0.899	0.921	0.944	0.967	1.015	1.066	1.203	-----	-----	-----	-----	-----	12,000
16,000	0.930	-----	0.879	0.895	0.912	0.928	0.963	0.999	1.095	1.199	-----	-----	-----	-----	16,000
20,000	0.908	-----	-----	0.878	0.891	0.904	0.931	0.959	1.032	1.111	1.196	-----	-----	-----	20,000
30,000	0.870	-----	-----	-----	-----	0.870	0.887	0.905	0.951	0.999	1.050	1.103	1.218	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	0.866	0.879	0.912	0.947	0.943	1.020	1.099	1.184	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	0.862	0.888	0.915	0.916	0.972	1.032	1.095	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	0.871	0.893	0.882	0.939	0.987	1.038	60,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	0.849	0.865	0.859	0.898	0.933	0.969	80,000
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.846	0.943	0.872	0.899	0.927	100,000

*For larger numbers of units, enter table with 100 units and 100 times the average area per unit.
For instance, a building with 120 units and 400 square feet per unit, use 100 units and 40,000 Sq. Ft. for a multiplier of 1.184.
Do not use basement factors with basement apartment living units.

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – ELDERLY ASSISTED LIVING (ALTERNATE METHOD)

OCCUPANCY DESCRIPTION: Shell, This occupancy, together with occupancy Interior Space, Multi. Res. - Elderly Assisted Living, allows you to individually price the shell and the tenant improvement costs for an apartment. This provides an alternative to occupancy Multiple Residence, Assisted Living, which includes both the shell and tenant improvement costs.

These shells are low-rise or garden apartments with three or fewer stories for multiple dwelling units. The light residential framed structures are built of class C, D, and S construction.

Better shell structures have good finished lobbies, recreation and service areas, interior hall access to dwelling units and some type of stairway for fire exit. These shell structures include common area finishes only for the small recreation or lounge and laundry areas associated with congregate housing for the elderly, which are about 3% - 16%. Interior build-out costs can be added using Interior Build-out, Retirement Complex.

Interior Build-out
This occupancy, together with occupancy Shell, Multiple Residence - Elderly Assisted Living, allows you to individually price the shell and the tenant improvement costs for a multiple residence. This provides an alternative to occupancy Multiple Residence - Elderly Assisted Living, which includes both the shell and tenant improvement costs.

The lower qualities typically have low-cost partitions, floor covers, and minimal cabinetry, designed for congregated living. The better qualities have plaster, paneling, good detailing in molding and trim designed for both independent and congregate living. Some of the special refinements found include task lighting, railings, intercoms, television jacks and antennas, alarm system, emergency call systems and handicap units.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Intercoms and master antenna/cable services as indicated.

NOT INCLUDED IN COSTS: Fireplaces, built-in appliances, balconies, furnishings, and kitchen, laundry, therapy or recreation equipment.

SHELL MULTIPLE RESIDENCE BUILDINGS- ELDERLY ASSITED LIVING

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 85.00	Face brick, concrete/metal panels, good roof structure and roofing	Core lobby and service finishes, good detail, some special care, good hardwood, vinyl and carpet	*Good core lighting, alarm system, some special plumbing fixtures	None
	Good	72.50	Good brick/stucco on block, good trim, roof structure and roofing	Core lobby and service finishes, hardwood, vinyl composition, carpet	*Good core lighting/plumbing, some extras	None
	Average	62.00	Brick or block, some trim, asphalt shingle or built-up roof	Average lobby and support services, hardwood, vinyl composition, carpet	*Adequate core lighting/plumbing, few extra activity facilities	None
	Fair	57.50	Block or brick, standard sash, asphalt shingle roof	Small lobby and limited service finishes, carpet, vinyl composition tile	*Adequate core lighting and plumbing, alarm, minimum extra facilities	None
D MASONRY VENEER	Excellent	80.00	Face brick, stone veneer, good wood or steel frame and roof	Core lobby and service finishes, good detail, some special care, good hardwood, vinyl and carpet	*Good core lighting, alarm system, some special plumbing fixtures	None
	Good	68.50	Good brick veneer and fenestration, good roof structure and roofing	Core lobby and service finishes, hardwood, vinyl composition, carpet	*Good core lighting/plumbing, some extras	None
	Average	58.50	Brick veneer, some ornamentation, average code construction	Average lobby and support services, hardwood, vinyl composition, carpet	*Adequate core lighting/plumbing, few extra activity facilities	None
	Fair	54.00	Brick veneer, little trim, standard sash, asphalt shingle	Small lobby and limited service finishes, carpet, vinyl composition tile	*Adequate core lighting and plumbing, alarm, minimum extra facilities	None
D	Excellent	77.50	Best stucco or siding, brick and stone trim, heavy basic structure	Core lobby and service finishes, good detail, some special care, good hardwood, vinyl and carpet	*Good core lighting, alarm system, some special plumbing fixtures	None
	Good	66.00	Good stucco/siding, some brick or stone trim, good roof	Core lobby and service finishes, hardwood, vinyl composition, carpet	*Good core lighting/plumbing, some extras	None
	Average	57.00	Stucco or siding, some trim, average code construction	Average lobby and support services, hardwood, vinyl composition, carpet	*Adequate core lighting/plumbing, few extra activity facilities	None
	Fair	52.50	Stucco or siding, standard sash, asphalt shingles or built-up rock	Small lobby and limited service finishes, carpet, vinyl composition tile	*Adequate core lighting and plumbing, alarm, minimum extra facilities	None
	Low cost	48.50	Low-cost stucco or siding, very plain, minimum fenestration	Small lobby and limited service finishes, asphalt tile and low-cost carpet, minimum detail	*Minimum core lighting/plumbing, call system, per code	None
S	Good	64.00	Good sandwich panels on pre-engineered frame, good fenestration	Core lobby and service finishes, hardwood, vinyl composition, carpet	*Good core lighting/plumbing, some extras	None
	Average	47.00	Sandwich panels, adequate fenestration	Average lobby and support services, hardwood, vinyl composition, carpet	*Adequate core lighting/plumbing, few extra activity facilities	None

INTERIOR BUILD-OUT

(SQUARE FEET OF BUILD-OUT FINISH)

TYPE	COST/ SQ.FT.	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
Excellent	$119.50	High-cost partitions and wall and floor finishes, large dining area, kitchen, good master bedroom and bath, good cabinetry, closets, some extras	Good lighting, alarm system, some special plumbing fixtures	Warm and cool air
Good	95.00	Plaster or drywall, good partitions, paneling, carpet, tile or vinyl, good room sizes, some good cabinetry and shelving	Good lighting/plumbing, some extras, emergency call system	Heat pump system
Average	76.50	Average drywall, vinyl composition, carpet, adequate shelving, counters, small dining area and kitchen, adequate bedrooms and bath	Adequate lighting/plumbing, some extras	Package A.C.
Fair	63.00	Low-cost drywall or plaster, paint, vinyl composition, carpet, counters and shelving, open kitchen offset, one-bedroom suites	Adequate lighting and plumbing, minimum extra facilities	Forced air
Low	56.50	Low-cost partitions, paint, vinyl composition, low-cost carpet, minimal counters and shelving, open kitchen offset, studios	Minimum lighting/plumbing, call system, per code	Individual thru-wall heat pumps

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – ELDERLY ASSISTED LIVING (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated costs, Section SEG 2.

	LOW	AVG	GOOD	EXCL
Allowance (if not itemized)	$1,820	$4,150	$7,550	$12,800

ELEVATORS: Buildings whose base cost include elevators are marked with an (*). If the building under construction has no elevators, deduct the following from the base costs so marked. For detailed costs see Section UIP 8.

Classes C/D/S

	Sq. Ft. Costs
Excellent	$ 2.96
Good	2.53
Average	2.10
Fair	1.92
Low	1.75

For basement elevator stops add $ 8,450 to $13,500 per stop.

CARPORTS: For complete listing of built-in, attached or detached garages, see Garages - Residential cost pages.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 4.51	$ 5.78	$ 7.38	$ 9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
40,000	3.08	3.81	4.71	5.84
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 40.25	$ 51.00	$ 65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$298 to $ 449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	10	1.03
8	.97	11	1.06
9	1.000 (base)	12	1.16

4

Total Area	NUMBER OF UNITS*														Total Area
Sq. Ft.	Basement	4	6	8	10	12	16	20	30	40	50	60	80	100	Sq. Ft.
4,000	1.076	0.977	1.050	1.129	1.214	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	0.947	1.004	1.063	1.127	1.194	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	0.977	0.888	0.914	0.941	0.969	0.998	1.057	1.121	-----	-----	-----	-----	-----	-----	10,000
12,000	0.958	-----	0.899	0.921	0.944	0.967	1.015	1.066	1.203	-----	-----	-----	-----	-----	12,000
16,000	0.930	-----	0.879	0.895	0.912	0.928	0.963	0.999	1.095	1.199	-----	-----	-----	-----	16,000
20,000	0.908	-----	-----	0.878	0.891	0.904	0.931	0.959	1.032	1.111	1.196	-----	-----	-----	20,000
30,000	0.870	-----	-----	-----	-----	0.870	0.887	0.905	0.951	0.999	1.050	1.103	1.218	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	0.866	0.879	0.912	0.947	0.943	1.020	1.099	1.184	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	0.862	0.888	0.915	0.916	0.972	1.032	1.095	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	0.871	0.893	0.882	0.939	0.987	1.038	60,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	0.849	0.865	0.859	0.898	0.933	0.969	80,000
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.846	0.943	0.872	0.899	0.927	100,000

*For larger numbers of units, enter table with 100 units and 100 times the average area per unit.
For instance, a building with 120 units and 400 square feet per unit, use 100 units and 40,000 Sq. Ft. for a multiplier of 1.184.
Do not use basement factors with basement apartment living units.

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – RETIREMENT COMMUNITY COMPLEX



GOOD CLASS C

OCCUPANCY DESCRIPTION: These structures are three stories or fewer and include a mix of independent, assisted living and skilled nursing living units, with fitness and care facilities commensurate with the quality. The better qualities have good lounges, craft and game areas, beauty parlor and therapy rooms and fitness rooms. They also have plaster, paneling, good detailing in molding and trim, and high cost floor finishes.

The structures commonly have solid masonry or wood frame walls. Some of the special refinements found include task lighting, railings, intercoms, television jacks and antennas, emergency call systems and nursing stations.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Intercoms and master antenna/cable services as indicated.

Elevators are included where designated with an asterisk (*).

NOT INCLUDED IN COSTS: Fireplaces, built-in appliances, balconies, furnishings, and kitchen, laundry, therapy or recreation equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 237.00	Face brick, concrete/metal panels, good roof structure and roofing	Good plaster, paper, paneling, carpet, complete retirement care complex	*Good lighting, alarm, skilled care, some special fixtures	Warm and cool air
	Average	191.00	Good brick/stucco on block, good trim, roof structure and roofing	Good plaster or drywall, painted, good senior, assisted mix, some skilled	*Good lighting/plumbing, good extras, emergency call system	Heat pump system
	Fair	171.50	Brick or block, some trim, asphalt shingle or built-up roof	Plaster/drywall, carpet, vinyl comp., senior, assisted with special care	*Adequate lighting/plumbing, complete fitness/care facilities	Package A.C.
	Low cost	149.00	Block or brick, standard sash, asphalt shingle roof	Drywall or plaster, carpet, vinyl comp., good senior and assisted mix	*Adequate lighting and plumbing, alarm, good activity facilities	Indiv. thru-wall heat pumps
D MASONRY VENEER	Good	236.00	Face brick, stone veneer, good wood or steel frame and roof	Good plaster, paper, paneling, carpet, complete retirement care complex	*Good lighting, alarm, skilled care, some special fixtures	Warm and cool air
	Average	190.00	Good brick veneer and fenestration, good roof structure and roofing	Good plaster or drywall, painted, good senior, assisted mix, some skilled	*Good lighting/plumbing, good extras, emergency call system	Heat pump system
	Fair	170.50	Brick veneer, some ornamentation, average code construction	Plaster/drywall, carpet, vinyl comp., senior, assisted with special care	*Adequate lighting/plumbing, complete fitness/care facilities	Package A.C.
	Low cost	147.50	Brick veneer, little trim, standard sash, asphalt shingle	Drywall or plaster, carpet, vinyl comp., good senior and assisted mix	*Adequate lighting and plumbing, alarm, good activity facilities	Indiv. thru-wall heat pumps
D	Good	231.00	Best stucco, EIFS or siding, brick and stone trim, heavy basic structure	Good plaster, paper, paneling, carpet, complete retirement care complex	*Good lighting, alarm, skilled care, some special fixtures	Warm and cool air
	Average	185.00	Good stucco/siding, EIFS, some brick or stone trim, good roof	Good plaster or drywall, painted, good senior, assisted mix, some skilled	*Good lighting/plumbing, good extras, emergency call system	Heat pump system
	Fair	166.00	Stucco or siding, some trim, average code construction	Plaster/drywall, vinyl comp., carpet, senior, assisted with special care	*Adequate lighting/plumbing, complete fitness/care facilities	Package A.C.
	Low cost	143.50	Stucco or siding, standard sash, asphalt shingles or built-up rock	Drywall or plaster, carpet, vinyl comp., good senior and assisted mix	*Adequate lighting and plumbing, alarm, good activity facilities	Indiv. thru-wall heat pumps
S	Average	181.00	Good sandwich panels on pre-engineered frame, good fenestration	Gypsum board and plastics, carpet, senior, assisted mix, some skilled	*Good lighting/plumbing, good extras, emergency call system	Heat pump system
	Fair	161.50	Sandwich panels, adequate fenestration	Drywall, carpet, vinyl composition, senior, assisted with special care	*Adequate lighting/plumbing, complete fitness/care facilities	Package A.C.

For basement units, use 80% of comparable above ground units. For semi-basement units, use 90%.
NOTE: These complexes represent group averages which can be quite varied in the mix of independent/congregate senior living apartments, assisted living suites and skilled nursing room units and the auxiliary amenities that are offered. For greater accuracy, it is recommended that they be priced by breaking the complex into its various components.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – RETIREMENT COMMUNITY COMPLEX

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base cost include elevators are marked with an (*). If the building under construction has no elevators, deduct the following from the base costs so marked. For detailed costs see Allowance (if not itemized)

Classes C/D/S

	Sq. Ft. Costs
Good	$2.19
Average	1.92
Fair	1.83
Low	1.67

NOTE: Care must be exercised when using square foot elevator costs. Small apartment buildings may have only one elevator and/or handicap lift regardless of size.

CARPORTS: For complete listing of built-in, attached or detached garages, see Garages – Residential cost pages.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$4.51	$5.78	$7.38	$9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
40,000	3.08	3.81	4.71	5.84
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$31.75	$40.25	$51.00	$65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$298 to $449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	10	1.03
8	.97	11	1.06
9	1.000 (base)	12	1.16

4

Total Area	NUMBER OF UNITS*														Total Area
Sq. Ft.	Basement	4	6	8	10	12	16	20	30	40	50	60	80	100	Sq. Ft.
4,000	1.076	0.977	1.050	1.129	1.214	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	0.947	1.004	1.063	1.127	1.194	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	0.977	0.888	0.914	0.941	0.969	0.998	1.057	1.121	-----	-----	-----	-----	-----	-----	10,000
12,000	0.958	-----	0.899	0.921	0.944	0.967	1.015	1.066	1.203	-----	-----	-----	-----	-----	12,000
16,000	0.930	-----	0.879	0.895	0.912	0.928	0.963	0.999	1.095	1.199	-----	-----	-----	-----	16,000
20,000	0.908	-----	-----	0.878	0.891	0.904	0.931	0.959	1.032	1.111	1.196	-----	-----	-----	20,000
30,000	0.870	-----	-----	-----	-----	0.870	0.887	0.905	0.951	0.999	1.050	1.103	1.218	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	0.866	0.879	0.912	0.947	0.943	1.020	1.099	1.184	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	0.862	0.888	0.915	0.916	0.972	1.032	1.095	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	0.871	0.893	0.882	0.939	0.987	1.038	60,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	0.849	0.865	0.859	0.898	0.933	0.969	80,000
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.846	0.943	0.872	0.899	0.927	100,000

*For larger numbers of units, enter table with 100 units and 100 times the average area per unit.
For instance, a building with 120 units and 400 square feet per unit, use 100 units and 40,000 Sq. Ft. for a multiplier of 1.184.
Do not use basement factors with basement apartment living units.

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – RETIREMENT COMMUNITY COMPLEX (ALTERNATE METHOD)

OCCUPANCY DESCRIPTION: Shell, This occupancy, together with occupancy Interior Space, Retirement Complex, allows you to individually price the shell and the tenant improvement costs for an apartment (in separate sections of the report). This provides an alternative to occupancy Retirement Community Complex, which includes both the shell and tenant improvement costs.

These shells are low-rise or garden apartments with three or fewer stories for multiple dwelling units. The light residential framed structures are built of class C, D, and S construction.

Better shell structures have good finished lobbies, recreation and service areas, interior hall access to dwelling units and some type of stairway for fire exit. These shell structures include common area finishes only for the lounges, craft and game areas, beauty parlor and therapy rooms and fitness rooms, facilities for Alzheimer's or dementia patients, which are about 3% - 16%. Interior build-out costs can be added using occupancy Interior Build-out, Retirement Complex.

Interior Build-out
This occupancy, together with occupancy Shell, Retirement Complex, allows you to individually price the shell and the tenant improvement costs for a multiple residence. This provides an alternative to occupancy Retirement Complex, which includes both the shell and tenant improvement costs.

The lower qualities typically have low-cost partitions, floor covers, and minimal cabinetry, designed for congregated living. The better qualities have plaster, paneling, good detailing in molding and trim designed for both independent and congregate living, as well as skilled nursing units. Some of the special refinements found include task lighting, railings, intercoms, television jacks and antennas, alarm system, emergency call systems and handicap units.

INCLUDED IN COSTS: Architects' fees, and contractors' overhead and profit. Intercoms and master antenna/cable services as indicated. Elevators are included where designated with an asterisk (*).

NOT INCLUDED IN COSTS: Fireplaces, built-in appliances, balconies, furnishings, and kitchen, laundry, therapy or recreation equipment.

SHELL MULTIPLE RESIDENCE - RETIREMENT COMMUNITY COMPLEX

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 118.50	Face brick, concrete/metal panels, good roof structure and roofing	Core lobby and service finishes, good detail, some special care	*Good core lighting, alarm, some special fixtures	None
	Average	99.50	Good brick/stucco on block, good trim, roof structure and roofing	Core lobby and service finishes, hardwood, vinyl composition, carpet	*Good core lighting & plumbing, good extras	None
	Fair	90.50	Brick or block, some trim, asphalt shingle or built-up roof	Average core lobby and support services, hardwood, vinyl composition, carpet	*Adequate core lighting & plumbing, complete fitness/care facilities	None
	Low cost	82.50	Block or brick, standard sash, asphalt shingle roof	Small core lobby and limited service finishes, carpet, vinyl composition tile	*Adequate core lighting & plumbing, alarm, good activity facilities	None
D MASONRY VENEER	Good	115.00	Face brick, stone veneer, good wood or steel frame and roof	Core lobby and service finishes, good detail, some special care	*Good core lighting, alarm, some special fixtures	None
	Average	95.50	Good brick veneer and fenestration, good roof structure and roofing	Core lobby and service finishes, hardwood, vinyl composition, carpet	*Good core lighting & plumbing, good extras	None
	Fair	87.00	Brick veneer, some ornamentation, average code construction	Average core lobby and support services, hardwood, vinyl composition, carpet	*Adequate core lighting & plumbing, complete fitness/care facilities	None
	Low cost	79.00	Brick veneer, little trim, standard sash, asphalt shingle	Small core lobby and limited service finishes, carpet, vinyl composition tile	*Adequate core lighting & plumbing, alarm, good activity facilities	None
D	Good	112.00	Best stucco or siding, brick and stone trim, heavy basic structure	Core lobby and service finishes, good detail, some special care	*Good core lighting, alarm, some special fixtures	None
	Average	92.50	Good stucco/siding, some brick or stone trim, good roof	Core lobby and service finishes, hardwood, vinyl composition, carpet	*Good core lighting & plumbing, good extras	None
	Fair	84.50	Stucco or siding, some trim, average code construction	Average core lobby and support services, hardwood, vinyl composition, carpet	*Adequate core lighting & plumbing, complete fitness/care facilities	None
	Low cost	76.50	Stucco or siding, standard sash, asphalt shingles or built-up rock	Small core lobby and limited service finishes, carpet, vinyl composition tile	*Adequate core lighting & plumbing, alarm, good activity facilities	None
S	Average	90.00	Good sandwich panels on pre-engineered frame, good fenestration	Core lobby and service finishes, hardwood, vinyl composition, carpet	*Good core lighting & plumbing, good extras	None
	Fair	81.50	Sandwich panels, adequate fenestration	Average core lobby and support services, hardwood, vinyl composition, carpet	*Adequate core lighting & plumbing, complete fitness/care facilities	None

INTERIOR BUILD-OUT

(SQUARE FEET OF BUILD-OUT FINISH)

TYPE	COST/ SQ.FT.	INTERIOR FINISH	LIGHTING AND PLUMBING	HEAT
Good	$ 117.00	Plaster or drywall, good partitions, paneling, carpet, tile or vinyl, good room sizes, some good cabinetry and shelving, complete retirement complex	Good lighting, skilled care	Warm and cooled air
Average	92.00	Average drywall, vinyl composition, carpet, adequate shelving, counters, small dining area and kitchen, good senior, assisted mix, some skilled	Good lighting & plumbing, emergency call system	Heat pump system
Fair	80.50	Low-cost drywall or plaster, paint, vinyl composition, carpet, counters and shelving, open kitchen offset, senior, assisted with special care	Adequate lighting & plumbing	Package A.C.
Low	66.50	Low-cost partitions, paint, vinyl composition, low-cost carpet, minimal counters and shelving, open kitchen offset, good senior and assisted mix	Adequate lighting & plumbing	Individual thru-wall heat pumps

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – RETIREMENT COMMUNITY COMPLEX (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base cost include elevators are marked with an (*). If the building under construction has no elevators, deduct the following from the base costs so marked. For detailed costs see Allowance (if not itemized)

Classes C/D/S

	Sq. Ft. Costs
Good	$2.19
Average	1.92
Fair	1.83
Low	1.67

NOTE: Care must be exercised when using square foot elevator costs. Small apartment buildings may have only one elevator and/or handicap lift regardless of size.

CARPORTS: For complete listing of built-in, attached or detached garages, see Garages – Residential cost pages.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$4.51	$5.78	$7.38	$9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
40,000	3.08	3.81	4.71	5.84
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$31.75	$40.25	$51.00	$65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$298 to $449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	10	1.03
8	.97	11	1.06
9	1.000 (base)	12	1.16

4

Total Area	NUMBER OF UNITS*														Total Area
Sq. Ft.	Basement	4	6	8	10	12	16	20	30	40	50	60	80	100	Sq. Ft.
4,000	1.076	0.977	1.050	1.129	1.214	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	0.947	1.004	1.063	1.127	1.194	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	0.977	0.888	0.914	0.941	0.969	0.998	1.057	1.121	-----	-----	-----	-----	-----	-----	10,000
12,000	0.958	-----	0.899	0.921	0.944	0.967	1.015	1.066	1.203	-----	-----	-----	-----	-----	12,000
16,000	0.930	-----	0.879	0.895	0.912	0.928	0.963	0.999	1.095	1.199	-----	-----	-----	-----	16,000
20,000	0.908	-----	-----	0.878	0.891	0.904	0.931	0.959	1.032	1.111	1.196	-----	-----	-----	20,000
30,000	0.870	-----	-----	-----	-----	0.870	0.887	0.905	0.951	0.999	1.050	1.103	1.218	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	0.866	0.879	0.912	0.947	0.943	1.020	1.099	1.184	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	0.862	0.888	0.915	0.916	0.972	1.032	1.095	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	0.871	0.893	0.882	0.939	0.987	1.038	60,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	0.849	0.865	0.859	0.898	0.933	0.969	80,000
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.846	0.943	0.872	0.899	0.927	100,000

*For larger numbers of units, enter table with 100 units and 100 times the average area per unit.
For instance, a building with 120 units and 400 square feet per unit, use 100 units and 40,000 Sq. Ft. for a multiplier of 1.184.
Do not use basement factors with basement apartment living units.

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – SENIOR CITIZEN



GOOD CLASS D



GOOD CLASS D

OCCUPANCY DESCRIPTION: These structures are three stories or fewer, with each unit within the building having a kitchen and at least one bath. They may have limited individual kitchen facilities and/or common kitchen, dining and lounge areas associated with congregate housing for the elderly. Large clubhouse buildings would be costed separately. The best qualities have combined heating and cooling systems. They also have plaster, paneling, good detailing in molding and trim, railings and grab bars and good task area and common area lighting. For complexes where all units have been modified to accommodate the handicapped, increase costs by 4%.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Intercoms and master antenna/cable services as indicated.

NOT INCLUDED IN COSTS: Elevators, sprinklers, balconies, furnishings, built-in appliances, or kitchen equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 191.50	Face brick, concrete/metal panels, good roof structure and roofing	Good plaster, paper, paneling, good detail, hardwood, carpet	Good lighting, many outlets, some special plumbing fixtures	Heat pump system
	Good	152.00	Good brick/stucco on block, good trim, roof structure and roofing	Good plaster or drywall, painted, hardwood, carpet, vinyl composition	Good lighting/plumbing, some extras, emergency call system	Package A.C.
	Average	122.50	Brick or block, some trim, asphalt shingle or built-up roof	Plaster/drywall, hardwood, carpet, vinyl composition	Adequate lighting/plumbing, few extras and handicap units	Hot water
	Fair	104.00	Block or brick, standard sash, asphalt shingle roof	Drywall or plaster, carpet, vinyl composition tile	Adequate standard lighting and plumbing per good codes	Forced air
D MASONRY VENEER	Excellent	190.00	Face brick, stone veneer, good wood or steel frame and roof	Good plaster, paper, paneling, good detail, hardwood, carpet	Good lighting, many outlets, some special plumbing fixtures	Heat pump system
	Good	150.50	Good brick veneer and fenestration, good roof structure and roofing	Good plaster or drywall, painted hardwood, vinyl composition, carpet	Good lighting/plumbing, some extras, emergency call system	Package A.C.
	Average	121.00	Brick veneer, some ornamentation, average code construction	Plaster or drywall, hardwood, vinyl composition, carpet	Adequate lighting/plumbing, few extras and handicap units	Hot water
	Fair	102.50	Brick veneer, little trim, standard sash, asphalt shingle	Drywall or plaster, carpet, vinyl composition tile	Adequate standard lighting and plumbing per good codes	Forced air
D	Excellent	185.00	Best stucco or siding, brick and stone trim, heavy basic structure	Good plaster, paper, paneling, good detail, hardwood, carpet	Good lighting, many outlets, some special plumbing fixtures	Heat pump system
	Good	146.50	Good stucco/siding, EIFS, some brick or stone trim, good roof	Good plaster or drywall, painted, hardwood, vinyl composition, carpet	Good lighting/plumbing, some extras, emergency call system	Package A.C.
	Average	117.50	Stucco or siding, some trim, average code construction	Plaster or drywall, hardwood, vinyl composition, carpet	Adequate lighting/plumbing, few extras and handicap units	Hot water
	Fair	99.50	Stucco or siding, standard sash, asphalt shingles or built-up rock	Drywall or plaster, carpet, vinyl composition tile	Adequate standard lighting and plumbing per good codes	Forced air
	Low cost	88.00	Low-cost stucco or siding, very plain, minimum fenestration	Drywall and paint, asphalt tile and low-cost carpet	Minimum lighting/plumbing per code	Electric baseboard
S	Good	114.50	Good sandwich panels on pre-engineered frame, good fenestration	Gypsum board and plastics, carpet and vinyl composition	Good lighting/plumbing, some extras, emergency call system	Package A.C.
	Average	86.00	Sandwich panels, adequate fenestration	Drywall, carpet, vinyl composition	Adequate lighting/plumbing, few extras and handicap units	Hot water
CDS†	Finished basement	48.75	Finished interior, add for saunas, pools, bars and equipment	Gypsum board ceiling, vinyl composition tile, or sheet vinyl	Adequate lighting/plumbing	None
	Unfin. bsmt.	34.50	Few partitions, little or no finish	Unfin. ceiling, slab, storage only	Minimum lighting/plumbing	None
	Finished mezzanine	70.00	Not included	Drywall, vinyl, some tile, carpet, VCT, finished loft	Adequate lighting and plumbing, extra outlets and fixtures	In building cost
	Open mezzanine	44.75	Not included	Finished floors, few partitions, open sleeping loft	Average lighting, no plumbing	In building cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $ 8.62 per square foot.
For basement apartments, use 80% of comparable above ground units. For semi-basement apartments, use 90%.
For parking basements, see CAL 210.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – SENIOR CITIZEN

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated costs, Section SEG 2.

	LOW	AVG	GOOD	EXCL
Allowance (if not itemized)	$ 1,820	$ 4,150	$ 7,550	$ 12,800

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Multiples with basements, add 40% to extend the foundation to the basement level. Custom oversized units can run 100% to 200% more.

TYPE	COST RANGE
One-story	$ 3,675 – $ 11,800
Two-stories	4,655 – 14,170
Three-stories	5,635 – 16,540

ELEVATORS: A small passenger or freight elevator with simple call system and push-button control, and two or three stops, costs $60,750 to $98,250

For detailed costs, see Section UIP 8
For basement elevator stops add $8,450 to $13,500 per stop.

CARPORTS: For complete listing of built-in, attached or detached garages, see Garages – Residential cost pages.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 4.51	$ 5.78	$ 7.38	$ 9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
40,000	3.08	3.81	4.71	5.84
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 40.25	$ 51.00	$ 65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$298 to $449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	10	1.03
8	.97	11	1.06
9	1.000 (base)	12	1.16

4

Total Area	NUMBER OF UNITS*														Total Area
Sq. Ft.	Basement	4	6	8	10	12	16	20	30	40	50	60	80	100	Sq. Ft.
4,000	1.076	0.977	1.050	1.129	1.214	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	0.947	1.004	1.063	1.127	1.194	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	0.977	0.888	0.914	0.941	0.969	0.998	1.057	1.121	-----	-----	-----	-----	-----	-----	10,000
12,000	0.958	-----	0.899	0.921	0.944	0.967	1.015	1.066	1.203	-----	-----	-----	-----	-----	12,000
16,000	0.930	-----	0.879	0.895	0.912	0.928	0.963	0.999	1.095	1.199	-----	-----	-----	-----	16,000
20,000	0.908	-----	-----	0.878	0.891	0.904	0.931	0.959	1.032	1.111	1.196	-----	-----	-----	20,000
30,000	0.870	-----	-----	-----	-----	0.870	0.887	0.905	0.951	0.999	1.050	1.103	1.218	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	0.866	0.879	0.912	0.947	0.943	1.020	1.099	1.184	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	0.862	0.888	0.915	0.916	0.972	1.032	1.095	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	0.871	0.893	0.882	0.939	0.987	1.038	60,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	0.849	0.865	0.859	0.898	0.933	0.969	80,000
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.846	0.943	0.872	0.899	0.927	100,000

*For larger numbers of units, enter table with 100 units and 100 times the average area per unit.
For instance, a building with 120 units and 400 square feet per unit, use 100 units and 40,000 Sq. Ft. for a multiplier of 1.184.
Do not use basement factors with basement apartment living units.

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – SENIOR CITIZEN (ALTERNATE METHOD)

OCCUPANCY DESCRIPTION: Shell, This occupancy, together with occupancy Interior Space, Multi. Res. - Senior Citizen, allows you to individually price the shell and the tenant improvement costs for an apartment. This provides an alternative to occupancy Multi. Res. - Senior Citizen, which includes both the shell and tenant improvement costs.

These shells are low-rise or garden apartments with three or fewer stories for multiple dwelling units. The light residential framed structures are built of class C, D, and S construction.

Better shell structures have good finished lobbies, recreation and service areas, interior hall access to dwelling units and some type of stairway for fire exit. These shell structures include common area finishes only for the small recreation or lounge and laundry areas associated with congregate housing for the elderly, which are about 3% - 16%. Interior build-out costs can be added using Build-out Interior Space, Multiple Residence - Senior Citizen.

Interior Build-out
This occupancy, together with occupancy Shell, Multiple Residence - Senior Citizen, allows you to individually price the shell and the tenant improvement costs for a multiple residence. This provides an alternative to occupancy Multiple Residence - Senior Citizen, which includes both the shell and tenant improvement costs.

The lower qualities typically have low-cost partitions, floor covers, and minimal cabinetry, designed for congregated living. The better qualities have plaster, paneling, good detailing in molding and trim designed for both independent and congregate living. Some of the special refinements found include task lighting, railings, intercoms, television jacks and antennas, emergency call systems and handicap units.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Intercoms and master antenna/cable services as indicated.

NOT INCLUDED IN COSTS: Elevators, sprinklers, balconies, furnishings, built-in appliances or kitchen equipment.

SHELL MULTIPLE RESIDENCES - SENIOR CITIZEN

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 100.50	Face brick, concrete/metal panels, good roof structure and roofing	Core lobby and service finishes, good stone, terrazzo, hardwood, carpet	Good core lighting, many outlets, some special plumbing fixtures	None
	Good	81.50	Good brick/stucco on block, good trim, roof structure and roofing	Core finish only, carpet, hardwood, vinyl composition, terrazzo, adequate lobby	Good core lighting & plumbing, some extras	None
	Average	65.50	Brick or block, some trim, asphalt shingle or built-up roof	Some entry, service areas and halls, plain finishes, hardwood, vinyl composition, carpet, adequate lobby	Adequate core lighting & plumbing, few extras	None
	Fair	59.00	Block or brick, standard sash, asphalt shingle roof	Some entry, service areas and halls, plain finishes, carpet, vinyl composition tile	Adequate standard core lighting & plumbing per good codes	None
D MASONRY VENEER	Excellent	96.00	Face brick, stone veneer, good wood or steel frame and roof	Core lobby and service finishes, good stone, terrazzo, hardwood, carpet	Good core lighting, many outlets, some special plumbing fixtures	None
	Good	77.50	Good brick veneer and fenestration, good roof structure and roofing	Core finish only, carpet, hardwood, vinyl composition, terrazzo, adequate lobby	Good core lighting & plumbing, some extras	None
	Average	62.50	Brick veneer, some ornamentation, average code construction	Some entry, service areas and halls, plain finishes, hardwood, vinyl composition, carpet, adequate lobby	Adequate core lighting & plumbing, few extras	None
	Fair	56.00	Brick veneer, little trim, standard sash, asphalt shingle	Some entry, service areas and halls, plain finishes, carpet, vinyl composition tile	Adequate standard core lighting & plumbing per good codes	None
D	Excellent	93.00	Best stucco or siding, brick and stone trim, heavy basic structure	Core lobby and service finishes, good stone, terrazzo, hardwood, carpet	Good core lighting, many outlets, some special plumbing fixtures	None
	Good	75.00	Good stucco/siding, some brick or stone trim, good roof	Core finish only, carpet, hardwood, vinyl composition, terrazzo, adequate lobby	Good core lighting & plumbing, some extras	None
	Average	60.00	Stucco or siding, some trim, average code construction	Some entry, service areas and halls, plain finishes, hardwood, vinyl composition, carpet, adequate lobby	Adequate core lighting & plumbing, few extras	None
	Fair	54.50	Stucco or siding, standard sash, asphalt shingles or built-up rock	Some entry, service areas and halls, plain finishes, carpet, vinyl composition tile	Adequate standard core lighting & plumbing per good codes	None
	Low cost	48.50	Low-cost stucco or siding, very plain, minimum fenestration	Some entry, service areas and halls, plain finishes, asphalt tile and low-cost carpet	Minimum lighting & plumbing per code	None
S	Good	72.50	Good sandwich panels on pre-engineered frame, good fenestration	Core finish only, carpet, hardwood, vinyl composition, terrazzo, adequate lobby	Good lighting & plumbing, some extras	None
	Average	58.50	Sandwich panels, adequate fenestration	Core finish only, carpet and vinyl composition, adequate lobby	Adequate lighting/plumbing, few extras	None

INTERIOR BUILD-OUT

(SQUARE FEET OF BUILD-OUT FINISH)

TYPE	COST/ SQ.FT.	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
Excellent	$ 90.50	High-cost partitions and wall and floor finishes, large dining area, kitchen, good master bedroom and bath, good cabinetry, closets, some extras, independent/ congregate living	Good lighting, and special plumbing fixtures, many outlets, some extras, TV jacks	Heat pump system
Good	70.50	Plaster or drywall, good partitions, paneling, carpet, tile or vinyl, good room sizes, some good cabinetry and shelving	Good lighting, one bath per bedroom, TV jacks, emergency call system	Package A.C.
Average	56.50	Average drywall, vinyl composition, carpet, adequate shelving, counters, small dining area and kitchen, adequate bedrooms and bath	Adequate lighting/plumbing, phone and TV jacks, handicap units	Hot water
Fair	45.00	Drywall, vinyl composition, carpet, adequate shelving, counters, small dining area and kitchen, adequate bedrooms and bath	Adequate standard lighting and plumbing per code	Forced air
Low cost	39.00	Low-cost partitions, paint, vinyl composition, low-cost carpet, minimal counters and shelving, open kitchen offset	Minimum lighting and plumbing per code	Electric baseboard

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MULTIPLE RESIDENCES – SENIOR CITIZEN (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated costs, Section SEG 2.

	LOW	AVG	GOOD	EXCL
Allowance (if not itemized)	$ 1,820	$ 4,150	$ 7,550	$ 12,800

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Multiples with basements, add 40% to extend the foundation to the basement level. Custom oversized units can run 100% to 200% more.

TYPE	COST RANGE
One-story	$ 3,675 – $ 11,800
Two-stories	4,655 – 14,170
Three-stories	5,635 – 16,540

ELEVATORS: A small passenger or freight elevator with simple call system and push-button control, and two or three stops, costs $60,750 to $98,250

For detailed costs, see Section UIP 8
For basement elevator stops add $ 8,450 to $13,500 per stop.

CARPORTS: For complete listing of built-in, attached or detached garages, see Garages – Residential cost pages.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 4.51	$ 5.78	$ 7.38	$ 9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
40,000	3.08	3.81	4.71	5.84
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 40.25	$ 51.00	$ 65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$298 to $ 449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	10	1.03
8	.97	11	1.06
9	1.000 (base)	12	1.16

4

Total Area	NUMBER OF UNITS*														Total Area
Sq. Ft.	Basement	4	6	8	10	12	16	20	30	40	50	60	80	100	Sq. Ft.
4,000	1.076	0.977	1.050	1.129	1.214	-----	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	1.051	0.947	1.004	1.063	1.127	1.194	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	0.977	0.888	0.914	0.941	0.969	0.998	1.057	1.121	-----	-----	-----	-----	-----	-----	10,000
12,000	0.958	-----	0.899	0.921	0.944	0.967	1.015	1.066	1.203	-----	-----	-----	-----	-----	12,000
16,000	0.930	-----	0.879	0.895	0.912	0.928	0.963	0.999	1.095	1.199	-----	-----	-----	-----	16,000
20,000	0.908	-----	-----	0.878	0.891	0.904	0.931	0.959	1.032	1.111	1.196	-----	-----	-----	20,000
30,000	0.870	-----	-----	-----	-----	0.870	0.887	0.905	0.951	0.999	1.050	1.103	1.218	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	-----	0.866	0.879	0.912	0.947	0.943	1.020	1.099	1.184	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	0.862	0.888	0.915	0.916	0.972	1.032	1.095	50,000
60,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.871	0.893	0.882	0.939	0.987	1.038	60,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.849	0.865	0.859	0.898	0.933	0.969	80,000
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	0.846	0.943	0.872	0.899	0.927	100,000

*For larger numbers of units, enter table with 100 units and 100 times the average area per unit.
For instance, a building with 120 units and 400 square feet per unit, use 100 units and 40,000 Sq. Ft. for a multiplier of 1.184.
Do not use basement factors with basement apartment living units.

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MUSEUMS



GOOD CLASS A-B

OCCUPANCY DESCRIPTION: These buildings are designed for long term display of works of art, crafts, natural history, etc., and include exhibit gallery, collection storage, vault, workshop, sales, lecture meeting, theater, food service areas, etc., commensurate with the quality.

INCLUDED IN COSTS: The basic building display structures and necessary permanent lighting, electrical connections and security.

NOT INCLUDED IN COSTS: Any display cases, food equipment, movable trade fixtures and chattels or works of art.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 415.50	Good masonry, concrete panels, good architecture and entry	Plaster, good ornamental detail, marble, terrazzo, many extras, theater	Special lighting and security system, good plumbing, kitchen	Hot and chilled water (zoned)
	Average	297.50	Face brick, concrete panels with trim, plain architecture	Drywall, terrazzo, good exhibition, work areas, good lecture facilities	Good lighting, adequate plumbing and surveillance, kitchenette	Warm and cool air (zoned)
A-B	Display basement	222.50	Plaster interior	Display finish, acoustic tile, carpet, terrazzo, vinyl composition, storage	Adequate exhibit lighting and plumbing	Warm and cool air (zoned)
	Finished basement	160.50	Concrete or masonry, partly finished interior	Masonry partitions, repair, storage and staff support rooms	Adequate lighting and plumbing	Hot water
	Parking basement	97.00	Unfinished interior	Unfinished (service booth)	Exposed lighting, drains	Ventilation
	Office mezzanine	105.00	Not included	Enclosed, average office finish, plaster soffit	Average office lighting and plumbing	In building cost
	Display mezzanine	76.50	Not included	Display finish, acoustic tile, carpet, hardwood, vinyl composition	Adequate exhibit lighting and plumbing	In building cost
	Storage mezzanine	45.50	Not included	Painted soffit, unfinished floor, reserve collection storage	Minimum, exposed lighting	In building cost
C	Excellent	388.50	Special architecture and trim, best masonry, good entrance	Best ornamental plaster and detail, terrazzo, marble, many extras, theater	Special lighting and security system, good plumbing, kitchen	Hot and chilled water (zoned)
	Good	288.00	Face brick, concrete panels, good architecture	Drywall, terrazzo, good exhibition, work areas, good lecture facilities	Good lighting and surveillance, adequate plumbing, kitchenette	Warm and cool air (zoned)
	Average	209.00	Brick, block, concrete panels, little trim	Drywall, some ornamentation, vinyl composition, terrazzo, some extras	Adequate lighting, plumbing and security	Package A.C.
	Low-cost	151.50	Low-cost brick, block, tilt-up	Painted, acoustic and asphalt tile	Minimum lighting and plumbing	Forced air
D	Excellent	357.00	Special architecture and trim, best sidings, good entrance	Best ornamental plaster and detail, terrazzo, marble, many extras, theater	Special lighting and security system, good plumbing, kitchen	Hot and chilled water (zoned)
	Good	260.00	Face brick, veneer, EIFS, good architecture	Drywall, terrazzo, good exhibition, work areas, good lecture facilities	Good lighting and surveillance, adequate plumbing, kitchenette	Warm and cool air (zoned)
	Average	199.00	Brick veneer, good stucco, trim, ornamental entrance	Drywall, some ornamentation, vinyl composition, terrazzo, some extras	Adequate lighting, plumbing and security	Package A.C.
	Low-cost	143.50	Low-cost stucco or siding, very plain, small lobby	Drywall, plywood, acoustic tile, wood or asphalt tile floors, few extras	Minimum lighting and plumbing, minimum gallery facility	Forced air
D POLE	Low-cost	126.00	Pole frame, metal siding, finished interior, small lobby, very plain	Drywall, plywood, acoustic tile, wood or asphalt tile floors, few extras	Minimum lighting and plumbing, minimum gallery facility	Forced air
S	Low-cost	130.50	Steel frame, metal siding, finished interior, small lobby, very plain	Drywall, plywood, acoustic tile, wood or asphalt tile floors, few extras	Minimum lighting and plumbing, minimum gallery facility	Forced air
CDS	Display basement	157.00	Plastered interior	Display finish, acoustic tile, carpet, vinyl comp., some storage rooms	Adequate exhibit lighting and plumbing	Forced air
	Finished basement	114.00	Painted interior	Workshop, storage, utility and staff support rooms	Adequate lighting and plumbing	Forced air
	Parking basement	62.50	Unfinished interior	Painted ceiling, concrete floor with hardener, lines and stops	Exposed lighting, adequate drains	Ventilation
	Office mezzanine	73.50	Not included	Plaster or drywall soffit, office partitions and finish	Average office lighting and plumbing	In building cost
	Display mezzanine	85.50	Not included	Plaster or drywall soffit, carpet, hardwood and vinyl composition	Adequate exhibit lighting and plumbing	In building cost
	Storage mezzanine	31.75	Not included	Drywall soffit, wood floor, light reserve collection storage	Minimum lighting, no plumbing	In building cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.52 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

MUSEUMS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.776	18	1.054
10	.833	20	1.106
12	.889	22	1.158
14	.945	24	1.210
16	1.000 (base)	28	1.313

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	250	300	350	400	450	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.205	1.264	1.322	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	-----	.999	1.011	1.023	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	**10,000**
14,000	-----	-----	-----	.982	.992	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	**14,000**
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	**25,000**
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	**40,000**
45,000	-----	-----	-----	-----	-----	-----	.934	.939	.946	.954	.962	.976	.989	1.001	**45,000**
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	**50,000**
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	**75,000**
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	**100,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

NATATORIUMS

OCCUPANCY DESCRIPTION: These structures are designed as specialized gymnasium type structures for aquatic sports.

Swimming pools and viewing facilities commensurate with the quality are included.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators or equipment and trade fixtures.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 336.50	Heavy frame, best masonry walls, good entrance and lobby	Good main pool, viewing facilities, high-cost finishes, many extras	Good lighting and outlets, good plumbing, extra features	Heat pump system
	Average	250.00	Steel columns and girders, face brick, best ornamental block	Acoustic treatment, tiled surfaces, good competition pools and detail	Adequate lighting and outlets, tiled showers and restrooms	Heat pump system
C	Good	249.00	Steel columns and girders, face brick, best ornamental block	Good tile surfaces and detail, competition pools, viewing facilities	Good lighting and outlets, tiled showers and restrooms	Heat pump system
	Average	177.50	Steel or Glulam trusses or girders, brick, block or tilt-up	Plaster or drywall, tile wainscot, Olympic or good municipal pools	Adequate lighting and plumbing, shower rooms	Package A.C.
	Low cost	131.50	Light frame, block or tilt-up, very plain	Concrete floor, some tile, single pool, minimal finish	Minimum sports lighting and plumbing	Forced air
D	Good	240.00	Steel or Glulam frame, trusses and girders, brick veneer, best stucco	Good tile surfaces and detail, competition pools, viewing facilities	Good lighting and outlets, tiled showers and restrooms	Heat pump system
	Average	170.00	Heavy frame, trusses or girders, good stucco or siding, little trim	Plaster or drywall, tile wainscot, Olympic or good municipal pools	Adequate lighting and plumbing, shower rooms	Package A.C.
	Low cost	124.00	Light frame, siding or stucco, very plain	Concrete floor, some tile, single pool, minimal finish	Minimum sports lighting and plumbing	Forced air
D POLE	Low cost	118.50	Pole frame, metal siding, some interior finish and insulation	Concrete floor, some tile, single pool, minimal finish	Minimum sports lighting and plumbing	Forced air
S	Average	164.50	Pre-engineered, finished interior, insulation	Plaster and drywall, tile wainscot, Olympic or good municipal pools	Adequate lighting and plumbing, shower rooms	Package A.C.
	Low cost	120.00	Pre-engineered, partly finished interior, some insulation	Concrete floor, some tile, single pool, minimal finish	Minimum sports lighting and plumbing	Forced air

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

NATATORIUMS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.