OFFICE BUILDINGS



EXCELLENT CLASS A



EXCELLENT CLASS A

OCCUPANCY DESCRIPTION: These buildings are designed for commercial occupancies and are normally subdivided into smaller units for tenant use.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, parking or balconies.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$430.00	Best metal or stone, brick or block backup, solar glass	Plaster, best veneers, vinyl wall coverings, vinyl, terrazzo, carpet	*Luminous ceilings, many outlets, many private restrooms	Hot and chilled water (zoned)
	Good	345.00	Good metal and solar glass, face brick, precast concrete panels	Drywall or plaster, some wall cover, acoustic tile, vinyl tile, carpet	*Good fluorescent, high intensity lighting, good restrooms	Hot and chilled water (zoned)
	Average	261.50	Brick, concrete or metal and glass panels, little trim	Average partitions, acoustic tile, vinyl composition, some extras	*Average intensity fluorescent lighting, average restrooms	Warm and cool air (zoned)
	Low cost	211.00	Minimum-cost walls and fenestration, little trim	Drywall, acoustic ceilings, asphalt tile, few partitions	*Minimum office lighting and plumbing	Warm and cool air (zoned)
B	Excellent	393.50	Best metal or stone, brick or block backup, tinted glass	Plaster, best veneers, vinyl wall coverings, vinyl tile, terrazzo	*Luminous ceilings, many outlets, many private restrooms	Hot and chilled water (zoned)
	Good	315.50	Good metal and solar glass, face brick, precast concrete panels	Drywall/plaster, some wall cover, acoustic tile, vinyl tile, carpet	*Good fluorescent, high intensity lighting, good restrooms	Hot and chilled water (zoned)
	Average	236.50	Brick, concrete or metal and glass panels, little trim	Average partitions, acoustic tile, vinyl composition, some extras	*Average intensity fluorescent lighting, average restrooms	Warm and cool air (zoned)
	Low cost	191.50	Minimum-cost walls and fenestration, little trim	Drywall, acoustic ceilings, asphalt tile, few partitions	*Minimum office lighting and plumbing	Warm and cool air (zoned)
A-B	Basement offices	194.00	Plaster interior	Average office finish, acoustic tile, vinyl composition	Adequate office lighting and plumbing	Warm and cool air (zoned)
	Stor. bsmt.	85.50	Painted interior	Partitions for storage and heating	Minimum lighting/ plumbing	Space heaters
	Pkg. bsmt.	92.00	Unfinished interior	Unfinished, small service area	Minimum lighting/ plumbing	Ventilation
C	Excellent	335.50	Steel frame, masonry and glass, stone ornamentation, top quality	Plaster, paneling, carpet and terrazzo, suspended ceilings	*Best fluorescent ceiling panels, tiled restrooms, good fixtures	Warm and cool air (zoned)
	Good	233.50	Steel frame or bearing walls, brick/ conc. panels, some ornamentation	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	*Good fluorescent lighting, good restrooms and fixtures	Package A.C.
	Average	166.00	Steel or concrete frame, or bearing walls, some trim	Paint, drywall partitions, acoustic tile, vinyl composition	*Fluorescent lighting, adequate outlets and plumbing	Forced air
	Low cost	107.50	Masonry bearing walls, light rafters, very plain	Paint, few low-cost partitions, acoustic tile, asphalt tile	Minimum office lighting and plumbing	Wall furnace
D	Excellent	318.50	Studs or steel columns, bar or web joists, brick or stone veneer, EIFS	Best plaster, paneling, carpet and vinyl tile	*Fluorescent panels, many outlets, good tiled restrooms	Warm and cool air (zoned)
	Good	221.50	Best stucco on good frame, brick or stone trim, good front	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	*Good fluorescent lighting, good restrooms and fixtures	Package A.C.
	Average	156.00	Stucco or wood siding on wood or steel studs, some trim	Drywall, acoustic tile, low-cost carpet or vinyl composition	*Adequate lighting and plumbing	Forced air
	Low cost	101.00	Light stucco or siding on wood or steel studs, very plain	Drywall, few partitions, acoustic tile, asphalt tile	Minimum lighting and plumbing	Wall furnace
D POLE	Good	208.00	Good metal panels, fenestration, some brick or stone trim	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	*Good fluorescent lighting, good restrooms and fixtures	Package A.C.
	Average	142.50	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, low-cost carpet or vinyl composition	Adequate lighting and plumbing	Forced air
	Low cost	92.50	Pole frame, finished interior, some insulation	Drywall, few partitions, acoustic tile, asphalt tile	Minimum lighting and plumbing	Wall furnace
S	Good	214.50	Good sandwich panels and fenestration, some brick or stone	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	*Good fluorescent lighting, good restrooms and fixtures	Package A.C.
	Average	147.00	Insulated wall or sandwich panels, adequate fenestration	Drywall, acoustic tile, low-cost carpet or vinyl composition	Adequate lighting and plumbing	Forced air
	Low cost	98.00	Steel or aluminum on light frame, finished interior, some insulation	Drywall, few partitions, acoustic tile, asphalt tile	Minimum lighting and plumbing	Wall furnace
CDS†	Basement offices	112.00	Plaster or drywall interior	Average office finish, acoustic tile, vinyl composition	Typical office lighting and plumbing	Forced air
	Stor. bsmt.	48.50	Painted interior	Paint only, few partitions	Minimum lighting, drains	None
	Pkg. bsmt.	60.00	†Unfinished interior	Finished ceiling, concrete floor	Minimum lighting, drains	Ventilation

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.54 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

OFFICE BUILDINGS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Classes C/D	Sq. Ft. Costs
Excellent	$ 17.75	Excellent	$ 8.96
Good	12.10	Good	5.39
Average	8.29	Average	3.25
Low cost	5.67		

ELEVATOR STOPS: For basements stops, add $9,400 to $14,400 per stop.

A small passenger elevator with simple call system and push button control, four passenger cab and two or three stops, costs $68,000 to $112,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99
75,000	3.39	4.20	5.22	6.46
100,000	3.27	4.01	4.96	6.13

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 41.00	$ 53.00	$ 69.00
Steel	29.75	40.50	55.00	75.50
Wood	25.25	33.75	45.00	60.00
Add for ornate finishes, balustrades	27.50	34.00	41.75	51.00
Add for roofs or awnings	15.20	20.15	26.75	35.75

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$ 2,950 to $ 3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$ 2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Up to 30 stories, add .5% (1/2%) for each story over three, above ground, to all base costs; over 30, add .4% (4/10%) for each additional story.

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.299	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	1.007	1.040	1.072	1.105	1.168	1.235	1.364	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	-----	-----	.958	.975	1.007	1.040	1.105	1.168	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.936	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.926	.942	.975	1.007	1.040	1.105	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.052	1.105	1.155	-----	**10,000**
14,000	-----	-----	-----	-----	-----	-----	.900	.920	.938	.956	.993	1.030	1.067	1.105	**14,000**
20,000	-----	-----	-----	-----	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.897	.915	.932	.949	.965	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.897	.910	.923	.936	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	**50,000**
75,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.873	.879	.885	.892	**75,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

OFFICE BUILDINGS (ALTERNATE METHOD)
CLASSES A AND B



EXCELLENT CLASS A

OCCUPANCY DESCRIPTION: Shell This occupancy, together with occupancy Interior Build-out, Office Building, allows you to individually price the shell and the tenant improvement costs for an office building. This provides an alternative to occupancy Office Building, which includes both the shell and tenant improvement costs.

These building shells are designed for commercial occupancies and are normally subdivided into smaller units for tenant use. Costs include the basic building shell and service core (lobby) area finishes only (commensurate with the building class and rank). Only rough electrical and plumbing are included, except for the lobby finishes and core restrooms.

Interior Build-out
This occupancy, together with occupancy Shell, Office Building, allows you to individually price the shell and the tenant improvement costs for an office building. This provides an alternative to occupancy Office Building, which includes both the shell and tenant improvement costs.

Office building build-out finish costs include typical partition density and finishes commensurate with the quality. Floor finishes are carpet, terrazzo or vinyl. Ceiling finishes vary with the quality.

Luminous ceilings and high intensity fluorescent lighting are found in the better qualities.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit and jail hardware.

NOT INCLUDED IN COSTS: Sprinklers, equipment, parking or balconies.

CLASSES A AND B: OFFICE SHELL BUILDINGS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$ 250.00	Best metal or stone curtain panels, solar glass, atrium, highly ornamental	Plaster, best veneers, vinyl, best marble and carpet, top lobby finishes	*Luminous lobby ceilings, good tiled core restrooms	None
	Good	194.50	Good metal and solar glass, face brick, best precast concrete panels	Plaster, paneling, vinyl, good pavers, terrazzo, carpet, good entry & lobbies	*Good fluorescent core ceilings, adequate restrooms	None
	Average	151.50	Brick, concrete or metal and glass, steel stud panels, some trim	Drywall or plaster, vinyl, terrazzo, carpet, adequate entry lobby	*Average-intensity core lighting, average restrooms	None
	Low cost	118.00	Minimum-cost walls and fenestration, little trim	Drywall, paint or paper, acoustic ceilings, vinyl comp., plain lobbies	*Minimum lobby lighting, few core extras, small restrooms	None
B	Excellent	223.50	Best metal or stone curtain panels, tinted glass, atrium, very ornamental	Plaster, best veneers, vinyl, best marble and carpet, top lobby finishes	*Luminous lobby ceilings, good tiled core restrooms	None
	Good	171.50	Good metal and solar glass, face brick, best precast concrete panels	Plaster, paneling, vinyl, good pavers, terrazzo, carpet, good entry & lobbies	*Good fluorescent core, ceilings, adequate restrooms	None
	Average	132.50	Brick, concrete or metal and glass panels, some trim, entry ornament	Drywall or plaster, vinyl, terrazzo, carpet, adequate entry lobby	*Average-intensity core lighting, average restrooms	None
	Low cost	102.50	Minimum-cost walls, precast elements and fenestration, little trim	Drywall, paint or paper, acoustic ceilings, vinyl comp., plain lobbies	*Minimum lobby lighting, few core extras, small restrooms	None

CLASSES A AND B: INTERIOR OFFICE BUILD-OUT

CLASS	TYPE	COST/ SQ. FT.	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 175.00	High-cost partitions, insulated, many private suites, high-density build-out, many workstations, best conference and reception finishes, standard administrative areas	Good private office lighting and restrooms, best upgrades	Hot and chilled water (zoned)
	Good	146.50	Good plaster, partitions, paneling, suspended acoustic, carpet, tile or vinyl, good reception and meeting-room space, good cabinetry, some communication room build-out	Good fluorescent lighting, wiring, outlets and cabling, some extras	Hot and chilled water (zoned)
	Average	107.00	Average drywall or plaster, acoustic tile, vinyl composition or carpet, adequate shelving and counters, small reception area, few plain meeting rooms, typical clerical	Adequate lighting and outlets, average break room and fixtures	Warm and cool air (zoned)
	Low cost	91.00	Low-cost partitions, paint, suspended ceiling, vinyl composition, low-cost carpet, minimal counters and shelving, low-density build-out, minimum workletter finishes	Minimum lighting and outlets, few extras, small break room	Warm and cool air (zoned)

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

OFFICE BUILDINGS (ALTERNATE METHOD)
CLASSES A AND B

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Excellent	$ 17.75
Good	12.10
Average	8.29
Low cost	5.67

ELEVATOR STOPS: For basements stops, add $9,400 to $14,400 per stop.

A small passenger elevator with simple call system and push button control, four passenger cab and two or three stops, costs $68,000 to $112,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99
75,000	3.39	4.20	5.22	6.46
100,000	3.27	4.01	4.96	6.13

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 41.00	$ 53.00	$ 69.00
Steel	29.75	40.50	55.00	75.50
Wood	25.25	33.75	45.00	60.00
Add for ornate finishes, balustrades	27.50	34.00	41.75	51.00
Add for roofs or awnings	15.20	20.15	26.75	35.75

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$ 2,950 to $ 3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$ 2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Up to 30 stories, add .5% (1/2%) for each story over three, above ground, to all base costs; over 30, add .4% (4/10%) for each additional story.

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.299	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	1.007	1.040	1.072	1.105	1.168	1.235	1.364	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	-----	-----	.958	.975	1.007	1.040	1.105	1.168	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.936	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.926	.942	.975	1.007	1.040	1.105	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.052	1.105	1.155	-----	-----	**10,000**
14,000	-----	-----	-----	-----	-----	.900	.920	.938	.956	.993	1.030	1.067	1.105	1.140	**14,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	-----	.897	.915	.932	.949	.965	.983	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.897	.910	.923	.936	.949	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	.928	**50,000**
75,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.873	.879	.885	.892	.900	**75,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

OFFICE BUILDINGS (ALTERNATE METHOD)
CLASSES C, D and S



EXCELLENT CLASS C

OCCUPANCY DESCRIPTION: Shell This occupancy, together with occupancy Interior Build-out, Office Building, allows you to individually price the shell and the tenant improvement costs for an office building. This provides an alternative to occupancy Office Building, which includes both the shell and tenant improvement costs.

These building shells are designed for commercial occupancies and are normally subdivided into smaller units for tenant use. Costs include the basic building shell and service core (lobby) area finishes only (commensurate with the building class and rank). Only rough electrical and plumbing are included, except for the lobby finishes and core restrooms.

Interior Build-out
This occupancy, together with occupancy Shell, Office Building, allows you to individually price the shell and the tenant improvement costs for an office building. This provides an alternative to occupancy Office Building, which includes both the shell and tenant improvement costs.

Office building build-out finish costs include typical partition density and finishes commensurate with the quality. Floor finishes are carpet, terrazzo or vinyl. Ceiling finishes vary with the quality.

Luminous ceilings and high intensity fluorescent lighting are found in the better qualities.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit and jail hardware.

NOT INCLUDED IN COSTS: Sprinklers, equipment, parking or balconies.

CLASSES C, D AND S: OFFICE SHELL BUILDINGS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 192.50	Steel frame, masonry and glass, stone ornamentation, high quality	Core finish only, veneers, vinyl, marble, carpet, good lobby finishes	*Luminous lobby ceilings, good core restrooms	None
	Good	128.00	Steel frame or bearing walls, brick/ conc. panels, some ornamentation	Core finish only, vinyl, standard terrazzo, carpet, adequate entry lobby	*Good fluorescent core ceilings, average restrooms, service fixtures	None
	Average	85.00	Steel or concrete frame, or bearing walls, some trim	Bare office space, unfinished floor, some service areas	*Rough office electrical and plumbing, some service outlets	None
	Low cost	54.00	Masonry bearing walls, light rafters, very plain	Bare office space, floor slab, no service areas	Rough electrical and plumbing	None
D	Excellent	177.00	Studs or steel columns, bar or web joists, best brick or stone veneer	Core finish only, veneers, vinyl, marble, carpet, good lobby finishes	*Luminous lobby ceilings, good core restrooms	None
	Good	117.00	Best stucco on good frame, brick or stone trim, good front	Core finish only, vinyl, standard terrazzo, carpet, adequate entry lobby	*Good fluorescent core ceilings, average restrooms, service fixtures	None
	Average	77.00	Stucco or wood siding on wood studs, some trim	Bare office space, unfinished floor, some service areas	*Rough office electrical and plumbing, some service outlets	None
	Low cost	47.50	Light stucco or siding on wood studs, very plain	Bare office space, floor slab, no service areas	Rough electrical and plumbing	None
DPOLE	Average	62.00	Pole frame, insulated metal panels, some ornamentation	Bare office space, unfinished floor, some service areas	Rough office electrical and plumbing, some service outlets	None
	Low cost	38.50	Pole frame, metal panels, finished inside, little trim	Bare office space, floor slab, no service areas	Rough electrical and plumbing	None
S	Good	108.50	Good sandwich panels and fenestration, some brick or stone	Core finish only, vinyl, standard terrazzo, carpet, adequate entry lobby	*Good fluorescent core ceilings, average restrooms, service fixtures	None
	Average	66.00	Insulated wall or sandwich panels, adequate fenestration	Bare office space, unfinished floor, some service areas	Rough office electrical and plumbing, some service outlets	None
	Low cost	41.50	Steel or aluminum on light frame, finished interior, some insulation	Bare office space, floor slab, no service areas	Rough electrical and plumbing	None

CLASSES C, D AND S: INTERIOR OFFICE BUILD-OUT

CLASS	TYPE	COST/ SQ. FT.	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
CDS	Excellent	$ 143.00	High-cost partitions, conference and reception finishes, standard administrative areas, good workstations, break room, some private suites, high-density build-out	Good fluorescent lighting, wiring, outlets and cabling, good extras	Warm and cool air (zoned)
	Good	105.00	Plaster or drywall, good partitions, paneling, suspended acoustic, carpet, tile or vinyl, good reception and meeting-room space, some good cabinetry and management offices	Good fluorescent lighting, outlets, average break room and fixtures	Package A.C.
	Average	80.00	Average drywall, acoustic tile, vinyl composition or carpet, adequate shelving, counters, small reception area, few plain management and meeting rooms, typical clerical	Adequate lighting and outlets, average restrooms and fixtures	Forced air
	Low cost	53.50	Low-cost partitions, paint, suspended ceiling, vinyl composition, low-cost carpet, minimal counters and shelving, low-density build-out	Minimum lighting and plumbing, few extras, small restrooms	Electric wall heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

OFFICE BUILDINGS (ALTERNATE METHOD)
CLASSES C, D and S

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes C/D/S	Sq. Ft. Costs
Excellent	$ 8.96
Good	5.39
Average	3.25

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,400 to $14,400 per stop.

A small passenger elevator with simple call system and push button control, four passenger cab and two or three stops, costs $68,000 to $112,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99
75,000	3.39	4.20	5.22	6.46
100,000	3.27	4.01	4.96	6.13

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 41.00	$ 53.00	$ 69.00
Steel	29.75	40.50	55.00	75.50
Wood	25.25	33.75	45.00	60.00
Add for ornate finishes, balustrades	27.50	34.00	41.75	51.00
Add for roofs or awnings	15.20	20.15	26.75	35.75

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$ 2,950 to $ 3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$ 2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Up to 30 stories, add .5% (1/2%) for each story over three, above ground, to all base costs; over 30, add .4% (4/10%) for each additional story.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.299	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	1.007	1.040	1.072	1.105	1.168	1.235	1.364	-----	-----	-----	-----	-----	-----	-----	2,000
4,000	-----	-----	.958	.975	1.007	1.040	1.105	1.168	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	.936	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	5,000
8,000	-----	-----	-----	-----	.926	.942	.975	1.007	1.040	1.105	-----	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.052	1.105	1.155	-----	-----	10,000
14,000	-----	-----	-----	-----	-----	.900	.920	.938	.956	.993	1.030	1.067	1.105	1.140	14,000
20,000	-----	-----	-----	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	20,000
30,000	-----	-----	-----	-----	-----	-----	-----	-----	.897	.915	.932	.949	.965	.983	30,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.897	.910	.923	.936	.949	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	.928	50,000
75,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.873	.879	.885	.892	.900	75,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

OFFICE BUILDINGS – REFINEMENTS

OCCUPANCY DESCRIPTION: Atrium/vestibule entries or lobbies are glassed structures which usually abut or are underneath elevated buildings.

Mechanical penthouses shelter the buildings' elevators and other mechanical equipment that is generally located on the roof. The excellent cost rank represents a full intermediate mechanical utility floor found in large high-rise construction. For finished penthouses, i.e., those containing roof apartments, restaurants, use the proper costs for that occupancy.

Mezzanines are generally partial floors between two finished floors, or between the ground floor and the roof, occupying a lesser area than the full floor or floors. The area may be open for general storage or to house the building's mechanicals, or it may be finished for a particular use, such as offices.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers, elevators or other mechanical equipment.

ATRIUMS/ VESTIBULES

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 740.50	Structural glass, decorative space frame and shed atrium glazing	Granite, marble, high-cost pavers, ornate finishes	Best lighting, adequate electrical and plumbing	Hot and chilled water (zoned)
	Good	482.50	Architectural glazed shed atrium, good space frame	Good stone, masonry pavers, good lobby wall treatment, trim	Good lighting and plumbing	Hot and chilled water (zoned)
	Average	323.00	Glass shed curtain wall, glass and some exposed roof deck	Terrazzo, masonry pavers, few partitions or extras	Adequate electrical and plumbing	Hot and chilled water (zoned)
	Low cost	206.00	Metal and glass, some concrete, brick or stucco panels, no roof	Under elevated building vestibule, low-cost terrazzo, vinyl and acoustic	Minimum electrical and plumbing	Warm and cool air (zoned)
	Cheap	100.00	Brick, block, concrete, very plain, no roof structure	Under elevated building, low-cost elevator/stairway vestibule only	Minimum electrical	None
CDS	Good	383.00	Good glazed shed atrium	Stone or masonry pavers, some good lobby wall treatment, trim	Good lighting and plumbing	Hot and chilled water (zoned)
	Average	238.00	Glass shed curtain wall, skylights, some exposed roof deck	Low-cost terrazzo, masonry pavers, few partitions or extras	Adequate electrical and plumbing	Warm and cool air (zoned)
	Low cost	162.00	Glass panels, block, brick veneer or stucco, no roof	Under building vestibule, vinyl composition and acoustic tile	Minimum electrical and plumbing	Warm and cool air (zoned)
	Cheap	71.50	Block, brick veneer or stucco, very plain, no roof structure	Under elevated building, low-cost elevator/stairway vestibule	Minimum electrical	None

MECHANICAL PENTHOUSES

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent (Full floor)	$ 134.50	Louvers, best curtain wall panels, matching spandrel	Intermediate full mechanical floor, utility space, some storage	Adequate lighting, utility outlets and drains	None
	Good	121.50	Good curtain panels, masonry, louvers, concrete roof	Mechanical and storage, some finish and partitions	Adequate lighting, utility outlets and drains	None
	Average	86.00	Curtain panels or masonry, steel roof deck	Unfinished equipment and storage, few partitions	Exposed lighting, adequate drains	None
	Low cost	60.50	Low-cost panels, masonry, very plain	Unfinished interior, roof access only	Minimum lighting, floor drains	None
CDS	Average	64.50	Frame or bearing walls, good panels, louvers or masonry, trim	Unfinished equipment and storage, few partitions	Exposed lighting, adequate drains	None
	Low cost	45.50	Light frame or stud single wall, low-cost metal, stucco or siding	Unfinished interior	Minimum lighting, floor drains	None

MEZZANINES

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Office	$ 121.00	Not included	Enclosed, average office finish, plaster soffit	Average office lighting and plumbing	In building cost
	Open	68.50	Not included	Carpet and vinyl composition, plaster soffit	Average lighting and plumbing	In building cost
	Good storage/ mechanical	82.50	Not included	Metal grating on steel structure	Adequate lighting, no plumbing	In building cost
	Average storage	46.00	Not included	Painted soffit, light storage, unfinished floor	Minimum, exposed lighting	In building cost
	Low storage/ mechanical	20.00	Not included	Interstitial space, walk-on platform ceiling assembly, unfinished interior	Minimum lighting, drains	In building cost
CDS	Office	87.00	Not included	Enclosed, average office finish, acoustic tile soffit	Average office lighting and plumbing	In building cost
	Open	48.00	Not included	Open, finished floors and soffit	Average lighting, no plumbing	In building cost
	Average storage	32.25	Not included	Drywall soffit, wood floor, light storage	Minimum lighting, no plumbing	In building cost

MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

OFFICE BUILDINGS – REFINEMENTS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: For vestibule, penthouse or mezzanine elevator stops, add $9,400 to $14,400 per stop.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99

For intermediate or ground-floor parking levels under elevated office buildings. see Parking Levels.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$ 2,950 to $ 3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$ 2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Up to 30 stories, add .5% (1/2%) for each story over three, above ground, to all base costs; over 30, add .4% (4/10%) for each additional story.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023	24	1.276
9	.928	14	1.046	28	1.367
10	.953	15	1.069	32	1.459
11	.977	16	1.092	36	1.552
12	1.000 (base)	20	1.184		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.299	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	1.007	1.040	1.072	1.105	1.168	1.235	1.364	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	-----	-----	.958	.975	1.007	1.040	1.105	1.168	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.936	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.926	.942	.975	1.007	1.040	1.105	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.052	1.105	1.155	-----	-----	**10,000**
14,000	-----	-----	-----	-----	-----	.900	.920	.938	.956	.993	1.030	1.067	1.105	1.140	**14,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	-----	.897	.915	.932	.949	.965	.983	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.897	.910	.923	.936	.949	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	.928	**50,000**
75,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.873	.879	.885	.892	.900	**75,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

PASSENGER TERMINALS



AVERAGE CLASS C



FAIR CLASS C

OCCUPANCY DESCRIPTION: These passenger or commuter terminal buildings include low-quality bus or train stop waiting structures to the high cost major airport type facility with separate baggage, ticket lobby, concession, lounge and concourse facilities.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Ticket, baggage, boarding, concession or other food service equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 664.00	Special architecture, metal and glass, stone, concrete, skylights	Special finishes, acoustic design, high-cost lobby, concourse finishes	*High-quality specialty lighting, best wiring throughout, good plumbing	Complete H.V.A.C.
	Good	474.00	Face brick, metal and glass, limestone, architectural concrete	Good finishes throughout, some extras, typical major terminal facility	*Special lighting, good sound systems and plumbing, some extras	Complete H.V.A.C.
	Average	337.50	Brick, concrete or metal panels, formed concrete, decorative lobby	Vaulted ceilings, pavers, terrazzo, good air or train-type terminal	*Good lighting, sound systems and plumbing, food service	Complete H.V.A.C.
	Low cost	241.50	Brick, precast concrete, good block, some trim	Finished interior, suspended ceiling, terrazzo lobby, small main terminal	*Average lighting, good sound and plumbing, lounge	Complete H.V.A.C.
A-B	Semi-fin. basement	115.00	Low cost finishes	Minimum lounge area, restrooms, some utility and storage	Minimum lighting, adequate plumbing	None
	Utility basement	70.50	Reinforced concrete, unfinished interior	Unfinished storage areas, some partitions	Minimum lighting and plumbing, drains	None
C	Excellent	455.50	High-cost roof, large arched entries and domed skylights	Special finishes, acoustic design, high-cost lobby, concourse finishes	*High-quality specialty lighting, best wiring throughout, good plumbing	Complete H.V.A.C.
	Very good	359.50	Face brick, stone, terra cotta, ornamental entrance and lobby	Good finishes throughout, some extras, typical major terminal facility	*Special lighting, good sound systems and plumbing, some extras	Complete H.V.A.C.
	Good	277.50	Brick, block, concrete, good decorative front and lobby	Vaulted ceilings, pavers, terrazzo, good air or train-type terminal	Good lighting, sound systems and plumbing, food service	Hot and chilled water (zoned)
	Average	170.00	Brick, block, concrete, good front and lobby, some trim	Finished interior, suspended ceiling, terrazzo lobby, small main terminal	Average lighting, good sound and plumbing, lounge	Warm and cool air (zoned)
	Fair	137.50	Brick, block, concrete panels, plain commercial building, small entry	Drywall, acoustic tile, vinyl comp. lobby, small city bus station	Minimum lighting, adequate sound, minimum plumbing	Heat pump system
	Low cost	108.50	Low-cost block, tilt-up, very plain, acoustic sound walls	Few partitions, very plain, minimum waiting and concession/ticket area	Minimum code, public address system	Package A.C.
D	Very good	338.50	Face brick or stone veneer, ornamental entrance and lobby	Good finishes throughout, some extras, typical major terminal facility	*Special lighting, good sound systems and plumbing, some extras	Complete H.V.A.C.
	Good	259.50	Stucco, some brick or stone trim, decorative front and lobby	Vaulted ceilings, pavers, terrazzo, good air or train-type terminal	Good lighting, sound systems and plumbing, food service	Hot and chilled water (zoned)
	Average	159.00	Stucco or siding, good front and lobby, some trim	Finished interior, suspended ceiling, terrazzo lobby, small main terminal	Average lighting, good sound and plumbing, lounge	Warm and cool air (zoned)
	Fair	128.00	Siding or stucco, small entrance	Drywall, acoustic tile, vinyl comp. lobby, small city bus station	Minimum lighting, adequate sound, minimum plumbing	Heat pump system
	Low cost	101.00	Low-cost wood or stucco, very plain	Few partitions, very plain, minimum waiting and concession/ticket area	Minimum code, public address system	Package A.C.
D POLE	Fair	123.00	Metal panels on pole frame, finished interior, small entrance	Drywall, acoustic tile, vinyl comp. lobby, small city bus station	Minimum lighting, adequate sound, minimum plumbing	Heat pump system
	Low cost	96.50	Pole frame and truss, metal siding, low-cost finish and insulation	Few partitions, very plain, minimum waiting and concession/ticket area	Minimum code, public address system	Package A.C.
S	Average	159.00	Good metal panels, roof, front and lobby, some trim	Finished interior, suspended ceiling, terrazzo lobby, small main terminal	Average lighting, good sound and plumbing, lounge	Warm and cool air (zoned)
	Fair	128.50	Metal panels, finished interior, small entrance, masonry sound walls	Drywall, acoustic tile, vinyl comp. lobby, small city bus station	Minimum lighting, adequate sound, minimum plumbing	Heat pump system
	Low cost	101.00	Single wall, low-cost interior finish and insulation	Few partitions, very plain, minimum waiting and concession/ticket area	Minimum code, public address system	Package A.C.
CDS	Semi-fin. basement	78.00	Low cost finishes	Minimum lounge area, restrooms, some utility and storage	Minimum lighting, adequate plumbing	None
	Utility basement	44.75	Reinforced concrete, unfinished interior	Unfinished storage area	Minimum lighting and drains	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

PASSENGER TERMINALS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked.

For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Classes C/D/S	Sq. Ft. Costs
Excellent	$18.40	Excellent	$11.50
Good	13.50	Very Good	8.25
Average	9.85		
Low cost	7.19		

A small freight elevator with simple call system and push-button control, four-passenger cab and two or three stops, costs $66,500 to $109,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.16	$ 5.51	$ 7.28	$ 9.63
10,000	3.78	4.95	6.48	8.49
20,000	3.37	4.37	5.70	7.43
40,000	3.18	4.12	5.34	6.89
50,000	2.96	3.79	4.89	6.27
80,000	2.75	3.49	4.47	5.72
100,000	2.67	3.39	4.32	5.51
200,000	2.40	3.04	3.84	4.85
400,000	2.17	2.73	3.39	4.23

For pedestrian bridges or tunnels, see Page CAL 248.

2

PASSENGER TERMINAL HEATING, COOLING AND AIR CONDITIONING

Costs of some high-quality terminal mechanical items are listed separately from those of other buildings because of special requirements. These costs are averages of total installed cost of the entire heating or cooling installation including its prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated costs.

COMPLETE H.V.A.C. Classes A/B	Sq. Ft. Costs	COMPLETE H.V.A.C. Classes A/B	Sq. Ft. Costs	COMPLETE H.V.A.C. Classes C/D	Sq. Ft. Costs
Excellent	$ 91.00	Average	$ 55.50	Excellent	$ 68.50
Good	71.00	Low	43.50	Very Good	53.50
HEATING ONLY		**HEATING & COOLING**		**COOLING ONLY**	
Forced air furnace	10.15	Package A.C. (short ductwork)	19.75	Central refrigeration (zoned)	16.70
Hot water, baseboard/convector	17.95	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Space heaters, with fan	5.11	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
radiant	5.72	Heat pump system	24.85		
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.885	18	1.086	28	1.331
10	.921	20	1.133	30	1.382
12	.960	22	1.181	35	1.515
14	1.000 (base)	24	1.231	40	1.650
16	1.041	26	1.281	50	1.930

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	300	400	500	600	800	1000	1200	1400	1600	1800	2000	2200	2400	3000	Sq. Ft./Story
5,000	1.083	1.168	1.252	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	.996	1.040	1.083	1.168	-----	-----	-----	-----	-----	-----	-----	-----	-----	**10,000**
14,000	-----	.945	.977	1.008	1.071	1.132	-----	-----	-----	-----	-----	-----	-----	-----	**14,000**
20,000	-----	-----	.926	.949	.996	1.040	1.083	-----	-----	-----	-----	-----	-----	-----	**20,000**
25,000	-----	-----	.907	.924	.959	.996	1.032	1.066	-----	-----	-----	-----	-----	-----	**25,000**
30,000	-----	-----	-----	.907	.935	.965	.995	1.025	-----	-----	-----	-----	-----	-----	**30,000**
40,000	-----	-----	-----	-----	.907	.926	.949	.972	.995	1.019	-----	-----	-----	-----	**40,000**
50,000	-----	-----	-----	-----	.891	.907	.924	.942	.959	.977	.996	1.015	-----	-----	**50,000**
80,000	-----	-----	-----	-----	-----	.875	.887	.898	.907	.916	.926	.937	.949	.984	**80,000**
100,000	-----	-----	-----	-----	-----	.863	.872	.882	.891	.899	.907	.916	.924	.950	**100,000**
200,000	-----	-----	-----	-----	-----	-----	.846	.850	.855	.859	.863	.868	.873	.887	**200,000**
400,000	-----	-----	-----	-----	-----	-----	-----	-----	.835	.838	.841	.843	.846	.853	**400,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

PAVILIONS





AVERAGE CLASS D

OCCUPANCY DESCRIPTION: These structures range from a low quality open park/picnic shelter structure to a high cost bandstand pavilion. The average to good pavilion is an average of a gazebo, bandstand and walled pavilion.

LOW COST CLASS D

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Picnic units, benches or audio visual equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING & PLUMBING	HEAT
C	Excellent	$ 342.50	Face brick, cast stone, ornate trim and railings, slate, copper cover	Raised colored slab, pavers, plank ceiling, best bandstand	Good electrical, ornamental lighting, some extras	None
	Very Good	266.50	Brick or face block, stone trim, concrete or clay tile cover	Raised slab, decorative balustrading, ornate bandstand pavilion	Good electrical and lighting	None
	Good	205.50	Enclosed, arched openings, brick or block, good trim, heavy shingles	Raised slab on fill, good balustrades, good bandstand	Adequate electrical, outlets and lighting	None
	Average	124.50	Enclosed, concrete block, little trim, composition shingle cover	Unfinished, concrete slab, walled park pavilion	Adequate electrical and lighting	None
	Fair	96.50	Open, face block, brick columns, timber roof framing, trellis, tile	Unfinished, concrete slab, exposed roof deck, best picnic shelter	Minimum electrical or water service, service wall	None
	Low-cost	75.50	Open, no walls, block columns, some trim, wood trusses, architectural shingles	Unfinished, concrete slab, good park shelter	Minimum lighting	None
	Cheap	58.50	Open air, no walls, masonry supports, composition shingle cover	Unfinished, concrete slab, minimum park picnic shelter	None	None
D	Excellent	327.00	Face brick veneer, cast stone trim, heavy trusses, slate, copper cover	Raised colored slab, pavers, plank ceiling	Good electrical, ornamental lighting, some extras	None
	Very Good	252.00	Masonry veneer, custom woods, trim, concrete or clay tile cover	Raised deck or slab, decorative balustrading, ornate bandstand	Good electrical and lighting	None
	Good	194.00	Enclosed, arched openings, best sidings, trim, trellis, heavy shingles	Raised wood deck on piers, good balustrades, good bandstand	Adequate electrical, outlets and lighting	None
	Average	116.00	Enclosed, siding or stucco, some trim	Unfinished, slab or light plank, walled pavilion, average bandstand, gazebo	Adequate electrical and lighting	None
	Fair	89.50	Open timber framing, trellis, heavy shingle or tile cover	Unfinished, concrete slab, exposed roof deck, best picnic shelter, plain gazebo	Minimum electrical or water service, service wall	None
	Low-cost	69.00	Open, no walls, wood columns, some trim, composition shingles	Unfinished, concrete slab, good shelter, minimum gazebo	Minimum lighting	None
	Cheap	53.00	Open air, no walls, wood posts, composition, roll or shingle cover	Unfinished, concrete slab, prefabricated shelter	None	None
D POLE	Fair	82.50	Open, pole frame, wide span, formed metal cover, good trim	Unfinished, concrete slab, brick ribbons, best picnic shelter	Minimum electrical or water service, service wall	None
	Low-cost	63.50	Open, no walls, pole frame, metal cover, some trim	Unfinished, concrete slab, good picnic shelter	Minimum lighting	None
	Cheap	49.00	Open air, no walls, light metal cover on pole frame	Unfinished, concrete slab, prefabricated picnic shelter	None	None
S	Average	113.00	Enclosed, steel frame, metal siding, masonry trim	Unfinished, concrete slab, walled park pavilion	Adequate electrical and lighting	None
	Fair	87.50	Open, wide span truss, formed metal cover, good trim	Unfinished, concrete slab, brick ribbons, best picnic shelter	Minimum electrical or water service, service wall	None
	Low-cost	68.00	Open, partial wall panels, steel frame, metal cover, some trim	Unfinished, concrete slab, good picnic or play shelter	Minimum lighting	None
	Cheap	52.50	Open air, no walls, light steel, colored panels or heavy canvas	Unfinished, concrete slab, prefabricated picnic shelter	None	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

PAVILIONS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 **SPRINKLERS:** Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93

2 **HEATING AND COOLING**

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3 **HEIGHT REFINEMENTS**

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.776	18	1.054
10	.833	20	1.106
12	.889	22	1.158
14	.945	24	1.210
16	1.000 (base)	28	1.313

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	250	300	350	400	450	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.205	1.264	1.322	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	-----	.999	1.011	1.023	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	**10,000**
14,000	-----	-----	-----	.982	.992	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	**14,000**
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	**25,000**
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	**40,000**
45,000	-----	-----	-----	-----	-----	-----	.934	.939	.946	.954	.962	.976	.989	1.001	**45,000**
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	**50,000**
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	**75,000**
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	**100,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

POST OFFICES – BRANCH/MAIL PROCESSING FACILITIES



GOOD CLASS C BRANCH



AVERAGE CLASS C BRANCH

OCCUPANCY DESCRIPTION: Branch post offices are small buildings, typically under 10,000 square feet, usually built under lease agreements with the U.S. Postal Service. The exteriors vary, but generally include some ornamentation, even at the low quality levels. Interiors are generally drywall. The most common floor finish is vinyl composition.

Mail and package sorting centers are usually built under lease agreements with the U.S. Postal Service, or by commercial packages delivery companies. They are designed with large areas to accommodate the processing and shipment of small lots of packages and mail. They have more plumbing and lighting than main post offices in order to service the large personnel load.

A post office commonly has work space, lobby, office, restrooms, directory, loading area and mechanical rooms. The area associated with each of these segments varies due to the overall size of the building and community served. The better quality levels include some security wiring.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*). Costs for mail-processing facilities include lookout galleries and security wiring.

NOT INCLUDED IN COSTS: Material-handling equipment, dock levelers, signs and furnishings

SQUARE FOOT COST TABLE

BRANCH POST OFFICES

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 222.00	Concrete, metal/glass, or masonry panels, usually part of a building	Plaster and drywall, vinyl wall finish, resilient floors	Good illumination and wiring, adequate plumbing	Warm and cool air (zoned)
C	Excellent	315.00	Best brick, ashlar on block, stone trim, good ornamentation	Plaster/drywall, vinyl wall finishes, tiled lobby	Good lighting and security wiring, good plumbing	Heat pump system
	Good	232.00	Ornamental brick or block, precast concrete, good trim	Plaster/drywall, vinyl or enamel wall finish, resilient floors, good lobby	Good illumination, adequate plumbing and wiring,	Package A.C.
	Average	175.00	Brick, block, tilt-up, some trim	Drywall interiors, vinyl composition tile, acoustic tile, adequate lobby	Adequate illumination and plumbing, standard fixtures	Package A.C.
	Low cost	124.00	Block or brick, stock plans, plain, minimum fenestration	Gypsum board and paint, vinyl composition, very small lobby	Adequate lighting, minimum plumbing and wiring	Forced air
D	Excellent	286.00	Best sidings, shingles, EIFS, elastomeric roof cover	Plaster/drywall, vinyl wall finishes, tiled lobby	Good lighting and security wiring, good plumbing	Heat pump system
	Good	213.50	Good siding or stucco, good trim	Plaster/drywall, vinyl or enamel wall finish, resilient floors, good lobby	Good illumination, adequate plumbing and wiring	Package A.C.
	Average	164.00	Stucco, EIFS, or siding, some trim	Drywall interiors, vinyl composition tile, acoustic tile, adequate lobby	Adequate lighting and plumbing, standard fixtures	Package A.C.
	Low cost	116.50	Stucco or siding, stock plans, plain, minimum fenestration	Drywall, few partitions, asphalt tile, few extras, very small lobby	Adequate lighting, minimum plumbing and wiring	Forced air
D Masonry Veneer	Excellent	302.50	Brick or stone veneer, good ornamentation	Plaster/drywall, vinyl wall finishes, tiled lobby	Good lighting and security wiring, good plumbing	Heat pump system
	Good	223.50	Good brick veneer, good trim	Plaster/drywall, vinyl or enamel wall finish, resilient floors, good lobby	Good illumination, adequate plumbing and wiring	Package A.C.
	Average	169.50	Brick veneer, built-up or shingle roof, some trim	Drywall interiors, vinyl composition tile, acoustic tile, adequate lobby	Adequate illumination and plumbing, standard fixtures	Package A.C.
	Low cost	120.00	Brick veneer, stock plans, plain, minimum fenestration	Gypsum board and paint, vinyl composition, very small lobby	Adequate lighting, minimum plumbing and wiring	Forced air
S	Average	168.00	Sandwich panels, some ornamentation	Drywall interiors, vinyl composition tile, acoustic tile, adequate lobby	Adequate illumination and plumbing, standard fixtures	Package A.C.

MAIL-PROCESSING FACILITIES

CLASS	TYPE	COST/ SQ. Ft.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 226.00	Brick, precast or metal and glass panels, good trim	Plaster and drywall, good office and sorting areas, lookout galleries	*Good illumination, security wiring, adequate plumbing	Hot and chilled water (zoned)
C	Good	194.00	Ornamental brick or block, precast concrete, good trim	Some good offices and interior finish, sorting areas, lookout galleries	High-level lighting and good plumbing and wiring	Hot and chilled water(zoned)
	Average	134.50	Brick, block, tilt-up, some trim, bar or web joists	Painted walls, finished offices and sorting areas, hardened slab	Reading-level lighting, adequate plumbing, security wiring	Warm and cool air (zoned)
S	Good	188.00	Steel frame, sandwich panels, good trim	Some good offices and interior finish, sorting areas, lookout galleries	High-level lighting and good plumbing and wiring	Hot and chilled water (zoned)
	Average	130.50	Sandwich panels, some trim, bar or web joists	Drywall interiors, finished offices and sorting areas, hardened slab	Reading-level lighting, adequate plumbing, security wiring	Warm and cool air (zoned)

NOTE: Basement and mezzanine costs are listed under Main Post Offices.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

POST OFFICES – BRANCH/MAIL-PROCESSING FACILITIES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Average	$ 9.34

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,700 to $14,600 per stop.

DOCK HEIGHT FLOORS: Add $2.39 to $9.03 per square foot to base cost of first floor.

AUTOMATIC DOCK LEVELERS: Cost $8,700 to $16,600 each. See Section UIP 15 for greater detail.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.91	$ 6.57	$ 8.82	$ 11.74
2,500	4.63	6.17	8.24	10.95
5,000	4.16	5.51	7.28	9.63
10,000	3.78	4.95	6.48	8.49
15,000	3.54	4.62	6.03	7.88
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
40,000	3.04	3.94	5.06	6.53
50,000	2.96	3.79	4.89	6.27
80,000	2.75	3.49	4.47	5.72
100,000	2.67	3.39	4.32	5.51
150,000	2.49	3.17	4.02	5.11

Loading docks, see Page CAL 398.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.885	16	1.041
10	.921	18	1.086
12	.960	20	1.133
14	1.000 (base)	22	1.181

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 100	150	200	250	300	350	400	450	500	800	1000	1200	1500	2000	Average Floor Area Sq. Ft./Story
1,000	1.252	1.468	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	-----	1.147	1.252	1.360	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	-----	.996	1.040	1.083	1.125	1.168	1.210	1.252	-----	-----	-----	-----	-----	**5,000**
10,000	-----	-----	-----	-----	-----	.972	.996	1.019	1.040	1.168	-----	-----	-----	-----	**10,000**
14,000	-----	-----	-----	-----	-----	-----	.945	.961	.977	1.071	1.132	-----	-----	-----	**14,000**
20,000	-----	-----	-----	-----	-----	-----	-----	-----	.926	.996	1.040	1.083	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	-----	-----	-----	.907	.959	.996	1.032	-----	-----	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.935	.965	.995	1.040	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.907	.926	.949	.984	-----	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.891	.907	.924	.950	.996	**50,000**
70,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.884	.896	.913	.945	**70,000**
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.863	.872	.887	.907	**100,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

POST OFFICES – MAIN



GOOD CLASS C



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These larger buildings, typically between 10,000 and 30,000 square feet, are usually built under lease agreements with the U.S. Postal Service. The exteriors vary, but generally include some ornamentation even at the low quality levels. Interiors are plaster or drywall. The most common floor finishes are vinyl composition with terrazzo or pavers in the lobby areas.

A post office commonly has work space, lobby, office, restrooms, directory, loading area and mechanical rooms. The area associated with each of these segments varies due to the overall size of the building and community served. The better quality levels include lookout galleries, as well as good security wiring.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Material handling equipment, dock levelers, signs and furnishings.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 389.00	Face brick, metal panels, good glass, ornamentation	Plaster, vinyl wall finishes, vinyl composition, some terrazzo or pavers	*High-quality lighting and security wiring, good plumbing	Hot and chilled water (zoned)
	Average	292.00	Brick, precast or metal and glass panels, ornamentation	Plaster and drywall, vinyl wall finish, vinyl composition tile	*Good illumination, security wiring, adequate plumbing	Warm and cool air (zoned)
A-B	Parking basement	89.00	Unfinished concrete, water proofed walls	Unfinished, concrete floor, striped	Minimum lighting, adequate drains	Ventilation
	Good storage bsmt.	95.00	Reinforced concrete, semifinished, painted interior	Some partitions, heavy floor, good storage or work areas	Adequate lighting and plumbing, good drains	Space heaters
	Avg. storage bsmt.	70.50	Reinforced concrete, unfinished interior	Unfinished storage areas, some partitions	Minimum lighting and plumbing, drains	None
C	Excellent	359.00	Stone, ashlar or panels, highly ornamental	Plaster, vinyl wall finishes, vinyl composition, some terrazzo or pavers	High-quality lighting and security wiring, good plumbing	Hot and chilled water (zoned)
	Good	263.00	Ornamental brick or block, precast concrete, good ornamentation	Plaster/drywall, vinyl or enamel wall finish, good resilient floors	Good illumination, security wiring, adequate plumbing	Warm and cool air (zoned)
	Average	201.50	Brick, block, tilt-up, some good ornamentation	Drywall, vinyl or enamel wall finish, resilient floors, adequate offices	Adequate illumination, security wiring and plumbing	Heat pump system
D	Very Good	276.00	Best sidings, much trim, highly ornamented, complex roof, skylights	Plaster/drywall, vinyl wall finishes, vinyl composition, some terrazzo or pavers	Good-quality lighting and security wiring, good plumbing	Warm and cool air (zoned)
	Good	244.00	Best stucco or siding, good ornamentation	Plaster/drywall, vinyl or enamel wall finish, good resilient floors	Good illumination, security wiring, adequate plumbing	Warm and cool air (zoned)
	Average	189.00	Stucco, EIFS, or siding, some good ornamentation	Drywall, vinyl or enamel wall finish, resilient floors, adequate offices	Adequate illumination, security wiring and plumbing	Heat pump system
D Masonry Veneer	Excellent	327.50	Best stone or brick veneer, good trim	Plaster, vinyl wall finishes, vinyl composition, some terrazzo or pavers	High-quality lighting and security wiring, good plumbing	Warm and cool air (zoned)
	Good	252.50	Brick or stone veneer, good built-up or shingle roof and trim	Plaster/drywall, vinyl or enamel wall finish, good resilient floors	Good illumination, security wiring, adequate plumbing	Warm and cool air (zoned)
	Average	193.50	Brick or block veneer, shingle or built-up roof, some good ornamentation	Drywall, vinyl or enamel wall finish, resilient floors, adequate offices	Adequate illumination, security wiring and plumbing	Heat pump system
S	Average	193.00	Steel frame, best sandwich panels, some good ornamentation	Drywall, vinyl or enamel wall finish, resilient floors, adequate offices	Adequate illumination, security wiring and plumbing	Heat pump system
CDS†	Parking basement	57.00	Unfinished concrete, waterproofed	Plaster or drywall ceiling, concrete floor, striped	Minimum lighting, adequate drains	Ventilation
	Storage basement	44.75	Reinforced concrete, unfinished interior	Unfinished storage areas, some partitions	Minimum lighting and drains	None

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $ 8.61 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

POST OFFICES – MAIN

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Good	$ 12.75
Average	9.34

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.16	$ 5.51	$ 7.28	$ 9.63
10,000	3.78	4.95	6.48	8.49
15,000	3.54	4.62	6.03	7.88
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
40,000	3.04	3.94	5.06	6.53
50,000	2.96	3.79	4.89	6.27
80,000	2.75	3.49	4.47	5.72
100,000	2.67	3.39	4.32	5.51
150,000	2.49	3.17	4.02	5.11

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,700 to $14,600 per stop.

DOCK HEIGHT FLOORS: Add $2.39 to $9.03 per square foot to base cost of first floor.

AUTOMATIC DOCK LEVELERS: Cost $8,700 to $16,600 each. See Section UIP 15 for greater detail.

For loading docks, see Page CAL 398.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.885	16	1.041
10	.921	18	1.086
12	.960	20	1.133
14	1.000 (base)	22	1.181

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	250	300	350	400	450	500	600	800	1000	1200	1500	2000	2400	2600	Sq. Ft./Story
5,000	1.040	1.083	1.125	1.168	1.210	1.252	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	-----	.972	.996	1.019	1.040	1.083	1.168	-----	-----	-----	-----	-----	-----	**10,000**
14,000	-----	-----	-----	.945	.961	.977	1.008	1.071	1.132	-----	-----	-----	-----	-----	**14,000**
20,000	-----	-----	-----	-----	-----	.926	.949	.996	1.040	1.083	-----	-----	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	.907	.924	.959	.996	1.032	-----	-----	-----	-----	**25,000**
30,000	-----	-----	-----	-----	-----	-----	.907	.935	.965	.995	1.040	-----	-----	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	.907	.926	.949	.984	-----	-----	-----	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	.891	.907	.924	.950	.996	-----	-----	**50,000**
70,000	-----	-----	-----	-----	-----	-----	-----	-----	.884	.896	.913	.945	.969	.982	**70,000**
80,000	-----	-----	-----	-----	-----	-----	-----	-----	.875	.887	.903	.926	.949	.961	**80,000**
100,000	-----	-----	-----	-----	-----	-----	-----	-----	.863	.872	.887	.907	.924	.933	**100,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.