RECTORIES



AVERAGE CLASS C



EXCELLENT CLASS D

OCCUPANCY DESCRIPTION: These are residential type buildings, including rooming houses and convents, with some additional plumbing and kitchen facilities for the number of unrelated occupants. The better qualities may be divided into suites with individual baths and have interiors with plaster or drywall, paneling, carpet and resilient flooring, and may include small office, meeting and or chapel rooms.

Average quality rectories generally have one bath per two bedrooms and some entrance ornamentation. Lower qualities are plain with minimum electrical and plumbing.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Furnishings, appliances, fireplaces, balconies or yard improvements.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 271.50	Fine masonry and windows, stained glass, special architecture and trim	Fine interior detail, ceramic tile, carpet, paneling, fine hardwood	Good fixtures, many outlets, one full bath per bedroom	Warm and cool air (zoned)
	Good	206.00	Face brick, stucco, stone trim, good windows and architecture	Plaster or drywall, paneling, carpet or hardwood and sheet vinyl	Individual baths, large kitchen, good electrical fixtures	Heat pump system
	Average	156.50	Brick or block, some trim and entrance ornamentation	Plaster or drywall, carpet, hardwood, vinyl composition	Adequate lighting/plumbing, one bath per two bedrooms	Package A.C.
	Low cost	116.50	Concrete block and stucco	Drywall, some carpet, asphalt tile	Minimum quantity and quality	Forced air
D	Excellent	264.50	Face brick or stone veneer, fine windows, special architecture	Fine interior detail, ceramic tile, carpet, paneling, fine hardwood	Good fixtures, many outlets, one full bath per bedroom	Warm and cool air (zoned)
	Good	198.00	Brick veneer, best stucco or siding, good windows and architecture	Plaster or drywall, paneling, carpet or hardwood and sheet vinyl	Individual baths, large kitchen, good electrical fixtures	Heat pump system
	Average	150.00	Brick veneer, good stucco or siding	Drywall, carpet, vinyl composition	Adequate lighting/plumbing	Package A.C.
	Low cost	110.00	Stucco or siding, very plain	Drywall, some carpet, asphalt tile	Minimum quantity and quality	Forced air

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RECTORIES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Country Clubs with basements, add 40% to extend the foundation to the basement level.

TYPE	COST RANGE
One-story	$3,850 – $12,400
Two-stories	4,890 – 14,890
Three-stories	5,930 – 17,380

RESIDENTIAL ELEVATORS: The small residential-style two or three passenger elevators found in rectories cost $28,600 to $57,500 for two stops plus $3,900 to $6,150 for each additional stop.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 5.14	$ 6.63	$ 8.55	$ 11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
30,000	3.58	4.52	5.68	7.15

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL
Concrete	$ 34.00	$ 43.50	$ 55.00	$ 71.00
Steel	31.75	42.50	56.50	75.50
Wood	29.75	39.50	52.50	68.50
Add for ornate finishes, balustrades	29.50	36.00	44.25	54.00
Add for roofs or awnings	15.35	20.40	27.00	36.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork)	$ 21.90	Central refrigeration (zoned)	$ 16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector	20.75	Heat pump system	25.50	Pkg. refrig.	$2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers.	$331 to $535 per MCFM capacity
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 3.18

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	11	1.027
9	.973	12	1.055
10	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER													Average Floor Area
Sq. Ft./Story	200	250	300	350	400	450	500	600	700	800	1000	1200	1400	Sq. Ft./Story
2,000	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	.959	.989	1.021	1.052	1.083	1.113	1.143	1.206	1.268	1.329	-----	-----	-----	**4,000**
6,000	.917	.938	.959	.980	1.000	1.021	1.042	1.083	1.123	1.165	-----	-----	-----	**6,000**
8,000	-----	.913	.929	.944	.959	.974	.989	1.021	1.052	1.083	1.143	1.206	1.268	**8,000**
10,000	-----	-----	.910	.922	.935	.947	.959	.984	1.009	1.034	1.083	1.133	1.181	**10,000**
12,000	-----	-----	-----	.907	.917	.928	.938	.959	.980	1.000	1.042	1.083	1.123	**12,000**
14,000	-----	-----	-----	-----	.906	.915	.924	.942	.959	.977	1.011	1.047	1.083	**14,000**
20,000	-----	-----	-----	-----	.885	.892	.898	.910	.922	.935	.959	.984	1.009	**20,000**
24,000	-----	-----	-----	-----	-----	-----	.886	.896	.907	.917	.938	.959	.980	**24,000**
28,000	-----	-----	-----	-----	-----	-----	.880	.888	.898	.906	.924	.942	.959	**28,000**
32,000	-----	-----	-----	-----	-----	-----	.874	.882	.889	.898	.913	.928	.944	**32,000**
36,000	-----	-----	-----	-----	-----	-----	.870	.877	.883	.890	.904	.917	.932	**36,000**
40,000	-----	-----	-----	-----	-----	-----	.866	.873	.879	.885	.898	.910	.922	**40,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RELIGIOUS BUILDINGS: CHURCH SANCTUARIES



GOOD CLASS C

OCCUPANCY DESCRIPTION: This occupancy includes special lighting, sound systems and some stained glass windows consistent with the overall quality of the building. Included in the costs are some type of kitchen, social, meeting and office facilities consistent with the level of quality.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Projection area, lighting and sound systems commensurate with the overall quality.

NOT INCLUDED IN COSTS: Pews, kitchen, organs, bells and other church equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$544.00	Fine masonry and windows, special architecture and trim	Finest plaster and wood detail, carpeting, marble, vinyl tile	Special lighting and sound system, good plumbing	Warm and cool air (zoned)
	Good	405.00	Stone, good curtain walls, good stained glass and trim	Ornamental plaster and detail, marble, carpeting, vinyl tile	Special lighting, sound system, good plumbing	Warm and cool air (zoned)
	Average	290.00	Concrete, metal and glass, leaded windows, stone trim	Drywall, some ornamentation, terrazzo, vinyl tile, carpeting	Adequate lighting and plumbing, sound system	Package A.C.
B	Excellent	486.00	Fine masonry and windows, special architecture and trim	Finest plaster and wood detail, carpeting, marble, vinyl tile	Special lighting and sound system, good plumbing	Warm and cool air (zoned)
	Good	363.50	Stone, good curtain walls, good stained glass and trim	Ornamental plaster and detail, marble, carpeting, vinyl tile	Special lighting, sound system, good plumbing	Warm and cool air (zoned)
	Average	260.50	Concrete, metal and glass, leaded windows, stone trim	Drywall, some ornamentation, terrazzo, vinyl tile, carpeting	Adequate lighting and plumbing, sound system	Package A.C.
A-B	Balcony Good	114.00	Not included	Stepped balcony with ornate finishes	Good lighting	In building cost
	Balcony Average	83.00	Not included	Stepped, plaster soffit, finished floor	Adequate lighting	In building cost
C	Excellent	377.00	Fine masonry and windows, special architecture and trim	Finest plaster & fine wood detail, carpeting, marble, vinyl tile	Special lighting and sound system, good plumbing	Warm and cool air (zoned)
	Good	282.00	Face brick or block, stone trim, good windows and architecture	Good plaster and detail, vinyl tile, carpeting, terrazzo	Good lighting and plumbing, good sound system	Warm and cool air (zoned)
	Average	200.50	Brick or block, stone trim, few simple stained-glass windows	Drywall, vinyl composition tile, little ornamental detail, carpet	Adequate lighting and plumbing, adequate sound system	Package A.C.
	Low-cost	142.00	Low-cost brick or block, composition roof, very plain	Painted masonry, plywood trim, asphalt tile, very plain, basic	Minimum lighting and plumbing, low-cost sound	Forced air
D	Excellent	360.00	Face brick or stone veneer, fine windows, special architecture	Ornamental plaster and fine detail, carpet, marble, vinyl	Special lighting and sound system, good plumbing	Warm and cool air (zoned)
	Good	269.50	Brick veneer, best stucco or siding, good windows and architecture	Good plaster or wood, vinyl tile, carpeting, terrazzo	Good lighting and plumbing, good sound system	Warm and cool air (zoned)
	Average	191.50	Stucco or siding, few stained-glass windows, some trim	Drywall and veneers, vinyl composition tile, little trim, carpet	Adequate lighting and plumbing, adequate sound system	Package A.C.
	Low-cost	134.00	Low-cost stucco or siding, composition roof, very plain	Drywall and plywood, asphalt and acoustic tile, basic worship center	Minimum lighting and plumbing, low-cost sound	Forced air
D POLE	Average	174.50	Pole frame, best metal panels, few stained-glass windows	Drywall partitions, acoustic tile, vinyl composition, some carpet	Adequate lighting and plumbing, adequate sound system	Package A.C.
	Low-cost	126.50	Pole frame, good metal panels, finished inside, little trim	Drywall, acoustic tile, vinyl composition tile, few extras, very basic	Minimum lighting and plumbing, low-cost sound	Forced air
S	Good	254.00	Good sandwich panels, good windows and trim	Good drywall or wood, vinyl tile, carpeting, terrazzo	Good lighting and plumbing, good sound system	Warm and cool air (zoned)
	Average	182.50	Insulated sandwich panels, few stained-glass windows	Drywall partitions, vinyl composition and acoustic tile, some carpet	Adequate lighting and plumbing, adequate sound system	Package A.C.
	Low-cost	131.00	Good metal panels and roof, finished interior, some trim	Drywall, acoustic tile, vinyl tile, few extras, basic worship center	Minimum lighting and plumbing, low-cost sound	Forced air
CDS	Balcony Good	93.50	Not included	Stepped balcony with ornate finishes	Good lighting	In building cost
	Balcony Average	64.00	Not included	Stepped, drywall soffit, finished floor	Adequate lighting	In building cost

BALCONIES: Do not use story height or area/perimeter multipliers with balcony cost.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RELIGIOUS BUILDINGS: CHURCH SANCTUARIES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

ORCHESTRA LIFTS: $156,000 – $245,000

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 39.25	$ 48.50	$ 60.00	$ 74.50
Light false-mansard	21.65	26.50	33.00	40.75
Steel frame	48.25	61.00	77.00	97.00
Light false-mansard	26.50	33.50	42.25	53.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93
150,000	3.04	3.69	4.49	5.47
200,000	2.93	3.55	4.30	5.21

Seating, curtains and snackbar equipment costs are located in Section UIP 15.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	.889	28	1.313	58	2.036
14	.945	30	1.364	62	2.128
16	1.000 (base)	34	1.463	66	2.219
18	1.054	38	1.561	70	2.309
20	1.106	42	1.658	74	2.398
22	1.158	46	1.754	78	2.486
24	1.210	50	1.849	82	2.573
26	1.262	54	1.943	86	2.659

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	175	200	250	300	400	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.117	1.147	1.205	1.264	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
5,000	.999	1.011	1.034	1.056	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	-----	-----	-----	1.011	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	10,000
14,000	-----	-----	-----	-----	.982	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	14,000
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	25,000
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	40,000
45,000	-----	-----	-----	-----	-----	-----	.934	.939	.946	.954	.962	.976	.989	1.001	45,000
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	50,000
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	75,000
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	100,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RELIGIOUS BUILDINGS: CHURCHES WITH SUNDAY SCHOOLS



GOOD CLASS C

OCCUPANCY DESCRIPTION: This occupancy includes special lighting, sound systems and some stained glass windows consistent with the overall quality of the building. It also includes multipurpose social/recreational and educational classroom facilities.

Because of the wide range in mix of facilities and qualities, it may be best to price each area individually, using the following occupancies: Church-Sanctuary, Church Educational Wing, Fellowship Hall and Narthex/Foyer.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Projection area, lighting and sound systems commensurate with the overall quality.

NOT INCLUDED IN COSTS: Pews, kitchen, classroom furnishings, organs, bells and other church equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 380.50	Stone, good curtain walls, good stained glass and trim	Ornamental plaster and detail, marble, carpeting, vinyl tile	Special lighting, sound system, good classroom outlets, plumbing	Warm and cool air (zoned)
	Average	279.00	Concrete, metal and glass, leaded windows, stone trim	Drywall, some ornamentation, terrazzo, vinyl tile, carpeting	Adequate lighting and plumbing, classroom fixtures, sound system	Package A.C.
B	Good	340.00	Stone, good curtain walls, good stained glass and trim	Ornamental plaster and detail, marble, carpeting, vinyl tile	Special lighting, sound system, good classroom outlets, plumbing	Warm and cool air (zoned)
	Average	249.50	Concrete, metal and glass, leaded windows, stone trim	Drywall, some ornamentation, terrazzo, vinyl tile, carpeting	Adequate lighting and plumbing, classroom fixtures, sound system	Package A.C.
A-B	Classroom basement	184.50	Reinforced concrete, plaster interior	Classroom finishes, some utility, storage, social/meeting functions	Adequate lighting and plumbing	Hot water
	Finished basement	168.50	Plaster interior	Finished rooms, asphalt tile	Adequate lighting and plumbing	Hot water
	Semifinished basement	120.00	Low-cost finishes	Minimum social functions, kitchenette	Minimum lighting, drains	Forced air
	Unfinished basement	87.00	Unfinished interior	Unfinished storage and utility	Minimum lighting, drains	None
C	Excellent	357.50	Fine masonry and windows, special architecture and trim	Finest plaster and fine wood detail, carpeting, marble, vinyl tile	Special lighting, sound system, good classroom outlets, plumbing	Warm and cool air (zoned)
	Good	271.50	Face brick or block, stone trim, good windows and architecture	Good plaster or wood, carpet, VCT, good or high density of classrooms	Good lighting and sound system, good classroom fixtures, plumbing	Warm and cool air (zoned)
	Average	194.50	Brick or block, stone trim, few simple stained-glass windows	Drywall, vinyl composition tile, little ornamental detail, std. classrooms	Adequate lighting and plumbing, low-cost sound	Package A.C.
	Low-cost	138.00	Low-cost brick or block, composition roof, very plain	Painted masonry, plywood trim, asphalt tile, very plain classrooms	Minimum lighting and plumbing, classroom features	Forced air
D	Excellent	336.50	Face brick or stone veneer, fine windows, special architecture	Ornamental plaster and fine detail, carpet, marble, vinyl	Special lighting, sound system, good classroom outlets, plumbing	Warm and cool air (zoned)
	Good	257.00	Brick veneer, best stucco or siding, good windows and architecture	Good plaster or wood, carpet, VCT, good or high density of meeting rooms	Good lighting and sound system, good classroom fixtures, plumbing	Warm and cool air (zoned)
	Average	184.50	Stucco or siding, few stained-glass windows, some trim	Drywall and veneers, vinyl comp. tile, little trim, standard classrooms	Adequate lighting and plumbing, low-cost sound	Package A.C.
	Low-cost	132.50	Low-cost stucco or siding, composition roof, very plain	Drywall and plywood, asphalt and acoustic tile, minimum classrooms	Minimum lighting and plumbing, classroom features	Forced air
D POLE	Low-cost	124.50	Pole frame, good metal panels, finished inside, little trim	Drywall, acoustic tile, vinyl comp. tile, few extras, minimum classrooms	Minimum lighting and plumbing, classroom features	Forced air
S	Good	246.00	Good sandwich panels, good windows and trim	Good drywall or wood, vinyl tile, carpet, good or high density of meeting rooms	Good lighting, sound system, good classroom fixtures, plumbing	Warm and cool air (zoned)
	Average	178.50	Insulated sandwich panels, few stained-glass windows	Drywall partitions, vinyl composition and acoustic tile, standard classrooms	Adequate lighting and plumbing, low-cost sound	Package A.C.
	Low-cost	130.00	Good metal panels and roof, finished interior, some trim	Drywall, acoustic tile, comp. tile, few extras, minimum classrooms	Minimum lighting and plumbing, classroom features	Forced air
CDS	Classroom basement	137.00	Reinforced concrete, plaster or drywall interior	Classroom finishes, some utility, storage, social/meeting functions	Adequate lighting and plumbing	Forced air
	Finished basement	124.00	Plaster or drywall interior	Finished rooms, asphalt tile	Adequate lighting and plumbing	Forced air
	Semifinished basement	72.50	Low-cost finishes	Minimum social functions, kitchenette	Minimum lighting and plumbing	Space heaters
	Unfinished basement	53.00	Unfinished interior	Unfinished storage and utility	Minimum lighting, drains	None

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.52 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RELIGIOUS BUILDINGS: CHURCHES WITH SUNDAY SCHOOLS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

ORCHESTRA LIFTS: $156,000 – $245,000

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 39.25	$ 48.50	$ 60.00	$ 74.50
Light false-mansard	21.65	26.50	33.00	40.75
Steel frame	48.25	61.00	77.00	97.00
Light false-mansard	26.50	33.50	42.25	53.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93
150,000	3.04	3.69	4.49	5.47
200,000	2.93	3.55	4.30	5.21

Seating, curtains and snackbar equipment costs are located in Section UIP 15.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	.889	28	1.313	58	2.036
14	.945	30	1.364	62	2.128
16	1.000 (base)	34	1.463	66	2.219
18	1.054	38	1.561	70	2.309
20	1.106	42	1.658	74	2.398
22	1.158	46	1.754	78	2.486
24	1.210	50	1.849	82	2.573
26	1.262	54	1.943	86	2.659

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	175	200	250	300	400	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.117	1.147	1.205	1.264	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
5,000	.999	1.011	1.034	1.056	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	-----	-----	-----	1.011	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	10,000
14,000	-----	-----	-----	-----	.982	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	14,000
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	25,000
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	40,000
45,000	-----	-----	-----	-----	-----	-----	.934	.939	.946	.954	.962	.976	.989	1.001	45,000
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	50,000
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	75,000
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	100,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RELIGIOUS BUILDINGS: FELLOWSHIP HALLS

OCCUPANCY DESCRIPTION: These church buildings are designed as multipurpose structures for recreation and social gatherings and include gymnasium-type flooring, stages, kitchens and other miscellaneous rooms commensurate with the quality.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Projection area, lighting and sound systems commensurate with the overall quality.

NOT INCLUDED IN COSTS: Recreation, kitchen, seating, tables, or any other church equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 301.00	Face brick, stone, concrete or metal panels, good trim	Plaster or drywall, acoustic tile, carpet and vinyl, stage, some extras	Good fluorescent fixtures, good plumbing and kitchen	Warm and cool air (zoned)
	Average	219.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or vinyl, small stage	Adequate lighting and plumbing, kitchen, some extras	Package A.C.
C	Excellent	293.50	Steel frame, best masonry walls, good trim	Plaster, acoustic tile, good wood athletic floor, stage, good detail	Good lighting and plumbing, kitchen, tiled surfaces	Warm and cool air (zoned)
	Good	210.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, hardwood or vinyl, stage	Good fluorescent fixtures, good plumbing, kitchen	Package A.C.
	Average	150.00	Steel frame, brick, block, concrete, some ornamentation	Plaster or drywall, acoustic tile, vinyl, carpet or hardwood, small stage area	Adequate lighting and plumbing, small kitchen, some extras	Forced air
	Low-cost	102.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum recreation lighting and plumbing	Space heaters
D	Good	199.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, hardwood or vinyl, stage	Good fluorescent fixtures, good plumbing, kitchen	Package A.C.
	Average	142.50	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl, carpet or hardwood, small stage area	Adequate lighting and plumbing, small kitchen, some extras	Forced air
	Low-cost	95.50	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, some carpet	Minimum recreation lighting and plumbing	Space heaters
	Cheap	74.00	Light frame, stucco or siding, very plain	Concrete floor, some vinyl composition, minimal finish	Minimum lighting and plumbing	Space heaters
D POLE	Average	129.00	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, vinyl comp., carpet or hardwood, small stage area	Adequate lighting and plumbing, small kitchen, some extras	Forced air
	Low-cost	88.50	Pole frame, metal panels, finished inside, insulated, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile, some carpet	Minimum recreation lighting and plumbing	Space heaters
	Cheap	70.00	Pole frame, metal siding, partly finished interior, some insulation	Concrete floor, some vinyl composition, minimal finish	Minimum lighting and plumbing	Space heaters
S	Good	193.00	Pre-engineered, good sandwich panels, some brick or stone trim	Plaster or drywall, acoustic tile, hardwood or vinyl, stage	Good fluorescent fixtures, good plumbing, kitchen	Package A.C.
	Average	138.00	Pre-engineered, sandwich panels, some ornamentation	Drywall, acoustic tile, vinyl comp., carpet or hardwood, small stage area	Adequate lighting and plumbing, small kitchen, some extras	Forced air
	Low-cost	92.50	Pre-engineered, finished interior, insulated, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile, some carpet	Minimum recreation lighting and plumbing	Space heaters
	Cheap	72.00	Pre-engineered, partly finished interior, some insulation	Concrete floor, some vinyl composition, minimal finish	Minimum lighting and plumbing	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RELIGIOUS BUILDINGS: FELLOWSHIP HALLS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

ORCHESTRA LIFTS: $156,000 – $245,000

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 39.25	$ 48.50	$ 60.00	$ 74.50
Light false-mansard	21.65	26.50	33.00	40.75
Steel frame	48.25	61.00	77.00	97.00
Light false-mansard	26.50	33.50	42.25	53.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93
150,000	3.04	3.69	4.49	5.47
200,000	2.93	3.55	4.30	5.21

Seating, curtains and snackbar equipment costs are located in Section UIP 15.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	.889	28	1.313	58	2.036
14	.945	30	1.364	62	2.128
16	1.000 (base)	34	1.463	66	2.219
18	1.054	38	1.561	70	2.309
20	1.106	42	1.658	74	2.398
22	1.158	46	1.754	78	2.486
24	1.210	50	1.849	82	2.573
26	1.262	54	1.943	86	2.659

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	175	200	250	300	400	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.117	1.147	1.205	1.264	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
5,000	.999	1.011	1.034	1.056	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	-----	-----	-----	1.011	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	10,000
14,000	-----	-----	-----	-----	.982	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	14,000
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	25,000
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	40,000
45,000	-----	-----	-----	-----	-----	-----	.934	.939	.946	.954	.962	.976	.989	1.001	45,000
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	50,000
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	75,000
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	100,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RELIGIOUS BUILDINGS: NARTHEXES AND EDUCATIONAL WINGS



EXCELLENT CLASS A-B

OCCUPANCY DESCRIPTION: Foyer/Narthex These structures are greeting rooms that usually abut or lie between the church sanctuary and fellowship facilities. The better qualities may include special lighting, sound systems and some stained glass windows consistent with the overall quality of the building.

Church Educational Wing
These buildings are subdivided into instructional/meeting room facilities found in a religious complex. The lower qualities include less interior and exterior refinements than is found in occupancy Classroom. Complete religious or private schools should be priced using the various school occupancies. Price a complete church facility using occupancy Church with Sunday School.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, and equipment.

RELIGIOUS BUILDINGS: FOYERS / NARTHEXES

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 415.50	Fine masonry and doors, special architecture and trim	Finest plaster and wood detail, carpeting, marble, vinyl tile	Special lighting, good sound system and plumbing	Warm and cool air (zoned)
	Good	322.50	Stone, good curtain walls, good entrance and trim	Ornamental plaster and detail, marble, carpeting, vinyl tile	Good lighting, sound system, good plumbing	Warm and cool air (zoned)
	Average	238.00	Concrete, metal and glass, small entry, stone trim	Drywall, some ornamentation, terrazzo, vinyl tile, carpeting	Adequate lighting and plumbing, sound system	Package A.C.
CDS	Excellent	330.50	Fine masonry and doors, special architecture and trim	Finest plaster and fine wood detail, carpeting, marble, vinyl tile	Special lighting, good sound system and plumbing	Warm and cool air (zoned)
	Good	252.50	Masonry veneer or brick, stone trim, good entrance and architecture	Good plaster and detail, vinyl tile, carpeting, terrazzo	Good lighting and plumbing, sound system	Warm and cool air (zoned)
	Average	182.00	Good siding or block, stone trim, small entry	Drywall, vinyl composition tile, little ornamental detail	Adequate lighting and plumbing, low-cost sound	Package A.C.
	Low-cost	130.00	Low-cost siding or block, very plain	Painted masonry or drywall, plywood trim, asphalt tile, very plain	Minimum lighting and sound	Forced air

RELIGIOUS BUILDINGS: CHURCH EDUCATIONAL WINGS

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 258.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or carpet	Good lighting and plumbing, some extra features, library room	Warm and cool air (zoned)
	Average	199.00	Brick, precast concrete, block, very plain	Low-cost finishes, acoustic tile, hardwood or vinyl composition	Adequate classroom lighting and plumbing, few extras, rehearsal rm.	Package A.C.
B	Good	235.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or carpet	Good lighting and plumbing, some extra features, library room	Warm and cool air (zoned)
	Average	180.50	Brick, precast concrete, block, very plain	Low-cost finishes, acoustic tile, hardwood or vinyl composition	Adequate classroom lighting and plumbing, few extras, rehearsal rm.	Package A.C.
C	Excellent	241.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, hardwood or carpet	Good fluorescent fixtures, good plumbing, extra features, library	Warm and cool air (zoned)
	Good	185.00	Steel frame or bearing walls, brick, block or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate classroom lighting and plumbing, rehearsal room	Package A.C.
	Average	141.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Adequate meeting room lighting and plumbing	Forced air
	Low-cost	102.50	Cheap block, tilt-up, light roof	Low-cost finishes, no partitions, asphalt tile	Minimum code	Wall furnace
D	Excellent	231.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, hardwood or carpet	Good fluorescent fixtures and plumbing, extra features, library	Warm and cool air (zoned)
	Good	175.50	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate classroom lighting and plumbing, rehearsal room	Package A.C.
	Average	133.50	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, linoleum or wood floors	Adequate meeting room lighting and plumbing	Forced air
	Low-cost	95.50	Low-cost stucco or siding	Low-cost finishes, no partitions, asphalt tile	Minimum code	Wall furnace
D POLE	Average	125.50	Pole frame, good metal panels, finished inside, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Adequate meeting room lighting and plumbing	Forced air
	Low-cost	89.00	Pole frame, metal siding	Low-cost finishes, no partitions, acoustic tile, asphalt tile	Minimum code	Wall furnace
S	Good	174.00	Pre-engineered, sandwich panels, some trim	Drywall, acoustic tile, vinyl composition	Adequate classroom lighting and plumbing, rehearsal room	Package A.C.
	Average	131.00	Pre-engineered, finished interior, insulation	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Adequate meeting room lighting and plumbing	Forced air
	Low-cost	92.50	Light steel frame, siding	Low-cost finishes, no partitions, acoustic tile, asphalt tile	Minimum code	Wall furnace

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RELIGIOUS BUILDINGS: NARTHEXES AND EDUCATIONAL WINGS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

ORCHESTRA LIFTS: $156,000 – $245,000

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 39.25	$ 48.50	$ 60.00	$ 74.50
Light false-mansard	21.65	26.50	33.00	40.75
Steel frame	48.25	61.00	77.00	97.00
Light false-mansard	26.50	33.50	42.25	53.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93
150,000	3.04	3.69	4.49	5.47
200,000	2.93	3.55	4.30	5.21

Seating, curtains and snackbar equipment costs are located in Section UIP 15.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	.889	28	1.313	58	2.036
14	.945	30	1.364	62	2.128
16	1.000 (base)	34	1.463	66	2.219
18	1.054	38	1.561	70	2.309
20	1.106	42	1.658	74	2.398
22	1.158	46	1.754	78	2.486
24	1.210	50	1.849	82	2.573
26	1.262	54	1.943	86	2.659

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	175	200	250	300	400	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.117	1.147	1.205	1.264	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
5,000	.999	1.011	1.034	1.056	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	-----	-----	-----	1.011	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	10,000
14,000	-----	-----	-----	-----	.982	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	14,000
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	25,000
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	40,000
45,000	-----	-----	-----	-----	-----	-----	.934	.939	.946	.954	.962	.976	.989	1.001	45,000
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	50,000
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	75,000
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	100,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS



VERY GOOD CLASS C



GOOD CLASS D

OCCUPANCY DESCRIPTION: These buildings are constructed for the preparation and service of food and beverages. They include cafeterias, bars and taverns where the design is of restaurant type. They include a combination of the following areas: consumption, production, serving, receiving and storage, sanitation, nondining and employee areas and restrooms. Good restaurants include the typical chain operation and suburban neighborhood restaurants catering to regional trade. Average quality includes neighborhood restaurants or coffee shops or lower priced franchise operations.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office areas and all necessary plumbing and electrical connections for kitchen equipment.

NOT INCLUDED IN COSTS: Elevators, sprinklers, kitchen equipment, restaurant fixtures, furnishings or signs.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 415.00	Stone, face brick, best metal walls, usually part of a building	Best plaster and paneling, highly ornamental, carpeted, deluxe quality	Special lighting fixtures and effects, deluxe restrooms	Complete H.V.A.C.
	Good	313.00	Concrete, metal/glass or masonry panels, usually part of a building	Plaster with enamel & vinyl, carpet & vinyl flooring, decorated interior	Good lighting and outlets, good plumbing and restrooms	Complete H.V.A.C.
	Average	237.50	Brick or concrete, usually part of a building	Plaster or drywall, acoustic tile, carpet, ceramic, rubber, or vinyl comp. tile	Adequate lighting outlets, adequate plumbing	Complete H.V.A.C
	Finished basement	160.00	Plaster interior	Finished ceiling and floors, banquet, service functions	Adequate lighting/plumbing, restrooms, utility rooms	Low-Cost Complete H.V.A.C.
	Open mezzanine	60.00	Not included	Open, finished floors, plaster soffit, minimum work stations	Adequate lighting, minimum plumbing	Included in building cost
C	Excellent	381.50	Individual design, highly ornamental exterior	High-quality detail, best acoustics, carpeted, deluxe quality	Special lighting effects, tiled restrooms, good fixtures	Complete H.V.A.C.
	Very good	297.50	Individual design, brick, good metal and glass, ornamentation	Typically best chain restaurants, carpeted lounge and dining room	Good lighting/restrooms with good-quality fixtures and tile	Complete H.V.A.C.
	Good	233.00	Brick, concrete or metal and glass panels, ornamentation	Typical chain restaurant or coffee shop, vinyl and ceramic floors	Good lighting and service outlets, tiled restrooms	Complete H.V.A.C.
	Average	182.00	Brick, block, tilt-up, plain building, stock plans	Typical neighborhood restaurant, vinyl composition, small kitchen	Adequate lighting and outlets, small restrooms	Complete H.V.A.C.
	Low cost	131.50	Cheap brick or block, very plain, low-cost front	Low-cost short order cafe, minimum finish, asphalt tile	Minimum lighting and outlets, minimum plumbing	Forced air and ventilation
D	Excellent	366.00	Individual design, highly ornamental exterior, stone veneer	High-quality detail, best acoustics, carpeted, deluxe quality	Special lighting effects, tiled restrooms, good fixtures	Complete H.V.A.C.
	Very good	281.00	Individual design, brick veneer, good metal and glass, ornamentation	Typically best chain restaurants, carpeted lounge and dining room	Good fixtures, good restrooms w/ good-quality fixtures and tile	Complete H.V.A.C.
	Good	217.50	Stucco or siding, metal and glass, some ornamentation	Typical chain restaurant or coffee shop, vinyl and ceramic floors	Good lighting and service outlets, tiled restrooms	Complete H.V.A.C.
	Average	168.50	Stucco or siding, plain building and front, stock plans	Typical neighborhood restaurant, vinyl composition, small kitchen	Adequate lighting and outlets, small restrooms	Complete H.V.A.C.
	Low cost	118.50	Cheap stucco or siding, very plain	Low-cost short order cafe, min. finish	Minimum lighting and plumbing	Forced air/vent.
DPOLE	Low cost	111.00	Pole frame, good metal panels, lined and insulated, plain front	Low-cost short order cafe, minimum finish, asphalt tile	Minimum lighting and outlets, minimum plumbing	Forced air and ventilation
S	Good	219.50	Insulated sandwich panels, metal and glass, some ornamentation	Comparable to typical chain coffee shop, vinyl and ceramic floors	Good lighting and service outlets, tiled restrooms	Complete H.V.A.C.
	Average	165.00	Insulated panels, metal and glass, little ornamentation	Typical neighborhood coffee shop, vinyl comp., some ceramic or pavers	Adequate lighting and outlets, small restrooms	Complete H.V.A.C.
	Low cost	113.50	Finished interior, some front	Low-cost finish, asphalt tile	Minimum lighting and plumbing	Forced air/vent.
CDS†	Finished basement	106.00	Plaster or drywall interior	Finished ceiling and floors, banquet, service functions	Adequate lighting/plumbing, restrooms, utility rooms	Forced air and ventilation
	Storage basement	49.25	Painted interior, outside entry	Paint only, some partitions	Adequate lighting, drains	None
	Open mezzanine	41.50	Not included	Open, finished floors and soffit, minimum work stations	Adequate lighting, minimum plumbing	Included in building cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $ 8.60 per square foot.
MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

DUMBWAITERS: Automatic electric dumbwaiters, 500# capacity, stainless steel cab, cost $25,100 to $64,750 plus $7,250 per stop over two. For hand operation, use 50%.

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Restaurants with basements, add 40% to extend the foundation to the basement level. Custom oversized units can run 100% to 200% more.

Type	COST RANGE
One story	$3,675 – $ 11,800
Two story	4,655 – 14,170

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

RESTAURANT HEATING, COOLING AND AIR CONDITIONING

These costs are averages of total installed cost of the entire heating or cooling installation including its prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated costs.

COMPLETE H.V.A.C

Classes A/B	Sq. Ft. Costs
Excellent	$ 47.75
Good	40.25
Average	35.00

Classes C/D/S	Sq. Ft. Costs
Excellent	$ 45.25
Very Good	38.25
Good	33.25
Average	27.25
Low-cost	23.25
Forced-air ventilation	11.55

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	13	1.021
10	.957	14	1.042
11	.979	15	1.064
12	1.000 (base)	16	1.085
		18	1.127

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Average Floor Area Sq. Ft./Story
1,000	1.183	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	.969	1.079	1.183	1.283	1.376	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	.878	.924	.969	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**5,000**
7,000	-----	-----	.870	.904	.937	1.000	1.060	1.121	1.183	-----	-----	-----	-----	-----	**7,000**
10,000	-----	-----	-----	-----	.878	.925	.969	1.011	1.054	1.097	1.140	1.183	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.892	.931	.969	1.005	1.042	1.079	1.117	1.183	-----	**12,000**
14,000	-----	-----	-----	-----	-----	.870	.904	.937	.969	1.000	1.030	1.060	1.121	-----	**14,000**
18,000	-----	-----	-----	-----	-----	-----	.866	.892	.917	.943	.969	.992	1.040	-----	**18,000**
20,000	-----	-----	-----	-----	-----	-----	.854	.878	.901	.924	.948	.969	1.011	-----	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.925	.969	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.878	.913	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	**50,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS – ATRIUMS/PLAY ROOMS



GOOD CLASS S ATRIUM



GOOD CLASS C PLAYROOM

OCCUPANCY DESCRIPTION: Dining atriums and playrooms are open shell extensions for enclosed extra seating or game/play areas, usually added to fast food restaurants. The lower qualities are playroom shells only, while the very good and excellent qualities are finished greenhouse seating atriums.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable restroom facilities.

NOT INCLUDED IN COSTS: Kitchen equipment, restaurant fixtures, furnishings and signs. Soft modular play systems, restaurant seating or other furnishings or fixtures.

DINING ATRIUMS/PLAY ROOMS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 190.50	Decorative block, brick, mostly metal and glass	Drywall, acoustic ceiling, vinyl walls, good playroom	Good lighting and plumbing	None
	Average	117.50	Stucco on block, tilt-up, good glass areas	Drywall, some acoustic tile, ceramic pavers, plain playroom	Adequate lighting, no plumbing	None
	Low cost	72.50	Concrete block, tilt-up, very plain, little glass	Drywall, vinyl composition tile, plain play area shell	Minimum lighting, no plumbing	None
D	Good	175.50	Brick veneer, EIFS, siding, mostly metal and glass	Drywall, acoustic ceiling, vinyl walls, good playroom	Good lighting and plumbing	None
	Average	103.50	Stucco or siding, good glass areas	Drywall, some acoustic tile, ceramic pavers, plain playroom	Adequate lighting, no plumbing	None
	Low cost	61.00	Stucco or siding, very plain, little glass	Drywall, vinyl composition tile, plain play area shell	Minimum lighting, no plumbing	None
S	Excellent	302.00	Greenhouse, curved eaves, colored frame, tinted glass	Good carpet, ceramic floors, minimum work stations	Decorative lighting and ceiling fans, adequate plumbing	None
	Very good	227.00	Shed greenhouse, tempered glass, little knee wall	Carpet, vinyl composition tile, seating alcove	Good electrical and lighting, plumbing	None
	Good	170.50	Steel frame, mostly metal and glass, metal panels	Drywall, acoustic ceiling, vinyl walls, good playroom	Good lighting and plumbing	None
	Average	97.00	Steel frame, metal siding, good glass areas	Drywall, some acoustic tile, ceramic pavers, plain playroom	Adequate lighting, no plumbing	None
	Low cost	55.00	Steel frame, metal siding, very plain, little glass	Drywall, vinyl composition tile, plain play area shell	Minimum lighting, no plumbing	None
	Cheap	31.50	Screen-netting enclosure, canopy top, light frame	Concrete floor, secure play area	Adequate illumination, no plumbing	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS – ATRIUMS/PLAYROOMS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

For restaurant equipment, see Section UIP 15, Page 8.

For soft, modular play equipment, see Section UIP 16, Page 7

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
500	$ 6.67	$ 8.71	$11.41	$ 14.89
1,000	6.02	7.78	10.10	13.05
1,500	5.66	7.28	9.35	12.00
2,000	5.43	6.95	8.88	11.35
2,500	5.25	6.69	8.55	10.92
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62

2

RESTAURANT HEATING, COOLING AND AIR CONDITIONING

These costs are averages of total installed cost of the entire heating or cooling installation including its prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated costs.

COMPLETE H.V.A.C

Classes A/B	Sq. Ft. Costs
Good	$40.25
Average	35.00

Classes C/D/S	Sq. Ft. Costs
Excellent	$ 45.25
Good	33.25
Average	27.25
Low-cost	23.25
Forced-air ventilation	11.55

ATRIUM/PLAY ROOM: Heating and cooling may be connected to existing systems; for additional connections only, add $ 5,000 to $7,750.

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	13	1.021
10	.957	14	1.042
11	.979	15	1.064
12	1.000 (base)	16	1.085
		18	1.127

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	175	200	225	250	275	300	350	400	450	500	Sq. Ft./Story
500	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
750	1.183	1.322	1.445	1.566	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**750**
1,000	1.079	1.183	1.283	1.376	1.470	1.566	1.660	1.753	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.969	1.042	1.115	1.183	1.256	1.322	1.384	1.445	1.506	1.566	-----	-----	-----	-----	**1,500**
2,000	.912	.969	1.025	1.079	1.130	1.183	1.233	1.283	1.330	1.376	1.470	-----	-----	-----	**2,000**
2,500	.878	.924	.969	1.011	1.054	1.097	1.140	1.183	1.227	1.270	1.351	1.420	-----	-----	**2,500**
3,000	.854	.892	.931	.969	1.005	1.042	1.079	1.115	1.149	1.183	1.256	1.322	1.380	-----	**3,000**
3,500	-----	.873	.907	.941	.973	1.006	1.038	1.070	1.101	1.131	1.194	1.253	1.300	-----	**3,500**
4,000	-----	.854	.883	.912	.941	.969	.997	1.025	1.052	1.079	1.131	1.183	1.232	1.280	**4,000**
4,500	-----	-----	.869	.895	.921	.947	.972	.997	1.021	1.045	1.093	1.140	1.186	1.232	**4,500**
5,000	-----	-----	.854	.878	.901	.924	.947	.969	.990	1.011	1.054	1.097	1.140	1.183	**5,000**
6,000	-----	-----	-----	-----	.873	.892	.912	.931	.950	.969	1.005	1.042	1.079	1.115	**6,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS – CAFETERIAS AND TRUCK STOPS



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: Cafeterias will have large, open dining rooms for self service of large groups, and include commercial as well as institutional facilities. They include a combination of the following areas: consumption, production, serving, receiving and storage, sanitation and restrooms.

Truck stops are of multipurpose design to include convenience stores, food service, shower and toilet, game and rest facilities for highway travelers and truckers. Good facilities include the typical coffee shop operation, while the average quality includes the limited fast food franchise operation. Lighting and plumbing, although adequate to service the operation, are not extensive or ornate.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. All necessary plumbing and electrical connections for kitchen equipment.

NOT INCLUDED IN COSTS: Kitchen equipment, restaurant or convenience store fixtures, furnishings or signs.

CAFETERIAS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 280.50	Concrete, metal/glass, or masonry panels, usually part of a building	Plaster with enamel and vinyl, carpet and vinyl flooring, decorated interior	Good lighting and outlets, good plumbing and restrooms	Complete H.V.A.C.
	Average	216.50	Brick or concrete, usually part of a building	Plaster or drywall, acoustic tile, ceramic, rubber or vinyl comp. tile	Adequate lighting and outlets, adequate plumbing	Complete H.V.A.C.
C	Excellent	321.00	Individual design, brick, good metal and glass, ornamentation	Best corporate or chain cafeterias, carpeted dining room, terrazzo	Good lighting/restrooms with good-quality fixtures and tile	Complete H.V.A.C.
	Good	231.00	Brick, concrete or metal and glass panels, some ornamentation	Typical institutional or chain cafeteria, vinyl and ceramic floors	Good lighting and service outlets, tiled preparation and restrooms	Complete H.V.A.C.
	Average	169.00	Brick, block, tilt-up, plain building and front	Typical neighborhood restaurant, vinyl composition, small kitchen	Adequate lighting and outlets, small restrooms	Complete H.V.A.C.
	Low cost	113.00	Cheap brick or block, very plain, small entry	Low-cost food service, minimum dining hall finish, asphalt tile	Minimum lighting and outlets, minimum plumbing	Forced air and ventilation
D	Excellent	309.00	Individual design, brick veneer, good metal and glass, ornamentation	Best corporate or chain cafeterias, carpeted dining room, terrazzo	Good fixtures, good restrooms w/ good-quality fixtures and tile	Complete H.V.A.C.
	Good	217.50	Stucco or siding, metal and glass, some ornamentation	Typical institutional or chain cafeteria, vinyl and ceramic floors	Good lighting and service outlets, tiled restrooms	Complete H.V.A.C.
	Average	157.00	Stucco or siding, plain building and front	Typical neighborhood restaurant, vinyl composition, small kitchen	Adequate lighting and outlets, small restrooms	Complete H.V.A.C.
	Low cost	103.00	Cheap stucco or siding, very plain construction, small entry	Low-cost food service, minimum dining hall finish, asphalt tile	Minimum lighting and outlets, minimum plumbing	Forced air and ventilation
DPOLE	Low cost	100.50	Pole frame, good metal panels, lined and insulated, plain entry	Low-cost food service, minimum dining hall finish, asphalt tile	Minimum lighting and outlets, minimum plumbing	Forced air and ventilation
S	Good	219.50	Insulated sandwich panels, metal and glass, some ornamentation	Typical institutional or chain cafeteria, vinyl and ceramic floors	Good lighting and service outlets, tiled restrooms	Complete H.V.A.C.
	Average	157.50	Insulated panels, metal and glass, little ornamentation	Typical neighborhood restaurant, vinyl comp., some ceramic or pavers	Adequate lighting and outlets, small restrooms	Complete H.V.A.C.
	Low cost	102.50	Finished interior, very plain construction, small entry	Low-cost food service, minimum dining hall finish, asphalt tile	Minimum lighting and outlets, minimum plumbing	Forced air and ventilation

TRUCK STOP RESTAURANTS

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	*HEAT
C	Excellent	$ 283.50	Brick, concrete or metal and glass panels, ornamentation	Good coffee shop, retail, separate rest area, shower room	Good lighting, showers, restrooms and kitchen with good fixtures	Very good comp. H.V.A.C.
	Good	233.50	Decorative block, tilt-up, good storefront, lobby	Full-service food seating, retail, rest and game rooms	Good electrical and plumbing, showers, full kitchen	Complete H.V.A.C.
	Average	191.50	Concrete block, tilt-up, plain storefront entry	Fast food service, small convenience store, rest area	Adequate electrical, plumbing, walk-in box storage	Complete H.V.A.C.
D	Excellent	270.00	Brick veneer, EIFS, metal and glass panels, ornamentation	Good coffee shop, retail, separate rest area, shower room	Good lighting, showers, restrooms and kitchen with good fixtures	Very good comp. H.V.A.C.
	Good	222.50	Brick veneer or good siding, good storefront lobby	Full-service food seating, retail, rest and game rooms	Good electrical and plumbing, showers, full kitchen	Complete H.V.A.C.
	Average	183.00	Stucco or siding, plain storefront entry	Fast food service, small convenience store, rest area	Adequate electrical, plumbing, walk-in box storage	Complete H.V.A.C.
S	Good	225.00	Good metal panels, good storefront, lobby	Full-service food seating, retail, rest and game rooms	Good electrical and plumbing, showers, full kitchen	Complete H.V.A.C.
	Average	183.50	Steel frame, metal siding, plain storefront entry	Fast food service, small convenience store, rest area	Adequate electrical, plumbing, walk-in box storage	Complete H.V.A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS – CAFETERIAS AND TRUCK STOPS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

DUMBWAITERS: Automatic electric dumbwaiters, 500# capacity, stainless steel cab, cost $25,100 to $64,750 plus $7,250 per stop over two. For hand operation, use 50%.

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 36.25	$ 45.00	$ 56.00	$ 69.50
Light false-mansard	18.10	22.55	28.00	34.75
Steel frame	46.25	59.00	75.00	96.00
Light false-mansard	23.10	29.50	37.50	48.00

For service station equipment and canopies, see Section UIP 14.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

RESTAURANT HEATING, COOLING AND AIR CONDITIONING

These costs are averages of total installed cost of the entire heating or cooling installation including its prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated costs.

COMPLETE H.V.A.C

Classes A/B	Sq. Ft. Costs
Good	$40.25
Average	35.00

Classes C/D/S	Sq. Ft. Costs
Excellent	$ 45.25
Good	33.25
Average	27.25
Low-cost	23.25
Forced-air ventilation	11.55

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	13	1.021
10	.957	14	1.042
11	.979	15	1.064
12	1.000 (base)	16	1.085
		18	1.127

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Average Floor Area Sq. Ft./Story
1,000	1.183	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	.969	1.079	1.183	1.283	1.376	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
5,000	-----	.878	.924	.969	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	5,000
7,000	-----	-----	.870	.904	.937	1.000	1.060	1.121	1.183	-----	-----	-----	-----	-----	7,000
10,000	-----	-----	-----	-----	.878	.925	.969	1.011	1.054	1.097	1.140	1.183	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.892	.931	.969	1.005	1.042	1.079	1.117	1.183	-----	12,000
14,000	-----	-----	-----	-----	-----	.870	.904	.937	.969	1.000	1.030	1.060	1.121	-----	14,000
18,000	-----	-----	-----	-----	-----	-----	.866	.892	.917	.943	.969	.992	1.040	-----	18,000
20,000	-----	-----	-----	-----	-----	-----	.854	.878	.901	.924	.948	.969	1.011	-----	20,000
30,000	-----	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.925	.969	30,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.878	.913	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	50,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS – FAST FOOD



AVERAGE CLASS C



GOOD CLASS D

OCCUPANCY DESCRIPTION: These structures have limited consumption or dining area in relation to the food preparation area. Drive-up windows consistent with the level of quality are included. The average fast food restaurant normally includes some outer roof overhang, but no large separate canopies and carports. The lower qualities are built to minimum building and health codes. The median area for a fast food restaurant is 3,150 square feet with a range of 1,375 to 4,250 square feet.

Newer outlets with a high percentage (35% to 45%) of eating space to food preparation area tend toward the larger areas with lower unit costs, while older outlets and drive-ins with no or limited seating tend toward the small side of the range and a higher overall unit cost, excluding extremes. As eating/play areas continue to increase in size, the very large fast food restaurants will approach conventional table service restaurants in cost or will require a reduction in the quality level for pricing purposes. Play or game room costs can be added separately (see Page CAL 172).

The seating space should normally be less than 45% of the total area.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office space and restroom facilities.

NOT INCLUDED IN COSTS: Canopies, sprinklers, kitchen equipment, restaurant fixtures, furniture or signs.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 344.00	Concrete, good metal and glass, face brick, usually part of a building	Typically, best chain stores, good plaster, ceramic, pavers throughout	Good lighting, restrooms with good fixtures and tile	Complete H.V.A.C.
	Average	262.50	Brick or concrete, usually part of a building	Plaster or drywall, acoustic tile, ceramic, carpet or vinyl composition	Adequate lighting and outlets, adequate plumbing	Complete H.V.A.C.
C	Excellent	418.00	Individual design, highly ornamental exterior	High-quality detail, best ceramic, pavers, limited seating area	Special lighting, tiled restrooms, good fixtures	Complete H.V.A.C.
	Very good	323.50	Face brick, good metal and glass, good mansard, canopy ornament	Typically better small chain stores, plaster, ceramic, pavers throughout	Good lighting, restrooms with good fixtures and tile	Complete H.V.A.C.
	Good	250.50	Brick, best block, stucco, good storefront, ornamentation	Typical chain and better large stores, plaster, ceramic, terrazzo, vinyl tile	Good lighting and service outlets, tiled restrooms	Complete H.V.A.C.
	Average	194.00	Brick, block, some mansard, parapet ornamentation	Drywall, paneling, acoustic tile, pavers, vinyl comp., large eating/play area	Adequate lighting and outlets, small restrooms	Complete H.V.A.C.
	Low cost	139.50	Cheap brick or block, very plain, low-cost front	Low-cost preparation area, minimum finish, asphalt tile	Minimum lighting and outlets, minimum plumbing	Forced air and ventilation
D	Excellent	401.50	Individual design, highly ornamental exterior	High-quality detail, best ceramic, pavers, limited seating area	Special lighting, tiled restrooms, good fixtures	Complete H.V.A.C.
	Very good	305.50	Face brick veneer, good front, mansard, canopy ornamentation	Typically better small chain stores, plaster, ceramic, pavers throughout	Good lighting, restrooms with good fixtures and tile	Complete H.V.A.C.
	Good	234.00	Stucco, siding or brick veneer, metal and glass, good ornamentation	Typical chain and better large stores, plaster, ceramic, terrazzo, vinyl tile	Good lighting and service outlets, tiled restrooms	Complete H.V.A.C.
	Average	178.50	Stucco or siding, some mansard, parapet ornamentation	Drywall, paneling, acoustic tile, pavers, vinyl comp., large eating/play area	Adequate lighting and outlets, small restrooms	Complete H.V.A.C.
	Low cost	126.50	Cheap stucco or siding, very plain construction	Low-cost preparation area, minimum finish, asphalt tile	Minimum lighting and outlets, minimum plumbing	Forced air and ventilation
S	Excellent	323.50	Stainless steel panels, steel roof, vestibule, modular diner	Good detail, acoustic, vinyl and ceramic tile, limited seating	Good electrical, plumbing and restrooms	Complete H.V.A.C.
	Good	238.00	Insulated sandwich panels, metal and glass, good ornamentation	Typical chain and better large stores, plaster, ceramic, terrazzo, vinyl tile	Good lighting and service outlets, tiled restrooms	Complete H.V.A.C.
	Average	177.50	Insulated panels, metal and glass, some mansard, parapet ornament	Drywall, paneling, acoustic tile, pavers, vinyl comp., large eating/play area	Adequate lighting and outlets, small restrooms	Complete H.V.A.C.
	Low cost	122.00	Finished interior, some front, little ornamentation	Low-cost preparation area, minimum finish, asphalt tile	Minimum lighting and outlets, minimum plumbing	Forced air and ventilation
CDS†	Storage basement	49.25	Painted interior, outside entry	Painted ceiling and floor, some partitions	Adequate lighting, drains	None

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $ 8.60 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS – FAST FOOD

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

DUMBWAITERS: Automatic electric dumbwaiters, 500# capacity, stainless steel cab, cost $25,100 to $64,750 plus $7,250 per stop over two. For hand operation, use 50%.

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 36.25	$ 45.00	$ 56.00	$ 69.50
Light false-mansard	18.10	22.55	28.00	34.75
Steel frame	46.25	59.00	75.00	96.00
Light false-mansard	23.10	29.50	37.50	48.00

For service station equipment and canopies, see Section UIP 14.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
500	$ 6.67	$ 8.71	$ 11.41	$ 14.89
1,000	6.02	7.78	10.10	13.05
1,500	5.66	7.28	9.35	12.00
2,000	5.43	6.95	8.88	11.35
2,500	5.25	6.69	8.55	10.92
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62

2

RESTAURANT HEATING, COOLING AND AIR CONDITIONING

These costs are averages of total installed cost of the entire heating or cooling installation including its prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated costs.

COMPLETE H.V.A.C

Classes A/B	Sq. Ft. Costs
Good	$40.25
Average	35.00

Classes C/D/S	Sq. Ft. Costs
Excellent	$ 45.25
Good	33.25
Average	27.25
Low-cost	23.25
Forced-air ventilation	11.55

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	13	1.021
10	.957	14	1.042
11	.979	15	1.064
12	1.000 (base)	16	1.085
		18	1.127

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	175	200	225	250	275	300	350	400	450	500	Sq. Ft./Story
500	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
750	1.183	1.322	1.445	1.566	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**750**
1,000	1.079	1.183	1.283	1.376	1.470	1.566	1.660	1.753	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.969	1.042	1.115	1.183	1.256	1.322	1.384	1.445	1.506	1.566	-----	-----	-----	-----	**1,500**
2,000	.912	.969	1.025	1.079	1.130	1.183	1.233	1.283	1.330	1.376	1.470	-----	-----	-----	**2,000**
2,500	.878	.924	.969	1.011	1.054	1.097	1.140	1.183	1.227	1.270	1.351	1.420	-----	-----	**2,500**
3,000	.854	.892	.931	.969	1.005	1.042	1.079	1.115	1.149	1.183	1.256	1.322	1.380	-----	**3,000**
3,500	-----	.873	.907	.941	.973	1.006	1.038	1.070	1.101	1.131	1.194	1.253	1.300	-----	**3,500**
4,000	-----	.854	.883	.912	.941	.969	.997	1.025	1.052	1.079	1.131	1.183	1.232	1.280	**4,000**
4,500	-----	-----	.869	.895	.921	.947	.972	.997	1.021	1.045	1.093	1.140	1.186	1.232	**4,500**
5,000	-----	-----	.854	.878	.901	.924	.947	.969	.990	1.011	1.054	1.097	1.140	1.183	**5,000**
6,000	-----	-----	-----	-----	.873	.892	.912	.931	.950	.969	1.005	1.042	1.079	1.115	**6,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS - DINERS (MODULAR)



GOOD CLASS S

OCCUPANCY DESCRIPTION: These prefabricated stainless steel diners have limited consumption or dining area in relation to the preparation area. Vestibules commensurate with the quality are included, except in the low quality. The average modular restaurant normally includes some outer roof dome, but no large separate canopies and carports. The lower qualities are built to minimum building and health codes. These buildings have suitable work space and restroom facilities.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office areas and all necessary plumbing and electrical connections for kitchen equipment.

NOT INCLUDED IN COSTS: Elevators, sprinklers, kitchen equipment, restaurant fixtures, furnishings or signs.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. Ft.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
S	Excellent	$ 352.50	Stainless steel panels and dome roof, large stainless steel and glass vestibule	Good detail, metal and acoustic, vinyl and ceramic tile	Good electrical illumination, plumbing and restrooms	Package A.C.
	Good	332.50	Stainless steel panels and roof, stainless steel vestibule	Drywall, paneling, some ornamentation, good vinyl and ceramic floors	Good lighting and service outlets, tiled restrooms	Package A.C.
	Average	313.00	Stainless steel panels, steel roof, small vestibule	Drywall, paneling, acoustic tile, some pavers, vinyl composition tile	Adequate lighting and outlets, small restrooms	Package A.C.
	Low cost	295.00	Stainless steel panels, steel roof	Low-cost preparation area, minimum finish, vinyl composition tile	Minimum lighting and outlets, minimum plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS - DINERS (MODULAR)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 The median area for modular diners is 1,850 square feet with a typical range of 840 to 2,950 square feet. The average area per seat is 21 square feet with a typical range of 15 to 28 square feet.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
500	$ 6.67	$ 8.71	$ 11.41	$ 14.89
1,000	6.02	7.78	10.10	13.05
1,500	5.66	7.28	9.35	12.00
2,000	5.43	6.95	8.88	11.35
2,500	5.25	6.69	8.55	10.92
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62

2 **HEATING AND COOLING**

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3 **HEIGHT REFINEMENTS**

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	14	1.042
10	.957	15	1.064
11	.979	16	1.085
12	1.000 (base)	18	1.127

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	175	200	225	250	275	300	350	400	450	500	Sq. Ft./Story
500	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
750	1.183	1.322	1.445	1.566	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**750**
1,000	1.079	1.183	1.283	1.376	1.470	1.566	1.660	1.753	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.969	1.042	1.115	1.183	1.256	1.322	1.384	1.445	1.506	1.566	-----	-----	-----	-----	**1,500**
2,000	.912	.969	1.025	1.079	1.130	1.183	1.233	1.283	1.330	1.376	1.470	-----	-----	-----	**2,000**
2,500	.878	.924	.969	1.011	1.054	1.097	1.140	1.183	1.227	1.270	1.351	1.420	-----	-----	**2,500**
3,000	.854	.892	.931	.969	1.005	1.042	1.079	1.115	1.149	1.183	1.256	1.322	1.380	-----	**3,000**
3,500	-----	.873	.907	.941	.973	1.006	1.038	1.070	1.101	1.131	1.194	1.253	1.300	-----	**3,500**
4,000	-----	.854	.883	.912	.941	.969	.997	1.025	1.052	1.079	1.131	1.183	1.232	1.280	**4,000**
4,500	-----	-----	.869	.895	.921	.947	.972	.997	1.021	1.045	1.093	1.140	1.186	1.232	**4,500**
5,000	-----	-----	.854	.878	.901	.924	.947	.969	.990	1.011	1.054	1.097	1.140	1.183	**5,000**
6,000	-----	-----	-----	-----	.873	.892	.912	.931	.950	.969	1.005	1.042	1.079	1.115	**6,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS – SNACK BARS



AVERAGE CLASS D



LOW COST CLASS C

OCCUPANCY DESCRIPTION: These structures have no seating area and include the very marginal seasonal camp type facility to the best municipal structure with completely finished food preparation area. The basic snack bar cost includes normal overhangs com- mensurate with the quality but not large canopies. The lower qualities are built to minimum building and health codes.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office space and restroom facilities.

NOT INCLUDED IN COSTS: Canopies, kitchen or seating equipment and signs.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. Ft.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 257.00	Decorative block and trim, heavy structure, glass or security shutters	Finished interior, good tile or glazed surfaces, best municipal facility	Good lighting, restrooms with good fixtures and tile	Evaporative Cooling
	Good	170.50	Standard block, concrete panels, some trim	Enameled walls, some wainscot, finished ceiling, good concrete floor	Good lighting, service outlets and plumbing, some extra fixtures	Wall furnace
	Average	114.50	Concrete block, bearing walls, little trim	Painted walls, some ceiling finish, sealed concrete	Adequate lighting and plumbing	Space heaters
	Low cost	73.50	Block, light roof, very plain	Low-cost finishes, few partitions	Minimum code	None
	Cheap	60.00	Low-cost block	Unfinished interior, open counter and storage	Minimum fixtures	None
D	Excellent	248.00	Brick veneer, best stucco or siding, glass or security shutters	Finished interior, good tile or glazed surfaces, best municipal facility	Good lighting, restrooms with good fixtures and tile	Evaporative Cooling
	Good	158.50	Stud frame, good stucco or siding, brick veneer	Enameled walls, some wainscot, finished ceiling, good concrete floor	Good lighting, service outlets and plumbing, some extra fixtures	Wall furnace
	Average	104.00	Wood frame, stucco or siding, little trim	Painted walls, some ceiling finish, sealed concrete	Adequate lighting and plumbing	Space heaters
	Low cost	63.50	Low-cost stucco or siding	Low-cost finishes, few partitions	Minimum code	None
	Cheap	45.50	Box frame, plywood, boards	Unfinished interior, open counter and storage	Minimum fixtures	None
D POLE	Average	96.50	Pole frame, good metal panels, finished inside, little trim	Painted walls, some ceiling finish, sealed concrete	Adequate lighting and plumbing	Space heaters
	Low cost	58.00	Pole frame, metal panels, finished inside	Low-cost finishes, few partitions	Minimum code	None
	Cheap	45.50	Pole frame, metal siding	Unfinished interior, open counter and storage	Minimum fixtures	None
S	Average	102.00	Good metal panels, lined, pre-engineered frame, little trim	Painted walls, some ceiling finish, sealed concrete	Adequate lighting and plumbing	Space heaters
	Low cost	61.50	Pre-engineered, metal panels, finished inside	Low-cost finishes, few partitions	Minimum code	None
	Cheap	49.00	Light steel frame, siding	Unfinished interior, open counter and storage	Minimum fixtures	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTAURANTS – SNACK BARS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

CANOPIES: This is the cantilevered portion of a building that extends over an entrance.

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 36.25	$ 45.00	$ 56.00	$ 69.50
Light false-mansard	18.10	22.55	28.00	34.75
Steel frame	46.25	59.00	75.00	96.00
Light false-mansard	23.10	29.50	37.50	48.00

LOAD-BEARING CONCESSION STAND ROOFS: (for press boxes or projection rooms), add $5.40 per square foot to the entire gross building area. For access stairways, add $2,200 to $4,825 each.

SCREENED ROOMS: Screen-enclosed seating area for snack bar facilities may be computed from Section UIP 16.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
500	$ 6.67	$ 8.71	$ 11.41	$ 14.89
1,000	6.02	7.78	10.10	13.05
1,500	5.66	7.28	9.35	12.00
2,000	5.43	6.95	8.88	11.35
2,500	5.25	6.69	8.55	10.92
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	14	1.042
10	.957	15	1.064
11	.979	16	1.085
12	1.000 (base)	18	1.127

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	175	200	225	250	275	300	350	400	450	500	Sq. Ft./Story
500	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
750	1.183	1.322	1.445	1.566	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**750**
1,000	1.079	1.183	1.283	1.376	1.470	1.566	1.660	1.753	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.969	1.042	1.115	1.183	1.256	1.322	1.384	1.445	1.506	1.566	-----	-----	-----	-----	**1,500**
2,000	.912	.969	1.025	1.079	1.130	1.183	1.233	1.283	1.330	1.376	1.470	-----	-----	-----	**2,000**
2,500	.878	.924	.969	1.011	1.054	1.097	1.140	1.183	1.227	1.270	1.351	1.420	-----	-----	**2,500**
3,000	.854	.892	.931	.969	1.005	1.042	1.079	1.115	1.149	1.183	1.256	1.322	1.380	-----	**3,000**
3,500	-----	.873	.907	.941	.973	1.006	1.038	1.070	1.101	1.131	1.194	1.253	1.300	-----	**3,500**
4,000	-----	.854	.883	.912	.941	.969	.997	1.025	1.052	1.079	1.131	1.183	1.232	1.280	**4,000**
4,500	-----	-----	.869	.895	.921	.947	.972	.997	1.021	1.045	1.093	1.140	1.186	1.232	**4,500**
5,000	-----	-----	.854	.878	.901	.924	.947	.969	.990	1.011	1.054	1.097	1.140	1.183	**5,000**
6,000	-----	-----	-----	-----	.873	.892	.912	.931	.950	.969	1.005	1.042	1.079	1.115	**6,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTROOM BUILDINGS



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These are freestanding, generally single purpose design, restroom buildings. Interior construction is paint enameled drywall or plaster and the floors are concrete. In higher qualities, there are ceramic tile walls and/or floors. There is adequate lighting and plumbing. The better qualities can include some storage and/or limited snack bar sales and finish.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers, lockers, therapy or recreational equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 276.00	Brick, decorative block or concrete, some trim	Finished interior, tile or glazed surfaces, some extras	Adequate lighting and plumbing, extra outlets and fixtures	Wall furnace
C	Excellent	391.50	Stone, rustic trim or block	Good finish or under 500 sq. ft.	High-cost fixtures	Wall furnace
	Good	286.50	Decorative block and trim, heavy structure	Finished interior, good tile or glazed surfaces, concession area	Good lighting and plumbing, extra outlets and fixtures	Wall furnace
	Average	210.00	Concrete block, bearing walls, little trim	Painted walls, some ceiling finish, sealed concrete	Adequate lighting and plumbing	Electric wall heaters
	Low cost	154.50	Block, light roof, very plain	Low-cost finishes, few partitions	Minimum code	Space heaters
	Cheap	108.50	Low-cost block	Unfinished interior	Minimum fixtures	None
D	Excellent	359.00	Stone veneer, rustic trim or log	Good finish or under 500 sq. ft.	High-cost fixtures	Wall furnace
	Good	265.00	Wood frame or pipe columns, good stucco or siding, brick veneer	Finished interior, good tile or glazed surfaces, concession area	Good lighting and plumbing, extra outlets and fixtures	Wall furnace
	Average	196.00	Wood frame, stucco or siding, little trim	Painted walls, some ceiling finish, sealed concrete	Adequate lighting and plumbing	Electric wall heaters
	Low cost	146.00	Low-cost stucco or siding	Low-cost finishes, few partitions	Minimum code	Space heaters
	Cheap	102.50	Box frame, plywood, boards	Unfinished interior	Minimum fixtures	None
D POLE	Low cost	139.00	Pole frame, metal panels, finished inside	Low-cost finishes, few partitions	Minimum code	Space heaters
	Cheap	105.50	Pole frame, metal siding	Unfinished interior	Minimum fixtures	None
S	Low cost	140.50	Pre-engineered, metal panels, finished inside	Low-cost finishes, few partitions	Minimum code	Space heaters
	Cheap	105.00	Light steel frame, siding	Unfinished interior	Minimum fixtures	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

RESTROOM BUILDINGS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $ 3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	125	150	175	200	250	300	400	500	600	700	800	1000	1200	Sq. Ft./Story
500	1.298	1.407	1.516	1.625	1.734	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
1,000	1.079	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.006	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	-----	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	-----	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	1.116	-----	-----	-----	**6,000**
7,000	-----	-----	-----	-----	-----	.939	.955	.984	1.015	1.048	1.079	1.110	-----	-----	**7,000**
8,000	-----	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.052	1.079	1.134	-----	**8,000**
10,000	-----	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.013	1.036	1.079	1.123	**10,000**
12,000	-----	-----	-----	-----	-----	-----	.915	.934	.959	.968	.985	1.006	1.043	1.079	**12,000**

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

ROOMING HOUSES



AVERAGE CLASS D



FAIR CLASS C

OCCUPANCY DESCRIPTION: These structures can be more commercial in character than multiple residences and provide minimum living quarters for transient occupancy. Lower qualities are plain, with minimum electrical and common plumbing.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Furnishings, appliances, fireplaces, balconies or yard improvements.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 167.50	Brick, some trim or good stucco, good roof, good fenestration	Plaster or drywall, carpeting, hardwood, vinyl composition	One bath per two rooms, built-in kitchen facilities, good electrical	Hot water
	Average	128.50	Brick, stucco on block, little trim, built-up roof or asphalt shingles	Plaster or drywall, some carpet, vinyl composition, cheap hardwood	Adequate electrical, common baths, small kitchen area	Forced air
	Fair	104.50	Block or cheap brick, low-cost roof and sash	Drywall and paint, asphalt tile, softwood, few cabinets	Minimum, common baths, sink or lavatory in room	Wall furnace
D	Good	159.00	Brick veneer, best stucco or siding, some good ornamentation	Plaster or drywall, carpeting, hardwood, vinyl composition	One bath per two rooms, built-in kitchen facilities, good electrical	Hot water
	Average	121.00	Good stucco or siding, some brick or stone trim	Plaster or drywall, some carpet, vinyl composition, cheap hardwood	Adequate electrical, common baths, small kitchen areas	Forced air
	Fair	97.50	Stucco or siding, very plain	Drywall, softwood, asphalt tile, few cabinets	Minimum, common baths, sink or lavatory in room	Wall furnace
	Low Cost	85.50	Low-cost siding or stucco	Drywall, softwood or asphalt tile	Minimum, common baths	Elec. wall htr.
CD	Utility Basement	43.25	Unfinished interior	Unfinished floor and ceiling	Minimum lighting and plumbing	None

For basement apartments, use 75% of the cost of comparable above ground units. For semi-basement apartments, use 85%.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

ROOMING HOUSES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Country Clubs with basements, add 40% to extend the foundation to the basement level.

TYPE	COST RANGE
One-story	$3,850 – $12,400
Two-stories	4,890 – 14,890
Three-stories	5,930 – 17,380

RESIDENTIAL ELEVATORS: The small residential-style two or three passenger elevators found in rooming houses cost $28,600 to $57,500 for two stops plus $3,900 to $6,150 for each additional stop.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 5.14	$ 6.63	$ 8.55	$ 11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
30,000	3.58	4.52	5.68	7.15

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL
Concrete	$ 34.00	$ 43.50	$ 55.00	$ 71.00
Steel	31.75	42.50	56.50	75.50
Wood	29.75	39.50	52.50	68.50
Add for ornate finishes, balustrades	29.50	36.00	44.25	54.00
Add for roofs or awnings	15.35	20.40	27.00	36.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork)	$ 21.90	Central refrigeration (zoned)	$ 16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector	20.75	Heat pump system	25.50	Pkg. refrig.	$2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers.	$331 to $535 per MCFM capacity
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 3.18

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	11	1.027
9	.973	12	1.055
10	1.000 (base)		

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 200	250	300	350	400	450	500	600	700	800	1000	1200	1400	Average Floor Area Sq. Ft./Story
2,000	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	.959	.989	1.021	1.052	1.083	1.113	1.143	1.206	1.268	1.329	-----	-----	-----	**4,000**
6,000	.917	.938	.959	.980	1.000	1.021	1.042	1.083	1.123	1.165	-----	-----	-----	**6,000**
8,000	-----	.913	.929	.944	.959	.974	.989	1.021	1.052	1.083	1.143	1.206	1.268	**8,000**
10,000	-----	-----	.910	.922	.935	.947	.959	.984	1.009	1.034	1.083	1.133	1.181	**10,000**
12,000	-----	-----	-----	.907	.917	.928	.938	.959	.980	1.000	1.042	1.083	1.123	**12,000**
14,000	-----	-----	-----	-----	.906	.915	.924	.942	.959	.977	1.011	1.047	1.083	**14,000**
20,000	-----	-----	-----	-----	.885	.892	.898	.910	.922	.935	.959	.984	1.009	**20,000**
24,000	-----	-----	-----	-----	-----	-----	.886	.896	.907	.917	.938	.959	.980	**24,000**
28,000	-----	-----	-----	-----	-----	-----	.880	.888	.898	.906	.924	.942	.959	**28,000**
32,000	-----	-----	-----	-----	-----	-----	.874	.882	.889	.898	.913	.928	.944	**32,000**
36,000	-----	-----	-----	-----	-----	-----	.870	.877	.883	.890	.904	.917	.932	**36,000**
40,000	-----	-----	-----	-----	-----	-----	.866	.873	.879	.885	.898	.910	.922	**40,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

ROW HOUSES/TOWN HOUSES



GOOD CLASS D



AVERAGE CLASS D

OCCUPANCY DESCRIPTION: This occupancy pertains to buildings with more than four one-family units. The primary characteristic of this occupancy is each one family unit shares two common walls with two other units, except for the end units. Generally only the front and rear elevations have exposed exterior walls.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers, exterior balconies, built-in appliances or fireplaces. Garage or carport costs are located on the Garages – Residential cost page.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ.FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 224.00	Face brick, stone, best windows, sloping roof, tile, slate, metal	Plaster, paint, paper, paneling, fine hardwood, vinyl, carpet	Best lighting and plumbing, one bath per bedroom	Warm and cool air (zoned)
	Good	164.50	Brick, some trim or good stucco, good roof, good fenestration	Plaster or gypsum board, paint, hardwood, vinyl composition, carpet	Good lighting and plumbing, one bath per two bedrooms	Package A.C.
	Average	119.00	Brick, stucco or block, little trim, built-up roof or asphalt shingles	Gypsum board and paint, hardwood, vinyl composition, carpet	Adequate lighting and plumbing, standard fixtures	Forced air
	Fair	102.00	Block or brick, standard sash	Drywall, carpet, vinyl composition	Standard fixtures	Electric baseboard
	Low Cost	85.00	Block or cheap brick, low-cost roof and sash	Gypsum board and paint, asphalt tile, low-cost cabinets	Minimum, low cost fixtures	Wall furnace
D MASONRY VENEER	Excellent	223.00	Best brick veneer, good stone trim, heavy roof, tile, slate, metal	Plaster, paint, paper, paneling, fine hardwood, vinyl carpet	Best lighting and plumbing, one bath per bedroom	Warm and cool air (zoned)
	Good	163.50	Brick veneer, good roof, some ornamentation, good fenestration	Plaster or gypsum board, paint, hardwood, vinyl composition, carpet	Good lighting and plumbing, one bath per two bedrooms	Package A.C.
	Average	118.00	Brick veneer, built-up or asphalt shingle roof, little trim	Plaster or gypsum board, hardwood, vinyl composition, low-cost carpet	Adequate lighting and plumbing, standard fixtures	Forced air
	Fair	102.00	Brick veneer, standard sash	Drywall, carpet, vinyl composition	Standard fixtures	Electric baseboard
	Low Cost	85.00	Brick veneer, minimum roof, sash	Drywall and paint, asphalt tile	Minimum, low cost fixtures	Wall furnace
D	Excellent	213.00	Best stucco, or siding, brick or stone trim, heavy roof, tile, slate, metal	Plaster, paint, paper, paneling, fine hardwood, vinyl, carpet	Best lighting and plumbing, one bath per bedroom	Warm and cool air (zoned)
	Good	157.00	Good stucco or siding, brick trim, good roof, good fenestration	Plaster or gypsum board, paint, hardwood, vinyl composition, carpet	Good lighting and plumbing, one bath per two bedrooms	Package A.C.
	Average	113.50	Stucco or siding, little trim, built up or asphalt shingle roof	Plaster or gypsum board, hardwood, vinyl composition, carpet	Adequate lighting and plumbing, standard fixtures	Forced air
	Fair	97.50	Siding or stucco, standard sash	Drywall, carpet, vinyl composition	Standard fixtures	Electric baseboard
	Low cost	81.00	Low-cost siding, roof, sash	Drywall and paint, asphalt tile	Minimum, low cost fixtures	Wall furnace
CDS†	Finished basement	47.75	Finished interior, stairwell, partitioned walls, game room	Gypsum or acoustic tile ceiling, vinyl composition floor, carpet	Good lighting/plumbing, half bath, laundry room	None
	Semi-fin. basement	34.75	Painted, block or concrete walls	Finished ceiling, concrete slab	Adequate outlets, laundry	None
	Unfinished basement	27.00	Unfinished wall, open stairs	Unfinished ceiling, slab, storage only	Minimum lighting/drains	None

Costs given above are for end row houses and basements having one common wall. Deduct 6% for inside units (having two common walls). Costs are for two-story dwelling units. For one-story row houses, add 4%. For three-story, deduct 1%. For senior citizen complexes, add 4%.
*Basement costs are for end units with one common wall. For inside basements (having two common walls), deduct 7%.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

ROW HOUSES/TOWN HOUSES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated costs, Section SEG 2.

	LOW	AVG	GOOD	EXCL
Allowance (if not itemized)	$ 1,820	$ 4,150	$ 7,550	$ 12,800

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Multiples with basements, add 40% to extend the foundation to the basement level. Custom oversized units can run 100% to 200% more.

TYPE	COST RANGE
One-story	$ 3,675 – $ 11,800
Two-stories	4,655 – 14,170
Three-stories	5,635 – 16,540

CARPORTS: For complete listing of built-in, attached or detached garages, see Garages – Residential cost pages.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 4.51	$ 5.78	$ 7.38	$ 9.42
5,000	4.21	5.34	6.77	8.55
10,000	3.77	4.74	5.98	7.55
20,000	3.39	4.24	5.29	6.62
30,000	3.08	3.81	4.71	5.84
50,000	2.94	3.66	4.53	5.61
75,000	2.80	3.46	4.27	5.28
100,000	2.65	3.26	4.01	4.94

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 40.25	$ 51.00	$ 65.50
Steel	31.00	40.75	54.50	73.00
Wood	26.00	34.75	46.00	61.00
Add for ornate finishes, balustrades	27.25	33.75	41.50	51.00
Add for roofs or awnings	15.15	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 7.33	Package A.C. (short ductwork)	$ 14.95	Central refrigeration (zoned)	$ 13.20
Electric wall heaters	3.15	Warm and cool air (zoned)	19.00	package (short ductwork)	8.72
Forced air furnace	8.49	Hot/chilled water (zoned)	27.75	Central evaporative	5.43
Hot water, baseboard/convector	14.40	Heat pump system	16.50	Pkg. refrig.	$2,320 to $2,975 per ton capacity
radiant floor/ceiling	15.60	Ind. thru-wall heat pumps	8.94	Evap. coolers.	$298 to $ 449 per MCFM capacity
Space heaters, with fan	4.09				
radiant	4.59				
Steam (including boiler)	12.00				
without boiler	10.40	Small indiv. heat pumps cost $2,070 to $2,825		**VENTILATION ONLY**	
Wall or floor furnace	3.42	per ton of rated capacity.		Vent. (blowers/ducts)	$2.24

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.94	11	1.09
8	1.000 (base)	12	1.12
9	1.03	13	1.15
10	1.06	14	1.18

4

AVERAGE FLOOR AREA PER UNIT

Sq. Ft.	Multiplier Houses	Basements	Sq. Ft.	Multiplier Houses	Basements
600	1.103	1.230	**1,800**	0.972	0.941
700	1.084	1.185	**2,000**	0.960	0.917
800	1.067	1.147	**2,200**	0.949	0.895
900	1.053	1.114	**2,400**	0.940	0.877
1,000	1.040	1.086	**2,800**	0.923	0.845
1,100	1.029	1.061	**3,200**	0.909	0.818
1,200	1.018	1.039	**3,600**	0.897	0.795
1,400	1.000	1.000	**4,000**	0.886	0.774
1,500	0.992	0.983	**4,400**	0.877	-----
1,600	0.985	0.969	**4,800**	0.868	-----

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.