SCHOOLS - ADMINISTRATION BUILDINGS



EXCELLENT CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: These buildings are designed for the administrative office functions for a school plant or board. The interior finish may have plaster or drywall and, depending on the quality, utilize paneling and special wall covering. The better facilities will have good meeting rooms and private offices.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers, signs and office furnishings or equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 399.00	Stone, best brick, metal and glass, highly ornamental	Plaster, best paneling, vinyl wall coverings, vinyl, terrazzo, carpet	Luminous ceilings, many outlets, cabling, private restrooms	Hot and chilled water (zoned)
	Good	317.50	Face brick, stone, concrete or metal panels, solar glass	Drywall or plaster, good veneers, acoustic tile, vinyl tile, carpet	Good fluorescent, high-intensity lighting, cabling, good restrooms	Hot and chilled water (zoned)
	Average	235.50	Brick, concrete or metal panels, formed concrete	Average partitions, acoustic tile, vinyl composition, some paneled offices	Average fluorescent lighting, signal system, average restrooms	Warm and cool air (zoned)
	Low cost	188.50	Precast concrete, block, little trim, minimum-cost fenestration	Drywall, acoustic ceilings, vinyl composition tile, very plain	Minimum office lighting, cabling, security and plumbing	Warm and cool air (zoned)
A-B	Finished office basement	185.00	Plaster interior	Average office finish, acoustic tile, vinyl composition	Adequate office lighting and plumbing	Warm and cool air (zoned)
C	Excellent	342.50	Steel frame, face brick, metal panels, tile, highly ornamental	Plaster, carpet and terrazzo, suspended ceilings, paneled boardrooms	Best office lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	243.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, some paneled offices, vinyl composition, carpet	Good lighting and outlets, good tiled restrooms and signal system	Warm and cool air (zoned)
	Average	184.50	Steel frame or bearing walls, brick, block or concrete, some trim	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	Adequate lighting and outlets, plumbing and signal systems	Heat pump system
	Low cost	132.00	Masonry bearing walls, light rafters, little trim	Paint, drywall partitions, acoustic tile, vinyl composition	Minimum office lighting, cabling, security and plumbing	Package A.C.
D	Excellent	334.50	Studs or steel columns, bar or web joists, brick or stone veneer, EIFS	Plaster, carpet and terrazzo, suspended ceilings, paneled boardrooms	Best office lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	235.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, some paneled offices, vinyl composition, carpet	Good lighting and outlets, good tiled restrooms and signal system	Warm and cool air (zoned)
	Average	177.00	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	Adequate lighting and outlets, plumbing and signal systems	Heat pump system
	Low cost	125.00	Light stucco or siding on wood or steel studs, little trim	Paint, drywall partitions, acoustic tile, vinyl composition	Minimum office lighting, cabling, security and plumbing	Package A.C.
D POLE	Average	169.00	Pole frame, insulated metal panels, some ornamentation	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	Adequate lighting and outlets, plumbing and signal systems	Heat pump system
	Low cost	119.00	Pole frame, finished interior, insulation, little trim	Paint, drywall partitions, acoustic tile, vinyl composition	Minimum office lighting, cabling, security and plumbing	Package A.C.
S	Good	225.00	Good sandwich panels and fenestration, some brick or stone	Plaster or drywall, some paneled offices, vinyl composition, carpet	Good lighting and outlets, good tiled restrooms and signal system	Warm and cool air (zoned)
	Average	170.00	Pre-engineered, sandwich panels, some ornamentation	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	Adequate lighting and outlets, plumbing and signal systems	Heat pump system
	Low cost	121.00	Pre-engineered, finished interior, insulation, little trim	Paint, drywall partitions, acoustic tile, vinyl composition	Minimum office lighting, cabling, security and plumbing	Package A.C.
CDS	Finished office basement	121.50	Plaster or drywall interior	Average office finish, acoustic tile, vinyl composition	Typical office lighting and plumbing	Forced air

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.59 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - ADMINISTRATION BUILDINGS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BELL TOWERS: Large major masonry campaniles or bell towers cost $62.50 to $103.00 per cubic foot of the tower structure.

Small towers cost $15.55 to $27.50 per cubic foot of the tower structure.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	**12,000**
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	**16,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	**20,000**

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - HIGH SCHOOL (ALTERNATIVE)

OCCUPANCY DESCRIPTION: This occupancy includes the entire school facility, which includes a mixture of classrooms, multipurpose space, administrative offices, etc. The school plant may consist of one building or several separate building and encompasses grades nine or ten through twelve and are generally much smaller in scope than the normal high school with limited support, assembly or athletic facilities.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Swimming pools, movable furnishing or equipment, exterior ground improvements (i.e., athletic fields), open shelters and site work.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 272.00	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, carpet hardwood or vinyl composition	Adequate lighting and plumbing	Heat pump system
C	Excellent	322.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, carpet, vinyl, ceramic tile, wood	Best classroom lighting and cabling systems, best plumbing	Warm and cool air (zoned)
	Good	260.00	Steel frame or bearing walls, brick, block, or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition, hardwood or tile	High-level lighting, audio-visual wiring, good plumbing	Heat pump system
	Average	202.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, carpet, VCT	Adequate school lighting and plumbing	Package A.C.
D	Excellent	311.50	Steel or Glulam frame and joists, brick veneer, glass, best EIFS	Plaster or drywall, acoustic tile, carpet, vinyl, ceramic tile, wood	Best classroom lighting and cabling systems, best plumbing	Warm and cool air (zoned)
	Good	251.00	Wood frame or pipe columns, good stucco, EIFS or siding with trim	Plaster or drywall, acoustic tile, vinyl composition, hardwood or tile	Good fluorescent fixtures, good plumbing, extra features	Heat pump system
	Average	193.00	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, vinyl composition, carpet	Adequate school lighting and plumbing	Package A.C.
D POLE	Average	188.00	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, vinyl composition, carpet	Adequate school lighting and plumbing	Package A.C.
S	Good	248.50	Pre-engineered, sandwich panels, some ornamentation	Drywall, acoustic tile, carpet, vinyl composition, hardwood or tile	Good fluorescent fixtures, good plumbing, extra features	Heat pump system
	Average	189.50	Pre-engineered, finished interior, insulation, little trim	Drywall, acoustic tile, vinyl composition, carpet	Adequate school lighting and plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - HIGH SCHOOL (ALTERNATIVE)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - ARTS & CRAFTS BUILDINGS



GOOD CLASS C

OCCUPANCY DESCRIPTION: These buildings are designed primarily as work and rehearsal centers with large, open areas and large window and door openings. The best qualities include well appointed performance or concert halls for dramatic arts and music. Portions of these buildings are designated for display and storage.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers, movable equipment and furnishings.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 493.50	Fine masonry, special architecture and trim	Acoustical design, performance and practice halls, good studios	High-quality lighting and sound, good plumbing	Hot and chilled water (zoned)
	Good	380.50	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl, good music, dramatic arts	Good lighting, plumbing and sound, extra features	Hot and chilled water (zoned)
	Average	296.00	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, vinyl, hardwood, rehearsal rooms, studios	Adequate lighting and plumbing, some extra features	Hot and chilled water (zoned)
	Low cost	213.50	Brick, precast concrete, good block, some trim	Plaster or drywall, acoustic tile, VCT, crafts, limited rehearsal facility	Minimum lighting and plumbing	Warm and cool air (zoned)
A-B	Good Balcony	122.00	Not included	Stepped balcony with some ornate finishes, hardwood, carpet	Good lighting	In building cost
	Average Balcony	96.50	Not included	Stepped balcony with drywall soffit, some acoustic finishes, carpet	Adequate lighting	In building cost
	Finished Basement	142.50	Concrete masonry, partly finished interior	Masonry partitions, utility, repair, storage and dressing rooms	Adequate lighting and plumbing	Hot water
C	Excellent	381.00	Steel frame, face brick, metal panels, tile, highly ornamental	Acoustical design, performance and practice halls, good studios	High-quality lighting and sound, good plumbing	Hot and chilled water (zoned)
	Good	296.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, hardwood or vinyl, small halls	Good fluorescent fixtures, good plumbing, some extra features	Hot and chilled water (zoned)
	Average	212.50	Steel frame, brick, block, concrete, some ornamentation	Plaster or drywall, acoustic tile, vinyl comp., hardwood, rehearsal stages	Adequate lighting and plumbing	Warm and cool air (zoned)
	Low cost	165.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile, craft studios	Minimum lighting and plumbing	Heat pump system
D	Good	287.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, hardwood or vinyl, small halls	Good fluorescent fixtures and plumbing, some extra features	Hot and chilled water (zoned)
	Average	204.50	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl comp., hardwood, rehearsal stages	Adequate lighting and plumbing	Warm and cool air (zoned)
	Low cost	157.50	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, linoleum or wood floors, craft studios	Minimum lighting and plumbing	Heat pump system
D POLE	Average	194.50	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic title, vinyl comp. or hardwood, studios, rehearsal stages	Adequate lighting and plumbing	Warm and cool air (zoned)
	Low cost	148.50	Pole frame, metal panels, finished inside, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile, craft studios	Minimum lighting and plumbing	Heat pump system
S	Average	199.00	Pre-engineered, sandwich panels, some trim	Drywall, acoustic tile, vinyl comp. or hardwood, studios, rehearsal stages	Adequate lighting and plumbing	Warm and cool air (zoned)
	Low cost	152.00	Pre-engineered, finished interior, insulation	Painted walls, acoustic tile or drywall ceilings, asphalt tile, craft studios	Minimum lighting and plumbing	Heat pump system
CDS	Good Balcony	99.50	Not included	Stepped balcony with some ornate finishes, hardwood, carpet	Good lighting	In building cost
	Average Balcony	75.50	Not included	Stepped balcony with drywall soffit, some acoustic finishes, carpet	Adequate lighting	In building cost
	Finished Basement	101.00	Painted interior	Utility, workshops, storage and dressing rooms	Adequate lighting and plumbing	Forced air

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.59 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - ARTS & CRAFTS BUILDINGS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - BOOKSTORE

OCCUPANCY DESCRIPTION: These buildings are designed for retail student sales and display. They have limited sales, lounge area, storage and office commensurate with the quality.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Furnishings, signs, trade fixtures and equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$183.50	Brick, precast concrete, block, some trim	Plaster or drywall, acoustic tile, carpet or vinyl composition	Adequate lighting and plumbing	Heat pump system
	Low cost	139.50	Precast concrete, block, very plain	Plaster or drywall, acoustic tile, vinyl composition, some carpet	Adequate lighting, minimum plumbing	Package A.C.
C	Good	184.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, vinyl composition or carpet	Good fluorescent fixtures, adequate plumbing	Heat pump system
	Average	138.50	Steel frame or bearing walls, brick, block, or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition, some carpet	Adequate lighting and plumbing	Package A.C.
	Low cost	109.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum lighting and plumbing	Forced air
D	Good	178.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, adequate plumbing	Heat pump system
	Average	132.00	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition, some carpet	Adequate lighting and plumbing	Package A.C.
	Low cost	103.00	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile or drywall ceilings, asphalt tile	Minimum lighting and plumbing	Forced air
D POLE	Low cost	95.50	Pole frame, good metal panels, finished inside, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum lighting and plumbing	Forced air
S	Low cost	97.00	Pre-engineered, finished interior, insulation, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum lighting and plumbing	Forced air

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - BOOKSTORE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - CLASSROOMS

OCCUPANCY DESCRIPTION: These buildings are subdivided into teaching units and designed primarily for academic work. Typically, the better qualities include more windows and better interior and exterior refinements.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers, movable equipment and furnishings.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 378.00	Stone, best brick, metal and glass, highly ornamental	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	311.00	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl	Good fluorescent fixtures, good plumbing, extra features	Hot and chilled water (zoned)
	Average	237.00	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or carpet	Adequate lighting and plumbing, some extra features	Warm and cool air (zoned)
	Low cost	181.50	Brick, precast concrete, block, very plain	Low-cost finishes, acoustic tile, hardwood or vinyl composition	Minimum school lighting and plumbing, few extras	Package A.C.
C	Excellent	303.50	Steel frame, face brick, metal panels, tile, highly ornamental	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	231.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, hardwood or carpet	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	178.00	Steel frame or bearing walls, brick, block or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Package A.C.
	Low cost	143.50	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Forced air
	Cheap	99.00	Cheap block, tilt-up, light roof	Low-cost finishes, no partitions, asphalt tile	Minimum code	Wall furnace
D	Excellent	294.50	Steel or wood frame, brick or stone veneer, metal and glass, ornamental	Plaster, enamel, glazed or vinyl finishes, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	223.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, hardwood or carpet	Good fluorescent fixtures and plumbing, extra features	Warm and cool air (zoned)
	Average	170.50	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Package A.C.
	Low cost	136.00	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, linoleum or wood floors	Minimum school lighting and plumbing	Forced air
	Cheap	92.50	Low-cost stucco or siding	Low-cost finishes, no partitions, asphalt tile	Minimum code	Wall furnace
D POLE	Good	217.00	Pole frame, good insulated panels, some brick or stone trim	Drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures and plumbing, extra features	Warm and cool air (zoned)
	Average	165.00	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, vinyl composition	Adequate lighting and plumbing	Package A.C.
	Low cost	130.50	Pole frame, good metal panels, finished inside, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Forced air
	Cheap	87.50	Pole frame, metal siding	Low-cost finishes, no partitions, acoustic tile, asphalt tile	Minimum code	Wall furnace
S	Good	219.50	Pre-engineered, good sandwich panels, some brick or stone trim	Drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures and plumbing, extra features	Warm and cool air (zoned)
	Average	166.00	Pre-engineered, sandwich panels, some trim	Drywall, acoustic tile, vinyl composition	Adequate lighting and plumbing	Package A.C.
	Low cost	131.50	Pre-engineered, finished interior, insulation	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Forced air
	Cheap	88.50	Light steel frame, siding	Low-cost finishes, no partitions, acoustic tile, asphalt tile	Minimum code	Wall furnace

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - CLASSROOMS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - CLASSROOMS - LABORATORY

OCCUPANCY DESCRIPTION: These laboratory classroom buildings include areas for lectures, demonstrations, audiovisual presentations, laboratory work and study. Typically, there is also an area designated for storage of materials and equipment. The laboratories have both AC and DC variable voltage and plumbing in the work areas.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers and lab equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 348.50	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, good workstations, lecture, support rooms	Good fluorescent fixtures, good lab plumbing, extra features	Hot and chilled water (zoned)
	Average	259.00	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, workstations, good demonstration areas	Adequate lighting and plumbing, some extras	Warm and cool air (zoned)
C	Excellent	320.00	Steel frame, face brick or block, tile, ornamental	Plaster or drywall, acoustic tile, good workstations, lecture, support rooms	Good lighting and plumbing, piped gases, air and pure water	Warm and cool air (zoned)
	Good	254.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, good workstations, lecture area	Good fluorescent fixtures, good lab plumbing, extra features	Warm and cool air (zoned)
	Average	190.00	Steel frame or bearing walls, brick, block or concrete, some trim	Plaster or drywall, acoustic tile, VCT, adequate work, demonstration areas	Adequate lighting and plumbing	Package A.C.
D	Excellent	312.00	Steel or wood frame, brick or stone veneer, metal and glass	Plaster or drywall, acoustic tile, good workstations, lecture, support rooms	Good lighting and plumbing, piped gases, air and pure water	Warm and cool air (zoned)
	Good	246.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, good workstations, lecture area	Good fluorescent fixtures, good lab plumbing, extra features	Warm and cool air (zoned)
	Average	182.50	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, VCT, adequate work, demonstration areas	Adequate lighting and plumbing	Package A.C.
D POLE	Average	177.00	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, vinyl comp., adequate work, demonstration areas	Adequate lighting and plumbing	Package A.C.
S	Good	242.50	Pre-engineered, good sandwich panels, some brick or stone	Drywall, acoustic tile, good workstations, lecture area	Good fluorescent fixtures, good lab plumbing, extra features	Warm and cool air (zoned)
	Average	178.00	Pre-engineered, sandwich panels, some trim	Drywall, acoustic tile, vinyl comp., adequate work, demonstration areas	Adequate lighting and plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - CLASSROOMS - LABORATORY

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - CLASSROOM - LECTURE

OCCUPANCY DESCRIPTION: These lecture classroom buildings are designed for a large number of students and appear to be very similar to a small auditorium. Offices and some small classrooms can also be found. Projection areas are usually a common design feature in large classrooms.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. All fixed seats, built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers movable equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 261.00	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood, stepped floor, fixed seats	Adequate lighting and plumbing, good audio-visual wiring	Warm and cool air (zoned)
C	Good	270.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, hardwood or carpet, stepped floor	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	194.50	Steel frame or bearing walls, brick, block, or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood, fixed seats	Adequate lighting and plumbing, audio-visual wiring	Package A.C.
D	Good	239.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, hardwood or carpet, stepped floor	Good fluorescent fixtures and plumbing, extra features	Warm and cool air (zoned)
	Average	178.00	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood, fixed seats	Adequate lighting and plumbing, audio-visual wiring	Package A.C.
S	Average	173.50	Pre-engineered, sandwich panels, some trim	Drywall, acoustic tile, vinyl composition, fixed seats	Adequate lighting and plumbing, audio-visual wiring	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - CLASSROOMS - LECTURE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - CLASSROOMS - SPECIAL EDUCATION

OCCUPANCY DESCRIPTION: These buildings are subdivided into teaching units and designed primarily for academic work for students with special needs including the exceptional child, as well as the physically challenged child. Typically, the better qualities include more windows, and better interior and exterior refinements. Floor finishes vary between carpet, hardwood and resilient floor coverings. Higher cost classrooms have carpet or hardwood. Acoustical tile ceiling finishes are found throughout all of the quality ranges. Lighting is commonly fluorescent fixtures.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built in bookshelves, cabinets and blackboards and plumbing associated with special needs.

NOT INCLUDED IN COSTS: Elevators, sprinklers, movable equipment and furnishings.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 344.00	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl, best cabinets	Good fluorescent fixtures, good plumbing, extra features	Hot and chilled water (zoned)
	Average	255.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or carpet, good built-ins	Adequate lighting and plumbing, some extra features	Warm and cool air (zoned)
C	Excellent	336.00	Steel frame, face brick, metal panels, tile	Plaster, glazed finishes, enamel, carpet & vinyl, best cabinets, closets	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	251.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster/drywall, acoustic tile, vinyl comp./carpet, good cabinets, storage	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	188.00	Steel frame or bearing walls, brick, block or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood, some extras	Adequate lighting and plumbing	Package A.C.
D	Excellent	327.00	Steel or wood frame, brick or stone veneer, metal and glass	Plaster, enamel, vinyl finishes, carpet and vinyl, best cabinets, closets	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	242.50	Steel or Glulam frame and joists, brick veneer, glass, best EIFS	Plaster/drywall, acoustic tile, vinyl comp./carpet, good cabinets, storage	Good fluorescent fixtures and plumbing, extra features	Warm and cool air (zoned)
	Average	180.00	Wood frame or pipe columns, good stucco, EIFS or siding with trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood, some extras	Adequate lighting and plumbing	Package A.C.
D POLE	Good	237.50	Pole frame, good insulated panels, some brick or stone trim	Drywall, acoustic tile, carpet, vinyl composition, good cabinets, storage	Good fluorescent fixtures and plumbing, extra features	Warm and cool air (zoned)
	Average	174.50	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, vinyl composition, some extras	Adequate lighting and plumbing	Package A.C.
S	Good	239.00	Pre-engineered, good sandwich panels, some brick or stone trim	Drywall, acoustic tile, carpet, vinyl composition, good cabinets, storage	Good fluorescent fixtures and plumbing, extra features	Warm and cool air (zoned)
	Average	176.00	Pre-engineered, sandwich panels, some trim	Drywall, acoustic tile, vinyl composition, some extras	Adequate lighting and plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - CLASSROOMS - SPECIAL EDUCATION

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - COLLEGE



GOOD/EXCELLENT CLASS C

OCCUPANCY DESCRIPTION: This occupancy includes the complete school facility with a mixture of classrooms, multipurpose buildings, administrative offices, etc. The schools may consist of one building or several separate buildings. This occupancy applies to colleges with all departments in one building.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Swimming pools, movable furnishings or equipment, exterior ground improvements (i.e., athletic fields), open shelters and site work.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$ 525.50	Stone, best brick, metal and glass, high ornamentation	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	415.50	Face brick, stone, concrete or metal panels, solar glass, ornamental	Plaster or drywall, acoustic tile, carpet and vinyl	High-level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Average	331.00	Brick, concrete or metal panels, formed concrete, good trim	Plaster or drywall, acoustic tile, hardwood or vinyl composition	Adequate lighting and plumbing	Hot and chilled water (zoned)
	Low cost	246.00	Brick, precast concrete, block, some trim	Plaster or drywall, acoustic tile, hardwood or vinyl composition	Minimum school lighting and plumbing	Warm and cool air (zoned)
B	Excellent	472.50	Stone, best brick, metal and glass, high ornamentation	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	375.50	Face brick, stone, concrete or metal panels, solar glass, ornamental	Plaster or drywall, acoustic tile, carpet and vinyl	High-level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Average	302.50	Brick, concrete or metal panels, formed concrete, good trim	Plaster or drywall, acoustic tile, hardwood or vinyl composition	Adequate lighting and plumbing	Hot and chilled water (zoned)
	Low cost	225.00	Brick, precast concrete, block, some trim	Plaster or drywall, acoustic tile, hardwood or vinyl composition	Minimum school lighting and plumbing	Warm and cool air (zoned)
C	Excellent	387.50	Steel frame, face brick, metal panels, tile, highly ornamental	Plaster, glazed finishes, enamel carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	308.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Hot and chilled water (zoned)
	Average	227.50	Steel frame or bearing walls, brick, block, or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Warm and cool air (zoned)
	Low cost	180.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Heat pump system
D	Excellent	377.50	Steel or wood frame, brick or stone veneer, metal and glass, ornamental	Plaster, enamel, glazed or vinyl finishes, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	278.50	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	216.50	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	161.00	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, linoleum or wood floor	Minimum school lighting and plumbing	Package A.C.
DPOLE	Average	210.50	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	155.00	Pole frame, finished interior, insulation, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Package A.C.
S	Good	272.50	Pre-engineered, good sandwich panels, some brick or stone trim	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	212.00	Pre-engineered, sandwich panels, some ornamentation	Drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	156.50	Pre-engineered, finished interior, insulation, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - COLLEGE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BELL TOWERS: Large major masonry campaniles or bell towers cost $62.50 to $103.00 per cubic foot of the tower structure.
Small towers cost $15.55 to $27.50 per cubic foot of the tower structure.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	**12,000**
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	**16,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	**20,000**

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - COLLEGE CLASSROOMS

OCCUPANCY DESCRIPTION: These buildings are subdivided into teaching units and designed primarily for academic work. Typically, the better qualities include more windows and better interior and exterior refinements.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers, movable equipment and furnishings.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$ 456.00	Stone, best brick, metal and glass, high ornamentation	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	368.00	Face brick, stone, concrete or metal panels, solar glass, ornamental	Plaster or drywall, acoustic tile, carpet and vinyl	Good fluorescent fixtures, good plumbing, extra features	Hot and chilled water (zoned)
	Average	299.00	Brick, concrete or metal panels, formed concrete, good trim	Plaster or drywall, acoustic tile, hardwood or vinyl composition	Adequate lighting and plumbing	Hot and chilled water (zoned)
	Low cost	225.00	Brick, precast concrete, block, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Minimum school lighting and plumbing	Warm and cool air (zoned)
B	Excellent	405.00	Stone, best brick, metal and glass, high ornamentation	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	331.50	Face brick, stone, concrete or metal panels, solar glass, ornamental	Plaster or drywall, acoustic tile, carpet and vinyl	Good fluorescent fixtures, good plumbing, extra features	Hot and chilled water (zoned)
	Average	272.50	Brick, concrete or metal panels, formed concrete, good trim	Plaster or drywall, acoustic tile, hardwood or vinyl composition	Adequate lighting and plumbing	Hot and chilled water (zoned)
	Low cost	206.50	Brick, precast concrete, block, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Minimum school lighting and plumbing	Warm and cool air (zoned)
C	Excellent	339.00	Steel frame, face brick, metal panels, tile, highly ornamental	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	278.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Hot and chilled water (zoned)
	Average	209.50	Steel frame or bearing walls, brick, block, or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Warm and cool air (zoned)
	Low cost	158.50	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Package A.C.
D	Excellent	330.50	Steel or wood frame, brick or stone veneer, metal and glass, ornamental	Plaster, enamel, glazed or vinyl finishes, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	249.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	200.50	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	152.00	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, linoleum or wood floors	Minimum school lighting and plumbing	Package A.C.
D POLE	Average	193.50	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	146.50	Pole frame, finished interior, insulation, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Package A.C.
S	Good	244.50	Pre-engineered, good sandwich panels, some brick or stone trim	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures and plumbing, extra features	Warm and cool air (zoned)
	Average	196.00	Pre-engineered, sandwich panels, some ornamentation	Drywall, acoustic tile, vinyl composition	Adequate lighting and plumbing	Heat pump system
	Low cost	147.50	Pre-engineered, finished interior, insulation, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - COLLEGE CLASSROOMS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BELL TOWERS: Large major masonry campaniles or bell towers cost $62.50 to $103.00 per cubic foot of the tower structure.
Small towers cost $15.55 to $27.50 per cubic foot of the tower structure.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - COMMONS

OCCUPANCY DESCRIPTION: A "commons" has a variety of uses. Although each "commons" varies depending on the number of students and the space available, there are some similar elements found in these occupancies: Administrative areas, food areas, study/quiet areas and hobby/game areas.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers, kitchen or recreational equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 452.50	Stone, best brick, metal and glass, good ornamentation	Plaster, glazed finishes, pavers, carpet, varied recreation	Best lighting, plumbing, food services and audio	Hot and chilled water (zoned)
	Good	370.00	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, carpet and vinyl, varied activity center	Good fluorescent fixtures, good plumbing and kitchens	Hot and chilled water (zoned)
	Average	304.00	Brick, precast concrete, block, some trim	Plaster or drywall, acoustic tile, hardwood or vinyl composition	Adequate lighting, plumbing and kitchen	Hot and chilled water (zoned)
A-B	Finished Basement	202.00	Reinforced concrete, plaster interior	Recreation, food service finishes, some utility and storage	Adequate lighting and plumbing	Warm and cool air (zoned)
C	Excellent	398.50	Steel frame, stone, brick, metal and glass, good ornamentation	Plaster, glazed finishes, pavers, carpet, varied recreation	Best lighting, plumbing, food services and audio	Hot and chilled water (zoned)
	Good	318.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, carpet and vinyl, good activity center	Good fluorescent fixtures, good plumbing and kitchens	Hot and chilled water (zoned)
	Average	235.00	Steel frame or bearing walls, brick, block or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting, plumbing and kitchen and snack bars	Warm and cool air (zoned)
	Low cost	186.50	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile, small game rooms	Minimum lighting and plumbing, few extras	Heat pump system
D	Good	308.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, carpet and vinyl, good activity center	Good fluorescent fixtures, good plumbing and kitchens	Hot and chilled water (zoned)
	Average	227.50	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting, plumbing and kitchen and snack bars	Warm and cool air (zoned)
	Low cost	179.00	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, linoleum or wood floors	Minimum lighting and plumbing, few extras	Heat pump system
D POLE	Low cost	174.50	Pole frame, good metal panels, finished inside, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile, small game rooms	Minimum lighting and plumbing, few extras	Heat pump system
S	Low cost	175.50	Pre-engineered, finished interior, insulation, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile, small game rooms	Minimum lighting and plumbing, few extras	Heat pump system
CDS	Finished Basement	139.50	Reinforced concrete, plaster or drywall interior	Recreation, food service finishes, some utility and storage	Adequate lighting and plumbing	Forced air

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.59 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - COMMONS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BELL TOWERS: Large major masonry campaniles or bell towers cost $62.50 to $103.00 per cubic foot of the tower structure.
Small towers cost $15.55 to $27.50 per cubic foot of the tower structure.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - ELEMENTARY SCHOOLS



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: This occupancy includes the entire school facility serving kindergarten through fifth or sixth grade.

There is a mixture of classrooms, multipurpose buildings, administrative offices, etc. The schools may consist of one building or several separate buildings.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Swimming pools, movable furnishings or equipment, exterior ground improvements (i.e., athletic fields), open shelters and site work.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 412.00	Stone, best brick, metal and glass, highly ornamental	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	323.50	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl	High level lighting, audio-visual wiring, good plumbing	Warm and cool air (zoned)
	Average	268.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or vinyl composition	Adequate lighting and plumbing	Warm and cool air (zoned)
A-B	Finished classroom Basement	191.00	Reinforced concrete, plaster interior	Classrooms, school finishes, some utility and storage	Adequate lighting and plumbing	Warm and cool air (zoned)
	Parking Basement	91.00	Unfinished interior	Concrete with hardener, lines and stops	Exposed lighting, drains	Ventilation
	Unfinished Basement	79.00	Unfinished interior	Unfinished storage and utility	Minimum lighting, drains	None
C	Excellent	344.50	Steel frame, face brick, metal panels, tile	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	265.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	205.00	Steel frame or bearing walls, brick, block, or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Package A.C.
	Low cost	165.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Forced Air
D	Excellent	333.50	Steel or wood frame, brick or stone veneer, metal and glass, ornamental	Plaster, enamel, glazed or vinyl finishes, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	255.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	196.00	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Package A.C.
	Low cost	157.50	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, linoleum or wood floors	Minimum school lighting and plumbing	Forced Air
D POLE	Average	190.00	Pole frame, good metal panels, finished inside, some trim	Drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Package A.C.
	Low cost	151.50	Pole frame, metal siding, finished interior, insulated, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Forced Air
S	Good	252.50	Pre-engineered, good sandwich panels, some brick or stone trim	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	192.50	Pre-engineered, sandwich panels, some ornamentation	Drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Package A.C.
	Low cost	153.00	Pre-engineered, finished interior, insulation, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Forced Air
CDS	Finished classroom Basement	129.50	Reinforced concrete, plaster or drywall interior	Classrooms, school finishes, some utility and storage	Adequate lighting and plumbing	Forced Air
	Parking Basement	59.50	Unfinished interior	Finished ceiling, concrete floor with hardener	Exposed lighting, adequate drains	Ventilation
	Unfinished Basement	48.25	Unfinished interior	Unfinished storage and utility	Minimum lighting, drains	None

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.59 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - ELEMENTARY SCHOOLS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - FINE ARTS BUILDING



GOOD CLASS B

OCCUPANCY DESCRIPTION: These fine arts buildings are designed primarily as rehearsal and work centers with large, open areas and large window and door openings. Floor finishes vary depending on the specific use of a given area. For example, vinyl composition tile is commonly found in the general band or fine art area, while hardened concrete flooring can be found in some craft areas.

Portions of these buildings are designated for display and storage. Extensive electrical outlets, lighting and plumbing are typically found.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers, furnishings or movable equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 360.50	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl, good music, dramatic arts	Good fluorescent fixtures, good plumbing, extra features	Hot and chilled water (zoned)
	Average	263.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, vinyl, hardwood, craft, rehearsal studios	Adequate lighting and plumbing	Warm and cool air (zoned)
C	Excellent	357.00	Steel frame, face brick or block, tile, ornamental	Plaster or drywall, acoustic tile, carpet and vinyl, good music, dramatic arts	Good fluorescent fixtures, good plumbing, extra features	Hot and chilled water (zoned)
	Good	261.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, hardwood or vinyl, small studios	Good fluorescent fixtures, good plumbing	Warm and cool air (zoned)
	Average	204.00	Steel frame, brick, block, concrete, some ornamentation	Plaster or drywall, acoustic tile, vinyl comp., hardwood, rehearsal stage	Adequate lighting and plumbing	Heat pump system
	Low cost	150.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile, craft centers	Minimum school lighting and plumbing	Package A.C.
D	Good	252.50	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, hardwood or vinyl, small studios	Good fluorescent fixtures, good plumbing	Warm and cool air (zoned)
	Average	194.00	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl comp., hardwood, rehearsal stage	Adequate lighting and plumbing	Heat pump system
	Low cost	141.50	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, linoleum or wood, craft centers	Minimum school lighting and plumbing	Package A.C.
D POLE	Average	189.50	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, vinyl comp. or hardwood, rehearsal stage	Adequate lighting and plumbing	Heat pump system
	Low cost	137.00	Pole frame, metal panels, finished inside, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile, craft centers	Minimum school lighting and plumbing	Package A.C.
S	Good	250.00	Pre-engineered, good sandwich panels, some brick or stone trim	Plaster or drywall, acoustic tile, hardwood or vinyl, small studios	Good fluorescent fixtures, good plumbing	Warm and cool air (zoned)
	Average	192.00	Pre-engineered, sandwich panels, some trim	Drywall, acoustic tile, vinyl comp. or hardwood, rehearsal stage	Adequate lighting and plumbing	Heat pump system
	Low cost	139.50	Pre-engineered, finished interior, insulation	Painted walls, acoustic tile or drywall ceilings, asphalt tile, craft centers	Minimum school lighting and plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - FINE ARTS BUILDING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - GYMNASIUM

OCCUPANCY DESCRIPTION: These buildings are usually designed with the basketball court as the focal point. There is usually an entry area or lobby, and there may be a storefront and large openings in the entry area. The building itself is subdivided and includes locker/shower room facilities, some small administrative offices and miscellaneous rooms for storage and/or meetings. They can also serve as a number of teaching stations utilizing the spectator seating in the basketball court area.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, lockers, equipment and seating.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 307.00	Heavy frame, best masonry walls, solar glass, good entrance and lobby	Basketball floor, high-cost finishes, many extra facilities	Good lighting and outlets, good plumbing, extra features	Heat pump system
	Average	229.50	Steel columns and girders, face brick, glass, best ornamental block	Plaster or drywall, basketball floor, vinyl, good detail	Good lighting and outlets, tiled showers and restrooms	Heat pump system
A-B	Finished classroom mezzanine	124.00	Not included	Classroom and office, typical school finishes	Adequate school lighting and plumbing	In bldg. cost
	Good open mezzanine	67.50	Not included	Finished running track, plaster or drywall soffit	Average lighting, no plumbing	In bldg. cost
	Average open mezzanine	49.75	Not included	Finished floors and soffit, add for spectator seating	Average lighting, no plumbing	In bldg. cost
C	Excellent	300.00	Heavy frame, best masonry walls, good entrance and lobby	Basketball floor, high-cost finishes, many extra facilities	Good lighting and outlets, good plumbing, extra features	Heat pump system
	Good	225.00	Steel columns and girders, face brick, best ornamental block	Plaster or drywall, basketball floor, vinyl, good detail	Good lighting and outlets, tiled showers and restrooms	Heat pump system
	Average	159.00	Steel or Glulam, trusses or girders, brick, block or tilt-up	Basketball floor, showers, vinyl composition, some interior finish	Adequate lighting and plumbing, shower rooms	Package A.C.
	Low cost	103.50	Light frame, block or tilt-up, very plain	Concrete floor, some vinyl composition, minimal finish	Minimum gym lighting, plumbing and shower facilities	Space heaters
D	Excellent	289.00	Heavy frame, masonry veneer walls, good entrance and lobby	Basketball floor, high-cost finishes, many extra facilities	Good lighting and outlets, good plumbing, extra features	Heat pump system
	Good	215.00	Steel or Glulam frame, trusses and girders, brick veneer, best stucco	Plaster or drywall, basketball floor, vinyl, good detail	Good lighting and outlets, tiled showers and restrooms	Heat pump system
	Average	150.50	Heavy frame, trusses or girders, good stucco or siding, little trim	Plaster or drywall, basketball floor, asphalt tile, few partitions	Adequate lighting and plumbing, shower rooms	Package A.C.
	Low cost	96.50	Light frame, stucco or siding, very plain	Concrete floor, some vinyl composition, minimal finish	Minimum gym lighting, plumbing and shower facilities	Space heaters
D POLE	Average	143.00	Pole frame, good metal panels, finished inside, little trim	Basketball floor, showers, vinyl composition, some interior finish	Adequate lighting and plumbing, shower rooms	Package A.C.
	Low cost	91.50	Pole frame, metal siding, finished interior, insulated	Concrete floor, vinyl composition, minimal finish	Minimum gym lighting, plumbing and shower facilities	Space heaters
	Cheap	77.00	Pole frame, metal siding, partly finished interior, some insulation	Concrete floor, some vinyl composition, minimal finish	Minimum gym lighting and plumbing	Space heaters
S	Good	213.00	Pre-engineered, good sandwich panels, some brick or stone trim	Plaster or drywall, basketball floor, vinyl, good detail	Good lighting and outlets, tiled showers and restrooms	Heat pump system
	Average	147.00	Pre-engineered, finished interior, insulation, little trim	Basketball floor, showers, vinyl composition, some interior finish	Adequate lighting and plumbing, shower rooms	Package A.C.
	Low cost	93.00	Pre-engineered, finished interior, insulated	Concrete floor, vinyl composition, minimal finish	Minimum gym lighting, plumbing and shower facilities	Space heaters
	Cheap	78.00	Pre-engineered, partly finished interior, some insulation	Concrete floor, some vinyl composition, minimal finish	Minimum gym lighting and plumbing	Space heaters
CDS	Finished classroom mezzanine	92.50	Not included	Finished running track, plaster or drywall soffit	Average lighting, no plumbing	In bldg. cost
	Good open mezzanine	53.00	Not included	Finished floors and soffit, add for spectator seating	Average lighting, no plumbing	In bldg. cost
	Average open mezzanine	35.75	Not included	Classroom and office, typical school finishes	Adequate school lighting and plumbing	In bldg. cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.59 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - GYMNASIUM

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055	20	1.183
9	.981	14	1.073	22	1.220
10	1.000 (base)	15	1.092	24	1.257
11	1.018	16	1.110	30	1.367
12	1.037	18	1.147	36	1.476

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	**12,000**
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	**16,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	**20,000**

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - HIGH SCHOOL



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: This occupancy includes the entire school facility, which includes a mixture of classrooms, multipurpose building, administrative offices, etc. The school may consist of one building or several separate buildings, and encompasses grades nine or ten through twelve.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Swimming pools, movable furnishing or equipment, exterior ground improvements (i.e., athletic fields), open shelters and site work.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$ 432.50	Stone, best brick, metal and glass, highly ornamental	Plaster, glazed finishes, enamel, carpet and vinyl	*Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	357.50	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl	*High level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Average	276.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or vinyl composition	*Adequate lighting and plumbing	Warm and cool air (zoned)
B	Excellent	390.50	Stone, best brick, metal and glass, highly ornamental	Plaster, glazed finishes, enamel, carpet and vinyl	*Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	324.50	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl	*High level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Average	252.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or vinyl composition	*Adequate lighting and plumbing	Warm and cool air (zoned)
C	Excellent	322.50	Steel frame, face brick, metal panels, tile, highly ornamental	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	251.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	208.00	Steel frame or bearing walls, brick, block, or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	164.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Package A.C.
D	Excellent	314.50	Steel or wood frame, brick or stone veneer, metal and glass, ornamental	Plaster, enamel, glazed or vinyl finishes, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	242.50	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	200.50	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	155.50	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, linoleum or wood floors	Minimum school lighting and plumbing	Package A.C.
D POLE	Average	194.50	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	150.50	Pole frame, finished interior, insulation, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Package A.C.
S	Good	239.00	Pre-engineered, good sandwich panels, some brick or stone trim	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	196.00	Pre-engineered, sandwich panels, some ornamentation	Drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	152.00	Pre-engineered, finished interior, insulation, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - HIGH SCHOOL

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Excellent	$ 5.18
Good	3.11
Average	2.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	**12,000**
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	**16,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	**20,000**

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - LECTURE HALL BUILDING



GOOD CLASS B

OCCUPANCY DESCRIPTION: These buildings are used as classrooms for a large number of students and appear to be very similar to a small auditorium. Offices and some small classrooms can also be found. Projection areas are usually a common design feature in large classrooms.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers, movable equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 467.50	Steel frame, face brick, metal panels, tile, highly ornamental	Plaster or drywall, acoustic tile, carpet, studios, main hall or auditorium	Best lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Good	375.00	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl, main hall, fixed seating	Good lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Average	303.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, VCT, hardwood, small studios or hall	Adequate lighting and plumbing, good audio-visual wiring	Hot and chilled water (zoned)
A-B	Balcony	107.00	Not included	Stepped balcony with plaster soffit, fixed seating	Adequate lighting	In building cost
C	Excellent	378.00	Steel frame, face brick, metal panels, tile, ornamental	Plaster or drywall, acoustic tile, carpet, studios, main hall or auditorium	Best lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Good	300.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, carpet, hardwood, main hall, fixed seating	Good fluorescent fixtures, good plumbing, extra features	Hot and chilled water (zoned)
	Average	221.00	Steel frame or bearing walls, brick, block, or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition, small studios, fixed seats	Adequate lighting and plumbing, audio-visual wiring	Warm and cool air (zoned)
D	Good	285.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, carpet, hardwood, main hall, fixed seats	Good fluorescent fixtures, good plumbing, extra features	Hot and chilled water (zoned)
	Average	210.00	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition, small studios, fixed seats	Adequate lighting and plumbing, audio-visual wiring	Warm and cool air (zoned)
S	Average	204.50	Pre-engineered, sandwich panels, some trim	Drywall, acoustic tile, vinyl composition, small studios or hall, fixed seats	Adequate lighting and plumbing, audio-visual wiring	Warm and cool air (zoned)
CDS	Balcony	87.00	Not included	Stepped balcony with drywall soffit, fixed seating	Adequate lighting	In building cost

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - LECTURE HALL BUILDING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055	20	1.183
9	.981	14	1.073	22	1.220
10	1.000 (base)	15	1.092	24	1.257
11	1.018	16	1.110	30	1.367
12	1.037	18	1.147	36	1.476

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	**12,000**
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	**16,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	**20,000**

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - MANUAL ARTS (SHOP) BUILDING

OCCUPANCY DESCRIPTION: These are buildings with large rooms used primarily for specialized education and vocational training. They are built of masonry, wood frame or pre-engineered steel. The walls are painted with some drywall and acoustic tile ceilings. Good lighting and many outlets can be found.

The buildings, when divided, have some classroom/lecture station and work areas. Cost includes all necessary components. The overall division of the building separates the various training specialties that may include wood working, graphic arts, electrical, metal, machine and automotive.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers, furnishings and movable equipment power wiring or equipment that may be found.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 214.50	Brick, precast concrete, block, some trim	Plaster or drywall, acoustic tile, good slab, hardwood or vinyl composition	Good lighting and outlets, good plumbing	Package A.C.
	Low cost	163.50	Precast concrete, block, very plain	Painted walls, acoustic tile or exposed ceilings, some asphalt tile	Adequate lighting, many outlets, adequate plumbing	Forced air
C	Good	213.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, vinyl composition, carpet, good slab	Good fluorescent fixtures and outlets, good plumbing	Package A.C.
	Average	162.50	Steel frame or bearing walls, brick block, concrete panels, some trim	Painted walls, acoustic tile or drywall ceilings, some asphalt tile	Good lighting, many outlets, adequate plumbing	Forced air
	Low cost	112.50	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, some ceiling and floor finish, sealed concrete	Adequate lighting and outlets, minimum plumbing	Space heaters
D	Good	203.50	Steel or Glulam frame and joists, brick veneer, best stucco	Plaster or drywall, acoustic tile, vinyl composition, carpet, good slab	Good fluorescent fixtures and outlets, good plumbing	Package A.C.
	Average	154.00	Wood frame or pipe columns, good stucco or siding with some trim	Plaster, acoustic tile or drywall ceiling, some asphalt tile	Good lighting, many outlets, adequate plumbing	Forced air
	Low cost	104.50	Wood frame, stucco or siding, very plain, industrial sash	Drywall, acoustic tile, some floor finish, sealed slab	Adequate lighting and outlets, minimum plumbing	Space heaters
D POLE	Average	135.50	Pole frame, metal siding, some interior finish and insulation	Painted walls, acoustic tile or drywall ceiling, some asphalt tile	Good lighting, many outlets, adequate plumbing	Forced air
	Low cost	90.00	Pole frame, metal siding, primarily exposed	Painted walls, some ceiling and floor finish, sealed concrete	Adequate lighting and outlets, minimum plumbing	Space heaters
S	Average	136.50	Pre-engineered, partly finished interior, some insulation	Painted walls, acoustic tile or drywall ceiling, some asphalt tile	Good lighting, many outlets, adequate plumbing	Forced air
	Low cost	92.00	Pre-engineered, light frame, primarily exposed	Painted walls, some ceiling and floor finish, sealed concrete	Adequate lighting and outlets, minimum plumbing	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - MANUAL ARTS (SHOP) BUILDING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - MIDDLE (JUNIOR HIGH) SCHOOL



GOOD CLASS C

OCCUPANCY DESCRIPTION: This occupancy includes the entire school facility covering sixth or seventh grade through eighth or ninth grade. There is a mixture of classrooms, multipurpose buildings, administrative offices, etc. The school may consist of one building or several separate buildings.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Swimming pools, movable furnishings or equipment, exterior ground improvements (i.e., athletic fields), open shelters and site work.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$ 404.00	Stone, best brick, metal and glass, highly ornamental	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	338.00	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl	High level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Average	264.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or vinyl composition	Adequate lighting and plumbing	Warm and cool air (zoned)
B	Excellent	364.50	Stone, best brick, metal and glass, highly ornamental	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	308.00	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl	High level lighting, audio-visual wiring, good plumbing	Hot and chilled water (zoned)
	Average	240.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or vinyl composition	Adequate lighting and plumbing	Warm and cool air (zoned)
C	Excellent	306.00	Steel frame, face brick, metal panels, tile, highly ornamental	Plaster, glazed finishes, enamel, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	241.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	202.50	Steel frame or bearing walls, brick, block, or concrete, some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	161.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Package A.C.
D	Excellent	296.00	Steel or wood frame, brick or stone veneer, metal and glass, ornamental	Plaster, enamel, glazed or vinyl finishes, carpet and vinyl	Best classroom lighting and cabling systems, best plumbing	Hot and chilled water (zoned)
	Good	231.50	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	194.00	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	153.00	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile, linoleum or wood floors	Minimum school lighting and plumbing	Package A.C.
D POLE	Average	189.00	Pole frame, good metal panels, finished inside, little trim	Drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	148.50	Pole frame, metal siding	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Package A.C.
S	Good	230.00	Pre-engineered, good sandwich panels, some brick or stone trim	Plaster or drywall, acoustic tile, carpet, vinyl composition	Good fluorescent fixtures, good plumbing, extra features	Warm and cool air (zoned)
	Average	191.50	Pre-engineered, sandwich panels, some ornamentation	Drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting and plumbing	Heat pump system
	Low cost	149.50	Pre-engineered, finished interior, insulation, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - MIDDLE (JUNIOR HIGH) SCHOOL

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - MULTIPURPOSE BUILDING

OCCUPANCY DESCRIPTION: These buildings are designed for large audience and participation groups. They may include combinations of uses within the same building, i.e., gymnasium and auditorium or cafeteria, plus offices and other rooms. They can be designed to accommodate two or more group activities at the same time with the better qualities having a small stage.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, fixed seating and cafeteria or kitchen equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 330.50	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl, stage, some extras	Good fluorescent fixtures, good plumbing, kitchen	Warm and cool air (zoned)
	Average	253.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, hardwood or vinyl, small stage	Adequate lighting and plumbing, some extras	Heat pump system
C	Excellent	326.00	Steel frame, best masonry walls, highly ornamental	Plaster, acoustic tile, good wood floor, stage, good detail	Good lighting and plumbing, kitchen, tiled surfaces	Warm and cool air (zoned)
	Good	239.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, hardwood or vinyl, stage	Good fluorescent fixtures, good plumbing, kitchen	Package A.C.
	Average	182.00	Steel frame, brick, block, concrete, some ornamentation	Plaster or drywall, acoustic tile, vinyl composition, hardwood, small stage	Adequate lighting and plumbing, some extras	Forced air
	Low cost	126.50	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Wall furnace
D	Good	232.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, hardwood or vinyl, stage	Good fluorescent fixtures, good plumbing, kitchen	Package A.C.
	Average	174.50	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood, small stage	Adequate lighting and plumbing, some extras	Forced air
	Low cost	120.00	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, asphalt tile linoleum or wood floors	Minimum school lighting and plumbing	Wall furnace
D POLE	Average	169.00	Pole frame, insulated metal panels, some ornamentation	Drywall, acoustic tile, vinyl composition or hardwood, small stage	Adequate lighting and plumbing, some extras	Forced air
	Low cost	114.50	Pole frame, metal panels, finished inside, little trim	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Wall furnace
S	Average	170.00	Pre-engineered, sandwich panels, some trim	Drywall, acoustic tile, vinyl composition or hardwood, small stage	Adequate lighting and plumbing, some extras	Forced air
	Low cost	115.50	Pre-engineered, finished interior, insulation	Painted walls, acoustic tile or drywall ceilings, asphalt tile	Minimum school lighting and plumbing	Wall furnace

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - MULTIPURPOSE BUILDING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - PHYSICAL EDUCATION BUILDING

OCCUPANCY DESCRIPTION: This building supplements the use of the gymnasium and includes classrooms that serve as instructional areas for athletic activities. There are also large areas that can be utilized for other uses such as intramural sports, demonstrations, exhibitions and informal recreation.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, lockers, furnishings or equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 330.50	Good frame, face brick, stone, concrete or metal panels, solar glass	Good exhibition floors, varied sports and teaching facilities	Good lighting and outlets, good plumbing, extra features	Warm and cool air (zoned)
	Average	247.00	Steel columns and girders, face brick, best ornamental block	Intramural and competitive sports venues, good teaching facilities	Good lighting and outlets, showers and restrooms	Heat pump system
C	Excellent	321.50	Heavy frame, best masonry walls, spectator entrance and lobby	Good exhibition floors, varied sports and teaching facilities	Good lighting and outlets, good plumbing, extra features	Warm and cool air (zoned)
	Good	242.50	Steel columns and girders, face brick, best ornamental block	Intramural and competitive sports venues, good teaching facilities	Good lighting and outlets, showers and restrooms	Heat pump system
	Average	173.50	Steel or Glulam, trusses or girders, brick, block or tilt-up	Multisport floors, co-recreation/sports/ teaching activities, some courts	Adequate lighting and plumbing, locker rooms, good classrooms	Package A.C.
	Low cost	115.00	Light frame, block or tilt-up, very plain	Low-cost finishes, minimal sports facilities, synthetic flooring	Minimum sports lighting and plumbing, adequate classrooms	Space heaters
D	Excellent	311.50	Heavy frame, masonry veneer walls, spectator entrance and lobby	Good exhibition floors, varied sports and teaching facilities	Good lighting and outlets, good plumbing, extra features	Warm and cool air (zoned)
	Good	232.50	Steel or Glulam frame, trusses and girders, brick veneer, best stucco	Intramural and competitive sports venues, good teaching facilities	Good lighting and outlets, showers and restrooms	Heat pump system
	Average	165.50	Heavy frame, trusses or girders, good stucco or siding, little trim	Multisport floors, co-recreation/sports/ teaching activities, some courts	Adequate lighting and plumbing, locker rooms, good classrooms	Package A.C.
	Low cost	108.50	Light frame, stucco or siding, very plain	Low-cost finishes, minimal sports facilities, synthetic flooring	Minimum sports lighting and plumbing, adequate classrooms	Space heaters
D POLE	Average	158.00	Pole frame, good metal panels, finished inside, little trim	Multisport floors, co-recreation/sports/ teaching activities, some courts	Adequate lighting and plumbing, locker rooms, good classrooms	Package A.C.
	Low cost	103.50	Pole frame, metal siding, finished interior, insulation	Low-cost finishes, minimal sports facilities, synthetic flooring	Minimum sports lighting and plumbing, adequate classrooms	Space heaters
S	Good	229.00	Pre-engineered, good sandwich panels, some brick or stone trim	Intramural and competitive sports venues, good teaching facilities	Good lighting and outlets, showers and restrooms	Heat pump system
	Average	162.50	Pre-engineered, finished interior, insulation, little trim	Multisport floors, co-recreation/sports/ teaching activities, some courts	Adequate lighting and plumbing, locker rooms and classrooms	Package A.C.
	Low cost	105.50	Pre-engineered, finished interior, some insulation	Low-cost finishes, minimal sports facilities, synthetic flooring	Minimum sports lighting and plumbing, adequate classrooms	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - PHYSICAL EDUCATION BUILDING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055	20	1.183
9	.981	14	1.073	22	1.220
10	1.000 (base)	15	1.092	24	1.257
11	1.018	16	1.110	30	1.367
12	1.037	18	1.147	36	1.476

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - RELOCATABLE CLASSROOM

OCCUPANCY DESCRIPTION: These relocatable buildings are designed as classroom structures, typically found in school facilities, and are generally smaller and utilitarian in scope.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Exterior ramps, landings or steps.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
D	Excellent	$ 202.00	Good siding or stucco panels on good modular frame	Drywall, good wall coverings and boards, good carpet and vinyl	Best classroom lighting and cabling systems, some plumbing	Package A.C.
	Good	159.00	Siding or stucco, some trim, modular structure	Drywall, vinyl wall coverings, acoustic tile, carpet and vinyl	Good fluorescent fixtures and wet sink, few extra features	Indiv. thru-wall heat pumps
	Average	133.00	Standard siding and fenestration, little trim	Drywall, tack board, acoustic tile, carpet and vinyl composition	Adequate lighting and signaling system	Indiv. thru-wall heat pumps
	Low cost	112.00	Low-cost siding on studs, metal roof	Drywall or paneling, acoustic tile, vinyl composition	Minimum classroom lighting and cabling, no plumbing	Indiv. thru-wall heat pumps
	Cheap	81.50	Metal siding on light studs, mobile structure	Low-cost paneling or drywall, vinyl composition, no partitions	Minimum electrical to code, no plumbing	Electric wall heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - RELOCATABLE CLASSROOM

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

Vertical wheelchair lifts cost $19,100 to $37,100.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87	Individual thru-wall heat pumps	12.40	Evap. coolers	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $ 3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	**12,000**
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	**16,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	**20,000**

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - RELOCATABLE OFFICE

OCCUPANCY DESCRIPTION: These relocatable buildings are designed as office structures, typically found in school facilities, and are generally smaller and utilitarian in scope. The lower qualities are generally composed of light mobile/modular structures with minimal finishes. The better qualities will have good modular frames with well-finished walls and floors, good acoustical ceilings, good lighting, cabling, and plumbing fixtures.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Exterior ramps, landings or steps.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
D	Excellent	$ 189.00	Good siding or stucco panels on good modular frame	Drywall, good vinyl and paneling, good flooring, many private offices	Good lighting, cabling, many outlets and plumbing, some extras	Heat pump system
	Good	153.50	Siding or stucco, some trim, modular structure	Drywall, vinyl wall covering, acoustic tile, carpet and vinyl	Good lighting and outlets, good signal systems and restrooms	Package A.C.
	Average	122.00	Standard siding and fenestration, little trim	Drywall, acoustic tile, carpet and vinyl composition	Adequate lighting and outlets, plumbing and signal system	Indiv. thru-wall heat pumps
	Low cost	105.00	Low-cost siding on studs, metal roof	Drywall partitions, paint, acoustic tile, vinyl composition tile	Minimum office lighting, cabling and plumbing	Indiv. thru-wall heat pumps
	Cheap	88.00	Metal siding on light studs, mobile structure	Low-cost paneling or drywall, vinyl composition, few partitions	Minimum electrical to code, few plumbing fixtures	Indiv. thru-wall heat pumps

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - RELOCATABLE OFFICE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

Vertical wheelchair lifts cost $19,100 to $37,100.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87	Individual thru-wall heat pumps	12.40	Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $ 3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	**12,000**
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	**16,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	**20,000**

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - SCIENCE BUILDING

OCCUPANCY DESCRIPTION: Science buildings include areas for lectures, demonstrations, audiovisual presentations, laboratory work and study and some administrative and stage areas. Typically, there is also an area designated for storage of materials and equipment. The laboratories have both AC and DC variable voltage and plumbing in the work areas.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers, lab equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	*HEAT
A-B	Excellent	$ 517.00	Stone, best brick, metal and glass, highly ornamental	Plaster, glazed finishes, enamel, tile, many workstations, support facilities	Best lab plumbing and lighting, many extras	Complete H.V.A.C.
	Good	405.00	Face brick, stone, concrete or metal panels, solar glass	Plaster or drywall, acoustic tile, carpet and vinyl, good teaching and research	Good fluorescent fixtures, good lab stations and plumbing	Complete H.V.A.C.
	Average	317.00	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, VCT, carpet, good teaching and support	Adequate lighting and plumbing, some extra features	Complete H.V.A.C.
	Low cost	249.00	Brick, precast concrete, block, little trim	Low cost finishes, acoustic tile, VCT, plain classrooms and offices	Minimum lab lighting and plumbing, few extras	Complete H.V.A.C.
A-B	Finished Basement	216.00	Reinforced concrete, plaster interior	Lab finish, administrative and technical facilities	Adequate lighting and plumbing for laboratory facilities	*Complete H.V.A.C.
C	Excellent	401.00	Steel frame, face brick, metal panels, tile, highly ornamental	Plaster, glazed finishes, enamel, tile, carpet, vinyl, good support facilities	Best lab stations and plumbing, good lighting and outlets	Complete H.V.A.C.
	Good	317.00	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, vinyl or carpet, teaching, good research	Good fluorescent fixtures, lab stations and plumbing	Complete H.V.A.C.
	Average	250.50	Steel frame or bearing walls, brick, block, or concrete, some trim	Plaster or drywall, acoustic tile, VCT, adequate teaching, support facilities	Adequate lighting, plumbing and workstations	Complete H.V.A.C.
	Low cost	198.00	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, acoustic tile or drywall, VCT, plain classrooms and offices	Minimum lab lighting and plumbing	Complete H.V.A.C.
D	Excellent	391.00	Steel or wood frame, brick or stone veneer, metal and glass, ornamental	Plaster, glazed finishes, enamel, tile, carpet, vinyl, good support facilities	Best lab stations and plumbing, good lighting and outlets	Complete H.V.A.C.
	Good	308.00	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, vinyl or carpet, teaching and research	Good fluorescent fixtures, lab stations and plumbing	Complete H.V.A.C.
	Average	242.00	Wood frame or pipe columns, good stucco or siding with some trim	Plaster or drywall, acoustic tile, vinyl composition or hardwood	Adequate lighting, plumbing and workstations	Complete H.V.A.C.
	Low cost	190.50	Wood frame, stucco or siding, little ornamentation	Drywall, acoustic tile, vinyl comp., plain classrooms and offices	Minimum lab lighting and plumbing	Complete H.V.A.C.
D POLE	Average	235.00	Pole frame, insulated metal panels, some ornamentation	Plaster or drywall, acoustic tile, VCT, adequate teaching, support facilities	Adequate lighting, plumbing and workstations	Complete H.V.A.C.
	Low cost	184.50	Pole frame, good metal panels, finished inside, little trim	Drywall, acoustic tile, vinyl comp., plain classrooms and offices	Minimum lab lighting and plumbing	Complete H.V.A.C.
S	Good	303.50	Pre-engineered, good sandwich panels, some brick or stone	Plaster or drywall, acoustic tile, vinyl or carpet, teaching and research	Good fluorescent fixtures, lab stations and plumbing	Complete H.V.A.C.
	Average	236.50	Pre-engineered, sandwich panels, some trim	Plaster or drywall, acoustic tile, VCT, adequate teaching, support facilities	Adequate lighting, plumbing and workstations	Complete H.V.A.C.
	Low cost	186.00	Pre-engineered, finished interior, insulation	Drywall, acoustic tile, vinyl comp., plain classrooms and offices	Minimum lab lighting and plumbing	Complete H.V.A.C.
CDS	Finished Basement	162.50	Reinforced concrete, plaster or drywall interior	Lab finish, administrative and technical facilities	Adequate lighting and plumbing for laboratory facilities	*Complete H.V.A.C.

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.59 per square foot.

* For Finished Basements with heat, adjust using table on following Refinements page. The costs include low-quality complete H.V.A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - SCIENCE BUILDING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

COMPLETE HEATING, COOLING AND AIR CONDITIONING

These costs are averages of total installed cost of the entire heating or cooling installation including its prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated costs.

COMPLETE H.V.A.C Classes A/B	Sq. Ft. Costs	HEATING & COOLING Classes C/D/S	Sq. Ft. Costs
Excellent	$ 96.00	Excellent	$ 85.50
Good	74.00	Good	65.00
Average	56.50	Average	49.50
Low Cost	43.50	Low Cost	38.00

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - TECHNICAL TRADES BUILDING

OCCUPANCY DESCRIPTION: Technical trades buildings have large rooms used primarily for specialized education and vocational training.

The buildings, when divided, have some classroom/lecture stations and work areas. Cost includes all necessary components. The overall division of the building separates the various training specialties, which may include woodworking, graphic arts, electrical, metal, machine and automotive.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in bookshelves, cabinets and blackboards.

NOT INCLUDED IN COSTS: Elevators, sprinklers, movable equipment and furnishings power wiring or equipment that may be found.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 338.00	Face brick, concrete, metal panels, EIFS, glass, ornamental	Plaster or drywall, glazed finishes, carpet, tile and vinyl, some lab space	High-level lighting, good plumbing, some extras	Hot and chilled water (zoned)
	Average	247.50	Brick, precast concrete, good block, some trim	Plaster or drywall, acoustic tile, good slab, hardwood or vinyl composition	Good lighting, many outlets, good plumbing	Warm and cool air (zoned)
	Low cost	193.00	Precast concrete, block, very plain	Painted walls, tile or drywall, some VCT	Adequate electrical and plumbing	Heat pump system
C	Good	242.00	Steel columns, web or joists, ornamental block or face brick	Plaster or drywall, acoustic tile, vinyl composition, carpet, good slab	Good fluorescent fixtures and outlets, good plumbing	Warm and cool air (zoned)
	Average	178.50	Steel frame or bearing walls, brick, block, concrete panels, some trim	Painted walls, acoustic tile or drywall ceilings, some asphalt tile	Good lighting, many outlets, adequate plumbing	Package A.C.
	Low cost	140.50	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, some ceiling and floor finish, sealed concrete	Adequate lighting and outlets, minimum plumbing	Package A.C.
D	Good	234.00	Steel or Glulam frame and joists, brick veneer, best stucco	Plaster or drywall, acoustic tile, vinyl composition, carpet, good slab	Good fluorescent fixtures and outlets, good plumbing	Warm and cool air (zoned)
	Average	171.00	Wood frame or pipe columns, good stucco or siding with some trim	Plaster, acoustic tile or drywall ceiling, some asphalt tile	Good lighting, many outlets, adequate plumbing	Package A.C.
	Low cost	134.00	Light frame, siding, very plain	Drywall, acoustic tile, some flooring	Adequate lighting, little plumbing	Package A.C.
D POLE	Average	166.50	Pole frame, metal siding, some interior finish and insulation	Painted walls, acoustic tile or drywall ceilings, some asphalt tile	Good lighting, many outlets, adequate plumbing	Package A.C.
	Low cost	129.50	Pole frame, metal single wall	Some ceiling and floor finish	Adequate lighting, little plumbing	Package A.C.
S	Average	168.50	Pre-engineered, partly finished interior, some insulation	Painted walls, acoustic tile or drywall ceilings, some asphalt tile	Good lighting, many outlets, adequate plumbing	Package A.C.
	Low cost	131.00	Pre-engineered, metal, primarily exposed	Drywall, acoustic tile, some flooring	Adequate lighting, little plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - TECHNICAL TRADES BUILDING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055	20	1.183
9	.981	14	1.073	22	1.220
10	1.000 (base)	15	1.092	24	1.257
11	1.018	16	1.110	30	1.367
12	1.037	18	1.147	36	1.476

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - VOCATIONAL

OCCUPANCY DESCRIPTION: This occupancy includes the entire school facility with a mixture of classrooms, multipurpose buildings, administrative offices, etc. The schools may consist of one building or several separate buildings. This occupancy's emphasis is on trade and technical skills with a greater proportion of shops and laboratories.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, lockers, therapy or recreational equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 342.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, carpet and vinyl, some sealed concrete	Best fluorescent fixtures and outlets, good plumbing	Hot and chilled water (zoned)
	Average	257.00	Brick, precast concrete, block, some trim	Plaster or drywall, acoustic tile, some hardwood or vinyl composition	Good lighting, many outlets, good plumbing	Warm and cool air (zoned)
B	Good	310.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, acoustic tile, carpet and vinyl, some sealed concrete	Best fluorescent fixtures and outlets, good plumbing	Hot and chilled water (zoned)
	Average	233.00	Brick, precast concrete, block, some trim	Plaster or drywall, acoustic tile, some hardwood or vinyl composition	Good lighting, many outlets, good plumbing	Warm and cool air (zoned)
A-B	Classroom Basement	191.00	Reinforced concrete, plaster interior	Classrooms, school finishes, some utility and storage	Adequate lighting and plumbing	Warm and cool air (zoned)
	Parking Basement	91.00	Unfinished interior	Concrete with hardener, lines and stops	Exposed lighting, drains	Ventilation
	Unfinished Basement	79.00	Unfinished interior	Unfinished storage and utility	Minimum lighting, drains	None
	Classroom Mezzanine	124.00	Not included	Classroom and office, typical school finishes	Adequate school lighting and plumbing	In bldg. cost
	Open Mezzanine	67.50	Not included	Finished floors and soffit, add for spectator seating	Average lighting, no plumbing	In bldg. cost
C	Excellent	319.50	Steel frame, face brick, metal panels, tile, some ornamentation	Plaster, glazed finishes, enamel, carpet and vinyl, some sealed concrete	Best lighting and wiring, good plumbing	Hot and chilled water (zoned)
	Good	237.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, acoustic tile, vinyl composition, carpet, good slab	Good fluorescent fixtures and outlets, good plumbing	Warm and cool air (zoned)
	Average	177.50	Steel frame or bearing walls, brick, block or concrete, some trim	Painted walls, acoustic tile or drywall ceilings, some asphalt tile	Good lighting, many outlets, adequate plumbing	Package A.C.
	Low cost	138.50	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Painted walls, some ceiling and floor finish, sealed concrete	Adequate lighting and outlets, minimum plumbing	Forced air
D	Excellent	310.50	Steel or wood frame, brick or stone veneer, metal and glass, ornamentation	Plaster, enamel, glazed or vinyl finishes, some carpet and vinyl	Best lighting and wiring, good plumbing	Hot and chilled water (zoned)
	Good	228.50	Steel or Glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, acoustic tile, vinyl composition, carpet, good slab	Good fluorescent fixtures and outlets, good plumbing	Warm and cool air (zoned)
	Average	169.50	Wood frame or pipe columns, good stucco or siding with some trim	Painted walls, acoustic tile or drywall ceilings, some asphalt tile	Good lighting, many outlets, adequate plumbing	Package A.C.
	Low cost	132.00	Wood frame, stucco or siding, very plain	Painted walls, some ceiling and floor finish, sealed concrete	Adequate lighting and outlets, minimum plumbing	Forced air
DPOLE	Good	221.50	Pole frame, best metal panels, some brick or stone trim	Plaster or drywall, acoustic tile, vinyl composition, carpet, good slab	Good fluorescent fixtures and outlets, good plumbing	Warm and cool air (zoned)
	Average	162.50	Pole frame, good metal panels, finished inside, little trim	Painted walls, acoustic tile or drywall ceiling, some asphalt tile	Good lighting, many outlets, adequate plumbing	Package A.C.
	Low cost	125.50	Pole frame, metal siding, some interior finish, insulation	Painted walls, some ceiling and floor finish, sealed concrete	Adequate lighting and outlets, minimum plumbing	Forced air
S	Good	225.00	Pre-engineered, good sandwich panels, some brick or stone trim	Plaster or drywall, acoustic tile, vinyl composition, carpet, good slab	Good fluorescent fixtures and outlets, good plumbing	Warm and cool air (zoned)
	Average	165.00	Pre-engineered, sandwich panels, some ornamentation	Painted walls, acoustic tile or drywall ceiling, some asphalt tile	Good lighting, many outlets, adequate plumbing	Package A.C.
	Low cost	127.50	Pre-engineered, some finished interior, insulation	Painted walls, some ceiling and floor finish, sealed concrete	Adequate lighting and outlets, minimum plumbing	Forced air
CDS†	Classroom Basement	127.50	Reinforced concrete, plaster or drywall interior	Classrooms, school finishes, some utility and storage	Adequate lighting and plumbing	Forced air
	Parking Basement	59.50	Unfinished interior	Finished ceiling, concrete floor with hardener	Exposed lighting, adequate drains	Ventilation
	Unfinished Basement	48.25	Unfinished interior	Unfinished storage and utility	Minimum lighting, drains	None
	Classroom Mezzanine	92.50	Not included	Classroom and office, typical school finishes	Adequate school lighting and plumbing	In bldg. cost
	Open Mezzanine	75.75	Not included	Finished floors and soffit, add for spectator seating	Average lighting, no plumbing	In bldg. cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.59 per square foot.
MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SCHOOLS - VOCATIONAL

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,500
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – ARCH-RIB (QUONSET), LIGHT COMMERCIAL



GOOD CLASS S



GOOD CLASS D

OCCUPANCY DESCRIPTION: Light commercial building with semi-circular (culvert) shaped roofs that curve to the ground to form the sides. These buildings have many uses, such as general material, commodity or equipment storage and repair, and are generally lighter than typical warehouse buildings. Interior modification can turn them into any one of several uses. The better qualities will have some built-in shop or workbench cabinetry and adequate lighting and plumbing.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers, furnishings or special utilities for industrial equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
D	Good	$ 45.00	Good laminated arch, siding, shingles, pedestrian and overhead doors	Small office or shop area, concrete floor, some extras	Good lighting and outlets, water service, few fixtures	Space heaters
	Average	31.00	Arched frame, shingles and siding, windows, overhead door	Unfinished, concrete or asphalt floor, some partitioning, cabinets	Adequate lighting and water outlets	None
	Low cost	23.00	Arch-rib frame, siding, composition shingles	Unfinished, cheap slab/asphalt	Minimum electrical service	None
D POLE	Good	43.50	Good laminated arch, metal siding, pedestrian and overhead doors	Small office or shop area, concrete floor, some extras	Good lighting and outlets, water service, few fixtures	Space heaters
	Average	29.50	Pre-engineered arched frame, metal siding, windows, overhead door	Unfinished, concrete or asphalt floor, some partitioning, cabinets	Adequate lighting and water outlets	None
	Low cost	22.00	Light arch-rib frame, metal siding	Unfinished, cheap slab/asphalt	Minimum electrical service	None
S	Good	44.00	Good self-framing quonset panels, pedestrian and overhead doors	Small office or shop area, concrete floor, some extras	Good lighting and outlets, water service, few fixtures	Space heaters
	Average	30.50	Pre-engineered quonset, metal siding, windows, overhead door	Unfinished, concrete or asphalt floor, some partitioning, cabinets	Adequate lighting and water outlets	None
	Low cost	23.00	Light self-framing quonset panels	Unfinished, cheap slab/asphalt	Minimum electrical service	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – ARCH-RIB (QUONSET), LIGHT COMMERCIAL

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 **FLOOR STRUCTURE**: Adjust for variations in floors as indicated in base square foot costs.

	LOW	AVG.	GOOD	EXCL.
Compacted earth	$ 0.34	$ 0.40	$ 0.47	$ 0.57
Gravel	0.72	0.85	1.00	1.19
Asphalt, including base	2.74	3.46	4.38	5.55
Concrete slab	4.50	5.46	6.64	8.06
Add for vapor barrier	0.94	1.31	1.83	2.56

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.94	$ 6.42	$ 8.34	$ 10.85
2,500	4.27	5.50	7.04	9.03
5,000	3.87	4.92	6.28	7.99
7,500	3.62	4.58	5.79	7.32
10,000	3.45	4.35	5.50	6.92
15,000	3.21	4.05	5.14	6.51

2 **HEATING AND COOLING**

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 6.36	Package A.C. (short ductwork)	$ 14.05	Central refrigeration (zoned)	$ 12.00
Electric wall heaters	2.71			package (short ductwork)	9.20
Forced air furnace	7.13			Evaporative coolers	5.48
Hot water, baseboard/convector	12.70				
Space heaters, with fan	3.49				
radiant	4.09				
Steam (including boiler)	11.30				
without boiler	4.78			**VENTILATION ONLY**	
Wall or floor furnace	3.23			Vent. (blowers/ducts)	$ 2.01

3 **HEIGHT REFINEMENTS**

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.058
9	.981	14	1.077
10	1.000 (base)	16	1.115
11	1.019	18	1.154
12	1.038	20	1.192

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	200	250	300	400	500	600	700	800	900	1000	Sq. Ft./Story
500	1.178	1.311	1.444	1.577	1.844	2.110	2.377	2.909	-----	-----	-----	-----	-----	-----	**500**
750	1.044	1.133	1.222	1.311	1.489	1.667	1.844	2.201	-----	-----	-----	-----	-----	-----	**750**
1,000	.980	1.044	1.110	1.178	1.311	1.444	1.577	1.844	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.911	.955	1.000	1.044	1.133	1.222	1.311	1.489	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.878	.911	.945	.977	1.044	1.110	1.178	1.311	-----	-----	-----	-----	-----	-----	**2,000**
2,500	.858	.884	.911	.938	.991	1.044	1.097	1.204	-----	-----	-----	-----	-----	-----	**2,500**
3,000	.843	.865	.889	.911	.955	1.000	1.044	1.133	-----	-----	-----	-----	-----	-----	**3,000**
3,500	-----	.854	.872	.892	.931	.967	1.006	1.080	1.157	-----	-----	-----	-----	-----	**3,500**
4,000	-----	-----	.860	.878	.911	.945	.977	1.044	1.110	1.178	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.844	.857	.884	.911	.938	.991	1.044	1.097	1.150	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.844	.860	.877	.911	.945	.977	1.010	1.044	1.076	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.844	.858	.884	.911	.938	.960	.991	1.018	1.044	**10,000**
14,000	-----	-----	-----	-----	-----	.825	.835	.854	.873	.892	.911	.931	.949	.967	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.818	.831	.844	.858	.871	.884	.898	.911	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.810	.820	.831	.841	.852	.863	.873	.884	**25,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – BOAT STORAGE



GOOD CLASS S BUILDING



AVERAGE CLASS S BUILDING

OCCUPANCY DESCRIPTION: The three walled shed buildings are designed for dry boat storage and include costs for the storage racks. Structures are typically designed with an open front and only three exterior walls, of either wood frame or steel construction. Floors are either concrete or asphalt. Security lighting can be found in the better qualities.

The four-walled buildings may include a small office and shop area as well as electrical wiring and water service at the better qualities.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Storage racks (four-walled buildings).

NOT INCLUDED IN COSTS: Special foundations, piers or flotation systems. Boat lifts or hoists.

4-WALL BUILDINGS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
D	Average	$ 43.50	Post frame and trusses, plywood or board siding	Some partitions, shop area, light floor, average racks	Minimum electrical and water service	None
	Low cost	32.50	Post frame, light plywood siding	Unfinished, asphalt floor, minimum racks	Minimum electrical and water outlets	None
D POLE	Average	40.00	Pole frame and truss, enameled siding	Some partitions, shop area, light floor, average racks	Minimum electrical and water service	None
	Low cost	30.00	Pole frame, light metal siding	Unfinished, asphalt floor, minimum racks	Minimum electrical and water outlets	None
S	Good	58.50	Good metal on heavy steel frame	Small office, concrete floor, good racks	Adequate electrical, some plumbing	None
	Average	44.00	Metal siding on steel frame	Some partitions, shop area, light floor, average racks	Minimum electrical and water service	None
	Low cost	32.50	Low-cost siding, light steel frame	Unfinished, asphalt floor, minimum racks	Minimum electrical and water outlets	None
S SLANT WALL	Good	56.00	Good metal on heavy steel slant frame	Small office, concrete floor, good racks	Adequate electrical, some plumbing	None
	Average	41.50	Metal on slant frame	Some partitions, average racks	Minimum electrical and water service	None
	Low cost	31.00	Low-cost siding, slant frame	Unfinished, minimum racks	Minimum electrical and water outlets	None

3-WALL SHEDS

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
D	Good	$ 45.50	Open front, good wood siding on post frame and rack	Unfinished, light concrete or asphalt floor, good racks	Security lighting, no plumbing	None
	Average	31.00	Open front, plywood or board on light frame and rack	Unfinished, asphalt floor, average racks	None	None
	Low cost	21.00	End walls only, low-cost plywood siding and rack framing	Unfinished, asphalt floor or gravel, minimum racks	None	None
D POLE	Good	43.00	Open front, good metal siding on pole frame and rack	Unfinished, light concrete or asphalt floor, good racks	Security lighting, no plumbing	None
	Average	29.00	Open front, metal on light pole frame and rack	Unfinished, asphalt floor, average racks	None	None
	Low cost	19.50	End walls only, low-cost siding, rack framing	Unfinished, asphalt floor or gravel, minimum racks	None	None
S	Good	46.00	Open front, good metal on siding steel rack and frame	Unfinished, light concrete or asphalt floor, good racks	Security lighting, no plumbing	None
	Average	31.00	Open front, metal siding on light frame and rack	Unfinished, asphalt floor, average racks	None	None
	Low cost	21.00	End walls only, low-cost siding, rack framing	Unfinished, asphalt floor or gravel, minimum racks	None	None

For buildings with fewer than four walls, use the total length of the walls to enter the Floor Area/Perimeter tables.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – BOAT STORAGE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

FLOOR STRUCTURE: Adjust for variations in floors as indicated in base square foot costs.

	LOW	AVG.	GOOD	EXCL.
Compacted earth	$ 0.34	$ 0.40	$ 0.47	$ 0.57
Gravel	0.72	0.85	1.00	1.19
Asphalt, including base	2.74	3.46	4.38	5.55
Concrete slab	4.50	5.46	6.64	8.06
Add for vapor barrier	0.94	1.31	1.83	2.56

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.94	$ 6.42	$ 8.34	$ 10.85
2,500	4.27	5.50	7.04	9.03
5,000	3.87	4.92	6.28	7.99
7,500	3.62	4.58	5.79	7.32
10,000	3.45	4.35	5.50	6.92
15,000	3.21	4.05	5.14	6.51
20,000	3.12	3.90	4.88	6.08
40,000	2.80	3.49	4.32	5.35

BOAT STORAGE RACKS: Costs of storage racks are included in the boat storage buildings and sheds. Costs of racks only are as follows:
Sq. Ft. costs: Good . . . $19.45 – $22.55; Average . . . $13.95 – $16.85; Minimum . . . $10.05 – $12.80

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 6.36	Package A.C. (short ductwork)	$ 14.05	Central refrigeration (zoned)	$ 12.00
Electric wall heaters	2.71			package (short ductwork)	9.20
Forced air furnace	7.13			Evaporative coolers	5.48
Hot water, baseboard/convector	12.70				
Space heaters, with fan	3.49				
radiant	4.09				
Steam (including boiler)	11.30				
without boiler	4.78			VENTILATION ONLY	
Wall or floor furnace	3.23			Vent. (blowers/ducts)	$ 2.01

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	14	1.077
9	.981	16	1.115
10	1.000 (base)	18	1.154
11	1.019	20	1.192
12	1.038	22	1.231
13	1.058	24	1.269

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	200	250	300	400	500	600	700	800	900	1000	Sq. Ft./Story
500	1.178	1.311	1.444	1.577	1.844	2.110	2.377	2.909	-----	-----	-----	-----	-----	-----	**500**
750	1.044	1.133	1.222	1.311	1.489	1.667	1.844	2.201	-----	-----	-----	-----	-----	-----	**750**
1,000	.980	1.044	1.110	1.178	1.311	1.444	1.577	1.844	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.911	.955	1.000	1.044	1.133	1.222	1.311	1.489	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.878	.911	.945	.977	1.044	1.110	1.178	1.311	-----	-----	-----	-----	-----	-----	**2,000**
2,500	.858	.884	.911	.938	.991	1.044	1.097	1.204	-----	-----	-----	-----	-----	-----	**2,500**
3,000	.843	.865	.889	.911	.955	1.000	1.044	1.133	-----	-----	-----	-----	-----	-----	**3,000**
3,500	-----	.854	.872	.892	.931	.967	1.006	1.080	1.157	-----	-----	-----	-----	-----	**3,500**
4,000	-----	-----	.860	.878	.911	.945	.977	1.044	1.110	1.178	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.844	.857	.884	.911	.938	.991	1.044	1.097	1.150	-----	-----	-----	**5,000**
10,000	-----	-----	-----	-----	-----	.844	.858	.884	.911	.938	.960	.991	1.018	1.044	**10,000**
25,000	-----	-----	-----	-----	-----	-----	.810	.820	.831	.841	.852	.863	.873	.884	**25,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – EQUIPMENT



AVERAGE CLASS S

OCCUPANCY DESCRIPTION: Equipment sheds are designed for the storage and maintenance of equipment. The better qualities will generally have good electrical circuits and/or water service. Those equipment sheds with extensive shop or office areas should be priced from Garages, Service, Repair. For light sheds, see Vol. I, Agricultural Structures.



AVERAGE CLASS DPOLE

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Tool cabinets.

NOT INCLUDED IN COSTS: Sprinklers or equipment.

4-WALL BUILDINGS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 58.50	Concrete block, low-cost brick, wood rafters, overhead doors	Unfinished, concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	44.50	Concrete block, light roof, windows	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	Space heaters
D	Good	48.50	Heavy wood frame, siding or stucco, overhead doors	Unfinished, concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	34.50	Open wood frame, exposed siding or stucco, windows	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	Space heaters
D POLE	Good	43.00	Good pole frame, color siding, overhead doors	Unfinished, concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	31.00	Pre-engineered pole frame, metal siding, windows	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	Space heaters
S	Good	47.00	Good frame, color siding, overhead doors	Unfinished, concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	34.50	Pre-engineered frame, metal siding, windows	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	Space heaters
SSLANT WALL	Good	43.50	Good slant frame, color siding, overhead doors	Unfinished, concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	32.00	Pre-engineered pole frame, metal siding, windows	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	Space heaters
CDS	Avg. storage mezzanine	26.75	In building cost	Heavy plywood or plank on wood or light steel structure, no partitions	Minimum lighting, no plumbing	Included in building cost
	Low storage mezzanine	20.00	In building cost	Light storage on plywood, minimum supports, no soffit	Minimum lighting	Included in building cost

NOTE: Do not use story height or area/perimeter with mezzanine costs.

3-WALL SHEDS

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 47.50	Open front, block or low-cost brick, wood rafters	Unfinished concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	36.50	Open front, concrete block, light wood rafters	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	Space heaters
D	Good	44.00	Open front, light frame and rafters, siding or stucco	Unfinished concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	33.00	Open front, exposed frame, siding or stucco	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	Space heaters
D POLE	Good	38.50	Open front, good metal and pole frame	Unfinished concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	29.00	Open front, enameled siding on wood pole frame	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	Space heaters
S	Good	42.00	Open front, good metal and steel frame	Unfinished concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	32.50	Open front, enameled siding on steel frame	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	Space heaters
SSLANT WALL	Good	39.00	Open front, good metal and steel slant frame	Unfinished concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	30.00	Open front, enameled siding on steel slant frame	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	Space heaters

For buildings with fewer than four walls, use the total length of the walls to enter the Floor Area/Perimeter tables.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – EQUIPMENT

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 **FLOOR STRUCTURE**: Adjust for variations in floors as indicated in base square foot costs.

	LOW	AVG.	GOOD	EXCL.
Compacted earth	$ 0.34	$ 0.40	$ 0.47	$ 0.57
Gravel	0.72	0.85	1.00	1.19
Asphalt, including base	2.74	3.46	4.38	5.55
Concrete slab	4.50	5.46	6.64	8.06
Add for vapor barrier	0.94	1.31	1.83	2.56

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.94	$ 6.42	$ 8.34	$ 10.85
2,500	4.27	5.50	7.04	9.03
5,000	3.87	4.92	6.28	7.99
7,500	3.62	4.58	5.79	7.32
10,000	3.45	4.35	5.50	6.92
15,000	3.21	4.05	5.14	6.51

2 **HEATING AND COOLING**

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 6.36	Package A.C. (short ductwork)	$ 14.05	Central refrigeration (zoned)	$ 12.00
Electric wall heaters	2.71			package (short ductwork)	9.20
Forced air furnace	7.13			Evaporative coolers	5.48
Hot water, baseboard/convector	12.70				
Space heaters, with fan	3.49				
radiant	4.09				
Steam (including boiler)	11.30				
without boiler	4.78			VENTILATION ONLY	
Wall or floor furnace	3.23			Vent. (blowers/ducts)	$ 2.01

3 **HEIGHT REFINEMENTS**

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.058
9	.981	14	1.077
10	1.000 (base)	16	1.115
11	1.019	18	1.154
12	1.038	20	1.192

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	200	250	300	400	500	600	700	800	900	1000	Sq. Ft./Story
500	1.178	1.311	1.444	1.577	1.844	2.110	2.377	2.909	-----	-----	-----	-----	-----	-----	500
750	1.044	1.133	1.222	1.311	1.489	1.667	1.844	2.201	-----	-----	-----	-----	-----	-----	750
1,000	.980	1.044	1.110	1.178	1.311	1.444	1.577	1.844	-----	-----	-----	-----	-----	-----	1,000
1,500	.911	.955	1.000	1.044	1.133	1.222	1.311	1.489	-----	-----	-----	-----	-----	-----	1,500
2,000	.878	.911	.945	.977	1.044	1.110	1.178	1.311	-----	-----	-----	-----	-----	-----	2,000
2,500	.858	.884	.911	.938	.991	1.044	1.097	1.204	-----	-----	-----	-----	-----	-----	2,500
3,000	.843	.865	.889	.911	.955	1.000	1.044	1.133	-----	-----	-----	-----	-----	-----	3,000
3,500	-----	.854	.872	.892	.931	.967	1.006	1.080	1.157	-----	-----	-----	-----	-----	3,500
4,000	-----	-----	.860	.878	.911	.945	.977	1.044	1.110	1.178	-----	-----	-----	-----	4,000
5,000	-----	-----	.844	.857	.884	.911	.938	.991	1.044	1.097	1.150	-----	-----	-----	5,000
8,000	-----	-----	-----	-----	.844	.860	.877	.911	.945	.977	1.010	1.044	1.076	-----	8,000
10,000	-----	-----	-----	-----	-----	.844	.858	.884	.911	.938	.960	.991	1.018	1.044	10,000
14,000	-----	-----	-----	-----	-----	.825	.835	.854	.873	.892	.911	.931	.949	.967	14,000
20,000	-----	-----	-----	-----	-----	-----	.818	.831	.844	.858	.871	.884	.898	.911	20,000
25,000	-----	-----	-----	-----	-----	-----	.810	.820	.831	.841	.852	.863	.873	.884	25,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – LUMBER YARD



GOOD CLASS D BUILDING



LOW COST CLASS S SHED

OCCUPANCY DESCRIPTION:

VERTICAL STORAGE – These buildings are designed for vertical lumber storage and include costs for the storage racks. These structures are typically designed with four exterior walls of either wood frame or steel construction. Floors are either concrete or wood at the better qualities and dirt at the lower qualities. Electrical wiring and open fixtures can be found in the better qualities. Commonly, no plumbing or heating is found.

HORIZONTAL STORAGE – The buildings are designed for horizontal lumber storage and include costs for the storage racks. They are generally designed with an open front and only three exterior walls. These wood-framed structures have wood, metal or plaster (stucco) exterior wall finishes. Floors are unfinished, with the quantity of the racks varying with the quality of the structure. Commonly, no plumbing or heating is found.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Storage racks.

NOT INCLUDED IN COSTS: Sprinklers, office or restroom facilities, or material-handling equipment.

VERTICAL STORAGE BUILDING (4 WALLS)

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING & PLUMBING AND MECHANICAL	HEAT
D	Good	$ 47.50	Good wood or stucco on wood frame, four walls	Unfinished, concrete or wood floor, good racks	Conduit, open fixtures, no plumbing	None
	Average	33.50	Wood or stucco on wood frame, four walls	Unfinished, light concrete or wood floor, average racks	Minimum electrical, no plumbing	None
	Low cost	23.50	Low-cost board siding, light frame, four walls	Unfinished, asphalt or wood floor, minimum racks	None	None
D POLE	Good	43.00	Good metal panels on pole frame, four walls	Unfinished, concrete or wood floor, good racks	Conduit, open fixtures, no plumbing	None
	Average	29.50	Metal on pole frame, four walls, vertical storage	Unfinished, light concrete or wood floor, average racks	Minimum electrical, no plumbing	None
	Low cost	21.00	Metal on pole frame, four walls, vertical storage	Unfinished, asphalt or wood floor, minimum racks	None	None
S	Good	47.50	Good metal panels on steel frame, four walls	Unfinished, concrete or wood floor, good racks	Conduit, open fixtures, no plumbing	None
	Average	33.50	Steel siding on steel frame, four walls	Unfinished, light concrete or wood floor, average racks	Minimum electrical, no plumbing	None
	Low cost	23.50	Low-cost steel siding, light frame, four walls	Unfinished, asphalt or wood floor, minimum racks	None	None

HORIZONTAL STORAGE SHED (3 WALLS)

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING & PLUMBING AND MECHANICAL	HEAT
D	Good	$ 39.50	Open front, some doors, good wood or stucco on wood frame	Unfinished, light concrete or asphalt floor, good racks	Few lights on front	None
	Average	27.00	Open front, good wood or stucco on wood frame	Unfinished, asphalt floor, average racks	None	None
	Low cost	18.50	Open front, low-cost board siding, light exposed frame	Unfinished, asphalt or dirt floor, minimum racks	None	None
D POLE	Good	34.50	Open front, some doors, good steel siding on pole frame	Unfinished, light concrete or asphalt floor, good racks	Few lights on front	None
	Average	23.50	Open front, metal on pole frame	Unfinished, asphalt floor, average racks	None	None
	Low cost	16.00	Open front, metal on pole frame	Unfinished, asphalt or dirt floor, minimum racks	None	None
S	Good	40.00	Open front, some doors, good steel siding on steel frame	Unfinished, light concrete or asphalt floor, good racks	Few lights on front	None
	Average	27.00	Open front, steel siding, steel frame	Unfinished, asphalt floor, average racks	None	None
	Low cost	18.50	Open front, low-cost steel siding, light frame	Unfinished, asphalt or dirt floor, minimum racks	None	None

For buildings with fewer than four walls, use the total length of the walls to enter the Floor Area/Perimeter tables.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – LUMBER YARD

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

FLOOR STRUCTURE: Adjust for variations in floors as indicated in base square foot costs.

	LOW	AVG.	GOOD	EXCL.
Compacted earth	$ 0.34	$ 0.40	$ 0.47	$ 0.57
Gravel	0.72	0.85	1.00	1.19
Asphalt, including base	2.74	3.46	4.38	5.55
Concrete slab	4.50	5.46	6.64	8.06
Add for vapor barrier	0.94	1.31	1.83	2.56

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.94	$ 6.42	$ 8.34	$ 10.85
2,500	4.27	5.50	7.04	9.03
5,000	3.87	4.92	6.28	7.99
7,500	3.62	4.58	5.79	7.32
10,000	3.45	4.35	5.50	6.92
15,000	3.21	4.05	5.14	6.51
20,000	3.12	3.90	4.88	6.08
40,000	2.80	3.49	4.32	5.35

LUMBER STORAGE RACKS: Costs of storage racks are included in the lumber storage buildings and sheds. Costs of racks only are as follows:
Sq. Ft. costs: Good . . . $3.90 – $5.41; Average . . . $2.87 – $3.75; Minimum . . . $2.00 – $2.79

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 6.36	Package A.C. (short ductwork)	$ 14.05	Central refrigeration (zoned)	$ 12.00
Electric wall heaters	2.71			package (short ductwork)	9.20
Forced air furnace	7.13			Evaporative coolers	5.48
Hot water, baseboard/convector	12.70				
Space heaters, with fan	3.49				
radiant	4.09				
Steam (including boiler)	11.30				
without boiler	4.78			**VENTILATION ONLY**	
Wall or floor furnace	3.23			Vent. (blowers/ducts)	$ 2.01

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	14	1.077
9	.981	16	1.115
10	1.000 (base)	18	1.154
11	1.019	20	1.192
12	1.038	22	1.231
13	1.058	24	1.269

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	200	250	300	400	500	600	700	800	900	1000	Sq. Ft./Story
500	1.178	1.311	1.444	1.577	1.844	2.110	2.377	2.909	-----	-----	-----	-----	-----	-----	**500**
750	1.044	1.133	1.222	1.311	1.489	1.667	1.844	2.201	-----	-----	-----	-----	-----	-----	**750**
1,000	.980	1.044	1.110	1.178	1.311	1.444	1.577	1.844	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.911	.955	1.000	1.044	1.133	1.222	1.311	1.489	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.878	.911	.945	.977	1.044	1.110	1.178	1.311	-----	-----	-----	-----	-----	-----	**2,000**
2,500	.858	.884	.911	.938	.991	1.044	1.097	1.204	-----	-----	-----	-----	-----	-----	**2,500**
3,000	.843	.865	.889	.911	.955	1.000	1.044	1.133	-----	-----	-----	-----	-----	-----	**3,000**
3,500	-----	.854	.872	.892	.931	.967	1.006	1.080	1.157	-----	-----	-----	-----	-----	**3,500**
4,000	-----	-----	.860	.878	.911	.945	.977	1.044	1.110	1.178	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.844	.857	.884	.911	.938	.991	1.044	1.097	1.150	-----	-----	-----	**5,000**
10,000	-----	-----	-----	-----	-----	.844	.858	.884	.911	.938	.960	.991	1.018	1.044	**10,000**
25,000	-----	-----	-----	-----	-----	-----	.810	.820	.831	.841	.852	.863	.873	.884	**25,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – MATERIAL STORAGE



4 WALL AVERAGE CLASS S

OCCUPANCY DESCRIPTION: Utility sheds are multipurpose structures that are usually lighter than typical industrial or warehouse buildings and form a large family of low cost utilitarian buildings which may use similar structural shells.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers.

MATERIAL STORAGE BUILDING - 4 WALL

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Very Good	$ 62.00	Concrete and siding walls, heavy frame, dome or conical roof	Asphalt floor, salt storage	Good lighting, no plumbing	None
	Good	54.50	Brick or block, heavy rafters, barred windows	Sealed walls and heavy slab	Rigid conduit, spark-proof fixtures, no plumbing	None
	Average	42.00	Block, structural clay tile, light roof structure	Unfinished walls, slab or plank floor	Few open fixtures, no plumbing	None
D	Very good	56.50	Siding on heavy posts, arch, dome or conical roof	Heavy concrete piers, asphalt floor, salt storage	Good lighting, no plumbing	None
	Good	47.00	Stucco, wood or metal siding on heavy wood studs	Wainscot, heavy slab or plank floor	Rigid conduit, spark-proof fixtures, no plumbing	None
	Average	32.50	Wood or cheap stucco, wood frame	Unfinished, concrete or plank floor	Few open fixtures, no plumbing	None
D POLE	Average	28.50	Metal panels, sheathing on pole frame	Concrete slab, some wainscot	Few open fixtures, no plumbing	None
S	Very good	56.50	Siding on heavy steel, arch or dome roof	Heavy concrete piers, asphalt floor, salt storage	Good lighting, no plumbing	None
	Good	47.00	Steel panels, sheathing, on heavy steel studs	Heavy slab, sealed walls	Rigid conduit, spark-proof fixtures, no plumbing	None
	Average	33.00	Steel panels, sheathing on steel frame	Sealed concrete slab, some wainscot	Few open fixtures, no plumbing	None
S SLANT WALL	Average	30.00	Steel panels, sheathing on light steel slant frame	Sealed concrete slab, some wainscot	Few open fixtures, no plumbing	None

MATERIAL STORAGE SHED - 3 WALL

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Average	$ 29.00	Open one side, block, steel or wood truss, average cover	Unfinished, light concrete or asphalt floor	Few lights on front	None
	Low cost	22.00	Open front, block, light shed cover	Unfinished, asphalt floor	None	None
D	Average	22.50	Open one side, wood or stucco on open wood frame	Unfinished, light concrete or asphalt floor	Few lights on front	None
	Low cost	16.00	Open front, board siding/frame	Unfinished, asphalt floor	None	None
D POLE	Average	18.50	Open one side, good metal on pole frame	Unfinished, light concrete or asphalt floor	Few lights on front	None
	Low cost	13.00	Open front, metal on pole frame	Unfinished, asphalt floor	None	None
S	Average	21.50	Open one side, good metal on steel frame	Unfinished, light concrete or asphalt floor	Few lights on front	None
	Low cost	15.50	Open front, steel frame/siding	Unfinished, asphalt floor	None	None
S SLANT WALL	Average	20.00	Open one side, good metal on steel slant frame	Unfinished, light concrete or asphalt floor	Few lights on front	None
	Low cost	14.50	Open front, steel frame/siding	Unfinished, asphalt floor	None	None

For buildings with fewer than four walls, use the total length of the walls to enter the Floor Area/Perimeter tables.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – MATERIAL STORAGE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 **FLOOR STRUCTURE**: Adjust for variations in floors as indicated in base square foot costs.

	LOW	AVG.	GOOD	EXCL.
Compacted earth	$ 0.34	$ 0.40	$ 0.47	$ 0.57
Gravel	0.72	0.85	1.00	1.19
Asphalt, including base	2.74	3.46	4.38	5.55
Concrete slab	4.50	5.46	6.64	8.06
Add for vapor barrier	0.94	1.31	1.83	2.56

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.94	$ 6.42	$ 8.34	$ 10.85
2,500	4.27	5.50	7.04	9.03
5,000	3.87	4.92	6.28	7.99
7,500	3.62	4.58	5.79	7.32
10,000	3.45	4.35	5.50	6.92
15,000	3.21	4.05	5.14	6.51

2 **HEATING AND COOLING**

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 6.36	Package A.C. (short ductwork)	$ 14.05	Central refrigeration (zoned)	$ 12.00
Electric wall heaters	2.71			package (short ductwork)	9.20
Forced air furnace	7.13			Evaporative coolers	5.48
Hot water, baseboard/convector	12.70				
Space heaters, with fan	3.49				
radiant	4.09				
Steam (including boiler)	11.30				
without boiler	4.78			**VENTILATION ONLY**	
Wall or floor furnace	3.23			Vent. (blowers/ducts)	$ 2.01

3 **HEIGHT REFINEMENTS**

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.058
9	.981	14	1.077
10	1.000 (base)	16	1.115
11	1.019	18	1.154
12	1.038	20	1.192

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	200	250	300	400	500	600	700	800	900	1000	Sq. Ft./Story
500	1.178	1.311	1.444	1.577	1.844	2.110	2.377	2.909	-----	-----	-----	-----	-----	-----	**500**
750	1.044	1.133	1.222	1.311	1.489	1.667	1.844	2.201	-----	-----	-----	-----	-----	-----	**750**
1,000	.980	1.044	1.110	1.178	1.311	1.444	1.577	1.844	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.911	.955	1.000	1.044	1.133	1.222	1.311	1.489	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.878	.911	.945	.977	1.044	1.110	1.178	1.311	-----	-----	-----	-----	-----	-----	**2,000**
2,500	.858	.884	.911	.938	.991	1.044	1.097	1.204	-----	-----	-----	-----	-----	-----	**2,500**
3,000	.843	.865	.889	.911	.955	1.000	1.044	1.133	-----	-----	-----	-----	-----	-----	**3,000**
3,500	-----	.854	.872	.892	.931	.967	1.006	1.080	1.157	-----	-----	-----	-----	-----	**3,500**
4,000	-----	-----	.860	.878	.911	.945	.977	1.044	1.110	1.178	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.844	.857	.884	.911	.938	.991	1.044	1.097	1.150	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.844	.860	.877	.911	.945	.977	1.010	1.044	1.076	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.844	.858	.884	.911	.938	.960	.991	1.018	1.044	**10,000**
14,000	-----	-----	-----	-----	-----	.825	.835	.854	.873	.892	.911	.931	.949	.967	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.818	.831	.844	.858	.871	.884	.898	.911	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.810	.820	.831	.841	.852	.863	.873	.884	**25,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – OFFICE STRUCTURE



AVERAGE CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: These structures are small rural office rooms, typically servicing bulk oil plants, grain elevator facilities, cement plants, etc. The lower qualities are bare office structures with minimum lighting and no plumbing, while the better qualities include finished floors and ceilings and adequate fluorescent lighting and plumbing.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers or office equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 115.00	Block, concrete, structural clay tile, light roof structure	Drywall, acoustic tile, low-cost carpet or vinyl composition	Adequate lighting and plumbing	Wall furnace
	Average	84.50	Masonry bearing walls, light rafters, very plain	Low-cost partitions, acoustic tile, VCT, minimal counter and shelving	Minimum fluorescent lighting and plumbing	Electric wall heaters
D	Good	110.50	Stucco or wood siding on wood or steel studs, some trim	Drywall, acoustic tile, low-cost carpet or vinyl composition	Adequate lighting and plumbing	Wall furnace
	Average	79.50	Light stucco or siding on wood studs, very plain	Low-cost partitions, acoustic tile, VCT, minimal counter and shelving	Minimum fluorescent lighting and plumbing	Electric wall heaters
	Low cost	55.50	Wood, metal or cheap stucco on studs, metal or composition roof	Bare office space, low-cost paneling, asphalt tile	Few open fixtures, no plumbing	None
D POLE	Average	77.50	Metal panels, sheathing on pole frame or studs	Low-cost partitions, acoustic tile, VCT, minimal counter and shelving	Minimum fluorescent lighting and plumbing	Electric wall heaters
	Low cost	54.00	Metal panels, sheathing on pole frame	Bare office space, low-cost paneling, asphalt tile	Few open fixtures, no plumbing	None
S	Average	79.50	Steel panels, sheathing, on steel studs or self-framing	Low-cost partitions, acoustic tile, VCT, minimal counter and shelving	Minimum fluorescent lighting and plumbing	Electric wall heaters
	Low cost	56.00	Metal panels, sheathing on steel frame	Bare office space, low-cost paneling, asphalt tile	Few open fixtures, no plumbing	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – OFFICE STRUCTURE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

FLOOR STRUCTURE: Adjust for variations in floors as indicated in base square foot costs.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.94	$ 6.42	$ 8.34	$ 10.85
2,500	4.27	5.50	7.04	9.03
5,000	3.87	4.92	6.28	7.99
7,500	3.62	4.58	5.79	7.32
10,000	3.45	4.35	5.50	6.92
15,000	3.21	4.05	5.14	6.51

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 6.36	Package A.C. (short ductwork)	$ 14.05	Central refrigeration (zoned)	$ 12.00
Electric wall heaters	2.71			package (short ductwork)	9.20
Forced air furnace	7.13			Evaporative coolers	5.48
Hot water, baseboard/convector	12.70				
Space heaters, with fan	3.49				
radiant	4.09				
Steam (including boiler)	11.30				
without boiler	4.78			**VENTILATION ONLY**	
Wall or floor furnace	3.23			Vent. (blowers/ducts)	$ 2.01

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.058
9	.981	14	1.077
10	1.000 (base)	16	1.115
11	1.019	18	1.154
12	1.038	20	1.192

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	200	250	300	400	500	600	700	800	900	1000	Sq. Ft./Story
500	1.178	1.311	1.444	1.577	1.844	2.110	2.377	2.909	-----	-----	-----	-----	-----	-----	**500**
750	1.044	1.133	1.222	1.311	1.489	1.667	1.844	2.201	-----	-----	-----	-----	-----	-----	**750**
1,000	.980	1.044	1.110	1.178	1.311	1.444	1.577	1.844	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.911	.955	1.000	1.044	1.133	1.222	1.311	1.489	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.878	.911	.945	.977	1.044	1.110	1.178	1.311	-----	-----	-----	-----	-----	-----	**2,000**
2,500	.858	.884	.911	.938	.991	1.044	1.097	1.204	-----	-----	-----	-----	-----	-----	**2,500**
3,000	.843	.865	.889	.911	.955	1.000	1.044	1.133	-----	-----	-----	-----	-----	-----	**3,000**
3,500	-----	.854	.872	.892	.931	.967	1.006	1.080	1.157	-----	-----	-----	-----	-----	**3,500**
4,000	-----	-----	.860	.878	.911	.945	.977	1.044	1.110	1.178	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.844	.857	.884	.911	.938	.991	1.044	1.097	1.150	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.844	.860	.877	.911	.945	.977	1.010	1.044	1.076	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.844	.858	.884	.911	.938	.960	.991	1.018	1.044	**10,000**
14,000	-----	-----	-----	-----	-----	.825	.835	.854	.873	.892	.911	.931	.949	.967	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.818	.831	.844	.858	.871	.884	.898	.911	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.810	.820	.831	.841	.852	.863	.873	.884	**25,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – UTILITY



AVERAGE CLASS S

OCCUPANCY DESCRIPTION: Utility sheds are multipurpose structures that are usually lighter than typical industrial or warehouse buildings and form a large family of low cost utilitarian buildings which may use similar structural shells.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers.

SQUARE FOOT COST TABLE LIGHT COMMERCIAL UTILITY BUILDING

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 51.50	Concrete block, low-cost brick, wood rafters, roll-up doors	Small office, good slab floor, few extras	Good lighting, adequate plumbing	Electric wall heaters
	Average	37.00	Concrete block, light roof, overhead doors	Unfinished, concrete floor, minimum office	Adequate lighting and water outlets, few fixtures	None
D	Good	42.00	Heavy wood frame, siding or stucco, roll-up doors	Small office, good slab floor, few extras	Good lighting, adequate plumbing	Electric wall heaters
	Average	28.00	Open wood frame, exposed siding or stucco, overhead doors	Unfinished, concrete floor, minimum office	Adequate lighting and water outlets, few fixtures	None
	Low cost	19.50	Wood frame, board siding	Unfinished, light slab/asphalt	Minimum electric service	None
D POLE	Good	37.00	Good pole frame, color siding, roll-up doors, some trim	Small office, good slab floor, few extras	Good lighting, adequate plumbing	Electric wall heaters
	Average	24.00	Pre-engineered pole frame, metal siding, overhead doors	Unfinished, concrete floor, minimum office	Adequate lighting and water outlets, few fixtures	None
	Low cost	17.00	Light pole frame, metal siding	Unfinished, light slab/asphalt	Minimum electric service	None
S	Good	41.00	Good frame, color siding, rollup doors, some trim	Small office, good slab floor, few extras	Good lighting, adequate plumbing	Electric wall heaters
	Average	27.50	Pre-engineered frame, metal siding, overhead doors	Unfinished, concrete floor, minimum office	Adequate lighting and water outlets	None
	Low cost	20.00	Light steel frame, siding	Unfinished, light slab/asphalt	Minimum electric service	None
S SLANT WALL	Good	38.00	Good slant frame, color siding, roll-up doors, some trim	Small office, good slab floor, few extras	Good lighting, adequate plumbing	Electric wall heaters
	Average	25.50	Pre-engineered frame, metal siding, end doors	Unfinished, concrete floor, minimum office	Adequate lighting and water outlets, few fixtures	None
	Low cost	18.50	Light steel slant frame, siding	Unfinished, light slab/asphalt	Minimum electric service	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHEDS – UTILITY

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 **FLOOR STRUCTURE**: Adjust for variations in floors as indicated in base square foot costs.

	LOW	AVG.	GOOD	EXCL.
Compacted earth	$ 0.34	$ 0.40	$ 0.47	$ 0.57
Gravel	0.72	0.85	1.00	1.19
Asphalt, including base	2.74	3.46	4.38	5.55
Concrete slab	4.50	5.46	6.64	8.06
Add for vapor barrier	0.94	1.31	1.83	2.56

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.94	$ 6.42	$ 8.34	$ 10.85
2,500	4.27	5.50	7.04	9.03
5,000	3.87	4.92	6.28	7.99
7,500	3.62	4.58	5.79	7.32
10,000	3.45	4.35	5.50	6.92
15,000	3.21	4.05	5.14	6.51

2 **HEATING AND COOLING**

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 6.36	Package A.C. (short ductwork)	$ 14.05	Central refrigeration (zoned)	$ 12.00
Electric wall heaters	2.71			package (short ductwork)	9.20
Forced air furnace	7.13			Evaporative coolers	5.48
Hot water, baseboard/convector	12.70				
Space heaters, with fan	3.49				
radiant	4.09				
Steam (including boiler)	11.30				
without boiler	4.78			VENTILATION ONLY	
Wall or floor furnace	3.23			Vent. (blowers/ducts)	$ 2.01

3 **HEIGHT REFINEMENTS**

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.058
9	.981	14	1.077
10	1.000 (base)	16	1.115
11	1.019	18	1.154
12	1.038	20	1.192

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	125	150	200	250	300	350	400	500	600	700	800	900	1000	Sq. Ft./Story
500	1.178	1.311	1.444	1.577	1.844	2.110	2.377	2.909	-----	-----	-----	-----	-----	-----	500
750	1.044	1.133	1.222	1.311	1.489	1.667	1.844	2.201	-----	-----	-----	-----	-----	-----	750
1,000	.980	1.044	1.110	1.178	1.311	1.444	1.577	1.844	-----	-----	-----	-----	-----	-----	1,000
1,500	.911	.955	1.000	1.044	1.133	1.222	1.311	1.489	-----	-----	-----	-----	-----	-----	1,500
2,000	.878	.911	.945	.977	1.044	1.110	1.178	1.311	-----	-----	-----	-----	-----	-----	2,000
2,500	.858	.884	.911	.938	.991	1.044	1.097	1.204	-----	-----	-----	-----	-----	-----	2,500
3,000	.843	.865	.889	.911	.955	1.000	1.044	1.133	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.860	.878	.911	.945	.977	1.044	1.110	1.178	-----	-----	-----	-----	4,000
5,000	-----	-----	.844	.857	.884	.911	.938	.991	1.044	1.097	1.150	-----	-----	-----	5,000
10,000	-----	-----	-----	-----	-----	.844	.858	.884	.911	.938	.960	.991	1.018	1.044	10,000
12,000	-----	-----	-----	-----	-----	.833	.843	.867	.888	.911	.934	.955	.977	1.000	12,000
14,000	-----	-----	-----	-----	-----	.825	.835	.854	.873	.892	.911	.931	.949	.967	14,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – COMMUNITY



GOOD CLASS C



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: A community shopping center building is typically an intermediate group or cluster of stores (also called a plaza). It is generally a much larger and better designed project than a neighborhood center and typically supports at least one major anchor.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Storefronts, basic plumbing and electrical for a typical mix of tenants including service areas. Some roof, canopy or mansard overhang consistent with the quality.

NOT INCLUDED IN COSTS: Elevators, sprinklers, fixtures, furnishings or equipment, pedestrian mall, balconies or signs, major anchor buildings and public pedestrian mall concourse balconies or walkways.

AVERAGE TENANT COMPOSITION

The shopping center building costs found on this page represent group averages of a typical mix of tenants as listed below.

Retail – All general retail and specialty occupancies	44%
Discount – Discount, including large drug, furniture, hardware, garden, etc.	17%
Food – Market, convenience specialty, delicatessen, baker, florist, etc.	9%
Food Service – Restaurant, lounge, cafeteria, fast food outlets	9%
Commercial – Office, financial, medical, post office, etc.	7%
Personal services – Laundry, barber/beauty, health club, repair	7%
Recreational – Theater, skating, bowling, clubhouse, day care	5%
Miscellaneous – Storage and center service area including nonpublic accessways and restrooms	2%

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 213.00	Stone, face brick, fine ornamentation and displays	Best plaster, ornamental ceilings, paneling, ceramic, hardwood, carpet	Special lighting and outlets, good plumbing	Warm and cool air (zoned)
	Good	176.00	Face brick, best block/mansard ornamentation, good displays	Plaster and paneling, ornamental finishes, carpet, plain terrazzo	Extensive lighting and outlets, good plumbing	Warm and cool air (zoned)
	Average	140.00	Brick, block, stucco, best tilt-up, bearing or frame, adequate displays	Drywall or plaster, good tile ceilings, vinyl composition and carpet	Good lighting and outlets, standard fixtures	Package A.C.
	Low cost	116.50	Adequate fronts, block, tilt-up panels, big-box center	Painted walls and roof deck, some acoustic, VCT, stained concrete	Adequate lighting and outlets, good plumbing	Package A.C.
D	Excellent	201.00	Best masonry veneer, fine ornamentation and displays	Best plaster, ornamental ceilings, paneling, ceramic, hardwood, carpet	Special lighting and outlets, good plumbing	Warm and cool air (zoned)
	Good	166.00	Masonry veneer, staggered set- backs, good fronts, mansard fascia	Plaster and paneling, ornamental finishes, carpet, plain terrazzo	Extensive lighting and outlets, good plumbing	Warm and cool air (zoned)
	Average	131.50	Good stucco or siding, masonry trim, adequate front facade	Drywall or plaster, good tile ceilings, vinyl composition and carpet	Good lighting and outlets, standard fixtures	Package A.C.
S	Average	130.00	Sandwich panels, adequate display fronts, ornamentation	Acoustic tile, vinyl composition, some carpet and interior trim	Good lighting and outlets, standard fixtures	Package A.C.
CDS†	Display basement	89.50	Plaster interior	Store finish, acoustic tile, vinyl composition tile	Average store lighting and plumbing	Forced air
	Storage basement	49.00	Plaster interior	Painted ceiling and floors, few partitions	Exposed lighting, few outlets, drains	Space heaters
	Parking basement	54.00	Unfinished interior	Finished ceiling, concrete floor with hardener	Exposed lighting, few outlets, drains	Ventilation

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $ 8.60 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTER – COMMUNITY

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $66,500 to $109,000.

For detailed costs, see Section UIP 8.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 29.25	$ 38.25	$ 49.25	$ 64.50
Steel	26.75	36.75	50.50	69.50
Wood	22.55	30.75	41.75	57.00
Add for ornate finishes, balustrades	24.40	30.75	38.50	47.75
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$2,300 to $3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.936	14	1.042
10	.957	15	1.064
11	.979	16	1.085
12	1.000 (base)	18	1.127
13	1.021	20	1.170

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	150	200	250	300	400	500	600	800	900	1000	1200	1500	2000	Sq. Ft./Story
2,000	.969	1.079	1.183	1.283	1.376	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	.892	.969	1.042	1.115	1.183	1.322	-----	-----	-----	-----	-----	-----	-----	-----	**3,000**
4,000	.854	.912	.969	1.025	1.079	1.183	1.280	-----	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	.878	.924	.969	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	-----	-----	-----	.878	.925	.969	1.011	1.097	1.140	1.183	-----	-----	-----	**10,000**
14,000	-----	-----	-----	-----	-----	.870	.904	.937	1.000	1.030	1.060	1.121	-----	-----	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.854	.878	.924	.948	.969	1.011	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.831	.850	.887	.906	.925	.959	1.011	-----	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.831	.862	.878	.894	.925	.969	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.831	.843	.854	.878	.913	-----	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	-----	**50,000**
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.792	.807	.831	**100,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – COMMUNITY (ALTERNATE METHOD)

OCCUPANCY DESCRIPTION: Shell This occupancy, together with occupancy Interior Build-out, Community Shopping Center, allows you to individually price the shell and the tenant improvement costs for a community shopping center. This provides an alternative to occupancy Community Shopping Center, which includes both the shell and tenant improvement costs.

A community shopping center shell is typically an intermediate group or cluster of unfinished store spaces (also called a plaza). It is generally a much larger and better-designed project than a neighborhood center. It usually supports at least one major anchor. Typical anchors in a community center include secondary or junior department or retail-discount stores and major restaurant buildings.

Shopping center costs are for the strip or plaza shell buildings only and include only the necessary rough plumbing and electrical connections to provide for the operation of the satellites, including service areas and fixtures. Interior finish consists of bare space with concrete floor, demising walls and storefront entries commensurate with the quality.

Interior Build-out This occupancy, together with occupancy Shell, Community Shopping Center, allows you to individually price the shell and the tenant improvement costs for a community shopping center. This provides an alternative to occupancy Community Shopping Center, which includes both the shell and tenant improvement costs.

The costs represent group averages of a typical mix of tenant finishes only (excluding major anchor occupancies). The floor and ceiling finishes and finished electrical and plumbing are normally commensurate with the quality and type of general occupancies found within a center.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Storefronts and basic plumbing and electrical for a typical mix of tenants including service areas. Some roof, canopy or mansard overhang commensurate with the quality.

NOT INCLUDED IN COSTS: Elevators, sprinklers, fixtures, furnishings or equipment, pedestrian mall, balconies or signs.

SHELL - COMMUNITY SHOPPING CENTER

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 106.50	Stone, face brick, fine ornamentation and display fronts	Bare retail, floor slab, some service-storage area	Rough retail electrical and plumbing, some service fixtures	None
	Good	85.00	Face brick, best block, mansard ornamentation and display fronts	Bare retail, floor slab, some service-storage area	Rough retail electrical and plumbing, some service fixtures	None
	Average	68.50	Brick, block, stucco, best tilt-up, bearing or frame, adequate displays	Bare retail, floor slab, some bare partitioning	Rough retail electrical and plumbing, some service outlets	None
D	Excellent	97.00	Best masonry veneer, fine ornamentation and display fronts	Bare retail, floor slab, some service-storage area	Rough retail electrical and plumbing, some service fixtures	None
	Good	77.00	Masonry veneer, staggered setbacks, good fronts, mansard fascia	Bare retail, floor slab, some service-storage area	Rough retail electrical and plumbing, some service fixtures	None
	Average	61.50	Good stucco or siding, masonry trim, adequate front facade	Bare retail, floor slab, some bare partitioning	Rough retail electrical and plumbing, some service outlets	None
S	Average	57.50	Good metal panels, adequate display fronts, ornamentation	Bare retail, floor slab, some bare partitioning	Rough retail electrical and plumbing, some service outlets	None

COMMUNITY SHOPPING CENTER INTERIOR RETAIL BUILD-OUT

(SQUARE FOOT OF RETAIL FINISH)

TYPE	COST/ SQ. FT.	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
Excellent	$ 102.50	Best plaster, ornamental ceilings, paneling, carpet, tile or hardwood	Special lighting and outlets, good plumbing	Warm and cool air (zoned)
Good	88.00	Drywall or plaster, some paneling, ornamental finishes, carpet, plain terrazzo	Extensive lighting and outlets, good plumbing	Warm and cool air (zoned)
Average	71.00	Drywall or plaster, some good tile ceilings, vinyl composition and carpet	Adequate lighting and outlets per unit, small restrooms	Package A.C.
Low cost	52.00	Painted walls, drywall or acoustic tile, asphalt or composition tile, few partitions	Minimum lighting, outlets and plumbing per unit	Forced air

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – COMMUNITY (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $ 66,500 to $109,000.

For detailed costs, see Section UIP 8.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 29.25	$ 38.25	$ 49.25	$ 64.50
Steel	26.75	36.75	50.50	69.50
Wood	22.55	30.75	41.75	57.00
Add for ornate finishes, balustrades	24.40	30.75	38.50	47.75
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.936	14	1.042
10	.957	15	1.064
11	.979	16	1.085
12	1.000 (base)	18	1.127
13	1.021	20	1.170

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	150	200	250	300	400	500	600	800	900	1000	1200	1500	2000	Sq. Ft./Story
2,000	.969	1.079	1.183	1.283	1.376	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	.892	.969	1.042	1.115	1.183	1.322	-----	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	.854	.912	.969	1.025	1.079	1.183	1.280	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	.878	.924	.969	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	-----	-----	-----	.878	.925	.969	1.011	1.097	1.140	1.183	-----	-----	-----	10,000
14,000	-----	-----	-----	-----	-----	.870	.904	.937	1.000	1.030	1.060	1.121	-----	-----	14,000
20,000	-----	-----	-----	-----	-----	-----	.854	.878	.924	.948	.969	1.011	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	-----	.831	.850	.887	.906	.925	.959	1.011	-----	25,000
30,000	-----	-----	-----	-----	-----	-----	-----	.831	.862	.878	.894	.925	.969	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.831	.843	.854	.878	.913	-----	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	-----	50,000
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.792	.807	.831	100,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – MALL CONCOURSE





EXCELLENT CLASS A-B ENCLOSED MALL

OCCUPANCY DESCRIPTION: The mall costs are for the public pedestrian concourse areas only, exclusive of open well areas, and include stairs and ramps as necessary. This may consist of a single access way or it may include a number of subsidiary approach routes connecting to the main shopping corridor. These malls are limited to three types: open, covered and enclosed.

Open mall costs are for an open air pedestrian concourse, generally referred to as an arcade or courtyard.

Covered mall are covered but open to the air pedestrian concourses. Costs include floor and roof finishes and supports commensurate with the quality of the center buildings. Apply costs to covered areas only.

EXCELLENT CLASS A-B ENCLOSED MALL

Enclosed Mall are completely enclosed, climatized pedestrian concourses in which the enclosing walls are part of the shopping center buildings. One, two and three level malls are included in the averages. Costs include floor, ceiling, roof and entryway finishes commensurate with the quality of the anchor buildings.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Typical paving, lighting and permanent focal elements such as built-in seating, planters, center court wells, stages and fountains consistent with the quality of the center buildings. Allowances for escalators and elevators are included where designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, all kiosks, landscaping, skating rinks, and monumental sculpture and other individual works of art.

OPEN MALL

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
CDS	Excellent	$ 78.50	Themed pathways, courtyard, varied elevations and finishes	Heavily rock and water scaped, open pavilion, amphitheater	Best luminaries, good streams, waterfalls, ponds and fountains	None
	Very Good	53.50	Best pavers, wood decks, varied patterns and elevations	High-cost seating and planters, good stage or display areas	High-quality luminaires, good reflection ponds, fountains	None
	Good	36.50	Good pavers, decorative concrete	Good planters, some seating and display areas	Good outdoor lighting and fixtures, small fountains	None
	Average	24.95	Patterned concrete, some pavers	Adequate raised planters, benches	Adequate area lighting, fixtures	None
	Low-cost	17.05	Concrete, some decorative finish	Some low-cost planters, benches and tree grates	Minimum lighting and fixtures	None

COVERED MALL

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
CDS	Excellent	$ 84.50	Completely roofed, comparable to average enclosed mall	Exposed deck, joists, carpet, vinyl, wood, plain seating and planters	Adequate lighting & plumbing, standard fixtures, few outlets	None
	Good	71.00	Substantial structure, good mansard, finished soffit	Pavers, terrazzo, best ornamental concrete	High-quality illumination and fixtures	None
	Average	60.00	Metal or wood canopies, decorative supports	Terrazzo, decorative concrete	Good illumination and fixtures	None
	Low-cost	51.00	Light trellises or awnings, plain supports	Patterned concrete, some plain terrazzo or pavers	Adequate illumination and fixtures	None

ENCLOSED MALL

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 230.50	Fine fronts, metal and glass, usually part of a building	Ornamental ceilings, best pavers, terrazzo, ceramic tiled finishes	*Special lighting fixtures and effects, tiled restrooms	Complete H.V.A.C.
	Good	181.00	Good entries, brick or concrete, usually part of a building	Plaster or tiled ceiling, carpet, terrazzo, some ornamentation	*Good lighting and outlets, public restrooms and fixtures	Complete H.V.A.C.
	Average	143.50	Built-up roof, skylights, adequate entries and trim	Exposed deck, joists, carpet, vinyl, pavers, plain seating and food courts	*Adequate lighting and plumbing, standard fixtures, few outlets	Complete H.V.A.C.
	Low-cost	100.50	Plain entry, exposed roof deck,	Vinyl composition, no extras	Minimum lighting and plumbing	Complete H.V.A.C.
CDS	Excellent	195.50	High-cost roof, large arched entries and domed skylights	Best plaster, vaulted ceiling, pavers, terrazzo, tiled seating, food cluster	*Special lighting fixtures, deluxe restrooms & fixtures, fountains	Complete H.V.A.C.
	Good	148.00	Good parapets, skylights and storefront entryways	Plaster or drywall, plain pavers or terrazzo, center court wells	*Good indirect lighting, public restrooms, small fountains	Complete H.V.A.C.
	Average	112.50	Light built-up roof, small skylights and entries	Exposed deck, joists, carpet, vinyl, wood, plain seating and planters	*Adequate lighting & plumbing, standard fixtures, few outlets	Complete H.V.A.C.
	Low-cost	73.00	Plain entry, exposed roof deck	Vinyl composition, no extras	Minimum lighting and plumbing	Complete H.V.A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – MALL CONCOURSE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked.

For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Classes C/D/S	Sq. Ft. Costs
Excellent	$16.75	Excellent	$15.70
Good	15.85	Good	14.80
Average	15.05	Average	13.90

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
2,500	$ 5.25	$ 6.69	$ 8.55	$ 10.92
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
15,000	3.97	4.98	6.22	7.78
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19
75,000	3.10	3.81	4.67	5.74
100,000	2.95	3.63	4.46	5.46
150,000	2.78	3.41	4.17	5.11
200,000	2.69	3.27	3.95	4.78

2

MALL CONCOURSE HEATING, COOLING AND AIR CONDITIONING

These costs are averages of total installed cost of the entire heating or cooling installation including its prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated costs.

COMPLETE H.V.A.C

Classes A/B	Sq. Ft. Costs	Classes C/D/S	Sq. Ft. Costs
Excellent	$ 25.25	Excellent	$ 20.70
Good	23.55	Good	16.55
Average	21.90	Average	12.70
Low-cost	20.45	Low-cost	10.30
		Heat and ventilation only	6.52

3

HEIGHT REFINEMENTS

NOT APPLICABLE

4

AREA/PERIMETER MULTIPLIERS

NOT APPLICABLE

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – MIXED WITH RESIDENTIAL/OFFICE UNITS



GOOD CLASS C



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These structures are generally two to three story buildings with retail store or neighborhood center use on the first level and one or more residential/office units on the upper levels.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Fireplaces, balconies, porches or built-in appliances.

MIXED WITH RESIDENTIAL UNITS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 162.50	Face brick, best block, some mansard trim, good display fronts	Above-average retail finishes, good residential units above	Good lighting and outlets, standard fixtures per unit	Package A.C.
	Average	131.50	Brick or block, bearing or light frame, plain storefronts	Average retail mix and finishes, few extras, standard residential above	Adequate lighting and plumbing per unit	Package A.C.
	Low cost	97.00	Brick or block, bearing walls, very plain fronts, simple design	Low-cost general retail and basic residential above, no extras	Minimum lighting and plumbing per code	Forced air
C MILL	Average	151.50	Mill-type construction, heavy brick walls, trusses, good wood sash	Average retail mix and finishes, few extras, standard residential above	Adequate lighting, some plumbing per unit	Hot water
D	Good	153.00	Best siding, EIFS, masonry veneer, good trim and display fronts	Above-average retail finishes, good residential units above	Good lighting and outlets, standard fixtures per unit	Package A.C.
	Average	122.50	Stucco, siding, plain storefronts, minimum fenestration	Average retail mix and finishes, few extras, standard residential above	Adequate lighting and plumbing per unit	Package A.C.
	Low cost	90.00	Low-cost wood or stucco, very plain, small fronts, simple design	Low-cost general retail and basic residential above, no extras	Minimum lighting and plumbing per code	Forced air

MIXED WITH OFFICE UNITS

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 161.50	Face brick, best block, some mansard trim, good display fronts	Above-average retail finishes, good office units above	Good lighting and outlets, standard fixtures per unit	Package A.C.
	Average	133.50	Brick or block, bearing or light frame, plain storefronts	Average retail mix and finishes, few extras, standard offices above	Adequate lighting, some plumbing per unit	Package A.C.
	Low cost	102.00	Brick or block, bearing walls, very plain fronts, simple design	Low-cost general retail and basic offices above, no extras	Minimum lighting and plumbing per code	Forced air
C MILL	Average	152.50	Mill-type construction, heavy brick walls, trusses, good wood sash	Average retail mix and finishes, few extras, standard offices above	Adequate lighting, some plumbing per unit	Hot water
D	Good	151.50	Best siding, EIFS, masonry veneer, good trim and display fronts	Above-average retail finishes, good office units above	Good lighting and outlets, standard fixtures per unit	Package A.C.
	Average	126.00	Stucco, siding, plain storefronts, minimum fenestration	Average retail mix and finishes, few extras, standard offices above	Adequate lighting, some plumbing per unit	Package A.C.
	Low cost	95.00	Low-cost wood or stucco, very plain, small fronts, simple design	Low-cost general retail and basic offices above, no extras	Minimum lighting and plumbing per code	Forced air

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – MIXED WITH RESIDENTIAL/OFFICE UNITS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $ 66,500 to $109,000.

For detailed costs, see Section UIP 8.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	13	1.021
10	.957	14	1.042
11	.979	15	1.064
12	1.000 (base)	16	1.085
		18	1.127

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Sq. Ft./Story
1,000	1.183	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	.969	1.079	1.183	1.283	1.376	1.470	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	.892	.969	1.042	1.115	1.183	1.256	1.322	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	.854	.912	.969	1.025	1.079	1.131	1.183	1.280	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	.878	.924	.969	1.011	1.054	1.097	1.183	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	-----	-----	-----	.878	.901	.925	.969	1.011	1.054	1.097	1.140	1.183	-----	10,000
14,000	-----	-----	-----	-----	-----	-----	.870	.904	.937	.969	1.000	1.030	1.060	-----	14,000
20,000	-----	-----	-----	-----	-----	-----	-----	.854	.878	.901	.924	.948	.969	-----	20,000
25,000	-----	-----	-----	-----	-----	-----	-----	.831	.850	.868	.887	.906	.925	1.011	25,000
30,000	-----	-----	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.969	30,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.913	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.877	50,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – NEIGHBORHOOD



GOOD CLASS C

OCCUPANCY DESCRIPTION: A neighborhood shopping center building is typically a row of open stores comprising a single line of storefronts with individual service entrances to the rear. It is generally a small, one-story project which may or may not have a major anchor.



GOOD CLASS C

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Storefronts, basic plumbing and electrical for a typical mix of tenants. Some roof canopy or mansard overhang consistent with the quality is included.

NOT INCLUDED IN COSTS: Sprinklers, furnishings, equipment, pedestrian mall concourse or signs. Anchor buildings and public walkways are not included in the costs.

AVERAGE TENANT COMPOSITION

The shopping center building costs found on this page represent group averages of a typical mix of tenants as listed below.

Retail – All general retail and specialty occupancies	25%
Discount – Discount, including large drug, furniture, hardware, garden, etc.	15%
Food – Market, convenience specialty, delicatessen, baker, florist, etc.	17%
Food Service – Restaurant, lounge, cafeteria, fast food outlets	13%
Commercial – Office, financial, medical, post office, etc.	11%
Personal services – Laundry, barber/beauty, health club, repair	14%
Recreational – Theater, skating, bowling, clubhouse, day care	3%
Miscellaneous – Storage and center service area including non-public accessways and restrooms	2%

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 157.50	Stucco or brick on block, light frame, good roof, mansard and storefronts	Drywall, some paneling, good VCT and acoustic tile, carpet	Good lighting and outlets per unit, small restrooms	Package A.C.
	Average	132.50	Good block, tilt-up, bearing or light frame, plain fronts, some trim	Drywall, acoustic tile, VCT, some carpet and masonry partitions	Adequate lighting and outlets per unit, small restrooms	Package A.C.
	Low cost	102.00	Low-cost fronts, block, tilt-up panels, bearing walls	Painted walls, drywall or acoustic tile, asphalt tile, few partitions	Minimum lighting, outlets and plumbing per unit	Forced air
C MILL	Average	149.00	Mill-type construction, heavy brick walls, trusses, good wood sash	Plaster, VCT, wood, some carpet, wainscot and trim	Adequate lighting and outlets per unit, small restrooms	Hot water
D	Good	148.50	Stucco or brick veneer, light frame, good roof, mansard and storefronts	Drywall, some paneling, good VCT and acoustic tile, carpet	Good lighting and outlets per unit, small restrooms	Package A.C.
	Average	123.50	Pipe columns, web or bar joists, stucco or siding, plain fronts	Drywall, acoustic tile, vinyl composition, some carpet and trim	Adequate lighting and outlets per unit, small restrooms	Package A.C.
	Low cost	94.50	Low-cost wood or stucco, very plain, small fronts	Low-cost acoustic tile, asphalt tile, few partitions	Minimum lighting, outlets and plumbing per unit	Forced air
D POLE	Low cost	90.00	Pole frame, metal siding, finished interior, small fronts	Drywall, low-cost tile, few partitions	Minimum lighting, outlets and plumbing per unit	Forced air
S	Average	122.00	Good metal panels, some trim, plain fronts	Acoustic tile, vinyl composition, some carpet and interior trim	Adequate lighting and outlets per unit, small restrooms	Package A.C.
	Low cost	93.00	Metal siding, finished interior, small fronts	Drywall, low-cost tile, few partitions	Minimum lighting, outlets and plumbing per unit	Forced air
CDS†	Display basement	89.50	Plaster interior	Store finish, acoustic tile, vinyl composition tile	Average store lighting and plumbing	Forced air
	Storage basement	49.00	Painted interior	Painted ceiling and floors, few partitions	Exposed lighting, few outlets, drains	Space heaters

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.60 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – NEIGHBORHOOD

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $ 66,500 to $109,000.

For detailed costs, see Section UIP 8.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	13	1.021
10	.957	14	1.042
11	.979	15	1.064
12	1.000 (base)	16	1.085
		18	1.127

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Sq. Ft./Story
1,000	1.183	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	.969	1.079	1.183	1.283	1.376	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	.878	.924	.969	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**5,000**
7,000	-----	-----	.870	.904	.937	1.000	1.060	1.121	1.183	-----	-----	-----	-----	-----	**7,000**
10,000	-----	-----	-----	-----	.878	.925	.969	1.011	1.054	1.097	1.140	1.183	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.892	.931	.969	1.005	1.042	1.079	1.117	1.183	-----	**12,000**
14,000	-----	-----	-----	-----	-----	.870	.904	.937	.969	1.000	1.030	1.060	1.121	-----	**14,000**
18,000	-----	-----	-----	-----	-----	-----	.866	.892	.917	.943	.969	.992	1.040	-----	**18,000**
20,000	-----	-----	-----	-----	-----	-----	.854	.878	.901	.924	.948	.969	1.011	-----	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.925	.969	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.878	.913	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	**50,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – NEIGHBORHOOD (ALTERNATE METHOD)

OCCUPANCY DESCRIPTION: Shell This occupancy, together with occupancy Interior Build-out, Neighborhood Shopping Center, allows you to individually price the shell and the tenant improvement costs for a neighborhood shopping center. This provides an alternative to occupancy Neighborhood Shopping Center, which includes both the shell and tenant improvement costs.

A neighborhood shopping center shell is typically a row of open unfinished store spaces comprising a single line of storefronts with individual service entrances in the rear. It is generally a small, one-story project that may or may not support a major anchor. Typical anchors in a neighborhood center include major markets, large drug stores (discount stores) and banks.

The costs for this occupancy are for the strip shell buildings only and include only the necessary rough plumbing and electrical connections to provide for the operation of the satellites, including service areas. Interior finish consists of bare space with concrete floor, demising walls and storefront entries consistent with the quality.

Add interior retail space build-out (tenant improvement) costs using, Interior Space, Neighborhood Shopping Center.

Interior Build-out
This occupancy, together with occupancy Shell, Neighborhood Shopping Center, allows you to individually price the shell and the tenant improvement costs for a neighborhood shopping center. This provides an alternative to occupancy Neighborhood Shopping Center, which includes both the shell and tenant improvement costs.

The costs represent group averages of a typical mix of tenant buildout costs only (excluding major anchor occupancies). The floor and ceiling finishes and finished electrical and plumbing are normally consistent with the quality and type of general occupancies found within a center.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Storefronts, basic plumbing and electrical for a typical mix of tenants. Some roof, canopy or mansard overhang commensurate with the quality is included.

NOT INCLUDED IN COSTS: Sprinklers, furnishings, equipment, pedestrian mall concourse or signs.

SHELL - NEIGHBORHOOD SHOPPING CENTER

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 75.50	Stucco or brick on block, light frame, good roof, mansard and storefronts	Bare retail space, floor slab, some bare partitioning	Rough retail electrical and plumbing, some service outlets	None
	Average	61.50	Good block, tilt-up, bearing or light frame, plain fronts, some trim	Bare retail space, floor slab, some bare partitioning	Rough retail electrical and plumbing, some service outlets	None
	Low cost	50.00	Low-cost fronts, brick, block, tilt-up panels, bearing walls, small fronts	Bare retail space, floor slab, no service areas	Rough retail electrical and plumbing, few service outlets	None
	Cheap	37.00	Light block or tilt-up, built-up cover, minimal openings, no storefronts	Bare space, dirt floor, no interior demising walls	Rough retail electrical and plumbing, few service outlets	None
D	Average	54.50	Pipe columns, web or bar joists, stucco or siding, plain fronts	Bare retail space, floor slab, some bare partitioning	Rough retail electrical and plumbing, some service outlets	None
	Low cost	44.00	Low-cost wood or stucco, very plain, small fronts	Bare retail space, floor slab, no service areas	Rough retail electrical and plumbing, few service outlets	None
	Cheap	31.50	Low-cost siding, no storefronts	Bare space, dirt floor, see above	Rough-ins only, see above	None
D POLE	Low cost	38.00	Pole frame, light metal siding, finished, small plain fronts	Bare retail space, floor slab, no service areas	Rough retail electrical and plumbing, few service outlets	None
	Cheap	25.50	Pole frame, light metal utility siding, minimal openings, no storefronts	Bare retail space, dirt floor, no interior demising walls	Rough retail electrical and plumbing, few service outlets	None
S	Average	51.00	Sandwich panels, some trim, plain fronts	Bare retail space, floor slab, some bare partitioning	Rough retail electrical and plumbing, some service outlets	None
	Low cost	41.00	Light pre-eng. frame, metal siding, finished, small plain fronts	Bare retail space, floor slab, no service areas	Rough retail electrical and plumbing, few service outlets	None
	Cheap	27.50	Light pre-eng. bldg., no storefronts	Bare space, dirt floor, see above	Rough-ins only, see above	None

INTERIOR BUILD-OUT NEIGHBORHOOD SHOPPING CENTER

(SQUARE FOOT OF RETAIL FINISH)

TYPE	COST/ SQ. FT.	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
Excellent	$ 102.50	Best plaster, ornamental ceilings, paneling, carpet, tile or hardwood	Special lighting and outlets, good plumbing	Warm and cool air (zoned)
Good	88.00	Drywall or plaster, some paneling, ornamental finishes, carpet, plain terrazzo	Extensive lighting and outlets, good plumbing	Warm and cool air (zoned)
Average	71.00	Drywall or plaster, some good tile ceilings, vinyl composition and carpet	Adequate lighting and outlets per unit, small restrooms	Package A.C.
Low cost	52.00	Painted walls, drywall or acoustic tile, asphalt or composition tile, few partitions	Minimum lighting, outlets and plumbing per unit	Forced air

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – NEIGHBORHOOD (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $ 66,500 to $109,000.

For detailed costs, see Section UIP 8.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	13	1.021
10	.957	14	1.042
11	.979	15	1.064
12	1.000 (base)	16	1.085
		18	1.127

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Average Floor Area Sq. Ft./Story
1,000	1.183	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	.969	1.079	1.183	1.283	1.376	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	.878	.924	.969	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**5,000**
7,000	-----	-----	.870	.904	.937	1.000	1.060	1.121	1.183	-----	-----	-----	-----	-----	**7,000**
10,000	-----	-----	-----	-----	.878	.925	.969	1.011	1.054	1.097	1.140	1.183	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.892	.931	.969	1.005	1.042	1.079	1.117	1.183	-----	**12,000**
14,000	-----	-----	-----	-----	-----	.870	.904	.937	.969	1.000	1.030	1.060	1.121	-----	**14,000**
18,000	-----	-----	-----	-----	-----	-----	.866	.892	.917	.943	.969	.992	1.040	-----	**18,000**
20,000	-----	-----	-----	-----	-----	-----	.854	.878	.901	.924	.948	.969	1.011	-----	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.925	.969	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.878	.913	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	**50,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – REGIONAL



GOOD CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: A regional shopping center building complex contains a large number of satellite stores in strips, with one or more major department store buildings as anchors.

NOT INCLUDED IN COSTS: Sprinklers, furnishings, special display shelving or equipment or pedestrian mall concourse or signs. The major anchor buildings and pedestrian mall concourse walkways are not included in the cost.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Service elevators, storefronts, basic plumbing and electrical for a typical mix of tenants including all service areas. Elevators are included where designated with an asterisk (*).

AVERAGE TENANT COMPOSITION

The shopping center building costs found on this page represent group averages of a typical mix of tenants as listed below.

Retail – All general retail and specialty occupancies	47%
Discount – Discount, including large drug, furniture, hardware, garden, etc.	19%
Food – Market, convenience specialty, delicatessen, baker, florist, etc.	8%
Food Service – Restaurant, lounge, cafeteria, fast food outlets	8%
Commercial – Office, financial, medical, post office, etc.	4%
Personal services – Laundry, barber/beauty, health club, repair	3%
Recreational – Theater, skating, bowling, clubhouse, day care	4%
Miscellaneous – Storage and center service area including non-public accessways and restrooms	7%

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 293.50	Stone, face brick, best metal and glass, staggered display front	Best plaster and drywall, ornamental ceilings, paneling, carpet, hardwood	*Special lighting, many good outlets, plumbing and restrooms	Hot and chilled water (zoned)
	Good	239.00	Brick, concrete, or metal and glass, good displays	Good partitions, acoustic ceilings, terrazzo, carpet, vinyl tile	*Good lighting and outlets, adequate employees' restrooms	Warm and cool air (zoned)
	Storage basement	79.50	Painted interior walls	Painted floor and ceilings, adequate partitioning, service tunnel	Exposed lighting, few outlets, drains, restrooms	Space heaters
C	Excellent	246.50	Face brick, stone, staggered setbacks, fine display fronts	Plaster/drywall, ornamental ceilings, paneling, ceramic, carpet, hardwood	*Special lighting and outlets, good plumbing and restrooms	Hot and chilled water (zoned)
	Good	196.00	Steel frame, brick, best block, stucco, good displays	Good partitions, acoustic ceilings, terrazzo, carpet, vinyl tile	*Good lighting and outlets, adequate employees' restrooms	Warm and cool air (zoned)
	Average	158.50	Steel columns, web or bar joists, brick, block, tilt-up, adequate fronts	Acoustic ceilings, vinyl composition, some carpet and masonry partitions	*Adequate lighting and plumbing, minimum service facilities	Package A.C.
D	Excellent	231.00	Brick veneer, EIFS, staggered setbacks, fine display fronts	Plaster/drywall, ornamental ceilings, paneling, ceramic, carpet, hardwood	*Special lighting and outlets, good plumbing and restrooms	Hot and chilled water (zoned)
	Good	182.50	Steel or Glulam frame, best stucco or siding, good display fronts	Good partitions, acoustic ceilings, terrazzo, carpet, vinyl tile	*Good lighting and outlets, adequate employees' restrooms	Warm and cool air (zoned)
	Average	147.50	Wood frame or steel columns, masonry trim, adequate fronts	Plaster or drywall, acoustic tile, vinyl composition, some carpet and trim	*Adequate lighting and plumbing, minimum service facilities	Package A.C.
S	Average	147.00	Sandwich panels, metal and glass, good ornamentation, displays	Good acoustic tile, vinyl composition, some carpet and masonry partitions	*Adequate lighting and plumbing, minimum service facilities	Package A.C.
CDS†	Storage basement	53.50	Painted interior walls	Painted ceiling and floors, adequate partitions, service tunnel	Exposed lighting, few outlets, drains, restrooms	Space heaters

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.60 per square foot.
For basement stores, use 80% of comparable above ground center cost.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – REGIONAL

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked.
For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Classes C/D	Sq. Ft. Costs
Excellent	$ 2.32	Excellent	$1.95
Good	1.97	Good	1.71
		Average	1.53

ELEVATOR STOPS: For basements stops, add $9,700 to $14,600 per stop.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 29.25	$ 38.25	$ 49.25	$ 64.50
Steel	26.75	36.75	50.50	69.50
Wood	22.55	30.75	41.75	57.00
Add for ornate finishes, balustrades	24.40	30.75	38.50	47.75
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.70	$ 5.98	$ 7.59	$ 9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19
75,000	3.10	3.81	4.67	5.74
100,000	2.95	3.63	4.46	5.46
300,000	2.51	3.03	3.66	4.44
600,000	2.26	2.71	3.26	3.89

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	1.000 (base)	16	1.085
13	1.021	18	1.127
14	1.042	20	1.170
15	1.064	22	1.213
		24	1.255

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 400	450	500	550	600	800	1000	1200	1500	2000	2600	3000	5000	7000	Average Floor Area Sq. Ft./Story
10,000	.925	.948	.969	.990	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**10,000**
14,000	.870	.886	.904	.921	.937	1.000	1.060	1.121	-----	-----	-----	-----	-----	-----	**14,000**
20,000	-----	.843	.854	.866	.878	.924	.969	1.011	-----	-----	-----	-----	-----	-----	**20,000**
25,000	-----	-----	.831	.841	.850	.887	.925	.959	1.011	-----	-----	-----	-----	-----	**25,000**
30,000	-----	-----	-----	-----	.831	.862	.894	.925	.969	-----	-----	-----	-----	-----	**30,000**
50,000	-----	-----	-----	-----	-----	-----	.831	.850	.877	-----	-----	-----	-----	-----	**50,000**
70,000	-----	-----	-----	-----	-----	-----	-----	.817	.838	.872	-----	-----	-----	-----	**70,000**
100,000	-----	-----	-----	-----	-----	-----	-----	.792	.807	.831	.859	-----	-----	-----	**100,000**
150,000	-----	-----	-----	-----	-----	-----	-----	-----	.781	.799	.819	.831	-----	-----	**150,000**
300,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.760	.771	.780	.815	-----	**300,000**
400,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.759	.765	.795	.820	**400,000**
500,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.780	.802	**500,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – REGIONAL (ALTERNATE METHOD)

OCCUPANCY DESCRIPTION: Shell This occupancy, together with occupancy Interior Build-out, Regional Shopping Center, allows you to individually price the shell and the tenant improvement costs for a regional shopping center. This provides an alternative to occupancy Regional Shopping Center, which includes both the shell and tenant improvement costs.

A regional shopping center shell contains a large number of unfinished satellite store spaces in strips with one or more major department store buildings as anchors.

Shopping center costs are for the strip shell buildings only and include only the necessary rough plumbing and electrical connections to provide for the operation of the satellites, including service areas, but excluding storefronts and the public pedestrian concourse.

You can add interior retail space build-out (tenant improvement) costs using occupancy, Interior Space, Regional Shopping Center.

Interior Build-out
This occupancy, together with occupancy Shell, Regional Shopping Center, allows you to individually price the shell and the tenant improvement costs for a regional shopping center. This provides an alternative to occupancy Regional Shopping Center, which includes both the shell and tenant improvement costs.

The costs represent group averages of a typical mix of tenant finishes only (excluding major anchor occupancies). The storefronts, floor and ceiling finishes and finished electrical and plumbing are normally commensurate with the quality and type of general occupancies found within a center.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Service elevators, storefronts, basic plumbing and electrical for a typical mix of tenants including all service areas. Elevators are included where designated with an asterisk (*)

NOT INCLUDED IN COSTS: Sprinklers, furnishings, special display shelving or equipment or pedestrian mall concourse or signs.

SHELL - REGIONAL SHOPPING CENTER

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 117.00	Exterior stone, face brick, best metal and glass, no displays	Bare retail, typical center office finish, service corridors, delivery court	*Rough electrical and plumbing, service area finish, elevators	None
	Good	107.50	Exterior brick, concrete or metal and glass, no fronts	Bare retail, typical center office finish, service corridors, delivery court	*Rough electrical and plumbing, service area finish, elevators	None
C	Excellent	78.50	Exterior face brick, stone, no retail storefronts	Bare retail, typical center office finish, service corridors, delivery court	*Rough electrical and plumbing, service area finish, elevators	None
	Good	69.50	Steel frame, exterior brick, best block, stucco finish, no fronts	Bare retail, typical center office finish, service corridors, delivery court	*Rough electrical and plumbing, service area finish, elevators	None
	Average	61.00	Steel columns, web or bar joists, brick, block, tilt-up, no fronts	Bare retail space, plain center, service-delivery space finish	*Rough electrical and plumbing, service area finish, elevators	None
D	Good	60.00	Steel or Glulam frame, best stucco, EIFS or siding, no fronts	Bare retail, typical center office finish, service corridors, delivery court	*Rough electrical and plumbing, service area finish, elevators	None
	Average	52.50	Wood frame or steel columns, stucco or siding, masonry trim	Bare retail space, plain center, service-delivery space finish	*Rough electrical and plumbing, service area finish, elevators	None
S	Average	50.00	Sandwich panels, metal and glass, good trim, no fronts	Bare retail space, plain center, service-delivery space finish	*Rough electrical and plumbing, service area finish, elevators	None

INTERIOR BUILD - OUT REGIONAL SHOPPING CENTER

(SQUARE FOOT OF RETAIL FINISH)

TYPE	COST/ SQ. FT.	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
Excellent	$ 181.00	Best plaster, ornamental ceilings, paneling, carpet, tile or hardwood	Special lighting, many good outlets, plumbing and restrooms	Hot and chilled water (zoned)
Good	136.00	Drywall or plaster, some good tile ceilings, vinyl composition and carpet	Good lighting and outlets, adequate employees' restrooms	Warm and cool air (zoned)
Average	104.50	Painted walls, drywall or acoustic tile, asphalt or composition tile, few partitions	Adequate lighting and plumbing, minimum service facilities	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – REGIONAL (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked.
For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Classes C/D	Sq. Ft. Costs
Excellent	$ 2.32	Excellent	$ 1.95
Good	1.97	Good	1.71
		Average	1.53

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 29.25	$ 38.25	$ 49.25	$ 64.50
Steel	26.75	36.75	50.50	69.50
Wood	22.55	30.75	41.75	57.00
Add for ornate finishes, balustrades	24.40	30.75	38.50	47.75
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.70	$ 5.98	$ 7.59	$ 9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19
75,000	3.10	3.81	4.67	5.74
100,000	2.95	3.63	4.46	5.46
300,000	2.51	3.03	3.66	4.44
600,000	2.26	2.71	3.26	3.89

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	1.000 (base)	16	1.085
13	1.021	18	1.127
14	1.042	20	1.170
15	1.064	22	1.213
		24	1.255

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	400	450	500	550	600	800	1000	1200	1500	2000	2600	3000	5000	7000	Sq. Ft./Story
10,000	.925	.948	.969	.990	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**10,000**
14,000	.870	.886	.904	.921	.937	1.000	1.060	1.121	-----	-----	-----	-----	-----	-----	**14,000**
20,000	-----	.843	.854	.866	.878	.924	.969	1.011	-----	-----	-----	-----	-----	-----	**20,000**
25,000	-----	-----	.831	.841	.850	.887	.925	.959	1.011	-----	-----	-----	-----	-----	**25,000**
30,000	-----	-----	-----	-----	.831	.862	.894	.925	.969	-----	-----	-----	-----	-----	**30,000**
50,000	-----	-----	-----	-----	-----	-----	.831	.850	.877	-----	-----	-----	-----	-----	**50,000**
70,000	-----	-----	-----	-----	-----	-----	-----	.817	.838	.872	-----	-----	-----	-----	**70,000**
100,000	-----	-----	-----	-----	-----	-----	-----	.792	.807	.831	.859	-----	-----	-----	**100,000**
150,000	-----	-----	-----	-----	-----	-----	-----	-----	.781	.799	.819	.831	-----	-----	**150,000**
300,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.760	.771	.780	.815	-----	**300,000**
400,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.759	.765	.795	.820	**400,000**
500,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.780	.802	**500,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – REGIONAL DISCOUNT



GOOD CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: A regional discount or off-price shopping center contains a large number of satellite stores in strips. There may or may not be one or more major anchor department store buildings. These centers generally have a greater mix of large or big-box retail outlets, with minimum finishes compared to the standard regional center. Shopping center costs are for the strip buildings only and include all necessary plumbing and electrical connections to provide for the operation of the satellites, including service areas. The costs represent group average of a typical mix of tenants (excluding major anchor occupancies). The following are normally consistent with the quality and type of anchors they sup- port: the mix of general occupancies found within a center and their display or decorative storefronts.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Service elevators, storefronts, basic plumbing and electrical for a typical mix of tenants including all service areas. Elevators are included where designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, furnishings, special display shelving or equipment or pedestrian mall concourse or signs.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 183.50	Brick veneer, EIFS, light open frame, staggered setbacks, some ornament.	Drywall, some acoustic, ornamental ceilings, VCT, carpet, decorative conc.	Good lighting and fixtures, adequate service facilities	Warm and cool air (zoned)
	Average	151.50	Steel studs, stucco, EIFS, some exposed roof deck, adequate fronts	Painted walls, some ceiling ornament, some carpet, VCT, stained concrete	Adequate lighting and plumbing, restrooms and service facilities	Package A.C.
C	Excellent	164.00	Face block, brick, staggered setbacks, some ornamentation	Drywall, some acoustic, ornamental ceilings, VCT, carpet, decorative conc.	Good lighting and fixtures, adequate service facilities	Warm and cool air (zoned)
	Good	135.00	Steel frame, best tilt-up block, EIFS, stucco, some exposed deck	Drywall, some acoustic, standard carpet, VCT, concrete	Adequate lighting and plumbing, restrooms and service facilities	Package A.C.
	Average	115.00	Tilt-up, block, web or bar joists, exposed deck, adequate fronts	Painted interior, some ceiling and finished floors, stained concrete	Adequate lighting, minimum service facilities and plumbing	Package A.C.
D	Good	125.50	Steel or Glulam frame, stucco or brick veneer, some exp. roof deck	Drywall, some acoustic, standard carpet, VCT, concrete	Adequate lighting and plumbing, restrooms and service facilities	Package A.C.
	Average	107.00	Stucco or siding, open frame, exposed deck, adequate fronts	Painted interior, some ceiling and finished floors, stained concrete	Adequate lighting, minimum service facilities, plumbing	Package A.C.
S	Average	106.00	Steel panels, exposed frame, adequate fronts	Painted interior, some finished ceiling and floors, stained concrete	Adequate lighting, minimum service facilities, plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOPPING CENTERS – REGIONAL DISCOUNT

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $66,500 to $109,000.

For detailed costs, see Section UIP 8.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 29.25	$ 38.25	$ 49.25	$ 64.50
Steel	26.75	36.75	50.50	69.50
Wood	22.55	30.75	41.75	57.00
Add for ornate finishes, balustrades	24.40	30.75	38.50	47.75
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.70	$ 5.98	$ 7.59	$ 9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19
75,000	3.10	3.81	4.67	5.74
100,000	2.95	3.63	4.46	5.46
300,000	2.51	3.03	3.66	4.44
600,000	2.26	2.71	3.26	3.89

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	1.000 (base)	16	1.085
13	1.021	18	1.127
14	1.042	20	1.170
15	1.064	22	1.213
		24	1.255

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	400	450	500	550	600	800	1000	1200	1500	2000	2600	3000	5000	7000	Sq. Ft./Story
10,000	.925	.948	.969	.990	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**10,000**
14,000	.870	.886	.904	.921	.937	1.000	1.060	1.121	-----	-----	-----	-----	-----	-----	**14,000**
20,000	-----	.843	.854	.866	.878	.924	.969	1.011	-----	-----	-----	-----	-----	-----	**20,000**
25,000	-----	-----	.831	.841	.850	.887	.925	.959	1.011	-----	-----	-----	-----	-----	**25,000**
30,000	-----	-----	-----	-----	.831	.862	.894	.925	.969	-----	-----	-----	-----	-----	**30,000**
50,000	-----	-----	-----	-----	-----	-----	.831	.850	.877	-----	-----	-----	-----	-----	**50,000**
70,000	-----	-----	-----	-----	-----	-----	-----	.817	.838	.872	-----	-----	-----	-----	**70,000**
100,000	-----	-----	-----	-----	-----	-----	-----	.792	.807	.831	.859	-----	-----	-----	**100,000**
150,000	-----	-----	-----	-----	-----	-----	-----	-----	.781	.799	.819	.831	-----	-----	**150,000**
300,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.760	.771	.780	.815	-----	**300,000**
400,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.759	.765	.795	.820	**400,000**
500,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.780	.802	**500,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOWER ROOM BUILDINGS



AVERAGE/GOOD CLASS C

OCCUPANCY DESCRIPTION: These buildings are used to provide shower and dressing facilities. Interior walls are paint-enameled drywall or plaster and the floors are concrete. There is adequate lighting and plumbing. Better qualities include saunas and/or steam rooms and finished offices consistent with the quality.

INCLUDED IN COSTS: Built-in lockers, Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, therapy or recreational equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 254.00	Brick, concrete or metal panels, formed concrete	Finished interior, good tile or glazed surfaces, some extra facilities	Good lighting and plumbing, some extras	Wall furnace
C	Excellent	337.50	Stone, rustic trim or block	Good finish or under 1,000 sq. ft.	High-cost fixtures	Forced air
	Good	248.50	Decorative block and trim, heavy structure	Finished interior, good tile or glazed surfaces, extra facilities	Good lighting and plumbing, extra outlets and fixtures, sauna	Wall furnace
	Average	193.00	Steel frame or bearing walls, brick, block, concrete panels, some trim	Enameled walls, some wainscot, plaster ceiling, good concrete floor	Adequate lighting and plumbing, showers, lockers	Space heaters
	Low cost	149.50	Block, light roof, very plain	Low-cost finishes, few partitions, sealed concrete	Minimum lighting and plumbing, showers, dressing stalls	Space heaters
	Cheap	105.00	Low-cost block, top ventilation	Light slab, unfin. interior, camp facility	Minimum lights, fixtures and drains	None
D	Good	238.50	Steel or Glulam frame and joists, brick veneer, best stucco	Finished interior, good tile or glazed surfaces, extra facilities	Good lighting and plumbing, extra outlets and fixtures, sauna	Wall furnace
	Average	183.00	Wood frame or pipe columns, good stucco or siding, little trim	Plaster, enameled walls, some wainscot, good concrete floors	Adequate lighting and plumbing, showers, lockers	Space heaters
	Low cost	140.50	Low-cost stucco or siding	Low-cost finishes, few partitions, sealed concrete	Minimum lighting and plumbing, showers, dressing stalls	Space heaters
	Cheap	94.50	Box frame, plywood, boards, top ventilation	Light slab, unfinished interior, camp facility	Minimum lights and fixtures, few drains	None
DPOLE	Average	170.00	Pole frame, good metal panels, finished inside, little trim	Enameled walls, some wainscot, plaster ceiling, good concrete floor	Adequate lighting and plumbing, showers, lockers	Space heaters
	Low cost	134.00	Pole frame, metal siding, finished interior	Low-cost finishes, few partitions, sealed concrete	Minimum lighting and plumbing, showers, dressing stalls	Space heaters
S	Average	171.00	Pre-engineered, finished interior, insulation, little trim	Enameled walls, some wainscot, plaster ceiling, good concrete floor	Adequate lighting and plumbing, showers, lockers	Space heaters
	Low cost	134.00	Pre-engineered, metal siding, finished interior	Low-cost finishes, few partitions, sealed concrete	Minimum lighting and plumbing, showers, dressing stalls	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SHOWER ROOM BUILDING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	125	150	175	200	250	300	400	500	600	700	800	1000	1200	Sq. Ft./Story
500	1.298	1.407	1.516	1.625	1.734	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
1,000	1.079	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.006	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	-----	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	-----	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	1.116	-----	-----	-----	**6,000**
7,000	-----	-----	-----	-----	-----	.939	.955	.984	1.015	1.048	1.079	1.110	-----	-----	**7,000**
8,000	-----	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.052	1.079	1.134	-----	**8,000**
10,000	-----	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.013	1.036	1.079	1.123	**10,000**
12,000	-----	-----	-----	-----	-----	-----	.915	.934	.959	.968	.985	1.006	1.043	1.079	**12,000**

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SKATING RINKS - ICE



AVERAGE CLASS S



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: Large, open structures which include areas for ice skating, lobby, restrooms and equipment storage. Ice skating rinks include the basic floor structure. For ice skating, the cost must be adjusted to account for the ice surface.

Lounge, snack bar, locker or shower room facilities are consistent with the quality as indicated.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office and gathering and/or lounge areas.

NOT INCLUDED IN COSTS: Elevators, sprinklers, snack bar equipment, seating, lockers or ice making equipment or surface.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 297.50	Special architecture, good materials, good entrance and lobby	Top sports rink, spectator seating, many extra facilities and rooms	Best sports lighting, plumbing, many extra support facilities	Hot and chilled water (zone)
	Average	214.00	Heavy frame, metal or concrete panels, good architecture	Good rink and viewers' seating, multiple locker rooms, food service	Good sports lighting, restrooms and shower rooms	Warm and cool air (zoned)
A-B	Finished basement	193.50	Reinforced concrete, plaster interior	Exercise and dressing room finishes, some utility and storage	Adequate lighting and plumbing, showers and restrooms	Package A.C.
	Good mezzanine	65.50	Not included	Open, finished running track, plaster or drywall soffit	Average lighting, no plumbing	In building cost
	Average mezzanine	48.00	Not included	Open, finished floors and soffit, add for spectator seating	Average lighting, no plumbing	In building cost
C	Excellent	281.50	Best masonry, good curtain walls, good entrance and lobby	Top sports rink, spectator seating, many extra facilities and rooms	Best sports lighting, plumbing, many extra support facilities	Warm and cool air (zoned)
	Good	194.50	Brick or concrete, good entrance	Acoustic treatment, good viewers' seating, snack bar and locker rooms	Good lighting and restrooms, some entertainment-type lighting	Package A.C.
	Average	144.50	Block or brick, little trim	Gypsum board, acoustic tile, few extras	Adequate lighting and plumbing	Package A.C.
	Low-cost	109.50	Block or tilt-up	No dressing rooms or showers, adequate subfloor insulation	Minimum lighting and plumbing	Package A.C.
D	Excellent	272.50	Best masonry veneer, EIFS, good entrance and lobby	Top sports rink, spectator seating, many extra facilities and rooms	Best sports lighting, plumbing, many extra support facilities	Warm and cool air (zoned)
	Good	186.50	Brick veneer, good siding or stucco, trim, good entrance	Acoustic treatment, good viewers' seating, snack bar and locker rooms	Good lighting and restrooms, some entertainment-lighting	Package A.C.
	Average	136.50	Stucco or siding, some trim	Some gypsum board and acoustic tile, few extras	Adequate lighting and plumbing	Package A.C.
	Low-cost	103.00	Stucco or siding, very plain	No dressing rooms or showers, adequate subfloor insulation	Minimum lighting and plumbing	Package A.C.
D POLE	Low-cost	96.50	Pole frame, metal, finished inside	No dressing rooms or showers, adequate subfloor insulation	Minimum lighting and plumbing	Package A.C.
S	Excellent	274.50	Heavy frame, metal sandwich panels, good architecture	Top sports rink, spectator seating, many extra facilities and rooms	Best sports lighting, plumbing, many extra support facilities	Warm and cool air (zoned)
	Good	185.00	Insulated metal sandwich panels, steel frame, good entrance	Acoustic treatment, good viewers' seating, snack bar and locker rooms	Good lighting and restrooms, some entertainment-lighting	Package A.C.
	Average	134.50	Good metal panels and roof, some interior finish, trim	Some gypsum board and acoustic tile, few extras	Adequate lighting and plumbing	Package A.C.
	Low-cost	100.50	Single wall, finished interior	No dressing rooms or showers, adequate subfloor insulation	Minimum lighting and plumbing	Package A.C.
CDS	Finished basement	128.00	Reinforced concrete, plaster or drywall interior	Exercise and dressing room finishes, some utility and storage	Adequate lighting and plumbing, showers and restrooms	Forced air
	Good mezzanine	50.50	Not included	Open, finished running track, drywall soffit	Average lighting, no plumbing	In building cost
	Average mezzanine	34.25	Not included	Open, finished floors and soffit, add for spectator seating	Average lighting, no plumbing	In building cost

Artificially made ice rinks are manufactured in various forms, but all include pumps, compressors, refrigerant fluids and freezing (piping) systems.

Refrigeration piping system may be found:

1. Laid on bare earth.
2. On bare earth with a concrete curbing.
3. On a concrete slab with a curbing.
4. In a formed concrete slab.

Basic mechanical equipment, pumps, compressors, fluid and freezing (piping) installed in a standard-size hockey rink:

(85' x 200') $32.00 to $45.25 per sq. ft. of frozen area

Smaller rinks tend to be more expensive, stage-size rinks, etc.

$70.50 to $100.00 per sq. ft. of frozen area

Additive costs, per square foot of rink:	COST RANGE
Excavation	$ .60 – $ 1.25
Subsoil heating	2.81 – 3.74
Sand floor	1.38 – 2.27
Wood sleepers	.87 – 1.19
Gravel base, 4"	.88 – 1.53
Plastic water barrier	.63 – 1.00
Insulation, rigid, 2"	2.81 – 4.49
Concrete slab, 5" – 6"	6.79 – 8.99
Concrete curbing	.72 – 1.40
Dehumidifier, per unit	5.01 – 7.75
Side boards, wood frame	6.54 – 9.64
metal frame	5.85 – 12.85
add for spectator protection, clear shield	4.11 – 5.01
chain link	.87 – 1.83

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SKATING RINKS - ICE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

LOCKERS: per opening:

	COST RANGE		
Single Tier	$ 194.00	–	$ 374.00
Double	127.00	–	240.00
Triple	91.50	–	202.00
Box Type	66.00	–	123.00

ICE SKATING RINKS: See Section UIP 17 for ice-making equipment.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	.889	20	1.106
14	.945	22	1.158
16	1.000 (base)	24	1.210
18	1.054	28	1.313

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	250	300	350	400	450	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
5,000	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
8,000	-----	1.005	1.020	1.034	1.048	1.061	1.089	-----	-----	-----	-----	-----	-----	-----	**8,000**
10,000	-----	-----	.999	1.011	1.023	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	**10,000**
12,000	-----	-----	-----	.995	1.005	1.015	1.034	1.052	1.071	1.089	-----	-----	-----	-----	**12,000**
14,000	-----	-----	-----	.982	.992	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	**14,000**
18,000	-----	-----	-----	-----	.971	.979	.995	1.008	1.021	1.034	1.047	-----	-----	-----	**18,000**
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	**25,000**
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	**40,000**
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	**50,000**
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	**75,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SKATING RINKS - ROLLER



AVERAGE CLASS S

OCCUPANCY DESCRIPTION: Large, open structures which include areas for roller skating, lobby, restrooms and equipment storage. Roller skating rinks include the basic skating surface. For ice skating, the cost must be adjusted to account for the ice surface.

Lounge, snack bar, locker or shower room facilities are consistent with the quality as indicated.



GOOD CLASS C

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office and gathering and/or lounge areas.

NOT INCLUDED IN COSTS: Elevators, sprinklers, snack bar equipment, seating, lockers or ice making equipment or surface.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 180.50	Brick or concrete, good entrance	Acoustic treatment, good viewers' seating, snack bar and locker rooms	Good lighting and restrooms, some entertainment-type lighting	Package A.C.
	Average	136.00	Block or brick, little trim	Gypsum board, acoustic tile	Adequate lighting and plumbing	Package A.C.
	Low-cost	94.00	Block or tilt-up	Little or none, no dressing rooms	Minimum lighting and plumbing	Forced air
D	Good	172.50	Brick veneer, good siding or stucco, trim, good entrance	Acoustic treatment, good viewers' seating, snack bar and locker rooms	Good lighting and restrooms, some entertainment lighting	Package A.C.
	Average	128.50	Stucco or siding, some trim	Gypsum board, acoustic tile	Adequate lighting and plumbing	Package A.C.
	Low-cost	88.00	Stucco or siding, very plain	Little or none, no dressing rooms	Minimum lighting and plumbing	Forced air
D POLE	Low-cost	81.00	Pole frame, metal, finished inside	No dressing rooms or showers	Minimum lighting and plumbing	Forced air
S	Good	171.00	Metal sandwich panels, steel frame, good entrance	Acoustic treatment, good viewers' seating, snack bar and locker rooms	Good lighting and restrooms, some entertainment-type lighting	Package A.C.
	Average	126.50	Good metal panels and roof, some interior finish, trim	Some gypsum board and acoustic tile, few extras	Adequate lighting and plumbing	Package A.C.
	Low-cost	85.00	Single wall, finished interior	Little or none, no dressing rooms	Minimum lighting and plumbing	Forced air

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

SKATING RINKS - ROLLER

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

LOCKERS: per opening:

	COST RANGE		
Single Tier	$ 194.00	–	$ 374.00
Double	127.00	–	240.00
Triple	91.50	–	202.00
Box Type	66.00	–	123.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	.889	20	1.106
14	.945	22	1.158
16	1.000 (base)	24	1.210
18	1.054	28	1.313

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	250	300	350	400	450	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
5,000	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
8,000	-----	1.005	1.020	1.034	1.048	1.061	1.089	-----	-----	-----	-----	-----	-----	-----	**8,000**
10,000	-----	-----	.999	1.011	1.023	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	**10,000**
12,000	-----	-----	-----	.995	1.005	1.015	1.034	1.052	1.071	1.089	-----	-----	-----	-----	**12,000**
14,000	-----	-----	-----	.982	.992	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	**14,000**
18,000	-----	-----	-----	-----	.971	.979	.995	1.008	1.021	1.034	1.047	-----	-----	-----	**18,000**
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	**25,000**
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	**40,000**
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	**50,000**
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	**75,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – DEPARTMENT



GOOD CLASS C



GOOD CLASS B

OCCUPANCY DESCRIPTION: These buildings are often two or more stories designed to display and sell multiple lines of merchandise. The front elevations usually vary with the quality of the store. The higher-quality department stores have large, ornate display areas and fronts, while at the average quality level, the displays are relatively smaller. Most department stores have elevators and escalators to transport people to the various levels in the building. Floor coverings are a mixture of carpet and resilient tile, with the better qualities utilizing high traffic type floor finishes such as terrazzo. Department stores generally have combined heating and cooling systems and good store lighting.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Allowances are included for suitable office and employee areas and restroom facilities. Elevators are included where designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, furnishings, signs or equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$ 327.00	Stone, face brick, best metal and glass, fine display front	Best plaster, vinyl and ornamental finishes, terrazzo, carpet	*High luminosity, many good outlets, tiled restrooms	Hot and chilled water (zoned)
	Good	265.50	Brick, concrete, or metal and glass, good display front	Plaster, acoustic plaster or tile ceiling, carpet and vinyl floors	*Good lighting and outlets, tiled restrooms	Hot and chilled water (zoned)
	Average	205.50	Brick, concrete or metal and glass, shallow displays	Plaster or drywall, acoustic tile, rubber or vinyl tile, some carpet	*Adequate store lighting and restrooms	Warm and cool air (zoned)
B	Excellent	297.00	Stone, face brick, best metal and glass, fine display front	Best plaster, vinyl and ornamental finishes, terrazzo, carpet	*High luminosity, many good outlets, tiled restrooms	Hot and chilled water (zoned)
	Good	241.50	Brick, concrete, or metal and glass, good display front	Plaster, acoustic plaster or tile ceiling, carpet and vinyl floors	*Good lighting and outlets, tiled restrooms	Hot and chilled water (zoned)
	Average	186.00	Brick, concrete or metal and glass, shallow displays	Plaster or drywall, acoustic tile, rubber or vinyl tile, some carpet	*Adequate store lighting and restrooms	Warm and cool air (zoned)
A-B	Display basement	150.00	Plaster interior	Store finish, acoustic tile, vinyl composition or rubber tile	Average store lighting and plumbing	Warm and cool air (zoned)
	Storage basement	79.00	Painted interior	Painted floor and ceiling	Exposed lighting, restrooms	Space heaters
	Parking basement	84.00	Unfinished interior	Unfinished (service booth)	Exposed lighting, drains	Ventilation
	Display mezzanine	76.00	(in store cost)	Store finish, acoustic tile, carpet, vinyl composition	Average store lighting and plumbing	(in store cost)
	Office mezzanine	103.00	(in store cost)	Office finish, drywall or plaster, vinyl composition	Average office lighting and plumbing	(in store cost)
	Storage mezzanine	42.25	(in store cost)	Painted soffit, unfinished floor	Minimum, exposed lighting	(in store cost)
C	Excellent	263.00	Stone, face brick, metal or concrete panels, good front	Plaster, acoustic plaster or tile, carpet and vinyl floors	*High-intensity lighting, good quality plumbing	Hot and chilled water (zoned)
	Good	199.50	Brick, concrete, metal panels, good display front	Plaster, acoustic tile ceilings, carpet and vinyl tile	*Good lighting and outlets, good restrooms	Warm and cool air (zoned)
	Average	160.00	Brick, stucco on block, concrete panels, adequate displays	Drywall or plaster, acoustic tile, some carpet, vinyl or ceramic	*Adequate lighting and restrooms, competitive fixtures	Warm and cool air (zoned)
C	Display basement	89.50	Plaster interior†	Store finish, acoustic tile, vinyl composition tile	Average store lighting and plumbing	Forced air
	Storage basement	49.00	Painted interior†	Painted ceiling and floors, few partitions	Exposed lighting, few outlets, drains	Space heaters
	Parking basement	54.00	Unfinished interior†	Finished ceiling, concrete floor with hardener	Exposed lighting, few outlets, drains	Ventilation
	Display mezzanine	51.00	(in store cost)	Plaster or drywall soffit, carpet and vinyl composition	Average store lighting and plumbing	(in store cost)
	Office mezzanine	68.00	(in store cost)	Plaster or drywall soffit, office partitions and finish	Average office lighting and plumbing	(in store cost)
	Storage mezzanine	30.25	(in store cost)	Drywall soffit, wood floor, light storage	Minimum lighting, no plumbing	(in store cost)

†For fire-resistant Type I basements, with concrete slab separation under Class C units, add $ 8.60 per square foot.
MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – DEPARTMENT

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked.

For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Class C	Sq. Ft. Costs
Excellent	$ 14.10	Excellent	$ 10.55
Good	10.60	Good	7.91
Average	7.97	Average	5.92

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,700 to $ 14,600 per stop.

Loading docks, see Page CAL 398.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.70	$ 5.98	$ 7.59	$ 9.62
10,000	4.23	5.32	6.68	8.40
15,000	3.97	4.98	6.22	7.78
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19
75,000	3.10	3.81	4.67	5.74
100,000	2.95	3.63	4.46	5.46
200,000	2.69	3.27	3.95	4.78

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.957	16	1.085
11	.979	18	1.127
12	1.000 (base)	20	1.170
13	1.021	22	1.213
14	1.042	24	1.255
15	1.064		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	300	350	400	450	500	550	600	700	800	900	1000	1500	2000	2600	Sq. Ft./Story
5,000	1.011	1.054	1.097	1.140	1.183	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	.878	.901	.925	.948	.969	.990	1.011	1.054	1.097	1.140	1.183	-----	-----	-----	10,000
14,000	-----	-----	.870	.886	.904	.921	.937	.969	1.000	1.030	1.060	-----	-----	-----	14,000
20,000	-----	-----	-----	.843	.854	.866	.878	.901	.924	.948	.969	-----	-----	-----	20,000
25,000	-----	-----	-----	-----	.831	.841	.850	.868	.887	.906	.925	1.011	-----	-----	25,000
30,000	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.969	-----	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.913	-----	-----	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.877	-----	-----	50,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.825	.854	-----	80,000
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.807	.831	.859	100,000
150,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.781	.799	.819	150,000
200,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.780	.797	200,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – DISCOUNT



AVERAGE CLASS C DISCOUNT



AVERAGE CLASS S WAREHOUSE DISCOUNT

OCCUPANCY DESCRIPTION: Discount stores are built as large, open shell, one story structures. Even though areas in better discount stores are commonly divided by departments, they generally do not match the quality of construction found in department stores. The better qualities will have some storefront and well-finished interiors. Some storage and office area consistent with the overall quality of the building are included.

Warehouse discount stores are of warehouse construction with minimal interior partitioning. Membership stores typically fall into this category.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers, furnishings, trade fixtures, checkout or food service equipment or signs.

DISCOUNT STORES

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 127.00	Tilt-up panels, brick, good front, some ornamentation	Acoustic tile, vinyl tile, some built-ins and extras	Adequate lighting, outlets, and plumbing	Package A.C.
C	Good	125.50	Brick, good tilt-up, steel columns, wide spans	Plaster, good offices, acoustic tile, rubber or vinyl composition	Good lighting and outlets, good restrooms	Warm and cool air (zoned)
	Average	100.00	Brick or block, tilt-up, wood or steel columns and trusses	Drywall, small office area, acoustic tile, vinyl composition	Adequate lighting and restrooms, competitive fixtures	Package A.C.
	Low cost	74.50	Minimum block or tilt-up, pipe or wood columns	Painted exterior walls, minimum finish and office	Minimum lighting and plumbing	Forced air
D	Good	118.50	Brick or stone veneer, wood or steel columns and trusses	Plaster or drywall, good offices, good acoustic tile, vinyl or rubber	Good lighting and outlets, good restrooms	Warm and cool air (zoned)
	Average	93.00	Good stucco or siding on wood frame or heavy studs	Drywall, small office area, acoustic tile, vinyl composition	Adequate lighting and restrooms	Package A.C.
	Low cost	67.50	Stucco or siding on studs, small front	Drywall, few partitions, minimum finish and office	Minimum lighting and plumbing	Forced air
D POLE	Low cost	61.50	Pole frame, metal siding, lined, small front	Drywall, few partitions, minimum finish and office	Minimum lighting and plumbing	Forced air
S	Good	118.00	Good sandwich panels, frame, some ornamentation	Drywall, good offices, acoustic tile, rubber or vinyl composition	Good lighting and outlets, good restrooms	Warm and cool air (zoned)
	Average	91.00	Sandwich panels, plain front	Few partitions, small office area, acoustic tile and vinyl composition	Adequate lighting and restrooms	Package A.C.
	Low cost	65.00	Steel panels, partly finished on interior, small front	Drywall, few partitions, minimum finish and office	Minimum lighting and plumbing	Forced air

WAREHOUSE DISCOUNT STORES

CLASS	TYPE	COST/ SQ. Ft.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 101.50	Brick, block, tilt-up, open frame, plain front	Plaster or drywall, partitioned offices, good finished ceilings, vinyl floor	Fluorescent lighting, adequate outlets and restrooms, good extras	Package A.C.
	Average	75.00	Average block or tilt-up, open pipe or wood columns, some trim	Painted walls, some partitions, office area, vinyl composition and acoustic	Adequate lighting, restrooms, small snack bar or deli/fast food	Forced air
	Low cost	56.50	Cheap block or tilt-up, light panel roof, no glass storefront	Unfinished, shell type, few partitions, concrete floor	Minimum code throughout	Space heaters
D	Good	93.50	Stucco or siding, open frame, plain front	Plaster or drywall, partitioned offices, good finished ceilings, vinyl floor	Fluorescent lighting, adequate outlets and restrooms, good extras	Package A.C.
	Average	68.00	Stucco or siding, open frame, small front, some trim	Painted walls, some partitions, office area, vinyl composition and acoustic	Adequate lighting, restrooms, small snack bar or deli/fast food	Forced air
	Low cost	51.00	Siding on box frame or studs, very plain, no glass except entry door	Unfinished, shell type, few partitions, concrete floor	Minimum code throughout	Space heaters
D POLE	Low cost	49.00	Metal panels on light pole-frame, very plain, no glass storefront	Unfinished, shell type, few partitions, concrete floor	Minimum code throughout	Space heaters
S	Good	92.00	Steel frame, sandwich panels, plain front	Plaster or drywall, partitioned offices, good finished ceilings, vinyl floor	Fluorescent lighting, adequate outlets and restrooms, good extras	Package A.C.
	Average	69.00	Pre-engineered frame and siding, small front, some trim	Painted walls, some partitions, office area, vinyl composition and acoustic	Adequate lighting, restrooms, small snack bar or deli/fast food	Forced air
	Low cost	53.00	Siding on box frame/studs, very plain, no glass except entry door	Unfinished, shell type, few partitions, concrete floor	Minimum code throughout	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – DISCOUNT

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $66,500 to $109,000.

For detailed costs, see Section UIP 8.

For dock-height floors, add the cost per square foot to the base cost of the first floor.

Elevated on compacted fill: $5.08 to $10.15 per square foot. For cut and balance, use proportional cost.

Loading docks, see Page CAL 398.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.70	$ 5.98	$ 7.59	$ 9.62
10,000	4.23	5.32	6.68	8.40
15,000	3.97	4.98	6.22	7.78
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19
75,000	3.10	3.81	4.67	5.74
100,000	2.95	3.63	4.46	5.46
150,000	2.78	3.41	4.17	5.11

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.957	16	1.085
11	.979	18	1.127
12	1.000 (base)	20	1.170
13	1.021	22	1.213
14	1.042	24	1.255
15	1.064		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	300	350	400	450	500	550	600	700	800	900	1000	1200	1500	2000	Sq. Ft./Story
5,000	1.011	1.054	1.097	1.140	1.183	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	.878	.901	.925	.948	.969	.990	1.011	1.054	1.097	1.140	1.183	-----	-----	-----	**10,000**
15,000	-----	-----	.862	.877	.894	.909	.925	.955	.985	1.014	1.043	1.101	-----	-----	**15,000**
20,000	-----	-----	-----	.843	.854	.866	.878	.901	.924	.948	.969	1.011	-----	-----	**20,000**
25,000	-----	-----	-----	-----	.831	.841	.850	.868	.887	.906	.925	.959	1.011	-----	**25,000**
30,000	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.925	.969	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.878	.913	-----	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	-----	**50,000**
60,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.815	.831	.854	-----	**60,000**
80,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.807	.825	.854	**80,000**
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.792	.807	.831	**100,000**
125,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.792	.812	**125,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – DRUG STORES



GOOD CLASS C



EXCELLENT CLASS C

OCCUPANCY DESCRIPTION: These buildings include both small neighborhood pharmacies and the large chain discount-type with a variety of merchandise departments including convenience foods containing built-in refrigerators.

The better qualities have some storefront and well-finished interiors. Some storage and office areas consistent with overall quality of the building are included.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office and restroom facilities.

NOT INCLUDED IN COSTS: Furnishings, signs, display freezers and cooler or other trade fixtures, checkout or prescription and food service equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 186.00	Brick or concrete, usually part of a building	Plaster or drywall, acoustic tile, VCT, small private or chain outlet	Adequate lighting, outlets, plumbing and pharmacy	Warm and cool air (zoned)
C	Excellent	212.50	Face brick, best design, highly ornamental exterior	Typically best variety type, good acoustic, vinyl tile and carpet	Good departmental lighting, good pharmacy and convenience foods	Package A.C.
	Good	179.50	Brick, best block, stucco, good storefront and ornamentation	Drywall, acoustic tile, vinyl comp., includes typical mini-drive-thru	Good lighting and outlets, standard fixtures and pharmacy	Package A.C.
	Average	151.50	Brick or block, some mansard, parapet ornamentation	Drywall, some vinyl, acoustic tile, vinyl composition tile	Adequate lighting, restrooms, prescription and sundries departments	Package A.C.
	Low cost	128.50	Minimum block or cheap brick, bar joists, built-up roof	Painted exterior walls, minimum retail finish, typical low-end chain	Adequate lighting and pharmacy, small employees' restroom	Package A.C
D	Excellent	202.50	Face brick veneer, best design, highly ornamental exterior	Typically best variety type, good acoustic, vinyl tile and carpet	Good departmental lighting, good pharmacy and convenience foods	Package A.C.
	Good	169.50	Brick veneer or good siding, good frame and storefront entrance	Drywall, acoustic tile, vinyl comp., includes typical mini-drive-thru	Good lighting and outlets, standard fixtures and pharmacy	Package A.C
	Average	143.50	Stucco or siding, some mansard, parapet ornamentation	Drywall, some vinyl, acoustic tile, vinyl composition tile	Adequate lighting, restrooms, prescription and sundries departments	Package A.C.
	Low cost	121.50	Stucco or siding on studs, small front, little trim	Painted exterior walls, minimum retail finish, typical low-end chain	Adequate lighting, plumb. and pharmacy, small employees' restroom	Package A.C
S	Low cost	143.50	Steel panels, finished interior, small front, little trim	Painted exterior walls, minimum retail finish, typical low-end chain	Adequate lighting, plumb. and pharmacy, small employees' restroom	Package A.C

BASEMENTS AND MEZZANINES: Use costs listed under Stores - Department, Page CAL 358.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – DRUG STORES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $66,500 to $109,000.

For detailed costs, see Section UIP 8.

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,700 to $14,600 per stop.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	14	1.042
10	.957	15	1.064
11	.979	16	1.085
12	1.000 (base)	18	1.127
13	1.021	20	1.170

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Sq. Ft./Story
1,000	1.183	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	.969	1.079	1.183	1.283	1.376	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	.878	.924	.969	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**5,000**
7,000	-----	-----	.870	.904	.937	1.000	1.060	1.121	1.183	-----	-----	-----	-----	-----	**7,000**
10,000	-----	-----	-----	-----	.878	.925	.969	1.011	1.054	1.097	1.140	1.183	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.892	.931	.969	1.005	1.042	1.079	1.117	1.183	-----	**12,000**
14,000	-----	-----	-----	-----	-----	.870	.904	.937	.969	1.000	1.030	1.060	1.121	-----	**14,000**
18,000	-----	-----	-----	-----	-----	-----	.866	.892	.917	.943	.969	.992	1.040	-----	**18,000**
20,000	-----	-----	-----	-----	-----	-----	.854	.878	.901	.924	.948	.969	1.011	-----	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.925	.969	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.878	.913	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	**50,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – FLORIST SHOPS



LOW COST CLASS S



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These structures are convenience stores for the sale of cut flowers, with the better stores containing finished display areas for other gift merchandise.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Display cases, coolers and other trade fixtures.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 159.00	Brick or concrete, usually part of a building	Drywall or plaster, good acoustic, some vinyl tile and carpet	Adequate lighting outlets, adequate plumbing	Warm and cool air (zoned)
C	Excellent	184.00	Individual design, highly ornamental storefront	Plaster, acoustic tile, some terrazzo, carpet or vinyl, good trim	Special lighting, good fixtures and plumbing	Package A.C.
	Good	153.50	Brick, best block, stucco, good storefront and ornamentation	Drywall or plaster, good acoustic, some vinyl tile and carpet	Good lighting and outlets, standard fixtures	Package A.C.
	Average	120.00	Brick or block, some mansard, parapet ornamentation	Acoustic tile, some vinyl composition, sundry display area	Adequate lighting and outlets, small employees' restrooms	Forced air
	Low cost	95.00	Minimum block or cheap brick, low-cost front	Painted exterior walls, minimum finish, sealed concrete	Minimum code throughout, minimum display wiring	Space heaters
D	Excellent	173.00	Individual design, highly ornamental storefront	Plaster, acoustic tile, some terrazzo, carpet or vinyl, good trim	Special lighting, good fixtures and plumbing	Package A.C.
	Good	144.50	Brick veneer or good siding, good frame and front	Drywall or plaster, good acoustic, some vinyl tile and carpet	Good lighting and outlets, standard fixtures	Package A.C.
	Average	112.00	Stucco or siding, some mansard, parapet ornamentation	Acoustic tile, vinyl composition, sundry display area	Adequate lighting and outlets, small employees' restrooms	Forced air
	Low cost	88.50	Stucco or siding, small front	Drywall, few partitions, sealed slab	Minimum code throughout	Space heaters
D POLE	Low cost	84.50	Pole frame, metal, lined	Minimum finish and partitions, sealed concrete	Minimum code throughout, minimum display wiring	Space heaters
S	Low cost	86.50	Steel panels, partly finished interior	Minimum finish and partitions, sealed concrete	Minimum code throughout, minimum display wiring	Space heaters
CDS	Storage basement	49.00	Painted interior	Painted ceiling and floors, few partitions	Exposed lighting, few outlets, drains	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – FLORIST SHOP

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 **SPRINKLERS:** Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2 **HEATING AND COOLING**

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3 **HEIGHT REFINEMENTS**

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	14	1.042
10	.957	15	1.064
11	.979	16	1.085
12	1.000 (base)	18	1.127
13	1.021	20	1.170

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 75	100	125	150	175	200	225	250	275	300	350	400	450	500	Average Floor Area Sq. Ft./Story
500	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
1,000	1.079	1.183	1.283	1.376	1.470	1.566	1.660	1.753	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.969	1.042	1.115	1.183	1.256	1.322	1.384	1.445	1.506	1.566	-----	-----	-----	-----	**1,500**
2,000	.912	.969	1.025	1.079	1.130	1.183	1.233	1.283	1.330	1.376	1.470	-----	-----	-----	**2,000**
2,500	.878	.924	.969	1.011	1.054	1.097	1.140	1.183	1.227	1.270	1.351	1.420	-----	-----	**2,500**
3,000	.854	.892	.931	.969	1.005	1.042	1.079	1.115	1.149	1.183	1.256	1.322	1.380	-----	**3,000**
3,500	-----	.873	.907	.941	.973	1.006	1.038	1.070	1.101	1.131	1.194	1.253	1.300	-----	**3,500**
4,000	-----	.854	.883	.912	.941	.969	.997	1.025	1.052	1.079	1.131	1.183	1.232	1.280	**4,000**
5,000	-----	-----	.854	.878	.901	.924	.947	.969	.990	1.011	1.054	1.097	1.140	1.183	**5,000**
6,000	-----	-----	-----	-----	.873	.892	.912	.931	.950	.969	1.005	1.042	1.079	1.115	**6,000**
7,000	-----	-----	-----	-----	-----	.870	.887	.904	.921	.937	.969	1.000	1.030	1.060	**7,000**
8,000	-----	-----	-----	-----	-----	-----	-----	.883	.898	.912	.941	.969	.997	1.025	**8,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – LUXURY BOUTIQUE



GOOD CLASS C



AVERAGE CLASS D

OCCUPANCY DESCRIPTION: These are one or two story buildings designed for upscale retail sales and display. They usually have very high cost display and/or decorative fronts. This occupancy includes small stores generally with limited merchandise lines or specialty shops designed to cater to a select clientele.

The stores are usually designed with designated areas for servicing customers, employee operations, merchandise storage, display areas, office and restroom facilities, all with expensive exterior and interior finishes and special lighting.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office and restroom facilities.

NOT INCLUDED IN COSTS: Elevators, sprinklers, furnishings or equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 456.00	Best cut stone, face brick, metals, fine marble and display front	Best plaster and paneling, highly ornamental, stone, carpet, fine woods	Special lighting fixtures and effects, deluxe restrooms	Hot and chilled water (zoned)
	Average	359.50	Brick or concrete, high-cost metal, stone and display fronts	Plaster, acoustic plaster, ornamental detail, custom carpet, parquet, vinyl	Good lighting and outlets, good restrooms and fixtures	Warm and cool air (zoned)
C	Good	391.00	Custom marble, face brick, metal, fine ornamentation and displays	Best plaster, ornamental ceilings, paneling, stone, carpet, fine woods	Special lighting effects, deluxe restrooms and fixtures	Warm and cool air (zoned)
	Average	309.00	Fine brick, cut stone and trim, special site-built custom sash	Good plaster, ornamental detail, marble, custom carpet, parquet, vinyl	Some special fixtures, good restrooms	Warm and cool air (zoned)
	Low cost	243.00	Face brick, stone trim, best metal, tile, some custom sash fronts	Plaster, good detail, custom ceiling, wall and floor finishes	Top quality standard fixtures, electrical and plumbing	Heat pump system
D	Good	374.50	Custom face brick or stone veneer, fine ornamentation and displays	Best plaster, ornamental ceilings, paneling, stone, carpet, fine woods	Special lighting effects, deluxe restrooms and fixtures	Warm and cool air (zoned)
	Average	294.50	Fine masonry veneer and trims, special site-built sash and entries	Good plaster, ornamental detail, marble, custom carpet, parquet, vinyl	Some special fixtures, good restrooms	Warm and cool air (zoned)
	Low cost	231.00	Best siding, stucco, marble trim, best metal, tile, some custom sash	Plaster, good detail, custom ceiling, wall and floor finishes	Top quality standard fixtures, electrical and plumbing	Heat pump system

BASEMENTS AND MEZZANINES: Use costs listed under Stores - Department, Page CAL 358.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – LUXURY BOUTIQUE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $ 66,500 to $109,000.

For detailed costs, see Section UIP 8.

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,700 to $14,600 per stop.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.936	14	1.042
10	.957	15	1.064
11	.979	16	1.085
12	1.000 (base)	18	1.127
13	1.021	20	1.170

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Average Floor Area Sq. Ft./Story
1,000	1.183	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	.969	1.079	1.183	1.283	1.376	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	.878	.924	.969	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**5,000**
7,000	-----	-----	.870	.904	.937	1.000	1.060	1.121	1.183	-----	-----	-----	-----	-----	**7,000**
10,000	-----	-----	-----	-----	.878	.925	.969	1.011	1.054	1.097	1.140	1.183	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.892	.931	.969	1.005	1.042	1.079	1.117	1.183	-----	**12,000**
14,000	-----	-----	-----	-----	-----	.870	.904	.937	.969	1.000	1.030	1.060	1.121	-----	**14,000**
18,000	-----	-----	-----	-----	-----	-----	.866	.892	.917	.943	.969	.992	1.040	-----	**18,000**
20,000	-----	-----	-----	-----	-----	-----	.854	.878	.901	.924	.948	.969	1.011	-----	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.925	.969	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.878	.913	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	**50,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – MALL ANCHOR DEPARTMENT STORE



GOOD CLASS A-B



GOOD CLASS A-B

OCCUPANCY DESCRIPTION: These buildings are often one or two stories that are a transition between the pure discount store and the old full-line department store. The front elevations usually vary with the quality of the store. The higher quality anchor stores have some display areas and fronts while at the lower quality levels, the entries are relatively plain.

Most anchor stores have some elevators and escalators. Floor coverings are a mixture of carpet and resilient tile, with the better qualities utilizing high traffic type floor finishes such as terrazzo. Anchor stores generally have combined heating and cooling systems and good store lighting. Allowances are included for suitable office and employee areas and restroom facilities.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Allowances are included for suitable office and employee areas and restroom facilities. Elevators are included where designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, furnishings, signs or equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 197.50	Brick, concrete or metal and glass, adequate entry displays	Plaster or drywall, acoustic tile, rubber or vinyl, some wood or carpet	*Good display lighting and restrooms	Warm and cool air (zoned)
	Average	162.00	Brick, concrete or face block, some entry display and mall front trim only	Drywall, some covering, acoustic tile, some carpet, vinyl, wood or ceramic	* Adequate lighting, outlets and plumbing fixtures	Warm and cool air (zoned)
	Low cost	127.50	Brick, concrete, EIFS or block, little trim, plain entries, no displays	Painted, some drywall, acoustic and VCT, typical big box or jr. dept. store	*Adequate lighting and plumbing	Package A.C.
C	Good	161.50	Brick, stucco on block, concrete panels, adequate entry displays	Drywall or plaster, acoustic tile, some carpet, vinyl, wood or ceramic	*Good display lighting and restrooms	Warm and cool air (zoned)
	Average	131.50	Brick, concrete or face block, some entry display and mall front trim only	Drywall, some coverings, acoustic tile, some carpet or vinyl	*Adequate lighting, outlets and plumbing fixtures	Warm and cool air (zoned)
	Low cost	102.00	Tilt-up, concrete or block, some EIFS trim, plain entries, no displays	Painted, some drywall, acoustic and VCT, typical big box or jr. dept. store	*Adequate lighting and plumbing	Package A.C.
D	Good	152.50	Brick veneer, EIFS or best siding, adequate entry displays	Drywall or plaster, acoustic tile, some carpet, vinyl, wood or ceramic	*Good display lighting and restrooms	Warm and cool air (zoned)
	Average	123.50	Good siding, masonry trim, some entry displays and mall front trim only	Drywall, some coverings, acoustic tile, some carpet or vinyl	*Adequate lighting, outlets and plumbing fixtures	Warm and cool air (zoned)
	Low cost	95.00	Stucco, EIFS or siding, very plain, plain entries, no displays	Painted, some drywall, acoustic and VCT, typical big box or jr. dept. store	*Adequate lighting and plumbing	Package A.C.
S	Low cost	94.00	Metal panels, little trim, plain entries, no displays	Painted, some drywall, acoustic and VCT, typical big box or jr. dept. store	*Adequate lighting and plumbing	Package A.C.

NOTES: The best anchor stores approach the good or better department stores in cost, with many departments, best lighting, elevators and escalators and fine detail. If the design and amenities appear closer to department finish to anchor, the department store cost should be used.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – MALL ANCHOR DEPARTMENT STORE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked.

For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Classes C/D/S	Sq. Ft. Costs
Good	$ 7.82	Good	$ 5.71
Average	6.03	Average	4.45
Low	4.63	Low	3.47

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,700 to $14,600 per stop.

Loading docks, see Page CAL 398.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.70	$ 5.98	$ 7.59	$ 9.62
10,000	4.23	5.32	6.68	8.40
15,000	3.97	4.98	6.22	7.78
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19
75,000	3.10	3.81	4.67	5.74
100,000	2.95	3.63	4.46	5.46
200,000	2.69	3.27	3.95	4.78

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.957	16	1.085
11	.979	18	1.127
12	1.000 (base)	20	1.170
13	1.021	22	1.213
14	1.042	24	1.255
15	1.064		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	300	350	400	450	500	550	600	700	800	900	1000	1500	2000	2600	Sq. Ft./Story
5,000	1.011	1.054	1.097	1.140	1.183	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	.878	.901	.925	.948	.969	.990	1.011	1.054	1.097	1.140	1.183	-----	-----	-----	10,000
14,000	-----	-----	.870	.886	.904	.921	.937	.969	1.000	1.030	1.060	-----	-----	-----	14,000
20,000	-----	-----	-----	.843	.854	.866	.878	.901	.924	.948	.969	-----	-----	-----	20,000
25,000	-----	-----	-----	-----	.831	.841	.850	.868	.887	.906	.925	1.011	-----	-----	25,000
30,000	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.969	-----	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.913	-----	-----	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.877	-----	-----	50,000
80,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.825	.854	-----	80,000
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.807	.831	.859	100,000
150,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.781	.799	.819	150,000
200,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.780	.797	200,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – MEGA WAREHOUSE (DISCOUNT)



GOOD CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: These structures are very large discount stores of warehouse type construction, over 200,000 square feet, with minimal interior partitioning. Low quality structures are unfinished shell types with minimum code throughout. Better qualities have partitioned offices and some finished sales areas for specialty personal products, auto supplies, groceries and fast food/snack bar outlets consistent with the quality.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Furnishings, signs, trade fixtures and checkout or food service equipment.

MEGA WAREHOUSE STORES

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 94.00	Decorative block, tilt-up, open frame, small front, some trim	Painted walls, partitioned departments, partial finished ceilings, vinyl floors	Good fluorescent lighting, outlets and restrooms, good extras	Package A.C.
	Average	69.50	Open steel or wood frame, block or tilt-up, good roof, web joists	Painted walls, some partitions, offices, some vinyl composition and acoustic	Adequate lighting, restrooms, small snack bar or deli/fast food outlet	Forced air
	Low Cost	53.00	Large tilt-up, light panelized const., built-up roof, exposed insulation	Painted walls or unfinished, small offices, hardened slab throughout	Adequate lighting and plumbing fixtures, food services, snack bar	Space heaters
S	Average	63.50	Good steel frame, siding and fenestration, bar or web joints	Painted walls, some partitions, offices, some vinyl composition and acoustic	Adequate lighting, restrooms small snack bar or deli/fast food outlet	Forced air
	Low Cost	49.50	Rigid steel frame, good metal siding and roof, exposed insulation	Unfinished, small offices, hardened slab throughout, retail, auto, foods	Adequate lighting and plumbing fixtures, food services, snack bar	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – MEGA WAREHOUSE (DISCOUNT)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $ 66,500 to $109,000.

For detailed costs, see Section UIP 8.

For dock-height floors, add the cost per square foot to the base cost of the first floor.

Elevated on compacted fill: $5.08 to $10.15 per square foot. For cut and balance, use proportional cost.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
100,000	$ 2.95	$ 3.63	$ 4.46	$ 5.46
125,000	2.87	3.52	4.32	5.29
150,000	2.78	3.41	4.17	5.11
200,000	2.69	3.27	3.95	4.78
250,000	2.60	3.15	3.81	4.61
300,000	2.51	3.03	3.66	4.44
400,000	2.42	2.89	3.47	4.17
500,000	2.34	2.80	3.37	4.03
600,000	2.26	2.71	3.26	3.89
800,000	2.18	2.61	3.10	3.70
1,000,000	2.11	2.51	2.97	3.54

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.957	16	1.085	28	1.340
11	.979	18	1.127	30	1.383
12	1.000 (base)	20	1.170	32	1.425
13	1.021	22	1.213	34	1.468
14	1.042	24	1.255		
15	1.064	26	1.296		

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 1100	1200	1400	1600	2000	2400	2600	3000	3500	4000	5000	6000	7000	8000	Average Floor Area Sq. Ft./Story
70,000	.810	.817	.831	.845	.872	-----	-----	-----	-----	-----	-----	-----	-----	-----	**70,000**
80,000	.800	.807	.820	.831	.854	-----	-----	-----	-----	-----	-----	-----	-----	-----	**80,000**
90,000	-----	.799	.810	.821	.842	.861	-----	-----	-----	-----	-----	-----	-----	-----	**90,000**
100,000	-----	.792	.802	.812	.831	.850	.859	-----	-----	-----	-----	-----	-----	-----	**100,000**
150,000	-----	-----	-----	.785	.799	.812	.819	.831	-----	-----	-----	-----	-----	-----	**150,000**
200,000	-----	-----	-----	.767	.780	.792	.797	.807	.819	.831	-----	-----	-----	-----	**200,000**
250,000	-----	-----	-----	.759	.767	.778	.783	.792	.802	.812	-----	-----	-----	-----	**250,000**
300,000	-----	-----	-----	-----	.760	.767	.771	.780	.791	.799	.815	-----	-----	-----	**300,000**
350,000	-----	-----	-----	-----	-----	.761	.764	.770	.780	.789	.803	.817	-----	-----	**350,000**
400,000	-----	-----	-----	-----	-----	-----	.759	.765	.771	.780	.795	.807	.820	-----	**400,000**
450,000	-----	-----	-----	-----	-----	-----	-----	.760	.766	.773	.787	.799	.810	.821	**450,000**
500,000	-----	-----	-----	-----	-----	-----	-----	-----	.761	.767	.780	.792	.802	.812	**500,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – RETAIL



GOOD CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: These buildings are designed for retail sales and display and usually have display and/or decorative fronts. Both one and two story stores are included in the cost sampling. They include stores occupied by secondary department stores with limited merchandise lines, specialty shops and commercial buildings designed for a general occupancy. The stores usually are designed with designated areas for servicing customers, employee operations, merchandise storage and display areas. The higher quality store has expensive exterior and interior finishes, large display areas, attractive storefronts and special lighting. Lower quality structures have small displays, minimum finish and mechanical items.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office and restroom facilities.

NOT INCLUDED IN COSTS: Elevators, sprinklers, furnishings or equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$ 282.50	Stone, face brick, best metal, fine display fronts	Best plaster and paneling, highly ornamental, terrazzo, carpet	Special lighting fixtures and effects, deluxe restrooms	Hot and chilled water (zoned)
	Good	212.00	Brick or concrete, good metal or stone display front	Plaster, acoustic plaster or tile, carpet, plain terrazzo, vinyl	Good lighting and outlets, good restrooms and fixtures	Warm and cool air (zoned)
	Average	168.50	Brick or concrete, average metal display fronts	Plaster or drywall, acoustic tile, rubber or vinyl composition tile	Adequate lighting and outlets, small restrooms	Warm and cool air (zoned)
	Low cost	128.00	Block and brick, concrete panels, plain front	Very plain, acoustic tile, asphalt tile	Minimum lighting, outlets and plumbing fixtures	Hot water
B	Excellent	257.00	Stone, face brick, best metal walls, fine display fronts	Best plaster and paneling, highly ornamental, terrazzo, carpet	Special lighting fixtures and effects, deluxe restrooms	Hot and chilled water (zoned)
	Good	192.50	Brick or concrete, good walls, fine display fronts	Plaster, acoustic plaster or tile, carpet, plain terrazzo, vinyl	Good lighting and outlets, good restrooms and fixtures	Warm and cool air (zoned)
	Average	152.50	Brick or concrete, average metal display fronts	Plaster or drywall, acoustic tile, rubber or vinyl composition tile	Adequate lighting and outlets, small restrooms	Warm and cool air (zoned)
	Low cost	115.00	Block and brick, concrete panels, plain front	Very plain, acoustic tile, asphalt tile	Minimum lighting, outlets, and plumbing fixtures	Hot water
C	Excellent	214.50	Face brick, metal, fine ornamentation and displays	Best plaster, ornamental ceilings, paneling, terrazzo, carpet	Special lighting effects, good restrooms and fixtures	Warm and cool air (zoned)
	Good	159.50	Brick, stucco on block, best tilt-up, good display front	Plaster, acoustic plaster or tile ceilings, carpet, vinyl tile	Good lighting and outlets, adequate restrooms	Package A.C.
	Average	122.50	Brick, block, tilt-up, plain front, some ornamentation	Drywall/plaster, exposed masonry, acoustic tile, vinyl composition	Adequate lighting and outlets, small employees' restroom	Package A.C.
	Low cost	86.00	Low-cost brick, block, tilt-up, low-cost front	Painted walls, drywall or acoustic tile, asphalt tile	Minimum lighting and employees' restroom	Forced air
D	Excellent	204.50	Good brick or stone veneer, good front and entrance	Plaster, acoustic plaster or good mineral tile, carpet and vinyl	High-level lighting and outlets, good restrooms	Warm and cool air (zoned)
	Good	151.00	Good stucco or siding, brick veneer, good display front, ornamentation	Plaster, acoustic plaster or good acoustic tile, vinyl composition	Good lighting and outlets, restrooms, standard fixtures	Package A.C.
	Average	115.00	Stucco or siding, plain front, little ornamentation	Plaster or drywall, acoustic tile, vinyl composition, little trim	Adequate store lighting, restrooms, low cost fixtures	Package A.C.
	Low cost	80.00	Low-cost stucco, siding, very plain exterior	Drywall, cheap acoustic tile, asphalt tile, few partitions	Minimum lighting and outlets, minimum plumbing	Forced air
D POLE	Low cost	75.50	Pole frame, metal panels, lined and insulated, small front	Drywall, cheap acoustic tile, vinyl composition, few partitions	Minimum lighting and employees' restroom	Forced air
S	Good	151.00	Sandwich panels, metal & glass, ornamentation, good display front	Acoustic tile, vinyl composition and carpet, some trim	Good lighting and outlets, restrooms, standard fixtures	Package A.C.
	Average	114.00	Good colored panels, little ornamentation, plain front	Acoustic tile, vinyl composition, carpet, interior finish	Adequate store lighting, restrooms, low-cost fixtures	Package A.C.
	Low cost	78.00	Metal panels on light frame, finished interior, small front	Acoustic tile, gypsum board wall finish, vinyl composition	Minimum lighting and outlets, minimum plumbing	Forced air

BASEMENTS AND MEZZANINES: Use costs listed under Stores - Department, Page CAL 358, and for classes D, D pole and S, use class C

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES - RETAIL

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $66,500 to $109,000.

For detailed costs, see Section UIP 8.

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,700 to $14,600 per stop.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 6.02	$ 7.78	$ 10.10	$ 13.05
2,000	5.43	6.95	8.88	11.35
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62
10,000	4.23	5.32	6.68	8.40
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.936	14	1.042
10	.957	15	1.064
11	.979	16	1.085
12	1.000 (base)	18	1.127
13	1.021	20	1.170

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Average Floor Area Sq. Ft./Story
1,000	1.183	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	.969	1.079	1.183	1.283	1.376	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	.878	.924	.969	1.011	1.097	1.183	-----	-----	-----	-----	-----	-----	-----	**5,000**
7,000	-----	-----	.870	.904	.937	1.000	1.060	1.121	1.183	-----	-----	-----	-----	-----	**7,000**
10,000	-----	-----	-----	-----	.878	.925	.969	1.011	1.054	1.097	1.140	1.183	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.892	.931	.969	1.005	1.042	1.079	1.117	1.183	-----	**12,000**
14,000	-----	-----	-----	-----	-----	.870	.904	.937	.969	1.000	1.030	1.060	1.121	-----	**14,000**
18,000	-----	-----	-----	-----	-----	-----	.866	.892	.917	.943	.969	.992	1.040	-----	**18,000**
20,000	-----	-----	-----	-----	-----	-----	.854	.878	.901	.924	.948	.969	1.011	-----	**20,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.925	.969	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.878	.913	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	**50,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – WAREHOUSE SHOWROOM AND FOOD



GOOD CLASS C WAREHOUSE FOOD



LOW COST CLASS S SHOWROOM

OCCUPANCY DESCRIPTION: Warehouse showrooms are typical of the large walk through furniture outlets with a semifinished showroom and large carryout warehouse as one complete facility. Low quality structures are unfinished shell types with minimum code throughout. Better qualities have partitioned offices.

Warehouse food stores are large markets of warehouse construction offering limited perishable products, excluding any built in coolers or refrigerated storage. The better qualities will merge into the market occupancy, with a number of finished major product departments, but excluding any storage/display walk in boxes. The better qualities will also have partitioned offices. Low quality structures are unfinished shell types with minimum code throughout.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Furnishings, signs, trade fixtures and checkout or food service equipment.

WAREHOUSE SHOWROOM STORES

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 108.00	Brick, block, tilt-up, open frame, small front, some trim	Plaster or drywall, partitioned offices, finished showroom ceilings and floors	Good display and office lighting, adequate restrooms	Package A.C.
	Average	81.00	Average block or tilt-up, open pipe or wood columns	Painted walls, some partitions, office area, vinyl composition, sales cubicles	Display, warehouse and office lighting, small restrooms	Forced air
	Low cost	62.00	Cheap block or tilt-up, light panelized roof	Unfinished, shell type, few partitions, concrete floor, little display finish	Adequate lighting, minimum plumbing	Space heaters
D	Good	100.00	Stucco or siding, open frame, small front, some trim	Plaster or drywall, partitioned offices, finished showroom ceilings and floors	Good display and office lighting, adequate restrooms	Package A.C.
	Average	74.00	Stucco or siding, open frame, plain front	Painted walls, some partitions, office area, vinyl composition, sales cubicles	Display, warehouse and office lighting, small restrooms	Forced air
	Low cost	56.00	Siding on box frame or studs, very plain	Unfinished, shell type, few partitions, concrete floor, little display finish	Adequate lighting, minimum plumbing	Space heaters
D POLE	Low cost	54.50	Metal panels on light pole frame, very plain, some lining	Unfinished, shell type, few partitions, concrete floor, little display finish	Adequate lighting, minimum plumbing	Space heaters
S	Good	99.00	Steel frame, sandwich panels, small front, some trim	Plaster or drywall, partitioned offices, finished showroom ceilings and floors	Good display and office lighting, adequate restrooms	Package A.C.
	Average	75.00	Pre-engineered frame and siding, plain front	Painted walls, some partitions, office area, vinyl composition, sales cubicles	Display, warehouse and office lighting, small restrooms	Forced air
	Low cost	58.50	Single wall on light frame, very plain, some lining	Unfinished, shell type, few partitions, concrete floor, little display finish	Adequate lighting, minimum plumbing	Space heaters

WAREHOUSE FOOD STORES

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 130.00	Brick, block, tilt-up, open frame, plain front	Plaster or drywall, partitioned offices, finished ceilings, vinyl composition	Good lighting, plumbing for frozen food, snack bar, etc.	Package A.C.
	Average	98.50	Average block or tilt-up, open pipe or wood columns	Painted walls, some partitions, office area, some vinyl composition	Adequate lighting and plumbing, few extra services	Forced air
	Low cost	76.50	Cheap block or tilt-up, light panelized roof	Unfinished, shell type, few partitions, sealed concrete floor	Minimum food store lighting and plumbing, small restrooms	Space heaters
D	Good	120.00	Stucco or siding, open frame, plain front	Plaster or drywall, partitioned offices, finished ceilings, vinyl composition	Good lighting, plumbing for frozen food, snack bar, etc.	Package A.C.
	Average	90.50	Stucco or siding, open frame, small front	Painted walls, some partitions, office area, some vinyl composition	Adequate lighting and plumbing, few extra services	Forced air
	Low cost	70.00	Siding on box frame or studs, very plain	Unfinished, shell type, few partitions, sealed concrete floor	Minimum food store lighting and plumbing, small restrooms	Space heaters
D POLE	Low cost	64.50	Metal panels on light pole frame, very plain	Unfinished, shell type, few partitions, sealed concrete floor	Minimum food store lighting and plumbing, small restrooms	Space heaters
S	Good	119.00	Steel frame, sandwich panels, plain front	Plaster or drywall, partitioned offices, finished ceilings, vinyl composition	Good lighting, plumbing for frozen food, snack bar, etc.	Package A.C.
	Average	88.50	Pre-engineered frame and siding, small front	Painted walls, some partitions, office area, some vinyl composition	Adequate lighting and plumbing, few extra services	Forced air
	Low cost	66.50	Single wall on light frame, very plain	Unfinished, shell type, few partitions, sealed concrete floor	Minimum food store lighting and plumbing, small restrooms	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – WAREHOUSE SHOWROOM AND FOOD

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

DOCK-HEIGHT FLOORS: Add the cost per square foot to the base cost of the first floor.

Elevated on compacted fill: $5.08 to $10.15 per square foot. For cut and balance, use proportional cost.

For loading docks, see Page CAL 398.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.70	$ 5.98	$ 7.59	$ 9.62
10,000	4.23	5.32	6.68	8.40
15,000	3.97	4.98	6.22	7.78
20,000	3.81	4.75	5.94	7.39
30,000	3.58	4.46	5.51	6.86
50,000	3.34	4.10	5.04	6.19
75,000	3.10	3.81	4.67	5.74
100,000	2.95	3.63	4.46	5.46
150,000	2.78	3.41	4.17	5.11

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.957	16	1.085
11	.979	18	1.127
12	1.000 (base)	20	1.170
13	1.021	22	1.213
14	1.042	24	1.255
15	1.064	28	1.340

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	300	350	400	450	500	550	600	700	800	900	1000	1200	1500	2000	Sq. Ft./Story
5,000	1.011	1.054	1.097	1.140	1.183	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	.878	.901	.925	.948	.969	.990	1.011	1.054	1.097	1.140	1.183	-----	-----	-----	**10,000**
15,000	-----	-----	.862	.877	.894	.909	.925	.955	.985	1.014	1.043	1.101	-----	-----	**15,000**
20,000	-----	-----	-----	.843	.854	.866	.878	.901	.924	.948	.969	1.011	-----	-----	**20,000**
25,000	-----	-----	-----	-----	.831	.841	.850	.868	.887	.906	.925	.959	1.011	-----	**25,000**
30,000	-----	-----	-----	-----	-----	-----	.831	.847	.862	.878	.894	.925	.969	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	.820	.831	.843	.854	.878	.913	-----	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.831	.850	.877	-----	**50,000**
60,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.815	.831	.854	-----	**60,000**
80,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.807	.825	.854	**80,000**
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.792	.807	.831	**100,000**
125,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.792	.812	**125,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – WINERY (TASTING - DISPLAY)



AVERAGE/GOOD CLASS D

OCCUPANCY DESCRIPTION: These generally rural style structures, are designed for the display, tasting and sale of wines directly from the vineyard, with the better shops containing finished display areas for other gift merchandise. Lower quality structures are simple sales barn outlets, while the better quality structures are highly decorative estate type facilities that can include some food services. Built-in refrigerated storage is included consistent with the quality.

The following are not included in the costs: Display cases and coolers, kitchen and bar equipment, other trade fixtures and signs.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, furnishings or equipment.

WINERY (TASTING – DISPLAY) SHOPS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 453.50	Individual design, highly ornamental, ashlar or face brick	Custom ceilings and plaster, inlaid parquet, matched stones and woods	Special lighting, custom fixtures and plumbing, best estate type	Hot and chilled water (zoned)
	Good	270.00	Best masonry, much fine trim and fenestration, heavy roof	High-quality detail, good wall and ceiling finishes, hardwoods, tile	Good lighting and outlets, some custom fixtures, food prep. area	Warm and cool air (zoned)
	Average	165.00	Brick or block, some mansard parapet ornamentation, good front	Acoustic tile, vinyl composition, paneling, some sundry display area	Adequate store lighting, restrooms, service fixtures and storage	Heat pump system
	Low cost	102.50	Minimum block or cheap brick, low-cost entry	Painted exterior walls, minimum finish, sealed concrete, vinyl composition	Minimum lighting and outlets, minimum plumbing, cooler room	Package A.C.
D	Excellent	436.00	Individual design, highly ornamental, stone or face brick veneer	Custom ceilings and plaster inlaid parquet, matched stones and woods	Special lighting, custom fixtures and plumbing, best estate type	Hot and chilled water (zoned)
	Good	254.50	Best siding, EIFS, masonry veneers, much fine trim and fenestration	High-quality detail, good wall and ceiling finishes, hardwood, tile	Good lighting and outlets, some custom fixtures, food prep. area	Warm and cool air (zoned)
	Average	154.00	Stucco or siding, some parapet ornamentation, half-timber framing	Acoustic tile, vinyl composition, paneling, some sundry display area	Adequate store lighting, restrooms, service fixtures and storage	Heat pump system
	Low cost	95.00	Stucco or siding, small entry	Drywall, few partitions, sealed slab, vinyl composition tile	Minimum lighting and outlets, minimum plumbing, cooler room	Package A.C.
D POLE	Low cost	90.50	Pole frame, metal, partial finished interior, small entry	Minimum finish and partitions, sealed concrete, vinyl composition	Minimum lighting and outlets, minimum plumbing, cooler room	Package A.C.
S	Average	151.00	Good colored panels, little ornamentation, good front and trim	Acoustic tile, vinyl composition, paneling, some sundry display area	Adequate store lighting, restrooms, service fixtures and storage	Heat pump system
	Low cost	93.00	Metal panels on light frame, partial finished interior, small entry	Acoustic tile, gypsum board wall finish, vinyl composition and sealed slab	Minimum lighting and outlets, minimum plumbing, cooler room	Package A.C.
CDS	Finished Basement	104.50	Reinforced concrete, plaster or drywall interior	Utility and tasting room finishes	Adequate lighting/plumbing, utility outlets and fixtures	Forced air
	Utility Basement	61.50	Painted interior	Paint only, some partitions	Adequate lighting and outlets, drains	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

STORES – WINERY (TASTING - DISPLAY)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

NOTES: Highly decorative estate type structures can run 100% to 200% more. Wine storage caves will cost $140.00 to $316.00 per square foot.

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Multiples with basements, add 40% to extend the foundation to the basement level. Custom oversized units can run 100% to 200% more.

Type	COST RANGE
One-story	$ 3,675 – $ 11,800
Two-story	4,655 – 14,170

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
500	$ 6.67	$ 8.71	$ 11.41	$ 14.89
1,000	6.02	7.78	10.10	13.05
1,500	5.66	7.28	9.35	12.00
2,000	5.43	6.95	8.88	11.35
2,500	5.25	6.69	8.55	10.92
3,000	5.11	6.49	8.28	10.55
4,000	4.86	6.20	7.90	10.04
5,000	4.70	5.98	7.59	9.62

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.23	Package A.C. (short ductwork)	$ 18.25	Central refrigeration (zoned)	$ 15.15
Electric wall heaters	3.35	Warm and cool air (zoned)	23.95	package (short ductwork)	10.10
Forced air furnace	8.97	Hot/chilled water (zoned)	36.25	Central evaporative	6.27
Hot water, baseboard/convector	16.60	Heat pump system	20.95	Pkg. refrig.	$ 2,650 to $ 3,400 per ton capacity
radiant floor/ceiling	18.00			Evap. coolers.	$ 368 to $ 610 per MCFM capacity
Space heaters, with fan	4.36				
radiant	5.23				
Steam (including boiler)	13.35				
without boiler	11.45	Small indiv. heat pumps cost	$ 2,300 to $ 3,300	**VENTILATION ONLY**	
Wall or floor furnace	3.76	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.56

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.915	14	1.042
10	.957	15	1.064
11	.979	16	1.085
12	1.000 (base)	18	1.127
13	1.021	20	1.170

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	175	200	225	250	275	300	350	400	450	500	Sq. Ft./Story
500	1.376	1.566	1.753	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
1,000	1.079	1.183	1.283	1.376	1.470	1.566	1.660	1.753	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.969	1.042	1.115	1.183	1.256	1.322	1.384	1.445	1.506	1.566	-----	-----	-----	-----	**1,500**
2,000	.912	.969	1.025	1.079	1.130	1.183	1.233	1.283	1.330	1.376	1.470	-----	-----	-----	**2,000**
2,500	.878	.924	.969	1.011	1.054	1.097	1.140	1.183	1.227	1.270	1.351	1.420	-----	-----	**2,500**
3,000	.854	.892	.931	.969	1.005	1.042	1.079	1.115	1.149	1.183	1.256	1.322	1.380	-----	**3,000**
3,500	-----	.873	.907	.941	.973	1.006	1.038	1.070	1.101	1.131	1.194	1.253	1.300	-----	**3,500**
4,000	-----	.854	.883	.912	.941	.969	.997	1.025	1.052	1.079	1.131	1.183	1.232	1.280	**4,000**
5,000	-----	-----	.854	.878	.901	.924	.947	.969	.990	1.011	1.054	1.097	1.140	1.183	**5,000**
6,000	-----	-----	-----	-----	.873	.892	.912	.931	.950	.969	1.005	1.042	1.079	1.115	**6,000**
7,000	-----	-----	-----	-----	-----	.870	.887	.904	.921	.937	.969	1.000	1.030	1.060	**7,000**
8,000	-----	-----	-----	-----	-----	-----	-----	.883	.898	.912	.941	.969	.997	1.025	**8,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.