TENNIS CLUBS – INDOOR



AVERAGE CLASS S

OCCUPANCY DESCRIPTION: These are shell-type structures which include tennis court facilities. The cost of individual facilities can vary greatly depending on the type of structure and its appointments, including the extent of the lounge, refreshment, exercise, shower and spectator areas. Costs are given for the entire facility excluding any furnishings and equipment. Lower cost facilities are generally constructed with a rigid steel or wood frame and an exterior cover of either wood or steel siding. These facilities have minimum lighting and plumbing and no dressing rooms or showers.

Clear heights typically vary between 20 and 28 feet. The average quality enclosed courts use either steel sandwich panels or masonry exterior walls and include dressing room and shower facilities. Clear heights typically vary between 24 and 32 feet. The best qualities include high cost lighting and fixtures, lounge areas, snackbar facilities, a sales area where equipment can be sold, showers, dressing rooms and saunas. Clear heights vary between 30 and 35 feet.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office and gathering areas.

NOT INCLUDED IN COSTS: Elevators, sprinklers, lockers, furnishings, exercise equipment or kitchen equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 137.00	Brick or concrete, good entrance	Plaster or drywall, carpeting, good lounge and court areas, gym	Good sports lighting, restrooms, sauna, shower and locker rooms	Package A.C.
	Average	100.00	Brick or block, concrete panels, some ornamentation	Drywall, concrete courts, snack bar area, exercise facilities	Adequate lighting, plumbing, showers, add for pool or spa	Forced air
	Low-cost	68.00	Block or tilt-up	Little or none, no dressing rooms	Minimum lighting and plumbing	Space heaters
D	Good	126.00	Brick veneer, best siding or stucco, trim, good entrance	Plaster or drywall, carpeting, good lounge and court areas, gym	Good sports lighting, restrooms, sauna, shower and locker rooms	Package A.C.
	Average	91.50	Good stucco or siding, some brick or stone trim	Drywall, concrete courts, snack bar area, exercise facilities	Adequate lighting, plumbing, showers, add for pool or spa	Forced air
	Low-cost	61.00	Stucco or siding, very plain	Little or none, no dressing rooms	Minimum lighting and plumbing	Space heaters
D POLE	Low-cost	54.00	Pole frame, metal single wall, very plain	No dressing rooms or showers, few facilities	Minimum lighting and restrooms	Space heaters
S	Good	125.00	Insulated metal sandwich panels, steel frame, good entrance	Plaster or drywall, carpeting, good lounge and court areas, gym	Good sports lighting, restrooms, sauna, shower and locker rooms	Package A.C.
	Average	89.50	Good metal panels and roof, some interior finish, trim	Drywall, concrete courts, snack bar area, exercise facilities	Adequate lighting, plumbing, showers, add for pool or spa	Forced air
	Low-cost	58.50	Single wall, very plain	Little or none, no dressing rooms	Minimum lighting and plumbing	Space heaters
CDS	Average mezzanine	34.25	Not included	Open, finished floors and soffit, add for spectator seating	Average lighting, no plumbing	In building cost

MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

TENNIS CLUBS – INDOOR

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

LOCKERS per opening:

	COST RANGE		
Single Tier	$ 194.00	–	$ 374.00
Double	127.00	–	240.00
Triple	91.50	–	202.00
Box Type	66.00	–	123.00

TENNIS EQUIPMENT: See Section UIP 16 for tennis equipment, and Sec-UIP 17 for air-supported (bubble) structures.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93
150,000	3.04	3.69	4.49	5.47

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
20	1.106	28	1.313
22	1.158	30	1.364
24	1.210	34	1.463
26	1.262	38	1.561

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	250	300	350	400	450	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
5,000	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	-----	.999	1.011	1.023	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	10,000
12,000	-----	-----	-----	.995	1.005	1.015	1.034	1.052	1.071	1.089	-----	-----	-----	-----	12,000
14,000	-----	-----	-----	.982	.992	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	14,000
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	25,000
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	30,000
35,000	-----	-----	-----	-----	-----	.936	.945	.954	.964	.973	.982	.997	1.011	-----	35,000
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	40,000
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	50,000
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	75,000
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	100,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

THEATERS – CINEMA



GOOD CLASS C



AVERAGE CLASS B

OCCUPANCY DESCRIPTION: These buildings are designed for motion picture presentations. They include little or no stage area, restroom facilities, a projection area and sound system.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Projection area, lighting and sound systems commensurate with the overall quality.

NOT INCLUDED IN COSTS: Seating, projection and snack bar equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 362.50	Face brick, stone, marble, ornamental entrance and lobby	Cinema stage, ornamental plaster, marble trim, carpeting, good detail	Special lighting and sound system, good plumbing	Warm and cool air (zoned)
	Average	275.50	Face brick, concrete, some ornamentation, good entrance	Small stage, ornamental plaster and trim, carpeting, vinyl composition	Adequate lighting, sound system and plumbing	Warm and cool air (zoned)
B	Good	323.50	Face brick, stone, terra cotta, ornamental entrance and lobby	Cinema stage, ornamental plaster, marble trim, carpeting, good detail	Special lighting and sound system, good plumbing	Warm and cool air (zoned)
	Average	250.50	Face brick, concrete, some ornamentation, good entrance	Small stage, ornamental plaster and trim, carpeting, vinyl composition	Adequate lighting, sound system and plumbing	Warm and cool air (zoned)
A-B	Average balcony	90.50	Not included	Stepped balcony with plaster soffit	Adequate lighting	Hot water
	Storage mezzanine	115.00	Not included	Plaster, unfinished floor, vinyl comp. tile, projection, storage rooms	Adequate lighting and outlets, no plumbing	Hot water
C	Excellent	323.50	Top design, best materials, very elaborate entrance	Special finishes, acoustic design, high-cost lobby finishes	High-quality specialty lighting, best sound throughout, good plumbing	Warm and cool air (zoned)
	Very good	273.50	Face brick, stone, terra cotta, ornamental entrance and lobby	Cinema stages, ornamental interior, carpeting, good main-feature screen	Special lighting and sound systems, good plumbing	Warm and cool air (zoned)
	Good	218.50	Brick, block, concrete, good decorative front and lobby	Some stage or ornamental plaster, some trim, carpeting, ceramic tile	Good lighting, sound systems and plumbing	Package A.C.
	Average	157.50	Brick, block, concrete, good front and lobby, some trim	Plaster or gypsum, suspended ceiling, stepped floor, carpeted lobby	Adequate lighting, good sound and plumbing	Package A.C.
	Fair	134.50	Brick, block, concrete panels, plain commercial building, small entry	Plain construction, small screens, vinyl composition in lobby	Minimum lighting, adequate sound, minimum plumbing	Package A.C.
	Low-cost	105.50	Low-cost block, tilt-up, very plain, acoustic sound walls	Painted masonry, very plain, minimum multiplex cinema facility	Minimum code, sound per screen	Forced air
D	Very good	261.50	Face brick or stone veneer, ornamental entrance and lobby	Cinema stages, ornamental interior, carpeting, good main-feature screen	Special lighting, sound systems, good plumbing	Warm and cool air (zoned)
	Good	207.50	Stucco, some brick or stone trim, decorative front and lobby	Some stage or ornamentation and trim, carpeting, ceramic tile	Good lighting, sound systems and plumbing	Package A.C.
	Average	148.50	Stucco or siding, good front and lobby, some trim	Drywall, suspended ceiling, carpeted lobby, stepped floor	Adequate lighting, good sound and plumbing	Package A.C.
	Fair	127.50	Siding or stucco, small entry, good acoustic or masonry sound walls	Drywall, acoustic tile, asphalt tile lobby, concrete slab, small screens	Minimum lighting, adequate sound, minimum plumbing	Package A.C.
	Low-cost	99.00	Low-cost wood or stucco, very plain, acoustic sound walls	Few partitions, very plain, minimum multiplex cinema facility	Minimum code, sound per screen	Forced air
D POLE	Low-cost	93.50	Pole frame and truss, metal siding, lined, insulated, acoustic sound walls	Few partitions, very plain, minimum multiplex cinema facility	Minimum code, sound per screen	Forced air
S	Good	207.00	Insulated sandwich panels, good storefront and trim	Some decorative and extras, carpet and tile, some small stagefronts	Good lighting, sound system and plumbing	Package A.C.
	Average	147.50	Good metal panels, roof, front and lobby, some trim	Finished interior, suspended ceiling, carpeted lobby, stepped floor	Adequate lighting, good sound and plumbing	Package A.C.
	Fair	125.50	Metal panels, finished interior, small entrance, good sound walls	Drywall, acoustic tile, vinyl-composition lobby, concrete slab	Minimum lighting, adequate sound, minimum plumbing	Package A.C.
	Low-cost	97.00	Single wall, low-cost interior finish and insulation, acoustic walls	Few partitions, very plain, minimum multiplex cinema facility	Minimum code, sound per screen	Forced air
CDS	Average balcony	70.00	Not included	Stepped balcony with drywall soffit	Adequate lighting	Forced air
	Storage mezzanine	94.00	Not included	Drywall, concrete or wood floor, vinyl comp. tile, projection, storage rooms	Adequate lighting and outlets, no plumbing	Forced air

BALCONIES: Do not use story height or area/perimeter multipliers with balcony cost.
For basement theaters, use 85% of the comparable above ground base costs. For utility basements, see Auditorium basements, Page CAL 18.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

THEATERS – CINEMA

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

Seating, curtains and snackbar equipment costs are located in Section UIP 15.

CANOPIES:

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 39.25	$ 48.50	$ 60.00	$ 74.50
Light false-mansard	21.65	26.50	33.00	40.75
Steel frame	48.25	61.00	77.00	97.00
Light false-mansard	26.50	33.50	42.25	53.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93
150,000	3.04	3.69	4.49	5.47
200,000	2.93	3.55	4.30	5.21

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	.889	28	1.313
14	.945	30	1.364
16	1.000 (base)	34	1.463
18	1.054	38	1.561
20	1.106	42	1.658
22	1.158	46	1.754
24	1.210	50	1.849
26	1.262	54	1.943

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	175	200	250	300	400	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.117	1.147	1.205	1.264	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
5,000	.999	1.011	1.034	1.056	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	-----	-----	-----	1.011	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	10,000
14,000	-----	-----	-----	-----	.982	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	14,000
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	25,000
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	40,000
45,000	-----	-----	-----	-----	-----	-----	.934	.939	.946	.954	.962	.976	.989	1.001	45,000
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	50,000
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	75,000
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	100,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

THEATERS – LIVE STAGE



GOOD CLASS B



GOOD CLASS A

OCCUPANCY DESCRIPTION: These buildings are designed for stage presentations and include a stage that is consistent with the quality of construction. Restroom and live stage dressing room facilities, entrances and suitable office and cloak room facilities are included.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Projection area, lighting and sound systems commensurate with the overall quality.

NOT INCLUDED IN COSTS: Elevators, sprinklers, movable wings or lights, border lights, projection and snack bar equipment, scenery, curtains or seating. Balcony and basement costs are listed separately.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$566.00	Top design, best materials, highly ornamented	Special finishes, acoustical design, major stage presentations	High-quality specialty lighting, best sound, good plumbing	Hot and chilled water (zoned)
	Good	414.00	Face brick, stone, marble, ornamented entrance and lobby	Large stage, ornamental plaster, marble trim, carpeting, good detail	Special lighting and sound system, good plumbing	Warm and cool air (zoned)
	Average	312.50	Face brick, concrete, some ornamentation, good entrance	Live-stage, ornamental plaster and trim, carpeting, vinyl composition	Adequate lighting, sound system and plumbing	Warm and cool air (zoned)
B	Excellent	502.50	Top design, best materials, highly ornamented	Special finishes, acoustical design, major stage presentations	High-quality specialty lighting, best sound, good plumbing	Hot and chilled water (zoned)
	Good	370.50	Face brick, stone, terra cotta, ornamented entrance and lobby	Large stage, ornamental plaster, marble trim, carpeting, good detail	Special lighting and sound system, good plumbing	Warm and cool air (zoned)
	Average	283.50	Face brick, concrete, some ornamentation, good entrance	Live-stage, ornamental plaster and trim, carpeting, vinyl composition	Adequate lighting, sound system and plumbing	Warm and cool air (zoned)
A-B	Finished basement	158.50	Concrete masonry, partly finished interior	Masonry partitions, utility, repair, storage and dressing rooms	Adequate lighting and plumbing	Hot water
	Good live-stage balc.	130.00	Not included	Stepped balcony with ornate finishes, hardwood, carpet	Good lighting	In bldg. cost
	Balcony	94.50	Not included	Stepped balcony with plaster soffit	Adequate lighting	In bldg. cost
	Finished mezzanine	142.00	Not included	Plaster, good detail, carpeting, tile, good intermission area, restrooms	Good lighting and plumbing, extra outlets and fixtures	In bldg. cost
	Open mezzanine	67.00	Not included	Finished floors, few partitions	Average lighting, no plumbing	In bldg. cost
C	Excellent	394.00	Top design, best materials, highly ornamented	Special finishes, acoustical design, major stage presentations	High-quality specialty lighting, best sound, good plumbing	Warm and cool air (zoned)
	Good	278.00	Face brick, stone, terra cotta, ornamental entrance and lobby	Large stage, ornamental interior, carpeting, good detail	Special lighting and sound system, good plumbing	Warm and cool air (zoned)
	Average	186.00	Brick, block, concrete, good decorative front and lobby	Live-stage, ornamental plaster, some trim, carpeting, vinyl comp.	Adequate lighting, sound system and plumbing	Package A.C.
	Low-cost	123.50	Brick, block, concrete, plain front and lobby, some trim	Plaster or gypsum, suspended ceiling, carpeted lobby, small stage	Minimum lighting, adequate sound, minimum plumbing	Forced air
D	Good	265.50	Face brick or stone veneer, ornamental entrance and lobby	Large stage, ornamental interior, carpeting, good detail	Special lighting and sound system, good plumbing	Warm and cool air (zoned)
	Average	176.00	Stucco, some masonry trim, decorative front and lobby	Live-stage, some ornamentation and trim, carpeting, vinyl composition	Adequate lighting, sound system and plumbing	Package A.C.
	Low-cost	116.00	Siding or stucco, plain entry	Drywall, acoustic tile, small stage	Minimum live-stage facility	Forced air
D POLE	Low-cost	108.00	Metal panels on pole frame, finished interior, small entrance	Drywall, acoustic tile, vinyl composition lobby, small stage	Minimum lighting, adequate sound, minimum plumbing	Forced air
S	Average	173.50	Insulated sandwich panels, good storefront and trim	Some decoration and extras, carpet and tile, live stage presentations	Adequate lighting, sound system and plumbing	Package A.C.
	Low-cost	112.50	Metal panels, finished interior	Drywall, acoustic tile, small stage	Minimum live-stage facility	Forced air
CDS	Basement†	110.00	Painted interior	Utility, repair, storage and dressing rooms	Adequate lighting and plumbing	Forced air
	Good live-stage balc.	107.00	Not included	Stepped balcony with ornate finishes, hardwood, carpet	Good lighting	In bldg. cost
	Balcony	72.00	Not included	Stepped balcony with drywall soffit	Adequate lighting	In bldg. cost
	Finished mezzanine	117.00	Not included	Drywall, vinyl, some tile, carpet or VCT, intermission area, restrooms	Adequate lighting and plumbing, extra outlets and fixtures	In bldg. cost
	Open mezzanine	48.25	Not included	Finished floors, few partitions	Average lighting, no plumbing	In bldg. cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.52 per square foot.

BALCONIES: Do not use story height or area/perimeter multipliers with balcony cost..

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

THEATERS – LIVE STAGE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

ORCHESTRA LIFTS: $156,000 – $245,000

CANOPIES:

	LOW	AVG.	GOOD	EXCL.
Wood frame	$ 39.25	$ 48.50	$ 60.00	$ 74.50
Light false-mansard	21.65	26.50	33.00	40.75
Steel frame	48.25	61.00	77.00	97.00
Light false-mansard	26.50	33.50	42.25	53.00

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93
150,000	3.04	3.69	4.49	5.47
200,000	2.93	3.55	4.30	5.21

Seating, curtains and snackbar equipment costs are located in Section UIP 15.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by following multipliers for any variation in average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	.889	28	1.313	58	2.036
14	.945	30	1.364	62	2.128
16	1.000 (base)	34	1.463	66	2.219
18	1.054	38	1.561	70	2.309
20	1.106	42	1.658	74	2.398
22	1.158	46	1.754	78	2.486
24	1.210	50	1.849	82	2.573
26	1.262	54	1.943	86	2.659

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	175	200	250	300	400	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.117	1.147	1.205	1.264	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
5,000	.999	1.011	1.034	1.056	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	-----	-----	-----	1.011	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	10,000
14,000	-----	-----	-----	-----	.982	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	14,000
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	25,000
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	40,000
45,000	-----	-----	-----	-----	-----	-----	.934	.939	.946	.954	.962	.976	.989	1.001	45,000
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	50,000
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	75,000
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	100,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

VISITOR CENTERS



GOOD CLASS D

OCCUPANCY DESCRIPTION: These buildings include the low quality travelers' aid or rest stop structure to the high-cost center with good orientation, exhibit, meeting, audiovisual theater and limited retail and food service facilities.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers and display or food service equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 354.00	Special architecture, good lobby	Good exhibit, theater, cafeteria	Good lighting, plumbing, kitchen	Warm and cool air
	Average	258.00	Brick, concrete, metal and glass, some ornamentation	Adequate exhibit rooms and lobby, theater, limited food service	Fluorescent lighting, good sound, plumbing and restrooms	Heat pump system
C	Excellent	326.00	Local stone, face brick, heavy timber or steel frame	Decorative lobby, pavers, carpet, good exhibit rooms or theater	Good display lighting, sound and restrooms, small kitchen	Heat pump system
	Good	241.50	Face brick, ornamental trim, good entrance, lobby	Good finish and detail, carpeting and tile, display and food service areas	Good fluorescent lighting, good plumbing and restrooms	Package A.C.
	Average	175.00	Brick, block, concrete panels, some ornamentation	Drywall, acoustic tile, hardwood and vinyl composition tile	Adequate lighting and plumbing, large restrooms	Forced air
	Low-cost	120.00	Low-cost block, concrete	Painted, some acoustic and asphalt tile	Minimum lighting and plumbing	Space heaters
D	Excellent	311.50	Local stone or brick veneer, rustic log, heavy frame	Decorative lobby, pavers, carpet, good exhibit rooms or theater	Good display lighting, sound and restrooms, small kitchen	Heat pump system
	Good	230.00	Brick veneer or best siding or stucco with trim, good entrance	Good finish and detail, carpet, vinyl, display and food service areas	Good fluorescent lighting, good plumbing and restrooms	Package A.C.
	Average	165.00	Stucco or siding, some brick or stone trim, small entrance	Drywall, acoustic tile, hardwood and vinyl composition	Adequate lighting and plumbing, large restrooms	Forced air
	Low-cost	113.50	Low-cost wood or stucco	Drywall, some acoustic and asphalt tile	Minimum lighting and plumbing	Space heaters
D POLE	Average	156.00	Pole frame, good metal siding, insulated, small entrance	Drywall, acoustic tile, hardwood and vinyl composition	Adequate lighting and plumbing, large restrooms	Forced air
	Low-cost	107.50	Metal skin on pole frame and truss, finished interior	Drywall, some acoustic and resilient tile, minimum visitor facility	Minimum lighting and plumbing	Space heaters
S	Low-cost	112.50	Steel or aluminum panels	Drywall, some acoustic and asphalt tile, minimum visitor facility	Minimum lighting and plumbing	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

VISITOR CENTERS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.776	18	1.054
10	.833	20	1.106
12	.889	22	1.158
14	.945	24	1.210
16	1.000 (base)	28	1.313

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	250	300	350	400	450	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.205	1.264	1.322	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	-----	.999	1.011	1.023	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	**10,000**
14,000	-----	-----	-----	.982	.992	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	**14,000**
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	**25,000**
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	**40,000**
45,000	-----	-----	-----	-----	-----	-----	.934	.939	.946	.954	.962	.976	.989	1.001	**45,000**
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	**50,000**
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	**75,000**
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	**100,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – DISTRIBUTION



GOOD CLASS C



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These buildings are designed with large areas to accommodate the breakdown and shipment of small lots of materials and goods. They have more plumbing and lighting than storage warehouses in order to service the large personnel load.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Heating and ventilation sufficient to protect goods from freezing or other forms of spoilage. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, material-handling equipment or dock levelers.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 167.00	Ornamental concrete, brick, or metal/glass panels, office front	Plaster or drywall with partitions, distribution areas, fin. ceilings, vaults	*Good lighting, plumbing, restrooms for personnel	Hot water
	Average	125.00	Brick on block or tile, concrete panels, good fenestration	Painted walls, offices, and distribution areas	*Reading-level lighting and adequate plumbing	Space heaters
B	Good	149.50	Ornamental concrete, brick, or metal/glass panels, office front	Plaster or drywall with partitions, distribution areas, fin. ceilings, vaults	*Good lighting, plumbing, adequate restrooms	Hot water
	Average	110.00	Brick on block or tile, concrete panels, good fenestration	Painted walls, offices and distribution areas	*Reading-level lighting, adequate plumbing	Space heaters
A-B	Storage basement	72.00	Reinforced concrete, unfinished interior	Unfinished storage areas, some partitions	Minimum lighting and plumbing, drains	None
	Good storage mezz.	77.00	In building cost	Metal grating on good steel structure, no partitions	Minimum lighting, no plumbing	Included in building cost
	Avg. storage mezz.	65.00	In building cost	Metal deck and concrete on good steel structure, no partitions	Minimum lighting, no plumbing	Included in building cost
C	Excellent	156.50	Brick, metal/glass, ornamental facades and fenestration	Completely finished, drugs, food, or bonded storage, large offices	High-level lighting and good plumbing	Package A.C.
	Good	106.00	Steel frame, good brick, block, or tilt-up, tapered girders	Plaster or drywall, some masonry partitions, good offices	Reading-level lighting, adequate plumbing	Forced air
	Average	72.50	Steel or wood frame or bearing walls, brick, block, or tilt-up	Painted walls, finished offices and distribution areas, hardened slab	Good lighting, adequate plumbing	Space heaters
	Low cost	52.50	Block, tilt-up, very plain, light construction	Unfinished, shell type, adequate offices, partitioned areas	Adequate lighting, plumbing fixtures	Space heaters
D	Good	95.00	Good wood frame with stucco or siding, some ornamentation	Some good offices and distribution areas	Reading-level lighting, adequate plumbing	Forced air
	Average	65.00	Stucco or siding on wood, good fenestration	Small office, partitions and distribution areas	Good lighting, adequate plumbing	Space heaters
D POLE	Average	59.00	Good pole frame, metal siding	Distribution areas, small offices	Adequate lighting/plumbing	Space heaters
	Low cost	43.00	Wood pole frame, metal siding	Unfinished, adequate offices, partitioned areas	Adequate lighting, plumbing fixtures	Space heaters
S	Excellent	144.50	Heavy steel frame, sandwich panels, good ornamentation	Completely finished, drugs, food, or bonded storage, large offices	High-level lighting and good plumbing	Package A.C.
	Good	97.00	Good steel frame, siding and fenestration	Some good offices and interior finish, distribution areas	Reading-level lighting, adequate plumbing	Forced air
	Average	66.00	Rigid steel frame and siding	Distribution areas, small offices	Adequate lighting/plumbing	Space heaters
	Low cost	47.50	Pre-eng. frame, plain shell	Adequate office, partitioned areas	Adequate lighting/plumbing	Space heaters
CDS	Storage basement	44.75	Reinforced concrete, unfinished interior	Unfinished storage area, some partitions	Minimum lighting and drains	None
	Avg. storage mezz.	30.50	In building cost	Heavy plywood or plank on wood or light steel structure, no partitions	Minimum lighting, no plumbing	Included in building cost
	Low. storage mezz.	22.65	In building cost	Light storage on plywood, minimum supports, no soffit	Minimum lighting	Included in building cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.61 per square foot.
MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – DISTRIBUTION

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Good	$ 4.03
Average	3.13

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.16	$ 5.51	$ 7.28	$ 9.63
10,000	3.78	4.95	6.48	8.49
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
50,000	2.96	3.79	4.89	6.27
80,000	2.75	3.49	4.47	5.72
100,000	2.67	3.39	4.32	5.51
200,000	2.40	3.04	3.84	4.85

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,700 to $14,600 per stop.

A small freight elevator with simple call system and push-button control, four-passenger cab and two or three stops, costs $66,500 to $109,000.

DOCK HEIGHT FLOORS: Add $2.39 to $9.03 per square foot to base cost of first floor.

For loading docks, see Page CAL 398.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$2.96

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.885	20	1.133
10	.921	22	1.181
12	.960	24	1.231
14	1.000 (base)	26	1.281
16	1.041	28	1.331
18	1.086	30	1.382

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	300	400	500	600	800	1000	1200	1400	1600	1800	2000	2200	2400	3000	Sq. Ft./Story
5,000	1.083	1.168	1.252	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	.996	1.040	1.083	1.168	-----	-----	-----	-----	-----	-----	-----	-----	-----	**10,000**
14,000	-----	.945	.977	1.008	1.071	1.132	-----	-----	-----	-----	-----	-----	-----	-----	**14,000**
20,000	-----	-----	.926	.949	.996	1.040	1.083	-----	-----	-----	-----	-----	-----	-----	**20,000**
25,000	-----	-----	.907	.924	.959	.996	1.032	1.066	-----	-----	-----	-----	-----	-----	**25,000**
30,000	-----	-----	-----	.907	.935	.965	.995	1.025	-----	-----	-----	-----	-----	-----	**30,000**
40,000	-----	-----	-----	-----	.907	.926	.949	.972	.995	1.019	-----	-----	-----	-----	**40,000**
50,000	-----	-----	-----	-----	.891	.907	.924	.942	.959	.977	.996	1.015	-----	-----	**50,000**
80,000	-----	-----	-----	-----	-----	.875	.887	.898	.907	.916	.926	.937	.949	.984	**80,000**
100,000	-----	-----	-----	-----	-----	.863	.872	.882	.891	.899	.907	.916	.924	.950	**100,000**
200,000	-----	-----	-----	-----	-----	-----	.846	.850	.855	.859	.863	.868	.873	.887	**200,000**
400,000	-----	-----	-----	-----	-----	-----	-----	-----	.835	.838	.841	.843	.846	.853	**400,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – MEGA (STORAGE/DISTRIBUTION)



AVERAGE CLASS S



GOOD CLASS S

OCCUPANCY DESCRIPTION: Typically 200,000 to over 1,000,000 square feet, designed for major regional distribution and storage centers. They include an amount of office and personnel support space consistent with the quality of the building (typically 1 to 5 percent). Support areas typically have plaster or drywall interior partitions and finished ceilings. The better qualities have large cafeterias and kitchens.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Heating and ventilation sufficient to protect goods from freezing or other forms of spoilage.

NOT INCLUDED IN COSTS: Sprinklers, material-handling equipment, dock levelers or site improvements.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 81.50	Glulam or steel frame, decorative block or tilt-up, elastomeric roof	Plaster or drywall, some masonry partitions, good offices, cafeteria	Good lighting and plumbing, kitchen	Space heaters
	Average	54.00	Open steel or wood frame, block or tilt-up, good roof	Painted walls, finished offices and break room, good flat slab	Adequate lighting, good plumbing fixtures, food service	Space heaters
	Low cost	37.00	Large tilt-up, light panelized const., built-up roof, exposed insulation	Painted walls or unfinished, small offices, hardened slab	Adequate lighting and plumbing, some extras	Space heaters
	Cheap	30.50	Tilt-up, very large shell type	Unfinished, bulk storage, few offices	Minimum lighting and plumbing	Space heaters
S	Good	79.00	Heavy steel frame, insulated panels, good facade, some trim	Plaster or drywall, partitioned, good offices, cafeteria	Good lighting and plumbing, kitchen	Space heaters
	Average	54.50	Good steel frame, siding and fenestration, bar or web joints	Some good offices, interior finish and floor, break room, good flat slab	Adequate lighting, good plumbing fixtures, food service	Space heaters
	Low cost	38.00	Rigid steel frame, good metal siding and roof, exposed insulation	Unfinished, small offices, hardened slab	Adequate lighting and plumbing, some extras	Space heaters
	Cheap	27.50	Steel frame, siding, large shell type	Unfinished, bulk storage, few offices	Minimum lighting and plumbing	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – MEGA (STORAGE/DISTRIBUTION)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
100,000	$ 2.67	$ 3.39	$ 4.32	$ 5.51
200,000	2.40	3.04	3.84	4.85
300,000	2.25	2.83	3.55	4.45
400,000	2.17	2.73	3.39	4.23
500,000	2.10	2.63	3.27	4.09
600,000	2.02	2.52	3.15	3.95
700,000	1.98	2.48	3.09	3.86
800,000	1.94	2.43	3.02	3.76
1,000,000	1.86	2.32	2.88	3.59
1,200,000	1.86	2.32	2.88	3.59
1,500,000	1.86	2.32	2.88	3.59

DOCK HEIGHT FLOORS: Add $2.39 to $9.03 per square foot to base cost of first floor.

Loading docks, see Page CAL 398.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$2.96

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
14	1.000 (base)	24	1.231	50	1.930
16	1.041	30	1.382	55	2.075
18	1.086	35	1.515	60	2.225
20	1.133	40	1.650	70	2.530
22	1.181	45	1.788	80	2.845

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	1000	1200	1400	1600	2000	2400	2600	3000	3500	4000	5000	6000	7000	8000	Sq. Ft./Story
100,000	.863	.872	.882	.891	.907	.924	.933	.950	-----	-----	-----	-----	-----	-----	**100,000**
200,000	-----	.846	.850	.855	.863	.873	.877	.887	-----	-----	-----	-----	-----	-----	**200,000**
300,000	-----	-----	.839	.842	.849	.855	.857	.863	.872	.880	-----	-----	-----	-----	**300,000**
400,000	-----	-----	-----	.835	.841	.846	.848	.853	.858	.863	.875	-----	-----	-----	**400,000**
500,000	-----	-----	-----	.831	.835	.840	.842	.846	.850	.855	.863	.873	-----	-----	**500,000**
600,000	-----	-----	-----	-----	-----	-----	.837	.841	.845	.849	.856	.863	-----	-----	**600,000**
700,000	-----	-----	-----	-----	-----	-----	-----	.836	.841	.845	.851	.857	.863	-----	**700,000**
800,000	-----	-----	-----	-----	-----	-----	-----	.834	.837	.841	.847	.853	.858	.863	**800,000**
900,000	-----	-----	-----	-----	-----	-----	-----	.832	.835	.838	.843	.849	.854	.858	**900,000**
1,000,000	-----	-----	-----	-----	-----	-----	-----	-----	.832	.835	.841	.846	.850	.855	**1,000,000**
1,200,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.832	.836	.841	.845	.849	**1,200,000**
1,500,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.832	.835	.839	.843	**1,500,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – MINI



GOOD CLASS C

OCCUPANCY DESCRIPTION: Mini warehouses are subdivided into cubicles of generally small size and are designed primarily to be rented for non-commercial storage. The interior cubicles are divided with either masonry, metal or wood frame walls. Drywall is a common interior finish on the framed walls. They are typically built with slab floors and have some electrical in each unit. This occupancy also has minimum plumbing with no heating.



AVERAGE CLASS D

High-rise Mini warehouses are multistory warehouses subdivided into cubicles of generally small size and are designed primarily to be rented for non-commercial storage. They will include some office/living space at the better qualities. The density of storage cubicles and ancillary support facilities will influence cost level.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in high rise structures only.

NOT INCLUDED IN COSTS: Sprinklers, security equipment or yard improvements.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 68.50	Brick, block or tilt-up, many doors	Subdivided cubicles, good security partitions, office-apartment	Electrical outlets and lighting in each space, minimum plumbing	None
	Average	51.00	Block, tilt-up, light construction	Subdivided into cubicles, mixed sizes, unfinished slab, small office	Adequate electrical service per space, minimum water	None
	Low cost	38.00	Low-cost block, tilt-up, light roof, low-cost door entries	Subdivided into large cubicles, light slab, no support facilities	Minimum electrical service	None
D	Good	63.50	Stucco, siding or brick veneer, many doors	Subdivided cubicles, good security partitions, office-apartment	Electrical outlets and lighting in each space, minimum plumbing	None
	Average	47.50	Wood frame and stucco or wood	Subdivided into cubicles, mixed sizes, unfinished slab, small office	Adequate electrical service per space, minimum water	None
	Low cost	35.50	Low-cost stucco or siding, low-cost door entries	Subdivided into large cubicles, light slab, no support facilities	Minimum electrical service	None
D POLE	Good	58.00	Good pole frame, metal siding, many doors	Subdivided cubicles, good security partitions, office-apartment	Electrical outlets and lighting in each space, minimum plumbing	None
	Average	43.50	Wood pole frame, metal siding	Subdivided into cubicles, mixed sizes, unfinished slab, small office	Adequate electrical service per space, minimum water	None
	Low cost	32.50	Pole frame, metal siding, low-cost door entries	Subdivided into large cubicles, light slab, no support facilities	Minimum electrical service	None
S	Good	63.00	Pre-engineered frame, insulated, many doors	Subdivided cubicles, good security partitions, office-apartment	Electrical outlets and lighting in each space, minimum plumbing	None
	Average	47.00	Light steel frame and metal siding	Subdivided into cubicles, mixed sizes, unfinished slab, small office	Adequate electrical service per space, minimum water	None
	Low cost	35.50	Light steel frame, siding, low-cost door entries	Subdivided into large cubicles, light slab, no support facilities	Minimum electrical service	None
	Cheap	26.00	Light steel frame, siding and doors	Extra large only; all cubes >300 sq. ft.	Minimum electrical only	None

HIGH-RISE MINI-WAREHOUSES

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 95.50	Brick, block, concrete, some metal and glass	Subdivided cubicles, good security partitions, office/apartment	*Good outlets and lighting, minimum plumbing	Ventilation
C	Good	87.50	Brick, block or tilt-up, metal and glass, good trim	Subdivided cubicles, good security partitions, office/apartment	*Good outlets and lighting, minimum plumbing	Ventilation
	Average	67.00	Block, tilt-up, some metal and glass trim	Subdivided into cubicles, mixed sizes, unfinished slab, adequate office	*Adequate electrical service, minimum plumbing	Ventilation
D	Good	80.00	Brick veneer, stucco, EIFS, metal and glass trim	Subdivided cubicles, good security partitions, office/apartment	*Good outlets and lighting, minimum plumbing	Ventilation
S	Good	81.50	Pre-engineered frame, good sandwich panels	Subdivided cubicles, good security partitions, office/apartment	*Good outlets and lighting, minimum plumbing	Ventilation

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – MINI

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

High-Rise All Classes	Sq. Ft. Costs
Good	$ 3.33
Average	2.41

ELEVATORS: A small passenger or freight elevator with simple call system and push button control, four passenger cab, and two or three stops, costs $66,500 to $109,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.16	$ 5.51	$ 7.28	$ 9.63
10,000	3.78	4.95	6.48	8.49
15,000	3.54	4.62	6.03	7.88
20,000	3.37	4.37	5.70	7.43
40,000	3.04	3.94	5.06	6.53

For load-bearing parking roofs, add $8.81 per square foot.

Access ramps cost $31.00 to $55.50 per square foot of ramp.

DOCK HEIGHT FLOORS: Add $2.39 to $9.03 per square foot to base cost of first floor.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.885	16	1.041
10	.921	18	1.086
12	.960	20	1.133
14	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	150	200	250	300	400	450	500	600	700	800	900	1000	1200	Sq. Ft./Story
1,000	1.252	1.468	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	-----	1.147	1.252	1.360	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	-----	1.112	1.182	1.252	1.395	-----	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	1.040	1.094	1.147	1.252	1.306	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	.996	1.040	1.083	1.168	1.210	1.252	-----	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	1.004	1.040	1.112	1.147	1.182	1.252	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.984	1.040	1.068	1.094	1.147	1.199	1.252	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.996	1.019	1.040	1.083	1.125	1.168	1.210	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.965	.984	1.003	1.040	1.077	1.112	1.147	1.182	-----	12,000
14,000	-----	-----	-----	-----	-----	.945	.961	.977	1.008	1.040	1.071	1.102	1.132	-----	14,000
18,000	-----	-----	-----	-----	-----	-----	.929	.942	.967	.991	1.016	1.040	1.065	-----	18,000
20,000	-----	-----	-----	-----	-----	-----	-----	.926	.949	.972	.996	1.019	1.040	1.083	20,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – STORAGE



AVERAGE CLASS S



AVERAGE CLASS S

OCCUPANCY DESCRIPTION: These buildings are designed for storage. An amount of office space, typically 3 to 12 percent, consistent with the quality of the building is included in the structure. They may be built in all classes of construction. Typically, they have plaster or drywall interior partitions and may have some finished ceilings. The better qualities have small office fronts with ornamental materials at the front elevation, while lower cost structures are plain with very little, if any, ornamentation.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Heating and ventilating facilities are sufficient to protect goods from freezing and other spoilage. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, special climate-control equipment, dock levelers or material handling equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 144.00	Ornamental concrete or brick, small office front	Plaster or drywall with partitions, some finished ceilings	*Good lighting, plumbing, adequate restrooms	Hot water
	Average	103.50	Brick on block or tile, concrete panels, very plain	Painted walls, few partitions, small offices	*Adequate lighting and plumbing	Space heaters
	Low cost	81.50	Low-cost block, tile or concrete	Unfin., small office, few partitions	*Minimum lighting/plumbing	Space heaters
B	Good	127.50	Ornamental concrete or brick, small office front	Plaster or drywall with partitions, finished ceilings in most areas	*Good lighting, plumbing, adequate restrooms	Hot water
	Average	90.00	Brick on block or tile, concrete panels, very plain	Painted walls, few partitions, small offices	*Adequate lighting and plumbing	Space heaters
	Low cost	71.00	Low-cost block, tile or concrete	Unfin., small office, few partitions	*Minimum lighting/plumbing	Space heaters
A-B	Storage basement	70.50	Reinforced concrete, unfinished interior	Unfinished storage areas, some partitions	Minimum lighting and plumbing, drains	None
	Good storage mezz.	77.00	In building cost	"Metal grating on good steel structure, no partitions"	Minimum lighting, no plumbing	"Included in building cost"
	Avg. storage mezz.	65.00	In building cost	"Metal deck and concrete on good steel structure, no partitions"	Minimum lighting, no plumbing	"Included in building cost"
C	Excellent	140.00	Brick, concrete, good facade	Plaster or drywall, partitioned, finished ceilings in most areas	Good lighting and plumbing	Package A.C.
	Good	88.50	Steel frame, good brick, block, or tilt-up, tapered girders	Plaster or drywall, some masonry partitions, good offices	Good lighting, adequate plumbing	Space heaters
	Average	62.50	Steel or wood frame or bearing walls, brick, block, or tilt-up	Painted walls, finished office, hardened slab	Adequate lighting, low-cost plumbing fixtures	Space heaters
	Low cost	45.00	Block, cheap brick, tilt-up, light construction	Unfinished, small office, shell type, minimum code	Minimum lighting and plumbing	Space heaters
CMILL	Good	123.50	Mill-type construction, brick walls, wood or steel trusses	Plaster walls, masonry partitions, painted trusses	*Good lighting, adequate plumbing	Steam
	Average	84.00	Mill-type construction, brick and block, wood trusses	Painted walls, few partitions, small offices	*Adequate lighting and plumbing	Space heaters
D	Good	80.00	Heavy wood frame, wood or stucco siding	Heavy slab or mill-type floors	Good lighting, adequate plumbing	Space heaters
	Average	56.50	Stucco on wood frame, wood trusses	Small office, average slab	Adequate lighting, low-cost plumbing fixtures	Space heaters
	Low cost	40.50	Stucco or siding on wood	Unfinished, slab, utility type, minimum office	Minimum lighting and plumbing	Space heaters
DPOLE	Average	50.00	Pole frame, good metal siding, insulated	Small office, some finish, slab	Adequate lighting, little plumbing	Space heaters
	Low cost	36.00	Pole frame, metal siding	Unfinished utility type, light slab, minimum office	Minimum lighting and plumbing	Space heaters
S	Excellent	131.00	Heavy steel frame, insulated panels, good facade	Plaster or drywall, partitioned, finished ceilings in most areas	Good lighting and plumbing	Package A.C.
	Good	81.50	Good steel frame, siding and fenestration	Some good office, interior finish and floor	Good lighting, adequate plumbing	Space heaters
	Average	57.00	Rigid steel frame, siding	Small office, average slab	Adequate lighting, low-cost plumbing fixtures	Space heaters
	Low cost	40.50	Pre-engineered frame, metal siding	Unfinished utility type, light slab, minimum office	Minimum lighting and plumbing	Space heaters
CDS†	Storage basement	44.75	Reinforced concrete, unfinished interior	Unfinished storage area	Minimum lighting and drains	None
	Avg. stor. mezz.	30.50	In building cost	Heavy plywood or plank on wood or light steel structure, no partitions	Minimum lighting, no plumbing	Included in building cost
	Low stor. mezz.	22.65	In building cost	Light storage on plywood, minimum supports, no soffit	Minimum lighting	Included in building cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $ 8.61 per square foot.
MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – STORAGE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B/C$_{MILL}$	Sq. Ft. Costs
Good	$ 3.85
Average	3.13
Low cost	2.41

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,700 to $14,600 per stop.

A small freight elevator with simple call system and push-button control, four-passenger cab and two or three stops, costs $66,500 to $109,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.16	$ 5.51	$ 7.28	$ 9.63
10,000	3.78	4.95	6.48	8.49
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
50,000	2.96	3.79	4.89	6.27
80,000	2.75	3.49	4.47	5.72
100,000	2.67	3.39	4.32	5.51
200,000	2.40	3.04	3.84	4.85

DOCK HEIGHT FLOORS: Add $2.39 to $9.03 per square foot to base cost of first floor.

Loading docks, see Page CAL 398.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$2.96

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	0.885	20	1.133	45	1.788
10	0.921	22	1.181	50	1.930
12	0.960	24	1.231	55	2.075
14	1.000 (base)	30	1.382	60	2.225
16	1.041	35	1.515	70	2.530
18	1.086	40	1.650	80	2.845

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	300	400	500	600	800	1000	1200	1400	1600	1800	2000	2200	2400	3000	Sq. Ft./Story
5,000	1.083	1.168	1.252	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	.996	1.040	1.083	1.168	-----	-----	-----	-----	-----	-----	-----	-----	-----	**10,000**
14,000	-----	.945	.977	1.008	1.071	1.132	-----	-----	-----	-----	-----	-----	-----	-----	**14,000**
20,000	-----	-----	.926	.949	.996	1.040	1.083	-----	-----	-----	-----	-----	-----	-----	**20,000**
25,000	-----	-----	.907	.924	.959	.996	1.032	1.066	-----	-----	-----	-----	-----	-----	**25,000**
30,000	-----	-----	-----	.907	.935	.965	.995	1.025	-----	-----	-----	-----	-----	-----	**30,000**
40,000	-----	-----	-----	-----	.907	.926	.949	.972	.995	1.019	-----	-----	-----	-----	**40,000**
50,000	-----	-----	-----	-----	.891	.907	.924	.942	.959	.977	.996	1.015	-----	-----	**50,000**
80,000	-----	-----	-----	-----	-----	.875	.887	.898	.907	.916	.926	.937	.949	.984	**80,000**
100,000	-----	-----	-----	-----	-----	.863	.872	.882	.891	.899	.907	.916	.924	.950	**100,000**
200,000	-----	-----	-----	-----	-----	-----	.846	.850	.855	.859	.863	.868	.873	.887	**200,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – TRANSIT



AVERAGE CLASS S



AVERAGE CLASS S

OCCUPANCY DESCRIPTION: This occupancy is designed for temporary closed storage, freight segregation and loading. Most commonly built with either masonry, wood frame or steel frame walls. The interiors have some finished offices and driver areas. Lighting and plumbing, although adequate to service the personnel, are not excessive or ornate.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Heating and ventilation are sufficient to protect stored goods and materials from freezing or other forms of spoilage. Costs include dock height floors.

NOT INCLUDED IN COSTS: Elevators, sprinklers, dock-leveling equipment or special material handling facilities.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 139.00	Brick or block, best tilt-up, good overhead doors	Good finished office, drivers' rest areas, dock-height floor	Good lighting, plumbing for transient drivers	Forced air
	Average	97.00	Block, good tilt-up, overhead doors	Some finished office, drivers' rest areas, dock-height floor	Adequate lighting, plumbing for transient drivers	Space heaters
D	Average	87.00	Wood frame, siding or stucco	Some finished office/drivers' rest areas, dock-height floor	Adequate lighting/plumbing	Space heaters
D POLE	Average	82.50	Wood pole frame, metal siding	Some finished office/drivers' rest areas, dock-height floor	Adequate lighting/plumbing	Space heaters
S	Good	126.00	Heavy steel frame and siding, good overhead doors	Good finished office, drivers' rest areas, dock-height floor	Good lighting, plumbing for transient drivers	Forced air
	Average	88.00	Steel frame and siding	Some finished office/drivers' rest areas, dock-height floor	Adequate lighting/plumbing	Space heaters
CDS	Storage basement	44.75	Reinforced concrete, unfinished interior	Finished storage area	Minimum lighting and drains	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – TRANSIT

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

AUTOMATIC DOCK LEVELERS: Cost $8,700 to $16,600 each.

See Section UIP 12, page 12 for greater detail.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.16	$ 5.51	$ 7.28	$ 9.63
10,000	3.78	4.95	6.48	8.49
15,000	3.54	4.62	6.03	7.88
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
40,000	3.04	3.94	5.06	6.53
50,000	2.96	3.79	4.89	6.27
80,000	2.75	3.49	4.47	5.72
100,000	2.67	3.39	4.32	5.51
150,000	2.49	3.17	4.02	5.11

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.885	20	1.133
10	.921	22	1.181
12	.960	24	1.231
14	1.000 (base)	26	1.281
16	1.041	28	1.331
18	1.086	30	1.382

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	300	400	500	600	800	1000	1200	1400	1600	1800	2000	2200	2400	3000	Sq. Ft./Story
5,000	1.083	1.168	1.252	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	.996	1.040	1.083	1.168	-----	-----	-----	-----	-----	-----	-----	-----	-----	**10,000**
14,000	-----	.945	.977	1.008	1.071	1.132	-----	-----	-----	-----	-----	-----	-----	-----	**14,000**
20,000	-----	-----	.926	.949	.996	1.040	1.083	-----	-----	-----	-----	-----	-----	-----	**20,000**
25,000	-----	-----	.907	.924	.959	.996	1.032	1.066	-----	-----	-----	-----	-----	-----	**25,000**
30,000	-----	-----	-----	.907	.935	.965	.995	1.025	-----	-----	-----	-----	-----	-----	**30,000**
40,000	-----	-----	-----	-----	.907	.926	.949	.972	.995	1.019	-----	-----	-----	-----	**40,000**
50,000	-----	-----	-----	-----	.891	.907	.924	.942	.959	.977	.996	1.015	-----	-----	**50,000**
60,000	-----	-----	-----	-----	-----	.895	.907	.921	.935	.949	.965	.980	.995	-----	**60,000**
70,000	-----	-----	-----	-----	-----	.884	.896	.907	.919	.932	.945	.957	.969	-----	**70,000**
80,000	-----	-----	-----	-----	-----	.875	.887	.898	.907	.916	.926	.937	.949	.984	**80,000**
100,000	-----	-----	-----	-----	-----	.863	.872	.882	.891	.899	.907	.916	.924	.950	**100,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – MISCELLANEOUS STORAGE BUILDING



CLASS S FERTILIZER STORAGE

OCCUPANCY DESCRIPTION: Flathouses are large grain storage structures. Bulk oil storage buildings provide for the temporary closed storage of bulk oil drums and include a dock-height floor. Interiors are basically unfinished, with adequate sparkproof lighting fixtures, but no plumbing. Fertilizer storage buildings provide for the blending and distribution of dry fertilizers in bulk or bag. Bag structures include dock-height floors.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers, heating and special storage and handling equipment are not included.

SQUARE FOOT COST TABLE

FLATHOUSE STORAGE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 61.50	Steel truss, good concrete, metal or composition shingle roof	Heavy-duty floor, grain, storage, etc.	Good wiring and lighting	None
	Average	42.50	Concrete walls, light roof	Good concrete slab	Adequate electric service	None
D	Good	51.00	Heavy wood frame, siding or stucco, sheathing	Finished walls, heavy-duty concrete slab and stem wall	Good wiring and lighting	None
	Average	34.00	Post frame, siding or stucco, bulkheads	Finished walls, good slab, grain storage	Adequate wiring and lighting	None
D POLE	Good	45.00	Heavy laminated frame, metal siding, sheathing	Sealed walls, heavy-duty concrete slab and stem wall	Good wiring and lighting	None
	Average	31.50	Post frame and truss, metal siding, sheathing, bulkheads	Lined walls, good slab, grain storage	Adequate wiring and lighting	None
S	Good	49.00	Heavy steel frame and truss, heavy steel panels	Heavy concrete slab and stem wall, grain, storage, etc.	Good wiring and lighting	None
	Average	34.00	Steel frame and truss, heavy steel panels, bulkheads	Good concrete slab, grain storage	Adequate wiring and lighting	None
S SLANT WALL	Good	46.00	Heavy steel slant frame and truss, heavy steel panels	Heavy concrete slab and stem wall, grain, storage, etc.	Good wiring and lighting	None
	Average	32.00	Steel slant frame and truss, heavy steel panels, bulkheads	Good concrete slab, grain storage	Adequate wiring and lighting	None

BULK OIL STORAGE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
D	Average	$ 45.00	Heavy wood frame, roof, stucco or wood siding, plywood skirting	Unfinished, concrete or plank dock-height floor	Rigid conduit, spark-proof fixtures, no plumbing	None
D POLE	Average	42.50	Metal siding on poles, sheathing, metal skirting	Unfinished, concrete or plank dock-height floor	Rigid conduit, spark-proof fixtures, no plumbing	None
S	Average	44.00	Steel frame, siding and sheathing, steel skirting	Unfinished, concrete or plank dock-height floor	Rigid conduit, spark-proof fixtures, no plumbing	None

BAG FERTILIZER STORAGE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
D	Average	$ 49.50	Heavy wood frame, composition roof, wood siding and skirting	Concrete or built-up wood dock-height floor, sealed, few partitions	Rigid conduit, spark-proof fixtures, no plumbing	None
D POLE	Average	47.00	Metal siding on poles, sheathing, metal skirting	Concrete or built-up wood dock-height floor, sealed, few partitions	Rigid conduit, spark-proof fixtures, no plumbing	None
S	Average	48.50	Pre-engineered frame, siding and sheathing, steel skirting	Concrete or built-up wood dock-height floor, sealed, few partitions	Rigid conduit, spark-proof fixtures, no plumbing	None

BULK FERTILIZER STORAGE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Average	$ 61.50	Wall-bearing block or concrete, wood trusses, driveway	Heavy bins, concrete slab, small finished office, blend area	Rigid conduit, spark-proof fixtures, some plumbing	None
D	Average	57.50	Heavy wood frame, roof, wood siding, driveway	Heavy bins, concrete slab, small finished office, blend area	Rigid conduit, spark-proof fixtures, some plumbing	None
D POLE	Average	54.00	Metal siding on poles, wood sheathing, driveway	Heavy bins, concrete slab, small finished office, blend area	Rigid conduit, spark-proof fixtures, some plumbing	None
S	Average	57.50	Steel frame, siding and sheathing, driveway	Heavy bins, concrete slab, small finished office, blend area	Rigid conduit, spark-proof fixtures, some plumbing	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

WAREHOUSES – MISCELLANEOUS STORAGE BUILDING

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

Loading platforms cost $23.55 to $26.00 per square foot; add $520 for steps.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.94	$ 6.42	$ 8.34	$ 10.85
2,500	4.27	5.50	7.04	9.03
5,000	3.87	4.92	6.28	7.99
7,500	3.62	4.58	5.79	7.32
10,000	3.45	4.35	5.50	6.92
15,000	3.21	4.05	5.14	6.51
20,000	3.12	3.90	4.88	6.08
40,000	2.80	3.49	4.32	5.35

DOCK HEIGHT FLOORS: Add $2.39 to $9.03 per square foot to base cost of first floor.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 6.36	Package A.C. (short ductwork)	$ 14.05	Central refrigeration (zoned)	$ 12.00
Electric wall heaters	2.71			package (short ductwork)	9.20
Forced air furnace	7.13			Evaporative coolers	5.48
Hot water, baseboard/convector	12.70				
Space heaters, with fan	3.49				
radiant	4.09				
Steam (including boiler)	11.30				
without boiler	4.78			VENTILATION ONLY	
Wall or floor furnace	3.23			Vent. (blowers/ducts)	$ 2.01

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.943	12	1.038	20	1.192
8	.963	13	1.058	22	1.231
9	.981	14	1.077	24	1.269
10	1.000 (base)	16	1.115	28	1.346
11	1.019	18	1.154	32	1.423

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	100	125	150	200	250	300	400	500	600	700	800	900	1000	Sq. Ft./Story
500	1.178	1.311	1.444	1.577	1.844	2.110	2.377	2.909	-----	-----	-----	-----	-----	-----	**500**
750	1.044	1.133	1.222	1.311	1.489	1.667	1.844	2.201	-----	-----	-----	-----	-----	-----	**750**
1,000	.980	1.044	1.110	1.178	1.311	1.444	1.577	1.844	-----	-----	-----	-----	-----	-----	**1,000**
1,500	.911	.955	1.000	1.044	1.133	1.222	1.311	1.489	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.878	.911	.945	.977	1.044	1.110	1.178	1.311	-----	-----	-----	-----	-----	-----	**2,000**
2,500	.858	.884	.911	.938	.991	1.044	1.097	1.204	-----	-----	-----	-----	-----	-----	**2,500**
3,000	.843	.865	.889	.911	.955	1.000	1.044	1.133	-----	-----	-----	-----	-----	-----	**3,000**
3,500	-----	.854	.872	.892	.931	.967	1.006	1.080	1.157	-----	-----	-----	-----	-----	**3,500**
4,000	-----	-----	.860	.878	.911	.945	.977	1.044	1.110	1.178	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.844	.857	.884	.911	.938	.991	1.044	1.097	1.150	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.844	.860	.877	.911	.945	.977	1.010	1.044	1.076	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.844	.858	.884	.911	.938	.960	.991	1.018	1.044	**10,000**
14,000	-----	-----	-----	-----	-----	.825	.835	.854	.873	.892	.911	.931	.949	.967	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.818	.831	.844	.858	.871	.884	.898	.911	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.810	.820	.831	.841	.852	.863	.873	.884	**25,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.