REDUCING BALANCE DEPRECIATION TABLE

COMMERCIAL AND INDUSTRIAL

(Please review Chapter 13, Volume III, of the Michigan Assessor's Manual for detailed guidance in the correct use of this table.)

Depreciation Rates

Age of Building	1-1/2%	2%	2-1/2%	3%	Age of Building
1	99	98	98	97	1
2	97	96	95	94	2
3	96	94	93	91	3
4	94	92	90	89	4
5	93	90	88	86	5
6	91	89	86	83	6
7	90	87	84	81	7
8	89	85	82	78	8
9	87	83	80	76	9
10	86	82	78	74	10
11	85	80	76	72	11
12	83	78	74	69	12
13	82	77	72	67	13
14	81	75	70	65	14
15	80	74	68	63	15
16	79	72	67	61	16
17	77	71	65	60	17
18	76	69	63	58	18
19	75	68	62	56	19
20	74	67	60	54	20
21	73	65	59	53	21
22	72	64	57	51	22
23	71	63	56	50	23
24	70	62	54	48	24
25	69	60	53	47	25
26	68	59	52	45	26
27	66	58	50	44	27
28	65	57	49	43	28
29	65	56	48	41	29
30	64	55	47	40	30
31	63	53	46	39	31
32	62	52	44	38	32
33	61	51	43	37	33
34	60	50	42	35	34
35	59	49	41		35
36	58	48	40		36
37	57	47	39		37
38	56	46	38		38
39	55	45	37		39
40	55	45	36		40
41	54	44	35		41
42	53	43			42
43	52	42			43
44	51	41			44
45	51	40			45
46	50				46
47	49				47
48	48				48
49	48				49
50	47				50
51	46				51
52	46				52
53	45				53

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

COST INDEXES (1926 = 100)
EQUIPMENT – NATIONAL AVERAGE

FOR USE IN 2025 EQUALIZATION STUDIES

These indexes can be used for analysis purposes. However, the valuation of machinery, equipment, furniture, fixtures, etc., for assessment purposes will usually be determined by applying the appropriate State Tax Commission personal property multipliers to the original cost, by year installed, of equipment, as discussed in Chapter 15 of the Michigan Assessor's Manual.

INDUSTRY	2024	2023	2022	2021	2020	2019	2018	2017	2016	2015	2014
Average of all	2289.6	2257.4	2216.7	1888.1	1736.4	1727.8	1667.7	1612.2	1580.9	1593.7	1578.8
Airplane mfg.	2684.9	2655.0	2648.4	2223.7	2027.2	2031.7	1965.7	1897.5	1857.2	1885.9	1878.5
Apartment	1591.3	1594.1	1548.8	1353.3	1254.1	1238.8	1202.2	1160.4	1140.1	1139.4	1123.8
Bakery	2253.6	2215.2	2168.0	1842.1	1702.1	1692.0	1634.7	1576.0	1541.2	1553.5	1537.3
Bank	1644.7	1640.2	1627.7	1395.5	1276.5	1267.9	1229.0	1188.1	1163.8	1167.7	1152.5
Bottling	2376.3	2341.8	2306.8	1943.4	1773.9	1768.5	1702.1	1645.4	1616.8	1636.0	1622.5
Brewery & distillery	2957.1	2892.8	2799.0	2377.9	2194.4	2176.8	2088.6	2028.7	2002.6	2014.9	1993.5
Candy	2906.4	2850.8	2781.2	2370.6	2200.0	2184.0	2108.7	2034.7	1990.8	2005.2	1982.6
Cannery (fish)	2831.0	2789.7	2749.7	2333.3	2151.3	2140.6	2067.4	1991.9	1946.2	1963.2	1942.2
Cannery (fruit)	2789.5	2751.7	2705.5	2320.7	2133.8	2119.9	2053.0	1977.4	1932.9	1946.1	1922.5
Cement mfg.	2477.7	2417.2	2352.1	1974.3	1820.2	1807.2	1728.1	1678.3	1651.0	1661.5	1649.1
Chemical	2362.7	2309.3	2255.8	1889.7	1736.0	1727.9	1655.5	1610.6	1590.4	1607.0	1594.1
Church	1882.2	1885.5	1855.6	1605.8	1455.0	1439.1	1393.8	1341.0	1313.0	1313.6	1292.2
Clay products	2417.4	2372.8	2304.7	1957.3	1822.8	1807.3	1731.8	1679.3	1647.2	1654.3	1639.4
Contractor's equip.	2583.3	2526.2	2419.0	2129.7	1990.2	1969.6	1903.2	1860.8	1831.9	1834.1	1812.5
Creamery & dairy	2491.5	2437.7	2362.9	2030.4	1886.0	1868.2	1801.5	1742.1	1711.4	1723.2	1702.5
Dwelling	1520.5	1523.0	1473.6	1292.3	1206.1	1189.8	1155.4	1116.8	1098.6	1097.5	1083.0
Elec. equip. mfg.	2246.9	2230.8	2243.6	1858.6	1679.3	1689.9	1638.1	1572.5	1536.4	1573.2	1574.4
Elec. power equip.	2157.4	2141.4	2139.9	1759.6	1582.1	1590.0	1542.6	1479.5	1445.7	1488.8	1494.8
Flour, cereal & feed	2324.8	2280.8	2228.4	1897.2	1753.6	1745.0	1685.6	1629.4	1598.4	1611.8	1596.2
Garage	2413.1	2379.0	2340.1	2010.9	1853.2	1848.6	1791.1	1734.5	1702.2	1720.3	1710.3
Glass mfg.	2272.7	2231.1	2182.8	1831.2	1676.8	1668.6	1601.6	1549.3	1522.8	1539.1	1529.1
Hospital	2095.7	2068.5	2012.3	1736.3	1615.9	1599.2	1546.7	1494.2	1464.2	1473.0	1456.8
Hotel	1967.2	1944.6	1875.9	1635.5	1528.3	1507.3	1458.7	1410.8	1384.6	1384.4	1364.1
Laundry & cleaning	1968.8	1947.5	1924.2	1628.7	1497.0	1492.6	1440.5	1390.5	1362.0	1374.7	1363.5
Library	2139.0	2135.9	2134.5	1800.5	1632.7	1629.7	1573.6	1512.9	1476.7	1491.8	1479.1
Logging equip.	2261.4	2239.3	2219.1	1902.6	1745.5	1745.3	1690.2	1638.8	1606.4	1623.8	1612.5
Metalworking	2491.4	2450.3	2442.8	2048.4	1891.8	1897.3	1829.9	1769.5	1731.7	1754.9	1746.7
Mining & milling	2666.6	2559.4	2462.8	2121.8	1957.6	1926.1	1842.6	1787.6	1757.3	1761.2	1741.6
Motion picture	2461.8	2446.7	2422.5	2073.0	1878.3	1875.0	1817.7	1750.9	1712.8	1731.7	1718.2
Office equip.	1745.1	1727.0	1681.1	1458.5	1365.7	1350.8	1308.4	1272.0	1251.4	1252.4	1236.5
Packing (fruit)	2578.8	2552.6	2503.2	2171.8	1984.7	1972.2	1911.2	1839.1	1798.0	1802.7	1778.0
Packing (meat)	2465.9	2419.0	2351.3	2018.0	1883.6	1867.9	1803.4	1743.4	1707.4	1713.3	1691.0
Paint mfg.	2428.8	2387.5	2346.8	1976.5	1813.7	1805.9	1736.4	1679.6	1648.4	1664.7	1651.3
Paper mfg.	2270.9	2242.5	2223.0	1883.6	1705.1	1701.5	1641.7	1583.5	1552.1	1567.1	1552.5
Petroleum	2528.1	2465.4	2393.5	2029.4	1880.4	1876.5	1802.7	1759.1	1741.3	1759.2	1745.6
Printing	1850.0	1835.4	1843.8	1581.2	1458.3	1459.9	1421.0	1375.0	1348.4	1363.8	1358.7
Refrigeration	2826.4	2779.7	2720.5	2315.9	2137.9	2127.2	2053.2	1982.5	1942.5	1957.0	1938.6
Restaurant	1874.6	1849.1	1791.9	1557.2	1451.8	1433.7	1386.0	1339.4	1312.6	1314.3	1295.5
Rubber	2462.7	2417.6	2373.1	1986.0	1832.6	1821.7	1756.2	1704.3	1670.8	1684.5	1672.0
School	2115.7	2092.6	2037.5	1757.7	1630.5	1614.0	1559.0	1505.7	1475.3	1479.5	1460.4
Shipbuilding	2694.1	2644.3	2610.2	2181.7	1993.1	1992.3	1910.3	1857.9	1826.4	1848.2	1833.9
Steam power	2363.9	2323.4	2282.6	1895.3	1736.0	1733.3	1662.2	1609.8	1581.6	1604.7	1597.0
Store	2154.9	2149.9	2133.6	1824.9	1659.0	1648.9	1595.1	1535.7	1501.7	1511.0	1492.5
Textile	2163.7	2148.2	2154.8	1828.0	1680.6	1683.4	1631.4	1585.1	1562.6	1583.6	1573.8
Theater	1849.9	1839.3	1812.0	1540.6	1410.9	1401.9	1353.3	1304.6	1276.2	1286.4	1273.9
Warehousing	1782.6	1768.4	1753.8	1506.1	1373.8	1374.8	1335.6	1288.5	1259.5	1267.0	1252.6
Woodworking	2219.1	2196.0	2185.0	1881.6	1690.6	1695.4	1633.0	1556.1	1509.7	1512.3	1485.4

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

COST INDEXES (1926 = 100)
EQUIPMENT – NATIONAL AVERAGE

FOR USE IN 2025 EQUALIZATION STUDIES

INDUSTRY	2013	2012	2011	2010	2008	2006	2004	2002	2000	1998	1996
Average of all	1558.7	1545.9	1503.2	1457.4	1427.3	1302.3	1157.3	1100.0	1084.3	1061.8	1036.0
Airplane mfg.	1860.6	1859.2	1806.1	1741.6	1721.2	1566.6	1375.5	1301.4	1287.8	1263.2	1238.5
Apartment	1109.7	1088.5	1060.4	1032.9	1005.1	942.4	856.7	826.3	812.4	793.1	774.1
Bakery	1516.0	1502.5	1461.6	1415.5	1392.1	1249.7	1110.9	1052.6	1034.3	1010.5	983.4
Bank	1136.5	1128.5	1102.0	1073.2	1050.7	979.4	887.3	847.6	837.0	821.3	803.6
Bottling	1602.8	1595.4	1552.8	1503.6	1479.8	1336.9	1172.9	1111.3	1096.3	1073.5	1049.4
Brewery & distillery	1966.8	1950.4	1900.0	1848.8	1808.7	1634.2	1438.6	1366.5	1343.2	1311.5	1278.1
Candy	1953.9	1935.6	1882.7	1823.7	1792.2	1604.0	1427.3	1354.6	1330.6	1300.4	1263.5
Cannery (fish)	1913.8	1897.6	1844.6	1786.0	1755.8	1575.7	1398.4	1323.3	1300.6	1271.4	1235.8
Cannery (fruit)	1893.0	1869.9	1819.6	1762.6	1735.6	1570.3	1403.1	1331.7	1308.8	1277.8	1240.9
Cement mfg.	1628.6	1612.5	1559.1	1516.4	1469.8	1337.2	1172.4	1104.9	1087.6	1065.1	1041.2
Chemical	1575.3	1572.5	1531.1	1490.9	1460.7	1319.5	1157.7	1096.6	1080.3	1057.8	1033.9
Church	1269.3	1245.8	1215.4	1186.6	1157.6	1092.5	993.4	949.4	933.2	909.6	881.5
Clay products	1617.3	1598.6	1548.3	1503.6	1448.3	1317.9	1165.3	1103.5	1083.8	1062.2	1035.1
Contractor's equip.	1788.0	1754.3	1698.1	1650.9	1609.6	1506.6	1349.7	1291.6	1274.0	1242.2	1204.6
Creamery & dairy	1679.1	1663.4	1618.7	1568.4	1540.6	1380.9	1222.8	1162.3	1142.1	1114.6	1084.9
Dwelling	1070.2	1051.1	1024.8	999.1	973.8	913.0	831.8	804.2	790.2	770.9	753.0
Elec. equip. mfg.	1566.0	1577.2	1537.3	1465.9	1462.1	1302.8	1126.3	1062.3	1055.9	1040.7	1026.5
Elec. power equip.	1492.8	1510.2	1477.2	1400.0	1405.6	1230.8	1048.5	986.3	983.0	968.4	961.5
Flour, cereal & feed	1575.6	1562.8	1519.1	1471.0	1445.0	1300.7	1147.0	1087.9	1070.3	1045.0	1019.4
Garage	1691.4	1679.6	1636.2	1587.7	1558.4	1434.1	1280.9	1223.6	1205.0	1180.8	1157.5
Glass mfg.	1512.4	1503.8	1460.1	1412.0	1381.5	1246.4	1086.8	1025.2	1010.1	989.1	968.3
Hospital	1438.3	1426.7	1388.7	1344.9	1312.2	1195.8	1070.8	1022.3	1005.2	983.2	960.2
Hotel	1343.4	1323.5	1290.0	1257.2	1224.4	1129.6	1025.6	984.0	965.7	941.7	915.1
Laundry & cleaning	1345.7	1335.7	1298.1	1257.4	1227.6	1118.0	991.8	940.0	927.1	908.4	887.1
Library	1458.2	1449.1	1410.3	1366.8	1338.9	1231.7	1096.7	1039.4	1026.4	1007.0	982.5
Logging equip.	1593.2	1577.1	1531.2	1488.5	1460.7	1354.1	1206.3	1147.0	1133.4	1109.0	1082.9
Metalworking	1727.3	1727.7	1676.9	1621.4	1593.2	1453.4	1289.9	1230.0	1219.5	1203.1	1176.6
Mining & milling	1716.3	1683.9	1612.8	1561.5	1494.8	1373.8	1208.0	1142.1	1120.7	1097.2	1068.2
Motion picture	1698.8	1682.3	1639.7	1580.1	1559.2	1430.6	1268.8	1207.4	1195.5	1172.7	1145.9
Office equip.	1221.8	1218.7	1190.9	1161.3	1132.4	1053.1	957.7	922.0	910.7	894.2	876.8
Packing (fruit)	1747.7	1715.0	1668.6	1620.1	1589.9	1467.7	1320.2	1257.4	1236.2	1204.9	1167.7
Packing (meat)	1665.1	1646.2	1599.4	1553.3	1512.5	1366.1	1222.1	1162.3	1141.3	1114.6	1082.9
Paint mfg.	1630.7	1622.4	1574.8	1524.7	1490.9	1349.2	1184.8	1118.6	1102.2	1078.6	1052.7
Paper mfg.	1531.0	1516.8	1472.5	1426.7	1397.5	1278.6	1128.6	1066.2	1050.8	1027.5	998.8
Petroleum	1725.8	1714.6	1665.9	1624.0	1584.6	1419.8	1234.2	1169.0	1142.9	1121.2	1088.4
Printing	1347.8	1342.6	1308.0	1269.1	1253.9	1148.0	1035.3	990.0	980.6	966.2	945.7
Refrigeration	1912.9	1900.2	1844.5	1783.4	1736.3	1572.7	1391.2	1316.4	1293.5	1263.6	1231.2
Restaurant	1274.4	1256.8	1224.2	1192.1	1162.8	1065.1	963.4	920.7	903.7	881.5	855.5
Rubber	1653.6	1652.5	1609.1	1563.8	1531.4	1398.3	1252.0	1185.2	1171.9	1150.0	1121.9
School	1438.8	1422.8	1384.7	1346.8	1311.3	1207.4	1088.9	1041.1	1024.4	1002.3	975.6
Shipbuilding	1811.5	1801.0	1743.9	1692.5	1659.5	1515.4	1322.7	1250.3	1236.8	1212.5	1180.7
Steam power	1580.5	1580.6	1537.0	1484.0	1448.9	1295.4	1128.4	1066.7	1054.5	1037.3	1019.3
Store	1469.7	1454.7	1417.2	1377.5	1346.7	1252.1	1126.7	1073.9	1060.2	1039.0	1012.7
Textile	1554.5	1546.1	1507.8	1471.1	1447.0	1341.0	1207.2	1156.2	1142.2	1123.6	1095.7
Theater	1256.6	1249.7	1218.1	1181.8	1153.6	1062.7	952.3	907.8	896.6	879.7	860.0
Warehousing	1235.2	1216.6	1182.2	1148.7	1120.6	1044.1	942.8	900.4	892.0	874.8	857.7
Woodworking	1459.8	1435.0	1397.6	1356.3	1335.8	1243.4	1122.1	1072.7	1062.1	1042.9	1013.3

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

COMPARATIVE COST MULTIPLIERS

FOR USE IN 2025 EQUALIZATION STUDIES

These multipliers can be used to trend historical costs to the current level for rough estimating or checking. Example: a Class C structure which cost $1,000,000 to build in July 2015 would cost approximately $1,481,000 (i.e., $1,000,000 x 1.481) for 2025 equalization purposes. The factors on this sheet do not allow for depreciation.

YEAR OF FORMER COST	CLASS A Fireproofed Steel Frame	CLASS B Reinforced Concrete Frame	CLASS C Masonry Bearing Walls	CLASS D Wood Frame	CLASS S Metal Frame and Walls
2025	1.000	1.000	1.000	1.000	1.000
OCT 2024	1.007	1.005	1.004	1.003	1.004
JUL 2024	1.017	1.014	1.013	1.011	1.012
APR 2024	1.021	1.015	1.015	1.011	1.012
JAN 2024	1.028	1.023	1.023	1.016	1.017
OCT 2023	1.033	1.023	1.025	1.018	1.017
JUL 2023	1.043	1.025	1.026	1.015	1.019
APR 2023	1.051	1.029	1.025	1.010	1.015
JAN 2023	1.044	1.026	1.014	0.995	1.002
OCT 2022	1.044	1.028	1.005	0.981	0.985
JUL 2022	1.070	1.050	1.014	0.984	1.000
APR 2022	1.123	1.111	1.085	1.066	1.074
JAN 2022	1.181	1.149	1.117	1.098	1.116
OCT 2021	1.244	1.164	1.104	1.067	1.128
JUL 2021	1.341	1.234	1.186	1.160	1.220
APR 2021	1.415	1.300	1.271	1.256	1.306
JAN 2021	1.432	1.319	1.291	1.279	1.325
OCT 2020	1.458	1.350	1.336	1.330	1.371
JUL 2020	1.466	1.359	1.347	1.341	1.381
APR 2020	1.469	1.365	1.354	1.349	1.389
JAN 2020	1.471	1.369	1.358	1.352	1.391
OCT 2019	1.474	1.375	1.364	1.357	1.397
JUL 2019	1.473	1.380	1.364	1.358	1.396
APR 2019	1.472	1.382	1.363	1.353	1.392
JAN 2019	1.477	1.385	1.360	1.350	1.390
OCT 2018	1.492	1.388	1.365	1.351	1.397
JUL 2018	1.525	1.397	1.380	1.368	1.425
APR 2018	1.555	1.411	1.395	1.385	1.447
JAN 2018	1.570	1.429	1.414	1.404	1.464
OCT 2017	1.575	1.437	1.431	1.421	1.477
JUL 2017	1.583	1.446	1.443	1.437	1.493
APR 2017	1.601	1.456	1.455	1.446	1.504
JAN 2017	1.613	1.469	1.467	1.457	1.517
OCT 2016	1.617	1.474	1.476	1.466	1.527
JUL 2016	1.620	1.481	1.484	1.473	1.532
APR 2016	1.619	1.482	1.484	1.471	1.531
JAN 2016	1.616	1.483	1.482	1.467	1.527
OCT 2015	1.610	1.482	1.479	1.462	1.521
JUL 2015	1.613	1.486	1.481	1.463	1.522
APR 2015	1.613	1.489	1.482	1.464	1.523
JAN 2015	1.615	1.492	1.486	1.467	1.525
JUL 2014	1.621	1.503	1.497	1.480	1.534
JAN 2014	1.638	1.518	1.510	1.493	1.546
JUL 2013	1.645	1.526	1.521	1.510	1.547
JAN 2013	1.669	1.553	1.556	1.552	1.561
JUL 2012	1.688	1.576	1.584	1.592	1.572
JAN 2012	1.710	1.597	1.607	1.620	1.589
JUL 2011	1.732	1.617	1.625	1.637	1.609
JAN 2011	1.763	1.643	1.641	1.647	1.635
JUL 2010	1.789	1.664	1.665	1.674	1.645
JAN 2010	1.827	1.701	1.703	1.717	1.679
JUL 2009	1.773	1.661	1.676	1.698	1.618
JAN 2009	1.700	1.601	1.629	1.650	1.534
JUL 2008	1.815	1.694	1.706	1.707	1.643
JAN 2008	1.861	1.729	1.723	1.704	1.683
JUL 2007	1.895	1.759	1.749	1.728	1.714
JAN 2007	1.917	1.780	1.759	1.730	1.731
JUL 2006	1.992	1.843	1.824	1.784	1.799
JAN 2006	2.056	1.897	1.875	1.827	1.852
JUL 2005	2.101	1.940	1.929	1.884	1.896
JAN 2005	2.134	1.967	1.960	1.914	1.929
JUL 2004	2.245	2.064	2.046	2.000	2.023
JAN 2004	2.367	2.164	2.120	2.065	2.133
JUL 2003	2.446	2.245	2.212	2.171	2.219
JAN 2003	2.446	2.250	2.216	2.173	2.221
JUL 2002	2.482	2.285	2.253	2.211	2.251
JAN 2002	2.510	2.310	2.278	2.234	2.274
JUL 2001	2.544	2.343	2.309	2.270	2.297
JAN 2001	2.542	2.345	2.314	2.283	2.304
JUL 2000	2.546	2.347	2.310	2.270	2.298
JAN 2000	2.580	2.375	2.347	2.309	2.327
JUL 1999	2.670	2.459	2.445	2.426	2.405
JAN 1999	2.695	2.487	2.474	2.455	2.423
JUL 1998	2.741	2.530	2.514	2.502	2.458
JAN 1998	2.766	2.555	2.529	2.506	2.477

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

ARCHITECTS' FEE

The architects' fees listed on the next page are based on averages of fees actually charged or recommended. Actual fees, since they are based on the size of the project, the technical difficulty, the artistic requirements, the reputation of the architect and his willingness to accept the assignment, vary greatly and the estimate of the fee is a matter for the valuator's judgment.

Architects fees normally will include part or all of the following:

1. Plans and specifications including consultations, estimates and engineering studies.
2. General administration and overall supervision of construction, not including superintending construction.
3. Approving payment vouchers to the contractor.
4. Approval and acceptance of completed construction.

Regardless of the size and type of construction, all of these services must be performed by someone. On some projects the owner or the general contractor may do the supervision. On governmental projects, many services are performed by government employees; however, in replacing the building, the cost of these services, whether performed by the architect or others, must be included.

The architects' fee multipliers given here are only a guide. On a simple pre-engineered structure, stock plans and specifications may be purchased for under $250, and on a large multi-house development, the architect may get full fees for each individual design and payments as low as $300 per unit for additional uses of the plans, or he may work as a corporate employee. Also, many shed, farm and utility buildings are commonly built without plans or from standard plans which can be obtained free or at a small price, and to add a full architects' fee would be unsuitable.

In actual practice, architects' fees normally are based, by contract, either on a percentage of the entire cost, on a multiplier of the technical payroll plus incidental expenses, or on a fixed sum plus listed expenses.

In the final analysis, the architect's function, when fully performed, is a proper cost of construction. A well-considered matching of structure to land may enhance the end value by more than the fees involved. However, when poorly performed, the cost of design and drafting work may be wasted and result in functional obsolescence in a brand-new structure. This determination is a matter of judgment. The average fees listed for buildings do not include fees for design of furniture, built-in equipment or appliances, plant or offsite, utilities or subdivision layout, or other detailed special items designed for a specific trade or personal use.

SECTION	QUALITY AVERAGE
SEG 1	7.0
SEG 2	7.0
SEG 3	7.0
SEG 4	6.0
SEG 5	7.0
SEG 6	7.0
SEG 7	5.5
SEG 8	7.0

Architectural fees for most UIP components are commensurate with the general SEG building types.

The following special supplemental cost section items already include architects' fees:

Manufactured Housing Parks
Service Stations
Golf Courses
Drive-in Theaters
Ski Lifts
Recreational Enclosures

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

ARCHITECTS' FEE

TABLE I

Furnishings and Interiors
Mausoleums and Memorials
Special Lighting

TABLE II

Airport Terminals
Laboratories & Computer Centers
Convention Centers
Museums, Galleries & Aquariums
Hospitals and Outpatient Centers

TABLE III

Banks and Financial Institutions
Luxury Apartments
Amphitheaters
Medical/Dental Office Buildings
Communications & Broadcasting
Major Post Office Buildings
Convalescent Hospitals
Public Health and Service Centers
Country Clubs and Marinas
Restroom and Shower Buildings
Firing Range Buildings
Specialty Shops
Fieldhouses and Natatoriums
Stadiums and Sports Facilities
Emergency Response Stations
Theaters, Auditoriums & Casinos
Fraternal Buildings
Veterinary Hospitals
Hotels, City Clubs/Resort Lodges
Vocational Schools

TABLE IV

Apartments and Dormitories
Group Care Homes
Bars and Lounges
Health Clubs and Fitness Centers
Branch Post Offices
Homes for the Elderly
Bus Stations and Visitor Centers
Hotels – Limited Service
Clubhouses and Gymnasiums
Laundries and Cleaners
Cold Storage Buildings
Maintenance Hangars
Rooming Houses
Mortuaries
Day Care Centers
Motels, Inns and Cottages
Department Stores
Office Buildings
Relocatable Classrooms
Public Recreation Facilities
Engineering & Research
Racquetball and Tennis Clubs
Industrial Buildings
Regional Shopping Centers
Equestrian Centers
Restaurants and Clubs
Fraternity and Sorority Houses

TABLE V

Arcade Buildings
Grain Elevators
Armories
Loft and Industrial Flex Buildings
Automotive Centers
Manufacturing Industrial Buildings
Barber and Beauty Shops
Markets and Convenience Stores
Bowling Centers
Multiples/Row Houses, Indiv. Des.
Car Washes
Neighborhood & Mixed Shop. Cent.
Community Shopping Centers
Retail Stores and Florist Shops
Creameries
Senior Citizen Residences
Dairies
Showrooms
Discount and Warehouse Stores
Complete Auto Dealerships
Dispensaries and Kennels
Skating Rinks/Rec. Enclosures
Distribution Warehouses
Stables and Horse Arenas
Docks and Wharfs
Storage Hangars
Fast Food, Truck Stops & Snack Bars

TABLE VI

Garages, Minilube and Service
Shipping Docks & Transfer Points
Greenhouse Structures
Storage & Emergency Response Garages
Prefab. Booths and Shelters
Recycling, Waste Transfer Struc.
Storage Warehouses
Roadside Markets
Service Stations/Pkg. Structures

EXPLANATION

The tables of architects' fees are based on composite curves for new construction derived from many actual fees charged, recommendations of several architectural committees in various states, and architectural time studies. In cases where superior quality and detail are required, the fee may be higher than the average, while very low quality and standardized buildings may call for a fee which is lower. Renovation or rehab work may require considerably more time, and fees can run 20% to 60% above those listed due to the many variables and complexities involved.

The fee schedules contain approximately 30% (20% to 40%) for contract administration and supervision. In many cases, this function may be performed by the contractor, an employee of the owner or an outside consultant. In any case, this is a proper charge against the building and the total fee should be added to building costs computed from the Unit-in-Place or the Segregated Costs.

PROJECT COST Up To	TABLE I	II	III	IV	V	VI
$ 50,000	10.7	9.7	8.7	7.9	7.1	6.4
100,000	10.3	9.4	8.4	7.6	6.9	6.2
200,000	10.0	9.1	8.2	7.4	6.7	6.0
500,000	9.5	8.7	7.8	7.1	6.4	5.8
1,000,000	9.2	8.4	7.6	6.9	6.2	5.6
2,000,000	8.9	8.1	7.3	6.6	6.0	5.5
3,000,000	8.7	7.9	7.2	6.5	5.9	5.4
5,000,000	8.4	7.7	7.0	6.4	5.8	5.3
10,000,000	8.1	7.5	6.8	6.2	5.6	5.1
20,000,000	7.9	7.2	6.6	6.0	5.4	5.0
50,000,000	7.5	6.9	6.3	5.7	5.2	4.8
and up	7.3	6.8	6.2	5.6	5.1	4.7

The following are the approximate percentages included in the manual costs for multifamily residences and miscellaneous light commercial structures not listed in the above table.

	LOW COST	FAIR	AVERAGE	GOOD
Multiple-Residential . . . . . Structures	1.5%	1.9%	2.4%	3.9%
Light Commercial . . . . . Utility-Shop Structures	1.7%	2.1%	2.5%	3.5%

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.