APARTMENTS



AVERAGE CLASS A



AVERAGE CLASS B

OCCUPANCY DESCRIPTION: High-rise apartments are structures with three or more stories of multiple dwelling units. Each dwelling unit consists of its own separate living area and kitchen facility.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Allowance for lo by area and interior hall access to dwelling units. Elevators included where designated with an (*) asterisk

NOT INCLUDED IN COSTS: Sprinklers, appliances or balconies.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 255.00	Face brick, limestone, metal or concrete and glass panels	Good interior detail, carpet, or hard-wood, sheet vinyl or ceramic tile	*Many good fixtures, TV jacks good baths and kitchens	Warm and cool air (zoned)
	Average	203.50	Little trim, brick, block, metal or concrete and glass	Drywall or plaster, average carpet and vinyl composition floors	*Few electric fixtures, average plumbing, one bath per unit	Heat pump system
	Low Cost	161.50	Very plain, brick or block, or low-cost concrete panels	Drywall, sprayed or painted ceilings, very plain, asphalt tile	*Minimum uniform code, one bath per unit	Hot water
B	Good	228.00	Face brick, limestone, metal or concrete and glass panels	Good interior detail, carpet or hard-wood, sheet vinyl or ceramic tile	*Many good fixtures, TV jacks, good baths and kitchens	Warm and cool air (zoned)
	Average	181.50	Little trim, brick, block, metal or concrete and glass	Drywall or plaster, vinyl composition tile and average carpet	*Few electric fixtures, average plumbing, one bath per unit	Heat pump system
	Low Cost	144.50	Very plain, brick or block or low-cost concrete panels	Drywall, sprayed or painted ceilings, very plain, asphalt tile	*Minimum uniform code, one bath per unit	Hot water
A-B	Basement units	160.00	Half exposed, good fenestration	Drywall or plaster, painted, vinyl composition and average carpet	Few electric fixtures, average plumbing, one bath per unit	Hot water
	Finished Basement	103.50	Finished interior	Finished floor and ceilings, game room	Adequate lighting/plumbing	Forced air
	Parking Basements	81.50	Unfinished interior	Concrete w/ hardener, lines & stops	Minimum lighting, floor drains	Ventilation
	Utility Basement	71.00	Painted interior	Utility and storage areas	Utility lighting and plumbing	None
C	Good	183.50	Brick, metal or concrete and glass panels, some trim	Drywall or plaster, good carpet or hardwood, vinyl composition, cer. tile	*Good electric/plumbing, good baths and kitchens	Heat pump system
	Average	138.50	Little ornamentation, brick or block, concrete panels	Drywall or plaster, average carpet and vinyl composition	*Average fixtures, one bath per unit, average circuits	Forced air
	Low Cost	104.00	Very plain brick or block, minimum fenestration	Drywall and painted masonry/plaster coat, asph. tile, low-cost carpet	Minimum uniform code, one bath per unit	Indiv. thru-wall heat pumps
CMILL	Good	207.00	Mill type construction, heavy brick wall, trusses, good sash	Drywall, or plaster, good carpet or hardwood, vinyl comp., ceramic tile	*Good electric/plumbing, good baths and kitchens	Heat pump system
	Average	168.50	Mill type construction, brick and block, wood trusses	Drywall, or plaster, average carpet and vinyl composition, softwood	*Average fixtures, one bath per unit, average circuits	Hot water
D	Good	174.00	Good stucco or siding with ornamentation	Good drywall or plaster, carpet, good vinyl composition tile or sheet	*Good fixtures, many outlets, over one bath per unit	Heat pump system
	Average	131.50	Frame and stucco, little trim, standard design	Plaster or drywall, carpet or hardwood, vinyl composition tile	*Average fixtures, one bath per unit, average circuits	Forced air
	Low Cost	98.00	Low-cost siding or stucco	Drywall, low-cost carpet, asphalt tile	Minimum uniform code, one bath per unit	Indiv. thru-wall heat pumps
D MASONRY VENEER	Good	179.00	Good brick veneer with ornamentation	Good drywall or plaster, carpet, good vinyl composition tile or sheet	*Good fixtures, many outlets, over one bath per unit	Heat pump system
	Average	135.50	Brick veneer, little trim, standard design	Plaster or drywall, carpet or hardwood, vinyl composition tile	*Average fixtures, one bath per unit, average circuits	Forced air
S	Good	169.50	Best insulated sandwich walls, good fenestration, good frame	Drywall, carpet and vinyl composition, ceramic tile	*Good fixtures, many outlets, over one bath per unit	Heat pump system
	Average	127.00	Sandwich walls, fenestration to code, little trim	Drywall, carpet and vinyl comp., average cabinetry and finish	*Average fixtures, one bath per unit, average circuits	Forced air
CDS†	Basement units	115.50	Half exposed, good fenestration	Drywall or plaster, vinyl composition tile and average carpet	Few electric fixtures, average plumbing, one bath per unit	Forced air
	Finished Basement	63.50	Finished interior, add for saunas, pools, bars and equip.	Gypsum board ceiling, vinyl composition tile sheet vinyl	Adequate lighting/plumbing	Electric wall heaters
	Parking Basement	51.50	Unfinished interior	Plaster or drywall ceiling, concrete floor	Minimum lighting, floor drains	Ventilation
	Utility Basement	44.25	Unfinished interior	Unfinished floor and ceiling	Minimum lighting/plumbing	None

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.79 per square foot to the basement cost.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

APARTMENTS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated Cost, Section SEG 1.

	LOW	AVG.	GOOD	EXCL.
Allowance (if not itemized)	$1,820	$4,150	$7,550	$12,800

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs. For detailed costs see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Class C	Sq. Ft. Costs	Classes D/S	Sq. Ft. Costs
Good	$8.39	Good	$5.47	Good	$4.86
Average	6.43	Average	4.42	Average	4.06
Low Cost	4.86				

ELEVATOR STOPS: For basement stops, add $ 9,550 to $14,400 per stop.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 5.14	$ 6.63	$ 8.55	$ 11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
50,000	3.36	4.20	5.24	6.50
100,000	3.00	3.73	4.59	5.71
200,000	2.69	3.30	4.06	5.01

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete . .	$ 34.00	$ 43.50	$ 55.00	$ 71.00
Steel	31.75	42.50	56.50	75.50
Wood	29.75	39.50	52.50	68.50
Add for ornate finishes, balustrades .	29.50	36.00	44.25	54.00
Add for roofs or awnings .	15.35	20.40	27.00	36.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork). . .	$ 21.90	Central refrigeration (zoned)	$ 16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector. .	20.75	Heat pump system	25.50	Pkg. refrig. . . $2,750 to $3,425 per ton capacity	
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers. $331 to $535 per MCFM capacity	
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 3.18

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	12	1.055
9	.973	13	1.084
10	1.000 (base)	14	1.114
11	1.027		

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 200	250	300	350	400	450	500	550	600	650	700	750	800	850	Average Floor Area Sq. Ft./Story
2,000	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	.959	.989	1.021	1.052	1.083	1.113	1.143	1.175	1.206	1.237	1.268	1.299	1.329	-----	**4,000**
6,000	.917	.938	.959	.980	1.000	1.021	1.042	1.063	1.083	1.103	1.123	1.144	1.165	-----	**6,000**
8,000	-----	.913	.929	.944	.959	.974	.989	1.005	1.021	1.037	1.052	1.068	1.083	1.098	**8,000**
10,000	-----	-----	.910	.922	.935	.947	.959	.972	.984	.997	1.009	1.022	1.034	1.047	**10,000**
12,000	-----	-----	-----	.907	.917	.928	.938	.949	.959	.970	.980	.990	1.000	1.010	**12,000**
14,000	-----	-----	-----	-----	.906	.915	.924	.933	.942	.951	.959	.968	.977	.986	**14,000**
16,000	-----	-----	-----	-----	.898	.906	.913	.921	.929	.937	.944	.952	.959	.967	**16,000**
18,000	-----	-----	-----	-----	.890	.897	.904	.911	.917	.925	.932	.939	.945	.952	**18,000**
20,000	-----	-----	-----	-----	.885	.892	.898	.904	.910	.916	.922	.929	.935	.941	**20,000**
22,000	-----	-----	-----	-----	-----	-----	.892	.898	.903	.909	.915	.920	.926	.932	**22,000**
25,000	-----	-----	-----	-----	-----	-----	.883	.888	.892	.897	.903	.907	.912	.916	**25,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

APARTMENTS (ALTERNATE METHOD)
CLASSES A and B



AVERAGE CLASS A



AVERAGE CLASS B

OCCUPANCY DESCRIPTION:

Shell, Apartment (High Rise)
This occupancy, together with occupancy Interior Space, Apartment High Rise, allows you to individually price the shell and the tenant improvement costs for an apartment (in separate sections of the manual). This provides an alternative to occupancy Apartment High Rise, which includes both the shell and tenant improvement costs.

High-rise apartment shells are structures with three or more stories of multiple dwelling units. The structures are built of all construction classes. Each dwelling unit consists of its own separate living area and kitchen facility. Normally, structures over three stories have elevators, but this depends on the height of the building and the need for transportation to the upper levels. These shell structures have finished lobby areas, interior hall access to dwelling units and some type of stairway for fire exit. These shell structures include common area finishes only, which are about 5%.

Although apartments built as condominiums sometimes are required by building and zoning codes to have certain items not required for rental units, basically, "condominium" is a type of ownership and not a type of construction and the apartment costs are valid.

Interior Space, Apartment (High Rise)
This occupancy, together with occupancy Shell, Apartment High Rise, allows you to individually price the shell and the tenant improvement costs for an apartment (in separate sections of the manual). This provides an alternative to occupancy Apartment High Rise, which includes both the shell and tenant improvement costs.

The lower qualities typically have low-cost partitions, floor covers, minimal cabinetry, small open kitchen and one bath or a bath and one-half for each unit, regardless of the number of bedrooms. The better qualities have plaster, paneling, good detailing in molding and trim, high cost floor finishes, and full kitchen and dining rooms. Some of the special refinements found in the better qualities include intercoms, television jacks and antennas, and at least one bath per bedroom.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Allowance for lobby area and interior hall access to dwelling units. Elevators included where designated with an (*) asterisk

NOT INCLUDED IN COSTS: Sprinklers, appliances or balconies.

SQUARE FOOT COST TABLE

APARTMENTS (HIGH-RISE)
CLASSES A AND B: SHELL APARTMENT BUILDINGS

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR CORE FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 151.00	Good metal and solar glass, face brick, best precast concrete panels	Plaster, paneling, vinyl, good pavers, terrazzo, carpet, good entry & lobbies	*Good fluorescent core ceilings, adequate service fixtures	None
	Average	119.50	Brick, concrete or metal and glass, steel stud panels, some trim	Drywall or plaster, vinyl, terrazzo, carpet, adequate entry lobby	*Average-intensity core lighting, average service fixtures	None
	Low cost	94.00	Minimum-cost walls and fenestration, very plain	Drywall, paint or paper, acoustic ceilings, vinyl comp., plain lobbies	*Minimum lobby lighting, few core extras	None
B	Good	130.50	Good metal and solar glass, face brick, best precast concrete panels	Plaster, paneling, vinyl, good pavers, terrazzo, carpet, good entry & lobbies	*Good fluorescent core ceilings, adequate service fixtures	None
	Average	102.50	Brick, concrete or metal and glass panels, some trim, entry ornament	Drywall or plaster, vinyl, terrazzo, carpet, adequate entry lobby	*Average-intensity core lighting, average service fixtures	None
	Low cost	81.00	Minimum-cost walls, precast elements and fenestration, very plain	Drywall, paint or paper, acoustic ceilings, vinyl comp., plain lobbies	*Minimum lobby lighting, few core extras	None

CLASSES A AND B: INTERIOR BUILD-OUT
(SQUARE FEET OF BUILD-OUT-FINISH)

TYPE	COST/ SQ. FT.	INTERIOR FINISH	LIGHTING AND PLUMBING	HEAT
Good	$ 102.00	Plaster or drywall, good partitions, paneling, carpet, tile or vinyl, good room sizes, some good cabinetry and shelving, powder room	Many good fixtures, TV jacks, good baths and kitchens	Warm and cool air (zoned)
Average	81.50	Average drywall, vinyl composition, carpet, adequate shelving, counters, small dining area and kitchen, adequate bedrooms and bath	Adequate lighting/plumbing, phone and TV jacks	Heat pump system
Low cost	65.50	Low-cost partitions, paint, vinyl composition, low-cost carpet, minimal counters and shelving, small kitchen area, one bath per unit	Adequate standard lighting and plumbing per good codes	Hot water

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

APARTMENTS CLASSES A and B (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated Cost, Section SEG 1.

	LOW	AVG.	GOOD	EXCL.
Allowance (if not itemized)	$1,820	$4,150	$7,550	$12,800

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs. For detailed costs see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Good	$8.39
Average	6.43
Low Cost	4.86

ELEVATOR STOPS: For basement stops, add $9,550 to $14,400 per stop.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 5.14	$ 6.63	$ 8.55	$ 11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
50,000	3.36	4.20	5.24	6.50
100,000	3.00	3.73	4.59	5.71
200,000	2.69	3.30	4.06	5.01

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete . .	$34.00	$43.50	$55.00	$71.00
Steel	31.75	42.50	56.50	75.50
Wood	29.75	39.50	52.50	68.50
Add for ornate finishes, balustrades .	29.50	36.00	44.25	54.00
Add for roofs or awnings .	15.35	20.40	27.00	36.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork). . .	$21.90	Central refrigeration (zoned)	$16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector. .	20.75	Heat pump system	25.50	Pkg. refrig. . .	$2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers. $331 to $535 per MCFM capacity	
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$3.18

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	12	1.055
9	.973	13	1.084
10	1.000 (base)	14	1.114
11	1.027		

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 200	250	300	350	400	450	500	550	600	650	700	750	800	850	Average Floor Area Sq. Ft./Story
2,000	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	.959	.989	1.021	1.052	1.083	1.113	1.143	1.175	1.206	1.237	1.268	1.299	1.329	-----	**4,000**
6,000	.917	.938	.959	.980	1.000	1.021	1.042	1.063	1.083	1.103	1.123	1.144	1.165	-----	**6,000**
8,000	-----	.913	.929	.944	.959	.974	.989	1.005	1.021	1.037	1.052	1.068	1.083	1.098	**8,000**
10,000	-----	-----	.910	.922	.935	.947	.959	.972	.984	.997	1.009	1.022	1.034	1.047	**10,000**
12,000	-----	-----	-----	.907	.917	.928	.938	.949	.959	.970	.980	.990	1.000	1.010	**12,000**
14,000	-----	-----	-----	-----	.906	.915	.924	.933	.942	.951	.959	.968	.977	.986	**14,000**
16,000	-----	-----	-----	-----	.898	.906	.913	.921	.929	.937	.944	.952	.959	.967	**16,000**
18,000	-----	-----	-----	-----	.890	.897	.904	.911	.917	.925	.932	.939	.945	.952	**18,000**
20,000	-----	-----	-----	-----	.885	.892	.898	.904	.910	.916	.922	.929	.935	.941	**20,000**
22,000	-----	-----	-----	-----	-----	-----	.892	.898	.903	.909	.915	.920	.926	.932	**22,000**
25,000	-----	-----	-----	-----	-----	-----	.883	.888	.892	.897	.903	.907	.912	.916	**25,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

APARTMENTS (ALTERNATE METHOD)
CLASSES C, D and S

OCCUPANCY DESCRIPTION:

Shell, Apartment (High Rise)

This occupancy, together with occupancy Interior Space, Apartment High Rise, allows you to individually price the shell and the tenant improvement costs for an apartment (in separate sections of the report). This provides an alternative to occupancy Apartment High Rise, which includes both the shell and tenant improvement costs.

High-rise apartment shells are structures with three or more stories of multiple dwelling units. The structures are built of all construction classes. Each dwelling unit consists of its own separate living area and kitchen facility. Normally, structures over three stories have elevators, but this depends on the height of the building and the need for transportation to the upper levels. These shell structures have finished lobby areas, interior hall access to dwelling units and some type of stairway for fire exit. These shell structures include common area finishes only, which are about 5%. Although apartments built as condominiums sometimes are required by building and zoning codes to have certain items not required for rental units, basically, “condominium” is a type of ownership and not a type of construction and the apartment costs are valid.

Interior Space, Apartment (High Rise)

This occupancy, together with occupancy Shell, Apartment High Rise, allows you to individually price the shell and the tenant improvement costs for an apartment (in separate sections of the report). This provides an alternative to occupancy Apartment High Rise, which includes both the shell and tenant improvement costs.

The lower qualities typically have low-cost partitions, floor covers, minimal cabinetry, small open kitchen and one bath or a bath and one-half for each unit, regardless of the number of bedrooms. The better qualities have plaster, paneling, good detailing in molding and trim, high cost floor finishes, and full kitchen and dining rooms. Some of the special refinements found in the better qualities include intercoms, television jacks and antennas, and at least one bath per bedroom.

INCLUDED IN COSTS: Architects’ fees and contractors’ overhead and profit. Allowance for lobby area and interior hall access to dwelling units. Elevators included where designated with an (*) asterisk

NOT INCLUDED IN COSTS: Sprinklers, appliances or balconies.

SQUARE FOOT COST TABLE

APARTMENTS (HIGH-RISE)
CLASSES C, D AND S: SHELL APARTMENT BUILDINGS

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR CORE FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$107.00	Steel frame or bearing walls, brick/ conc. panels, some ornamentation	Plaster, paneling, vinyl, good pavers, terrazzo, carpet, good entry & lobbies	*Good fluorescent core ceilings, adequate service fixtures	None
	Average	83.50	Steel or concrete frame, or bearing walls, some trim	Drywall or plaster, vinyl, terrazzo, carpet, adequate entry lobby	*Average-intensity core lighting, average service fixtures	None
	Low cost	62.50	Masonry bearing walls, light rafters, minimum fenestration, very plain	Drywall, paint or paper, acoustic ceilings, vinyl comp., plain lobbies	Minimum lobby lighting, few core extras	None
D MASONRY VENEER	Good	101.00	Good brick veneer with ornamentation	Plaster, paneling, vinyl, good pavers, terrazzo, carpet, good entry & lobbies	*Good fluorescent core ceilings, adequate service fixtures	None
	Average	79.50	Brick veneer, little trim, standard design	Drywall or plaster, vinyl, terrazzo, carpet, adequate entry lobby	*Average-intensity core lighting, average service fixtures	None
D	Good	98.00	Frame or bearing wall, good stucco or siding with trim	Plaster, paneling, vinyl, good pavers, terrazzo, carpet, good entry & lobbies	*Good fluorescent core ceilings, adequate service fixtures	None
	Average	76.50	Frame and stucco, little trim, standard design	Drywall or plaster, vinyl, terrazzo, carpet, adequate entry lobby	*Average-intensity core lighting, average service fixtures	None
	Low cost	56.50	Low-cost siding or stucco, minimum fenestration, very plain	Drywall, paint or paper, acoustic ceilings, vinyl comp., plain lobbies	Minimum lobby lighting, few core extras	None
S	Good	93.50	Best insulated sandwich walls, good fenestration, good frame	Plaster, paneling, vinyl, good pavers, terrazzo, carpet, good entry & lobbies	*Good fluorescent core ceilings, adequate service fixtures	None
	Average	73.00	Sandwich walls, fenestration to code, little trim	Drywall or plaster, vinyl, terrazzo, carpet, adequate entry lobby	*Average-intensity core lighting, average service fixtures	None

CLASSES C, D AND S: INTERIOR BUILD-OUT

(SQUARE FEET OF BUILD-OUT-FINISH)

TYPE	COST/ SQ. FT.	INTERIOR FINISH	LIGHTING AND PLUMBING	HEAT
Good	$ 77.50	Plaster or drywall, good partitions, paneling, carpet, tile or vinyl, good room sizes, some good cabinetry and shelving	Good fixtures, many outlets, over one bath per unit	Heat pump system
Average	56.00	Average drywall, vinyl composition, carpet, adequate shelving, counters, small dining area and kitchen, adequate bedrooms and bath	Average fixtures and circuits, one bath per unit	Forced air
Low cost	42.50	Low-cost partitions, paint, vinyl composition, low-cost carpet, minimal counters and shelving, small kitchen area	Minimum uniform code, one bath per unit	Indiv. thru-wall heat pumps

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

APARTMENTS CLASSES C, D and S (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated Cost, Section SEG 1.

	LOW	AVG.	GOOD	EXCL.
Allowance (if not itemized)	$1,820	$4,150	$7,550	$12,800

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs. For detailed costs see Section UIP 8.

Class C	Sq. Ft. Costs	Classes D/S	Sq. Ft. Costs
Good	$5.47	Good	$4.86
Average	4.42	Average	4.06

ELEVATOR STOPS: For basement stops, add $9,550 to $14,400 per stop.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 5.14	$ 6.63	$ 8.55	$ 11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
50,000	3.36	4.20	5.24	6.50
100,000	3.00	3.73	4.59	5.71
200,000	2.69	3.30	4.06	5.01

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete . .	$34.00	$43.50	$55.00	$71.00
Steel	31.75	42.50	56.50	75.50
Wood	29.75	39.50	52.50	68.50
Add for ornate finishes, balustrades .	29.50	36.00	44.25	54.00
Add for roofs or awnings .	15.35	20.40	27.00	36.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork). . .	$21.90	Central refrigeration (zoned)	$16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector. .	20.75	Heat pump system	25.50	Pkg. refrig. . .	$2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers.	$331 to $535 per MCFM capacity
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$3.18

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	12	1.055
9	.973	13	1.084
10	1.000 (base)	14	1.114
11	1.027		

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 200	250	300	350	400	450	500	550	600	650	700	750	800	850	Average Floor Area Sq. Ft./Story
2,000	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	.959	.989	1.021	1.052	1.083	1.113	1.143	1.175	1.206	1.237	1.268	1.299	1.329	-----	**4,000**
6,000	.917	.938	.959	.980	1.000	1.021	1.042	1.063	1.083	1.103	1.123	1.144	1.165	-----	**6,000**
8,000	-----	.913	.929	.944	.959	.974	.989	1.005	1.021	1.037	1.052	1.068	1.083	1.098	**8,000**
10,000	-----	-----	.910	.922	.935	.947	.959	.972	.984	.997	1.009	1.022	1.034	1.047	**10,000**
12,000	-----	-----	-----	.907	.917	.928	.938	.949	.959	.970	.980	.990	1.000	1.010	**12,000**
14,000	-----	-----	-----	-----	.906	.915	.924	.933	.942	.951	.959	.968	.977	.986	**14,000**
16,000	-----	-----	-----	-----	.898	.906	.913	.921	.929	.937	.944	.952	.959	.967	**16,000**
18,000	-----	-----	-----	-----	.890	.897	.904	.911	.917	.925	.932	.939	.945	.952	**18,000**
20,000	-----	-----	-----	-----	.885	.892	.898	.904	.910	.916	.922	.929	.935	.941	**20,000**
22,000	-----	-----	-----	-----	-----	-----	.892	.898	.903	.909	.915	.920	.926	.932	**22,000**
25,000	-----	-----	-----	-----	-----	-----	.883	.888	.892	.897	.903	.907	.912	.916	**25,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

APARTMENTS – LUXURY



GOOD CLASS A



GOOD CLASS B

OCCUPANCY DESCRIPTION: High-rise luxury apartments are structures with three or more floors of multiple dwelling units, typically owner or time-share occupied. Each dwelling unit consists of its own separate living area and kitchen facility. Normally, structures over three stories have elevators, but this dwelling units and some type of stairway for fire exit. Although apartments built as co-ops, condominiums, or time-shares sometimes are required by building and zoning codes to have certain items not required for typical rental units, basically, “condominium” is a type of ownership and not a type of construction and the luxury apartment costs are valid.

INCLUDED IN COSTS: Architects’ fees and contractors’ overhead and profit. Allowance for lobby area and interior hall access to dwelling units. Elevators are include.

NOT INCLUDED IN COSTS: Appliances, fireplaces, canopies, balconies, swimming pools, yard improvements and any developers’ or soft costs related to a type of ownership such as condominium.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 412.00	Best metal or stone, brick or block backup, solar glass, best lobby	Finest interior detail, hardwoods, ceramic, custom carpet, built-ins	Elevators, Master antennas, fine fixtures, more than one bath per bedroom	Hot and chilled water (zoned)
	Average	333.00	Good metal and solar glass, face brick, precast concrete panels, EIFS	Good interior detail, carpet, ceramic tile, some vinyl and fine hardwood	Elevators, Master antennas, fine fixtures, one full bath per bedroom	Hot and chilled water (zoned)
B	Good	366.00	Best metal or stone, brick or block backup, solar glass, best lobby	Finest interior detail, hardwoods, ceramic, custom carpet, built-ins	Elevators, Master antennas, fine fixtures, more than one bath per bedroom	Hot and chilled water (zoned)
	Average	298.00	Good metal and solar glass, face brick, precast concrete panels, EIFS	Good interior detail, carpet, ceramic tile, some vinyl and fine hardwood	Elevators, Master antennas, fine fixtures, one full bath per bedroom	Hot and chilled water (zoned)
C	Excellent	364.00	Best stones, metal, solar glass, highly ornamented lobby	Best interior detail, hardwoods, ceramic, carpet, built-ins	Elevators, Master antennas, fine fixtures, more than one bath per bedroom	Hot and chilled water (zoned)
	Good	285.00	Good masonry and glass, good ornamentation and lobby	Good interior detail, sheet vinyl, ceramic tile/carpet, paneling, fine hardwood	Elevators, Master antennas, extra fixtures, one full bath per bedroom	Warm and cool air (zoned)
	Average	234.00	Stone, brick, metal and glass, individual design, good lobby	Good plaster, paneling/paper, vinyl, carpeting or hardwood, some extras	Elevators, Master antennas, fine fixtures, one full bath per bedroom	Warm and cool air (zoned)
D MASONRY VENEER	Excellent	357.50	Best brick or stone veneer, highly ornamental lobby	Best interior detail, hardwoods, ceramic, carpet, built-ins	Elevators, Master antennas, fine fixtures, more than one bath per bedroom	Hot and chilled water (zoned)
	Good	279.00	Good veneers and trim, good ornamentation and lobby	Good interior detail, sheet vinyl, ceramic tile/carpet, paneling, fine hardwood	Elevators, Master antennas, extra fixtures, more than one bath per bedroom	Warm and cool air (zoned)
	Average	229.00	Face brick or stone veneer, individual design, good lobby	Good plaster, paneling/paper, vinyl, carpeting or hardwood, some extras	Elevators, TV and phone jacks, good fixtures, one bath per bedroom	Warm and cool air (zoned)
D	Excellent	350.00	Best EIFS, stone trim, highly ornamental lobby	Best interior detail, hardwoods, ceramic, carpet, built-ins	Elevators, Master antennas, fine fixtures, more than one bath per bedroom	Hot and chilled water (zoned)
	Good	272.50	Good EIFS or sidings, good ornamentation and lobby	Good interior detail, sheet vinyl, ceramic tile/carpet, paneling, fine hardwood	Elevators, Master antennas, extra fixtures, more than one bath per bedroom	Warm and cool air (zoned)
	Average	223.00	Good stucco or siding, brick and stone trim, good lobby	Good plaster, paneling/paper, vinyl, carpeting or hardwood, some extras	Elevators, TV and phone jacks, good fixtures, one bath per bedroom	Warm and cool air (zoned)

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

APARTMENTS – LUXURY

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated Cost, Section SEG 1.

	LOW	AVG.	GOOD	EXCL.
Allowance (if not itemized)	$1,820	$4,150	$7,550	$12,800

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs. For detailed costs see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Class C	Sq. Ft. Costs	Classes D	Sq. Ft. Costs
Excellent	$12.80	Excellent	$8.56	Excellent . . .	$7.57
Good	11.20	Good	7.57	Good	6.71
		Average	6.71	Average	5.91

ELEVATOR STOPS: For basement stops, add $9,550 to $14,400 per stop.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 5.14	$ 6.63	$ 8.55	$ 11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
50,000	3.36	4.20	5.24	6.50
100,000	3.00	3.73	4.59	5.71
200,000	2.69	3.30	4.06	5.01

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete . .	$34.00	$43.50	$55.00	$71.00
Steel	31.75	42.50	56.50	75.50
Wood	29.75	39.50	52.50	68.50
Add for ornate finishes, balustrades .	29.50	36.00	44.25	54.00
Add for roofs or awnings .	15.35	20.40	27.00	36.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork). . .	$21.90	Central refrigeration (zoned)	$16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector. .	20.75	Heat pump system	25.50	Pkg. refrig. . .	$2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers. $331 to $535 per MCFM capacity	
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$3.18

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	12	1.055
9	.973	13	1.084
10	1.000 (base)	14	1.114
11	1.027		

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 200	250	300	350	400	450	500	550	600	650	700	750	800	850	Average Floor Area Sq. Ft./Story
2,000	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	.959	.989	1.021	1.052	1.083	1.113	1.143	1.175	1.206	1.237	1.268	1.299	1.329	-----	**4,000**
6,000	.917	.938	.959	.980	1.000	1.021	1.042	1.063	1.083	1.103	1.123	1.144	1.165	-----	**6,000**
8,000	-----	.913	.929	.944	.959	.974	.989	1.005	1.021	1.037	1.052	1.068	1.083	1.098	**8,000**
10,000	-----	-----	.910	.922	.935	.947	.959	.972	.984	.997	1.009	1.022	1.034	1.047	**10,000**
12,000	-----	-----	-----	.907	.917	.928	.938	.949	.959	.970	.980	.990	1.000	1.010	**12,000**
14,000	-----	-----	-----	-----	.906	.915	.924	.933	.942	.951	.959	.968	.977	.986	**14,000**
16,000	-----	-----	-----	-----	.898	.906	.913	.921	.929	.937	.944	.952	.959	.967	**16,000**
18,000	-----	-----	-----	-----	.890	.897	.904	.911	.917	.925	.932	.939	.945	.952	**18,000**
20,000	-----	-----	-----	-----	.885	.892	.898	.904	.910	.916	.922	.929	.935	.941	**20,000**
22,000	-----	-----	-----	-----	-----	-----	.892	.898	.903	.909	.915	.920	.926	.932	**22,000**
25,000	-----	-----	-----	-----	-----	-----	.883	.888	.892	.897	.903	.907	.912	.916	**25,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

APARTMENTS – LUXURY (ALTERNATE METHOD) CLASSES A and B

OCCUPANCY DESCRIPTION:

Shell, Luxury Apartment
This occupancy, together with occupancy Interior Space, Luxury Apartment, allows you to individually price the shell and the tenant improvement costs for an apartment (in separate sections of the report). This provides an alternative to occupancy Luxury Apartment (High Rise), which includes both the shell and tenant improvement costs.

High-rise luxury apartment shells are structures with three or more floors of multiple dwelling units, typically owner or time-share occupied. Each dwelling unit consists of its own separate living area and kitchen facility. Normally, shell structures over three stories have elevators, but this depends on the height of the building and the need for transportation to the upper levels. These shell structures have a lobby area, hall access to dwelling units and some type of stairway for fire exit. These shell structures include common area finishes only, which are about 10%. Although apartments built as co-ops, condominiums, or time-shares sometimes are required by building and zoning codes to have certain items not required for typical rental units, basically, “condominium” is a type of ownership and not a type of construction and the luxury apartment costs are valid.

Interior Space, Luxury Apartment
This occupancy, together with occupancy Shell, Luxury Apartment, allows you to individually price the shell and the tenant improvement costs for an apartment (in separate sections of the report). This pro- vides an alternative to occupancy Luxury Apartment (High Rise), which includes both the shell and tenant improvement costs. These interiors have plaster, paneling, good detailing in molding and trim, high cost floor finishes, and full kitchen and dining rooms. Some of the special refinements found include master antennas, and more than one bath per bedroom at the better qualities.

SQUARE FOOT COST TABLE INCLUDED IN COSTS: Architects’ fees and contractors’ overhead and profit. Allowance for lobby area and interior hall access to dwelling units. Elevators are included where designated with an (*) asterisk.

NOT INCLUDED IN COSTS: Appliances, fireplaces, canopies, balconies, swimming pools, yard improvements and any developers’ or soft costs related to a type of ownership such as condominium.

CLASSES A AND B: SHELL LUXURY APARTMENT BUILDINGS

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 214.00	Best metal or stone, brick or block backup, solar glass	Plaster, best veneers, best marble and carpet, top lobby finishes	*Luminous lobby ceiling, excellent core lighting, finest service fixtures	None
	Average	168.50	Good metal and solar glass, face brick, precast concrete panels, EIFS	Plaster, ceramic tile, carpet, some vinyl and fine hardwood, good entry & lobby	*Luminous lobby ceiling, good core lighting, service fixtures	None
B	Good	182.00	Best metal or stone, brick or block backup, solar glass	Plaster, best veneers, best marble and carpet, top lobby finishes	*Luminous lobby ceiling, excellent core lighting, finest service fixtures	None
	Average	143.50	Good metal and solar glass, face brick, precast concrete panels, EIFS	Plaster, ceramic tile, carpet, some vinyl and fine hardwood, good entry & lobby	*Luminous lobby ceiling, good core lighting, service fixtures	None

CLASSES A AND B: INTERIOR BUILD-OUT

(SQUARE FEET OF BUILD-OUT-FINISH)

TYPE	COST/ SQ. FT.	INTERIOR FINISH	LIGHTING AND PLUMBING	HEAT
Good	$ 192.50	Finest interior detail, hardwoods, ceramic, custom carpet, built-ins	Master antennas, fine fixtures, more than one bath per bedroom	Hot and chilled water (zoned)
Average	161.00	Good interior detail, carpet, ceramic tile, some vinyl and fine hardwood	Master antennas, fine fixtures, one full bath per bedroom	Hot and chilled water (zoned)

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

APARTMENTS – LUXURY CLASSES A and B (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated Cost, Section SEG 1.

	LOW	AVG.	GOOD	EXCL.
Allowance (if not itemized)	$1,820	$4,150	$7,550	$12,800

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs. For detailed costs see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Excellent	$12.80
Good	11.20

ELEVATOR STOPS: For basement stops, add $9,550 to $14,400 per stop.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 5.14	$ 6.63	$ 8.55	$ 11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
50,000	3.36	4.20	5.24	6.50
100,000	3.00	3.73	4.59	5.71
200,000	2.69	3.30	4.06	5.01

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete . .	$34.00	$43.50	$55.00	$71.00
Steel	31.75	42.50	56.50	75.50
Wood	29.75	39.50	52.50	68.50
Add for ornate finishes, balustrades .	29.50	36.00	44.25	54.00
Add for roofs or awnings .	15.35	20.40	27.00	36.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork). . .	$21.90	Central refrigeration (zoned)	$16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector. .	20.75	Heat pump system	25.50	Pkg. refrig. . .	$ 2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers.	$ 331 to $535 per MCFM capacity
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$3.18

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	12	1.055
9	.973	13	1.084
10	1.000 (base)	14	1.114
11	1.027		

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 200	250	300	350	400	450	500	550	600	650	700	750	800	850	Average Floor Area Sq. Ft./Story
2,000	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	.959	.989	1.021	1.052	1.083	1.113	1.143	1.175	1.206	1.237	1.268	1.299	1.329	-----	**4,000**
6,000	.917	.938	.959	.980	1.000	1.021	1.042	1.063	1.083	1.103	1.123	1.144	1.165	-----	**6,000**
8,000	-----	.913	.929	.944	.959	.974	.989	1.005	1.021	1.037	1.052	1.068	1.083	1.098	**8,000**
10,000	-----	-----	.910	.922	.935	.947	.959	.972	.984	.997	1.009	1.022	1.034	1.047	**10,000**
12,000	-----	-----	-----	.907	.917	.928	.938	.949	.959	.970	.980	.990	1.000	1.010	**12,000**
14,000	-----	-----	-----	-----	.906	.915	.924	.933	.942	.951	.959	.968	.977	.986	**14,000**
16,000	-----	-----	-----	-----	.898	.906	.913	.921	.929	.937	.944	.952	.959	.967	**16,000**
18,000	-----	-----	-----	-----	.890	.897	.904	.911	.917	.925	.932	.939	.945	.952	**18,000**
20,000	-----	-----	-----	-----	.885	.892	.898	.904	.910	.916	.922	.929	.935	.941	**20,000**
22,000	-----	-----	-----	-----	-----	-----	.892	.898	.903	.909	.915	.920	.926	.932	**22,000**
25,000	-----	-----	-----	-----	-----	-----	.883	.888	.892	.897	.903	.907	.912	.916	**25,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

APARTMENTS – LUXURY (ALTERNATE METHOD) CLASSES C and D

OCCUPANCY DESCRIPTION:

Shell, Luxury Apartment
This occupancy, together with occupancy Interior Space, Luxury Apartment, allows you to individually price the shell and the tenant improvement costs for an apartment (in separate sections of the report). This provides an alternative to occupancy Luxury Apartment (High Rise), which includes both the shell and tenant improvement costs.

High-rise luxury apartment shells are structures with three or more floors of multiple dwelling units, typically owner or time-share occupied. Each dwelling unit consists of its own separate living area and kitchen facility. Normally, shell structures over three stories have elevators, but this depends on the height of the building and the need for transportation to the upper levels. These shell structures have a lobby area, hall access to dwelling units and some type of stairway for fire exit. These shell structures include common area finishes only, which are about 10%. Although apartments built as co-ops, condominiums, or time-shares sometimes are required by building and zoning codes to have certain items not required for typical rental units, basically, "condominium" is a type of ownership and not a type of construction and the luxury apartment costs are valid.

Interior Space, Luxury Apartment
This occupancy, together with occupancy Shell, Luxury Apartment, allows you to individually price the shell and the tenant improvement costs for an apartment (in separate sections of the report). This provides an alternative to occupancy Luxury Apartment (High Rise), which includes both the shell and tenant improvement costs. These interiors have plaster, paneling, good detailing in molding and trim, high cost floor finishes, and full kitchen and dining rooms. Some of the special refinements found include master antennas, and more than one bath per bedroom at the better qualities.

SQUARE FOOT COST TABLE INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Allowance for lobby area and interior hall access to dwelling units. Elevators are included where designated with an (*) asterisk.

NOT INCLUDED IN COSTS: Appliances, fireplaces, canopies, balconies, swimming pools, yard improvements and any developers' or soft costs related to a type of ownership such as condominium.

CLASSES C AND D: SHELL LUXURY APARTMENT BUILDINGS

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR CORE FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$184.50	Best stones, metal, solar glass	Plaster, best veneers, best marble and hardwoods, ceramic, carpet, finest entry & lobby finishes	*Luminous lobby ceiling, excellent core lighting, finest service fixtures	None
	Good	147.50	Good masonry and glass, good ornamentation	Plaster, good veneers, vinyl, ceramic tile/ carpet, paneling, fine hardwood, good entry & lobby finishes	*Luminous lobby ceiling, excellent core lighting, good service fixtures	None
	Average	118.50	Stone, brick, metal and glass, individual design	Plaster, ceramic tile carpet, some vinyl and fine hardwood, good entry & lobby finishes	*Luminous lobby ceiling, good core lighting, service fixtures	None
D MASONRY VENEER	Excellent	176.00	Best brick or stone veneer, highly ornamental lobby	Plaster, best veneers, best marble and hardwoods, ceramic, carpet, finest entry & lobby finishes	*Luminous lobby ceiling, excellent core lighting, finest service fixtures	None
	Good	140.00	Good veneers and trim, good ornamentation and lobby	Plaster, good veneers, vinyl, ceramic tile/ carpet, paneling, fine hardwood, good entry & lobby finishes	*Luminous lobby ceiling, excellent core lighting, good service fixtures	None
	Average	112.00	Face brick or stone veneer, individual design, good lobby	Plaster, ceramic tile carpet, some vinyl and fine hardwood, good entry & lobby finishes	*Luminous lobby ceiling, good core lighting, service fixtures	None
D	Excellent	172.00	Best EIFS, stone trim	Plaster, best veneers, best marble and hardwoods, ceramic, carpet, finest entry & lobby finishes	*Luminous lobby ceiling, excellent core lighting, finest service fixtures	None
	Good	136.50	Good EIFS or sidings, good ornamentation	Plaster, good veneers, vinyl, ceramic tile/ carpet, paneling, fine hardwood, good entry & lobby finishes	*Luminous lobby ceiling, excellent core lighting, good service fixtures	None
	Average	109.00	Good stucco or siding, brick and stone trim	Plaster, ceramic tile carpet, some vinyl and fine hardwood, good entry & lobby finishes	*Luminous lobby ceiling, good core lighting, service fixtures	None

CLASSES C AND D: INTERIOR BUILD-OUT

(SQUARE FEET OF BUILD-OUT-FINISH)

TYPE	COST/ SQ. Ft.	INTERIOR FINISH	LIGHTING AND PLUMBING	HEAT
Excellent	$ 183.50	High-cost partitions and wall and floor finishes, formal dining area, kitchen, good master bedroom and bath, good cabinetry, closets, some extras	TV and phone jacks, good fixtures, one bath per bedroom	Hot and chilled water (zoned)
Good	140.50	Plaster or drywall, good partitions, paneling, carpet, tile or vinyl, good room sizes, some good cabinetry and shelving	Good fixtures, many outlets, over one bath per unit	Warm and cool air (zoned)
Average	118.00	Average drywall, vinyl composition, carpet, adequate shelving, counters, small dining area and kitchen, adequate bedrooms and bath	Average fixtures and circuits, one bath per unit	Warm and cool air (zoned)

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

APARTMENTS – LUXURY CLASSES C and D (ALTERNATE METHOD)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated Cost, Section SEG 1.

	LOW	AVG.	GOOD	EXCL.
Allowance (if not itemized)	$1,820	$4,150	$7,550	$12,800

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs. For detailed costs see Section UIP 8.

Class C	Sq. Ft. Costs	Classes D	Sq. Ft. Costs
Excellent	$8.56	Excellent	$7.57
Good	7.57	Good	6.71
Average	6.71	Average	5.91

ELEVATOR STOPS: For basement stops, add $9,550 to $14,400 per stop.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 5.14	$ 6.63	$ 8.55	$ 11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
50,000	3.36	4.20	5.24	6.50
100,000	3.00	3.73	4.59	5.71
200,000	2.69	3.30	4.06	5.01

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete . .	$34.00	$43.50	$55.00	$71.00
Steel	31.75	42.50	56.50	75.50
Wood	29.75	39.50	52.50	68.50
Add for ornate finishes, balustrades .	29.50	36.00	44.25	54.00
Add for roofs or awnings .	15.35	20.40	27.00	36.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork). . .	$21.90	Central refrigeration (zoned)	$16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector. .	20.75	Heat pump system	25.50	Pkg. refrig. . .	$2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers.	$331 to $535 per MCFM capacity
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$3.18

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	12	1.055
9	.973	13	1.084
10	1.000 (base)	14	1.114
11	1.027		

4

Average Floor Area Sq. Ft./Story	AVERAGE PERIMETER 200	250	300	350	400	450	500	550	600	650	700	750	800	850	Average Floor Area Sq. Ft./Story
2,000	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	.959	.989	1.021	1.052	1.083	1.113	1.143	1.175	1.206	1.237	1.268	1.299	1.329	-----	**4,000**
6,000	.917	.938	.959	.980	1.000	1.021	1.042	1.063	1.083	1.103	1.123	1.144	1.165	-----	**6,000**
8,000	-----	.913	.929	.944	.959	.974	.989	1.005	1.021	1.037	1.052	1.068	1.083	1.098	**8,000**
10,000	-----	-----	.910	.922	.935	.947	.959	.972	.984	.997	1.009	1.022	1.034	1.047	**10,000**
12,000	-----	-----	-----	.907	.917	.928	.938	.949	.959	.970	.980	.990	1.000	1.010	**12,000**
14,000	-----	-----	-----	-----	.906	.915	.924	.933	.942	.951	.959	.968	.977	.986	**14,000**
16,000	-----	-----	-----	-----	.898	.906	.913	.921	.929	.937	.944	.952	.959	.967	**16,000**
18,000	-----	-----	-----	-----	.890	.897	.904	.911	.917	.925	.932	.939	.945	.952	**18,000**
20,000	-----	-----	-----	-----	.885	.892	.898	.904	.910	.916	.922	.929	.935	.941	**20,000**
22,000	-----	-----	-----	-----	-----	-----	.892	.898	.903	.909	.915	.920	.926	.932	**22,000**
25,000	-----	-----	-----	-----	-----	-----	.883	.888	.892	.897	.903	.907	.912	.916	**25,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

ARCADE BUILDINGS



AVERAGE CLASS C



LOW COST CLASS D

OCCUPANCY DESCRIPTION: These buildings are designed mainly for coin-operated game entertainment, while better qualities will include limited food service and lounges typically found at fun centers, miniature golf complexes, etc.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office and gathering and/or lounge areas.

NOT INCLUDED IN COSTS: Elevators, sprinklers, snack bar equipment, seating or lockers.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 226.50	Steel columns/girders, face brick, best ornamental block, storefront	Sports flooring, theme rooms, shops, restaurant, gaming facilities	Best lighting and outlets, good plumbing, kitchen, bar	Warm and cool air (zoned)
	Good	169.00	Steel frame, good brick, block or tilt-up, tapered girders, good trim	Acoustic treatment, some theme finishes and extra facilities and rooms	Good game lighting, sound, restrooms, limited food service	Heat pump system
	Average	125.00	Steel or wood frame or bearing walls, brick, block or tilt-up	Painted walls, VCT, carpet, large eating or game rooms	Adequate lighting, outlets and plumbing, snack bar	Package A.C.
	Low-cost	88.00	Block, tilt-up, light roof construction	Low-cost finishes, few partitions	Minimum lighting and plumbing	Forced air
D	Good	160.00	Heavy wood frame, wood, stucco or brick veneer, good ornamentation	Acoustic treatment, some theme finishes and extra facilities and rooms	Good game lighting, sound, restrooms, limited food service	Heat pump system
	Average	119.00	Stucco on wood frame, wood trusses, small front	Drywall, acoustic tile, VCT, carpet, large eating area and game rooms	Adequate lighting, outlets and plumbing, snack bar	Package A.C.
	Low-cost	83.50	Stucco or siding on studs	Low-cost finishes, few partitions	Minimum lighting and plumbing	Forced air
D POLE	Average	110.50	Pole frame, good metal siding, insulated, small front	Drywall, acoustic tile, VCT, carpet, large eating area and game rooms	Adequate lighting, outlets and plumbing, snack bar	Package A.C.
	Low-cost	77.00	Pole frame, metal siding	Low-cost game area, minimum finish, asphalt tile, open counter	Minimum lighting and plumbing, adequate outlets	Forced air
S	Average	116.50	Good metal panels and roof, little ornamentation, small front	Drywall, acoustic tile, VCT, carpet, large eating area and game rooms	Adequate lighting, outlets and plumbing, small snack bar	Package A.C.
	Low-cost	80.50	Steel or aluminum panels	Drywall, acoustic and asphalt tile	Minimum lighting and plumbing	Forced air
CDS	Storage basement	53.00	Unfinished interior	Unfinished storage and utility	Minimum lighting, drains	None
	Open mezzanine	51.50	Not included	Finished floors, few partitions	Average lighting, no plumbing	In building cost

MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

ARCADE BUILDINGS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.776	18	1.054
10	.833	20	1.106
12	.889	22	1.158
14	.945	24	1.210
16	1.000 (base)	28	1.313

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	175	200	250	300	400	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.117	1.147	1.205	1.264	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	.999	1.011	1.034	1.056	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	-----	-----	-----	1.011	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	**10,000**
12,000	-----	-----	-----	-----	.995	1.015	1.034	1.052	1.071	1.089	-----	-----	-----	-----	**12,000**
14,000	-----	-----	-----	-----	.982	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	**14,000**
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	**25,000**
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	**40,000**
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	**50,000**
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	**75,000**
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	**100,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

ARMORIES



GOOD CLASS C



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These buildings are designed for military training. Quality is determined primarily by the amount of interior finish, although the exterior appearance and the structural support influence the cost and quality selection. Armories generally have a large arena drill floor, office area, classrooms, locker areas, secure storage and kitchen support facilities.

Armories are commonly built up to three stories using masonry, wood or steel-frame construction. In addition to adequate plumbing, the better qualities have shower facilities. Lighting usually consists of fluorescent fixtures with some recessed lighting in the office areas.

Interior finishes are either drywall or plaster, with some paneling and special moldings used in the higher quality structures.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Training and classroom equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 237.00	Face brick, good ornamentation good frame, bar or web joists	Good interior finish, offices and classrooms, indoor range and vaults	Good lighting and outlets, tiled showers and restrooms	Package A.C.
	Good	176.50	Brick or block, some trim, wall bearing or frame	Finished interior, office and classrooms, secured storage	Good lighting and plumbing, showers	Forced air
	Average	132.50	Brick, block, very plain, some trim	Some finish, office and classroom	Adequate lighting and plumbing	Space heaters
D	Excellent	221.50	Brick veneer, good ornamentation, good frame, bar or web joists	Good interior finish, offices and classrooms, indoor range and vaults	Good lighting and outlets, tiled showers and restrooms	Package A.C.
	Good	164.50	Stucco or brick veneer, some trim, wall bearing or frame	Finished interior, office and classrooms, secured storage	Good lighting and plumbing, showers	Forced air
	Average	124.00	Wood frame and stucco or siding	Some finish, office and classroom	Adequate lighting and plumbing	Space heaters
S	Average	126.50	Steel frame, insulated panels, some fenestration	Some interior finish, office and classroom	Adequate lighting and plumbing	Space heaters
CDS	Average Basement	64.50	Reinforced concrete, unfinished interior	Unfinished secure storage area	Adequate lighting and plumbing	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

ARMORIES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small freight elevator with simple call system and push-button control, four passenger cab and two or three stops, $66,500 to $109,000.

For detailed costs see Section UIP 8.

For loading docks, see Page CAL 398.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.63	$ 6.17	$ 8.24	$ 10.95
10,000	4.16	5.51	7.28	9.63
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
50,000	2.96	3.79	4.89	6.27
80,000	2.75	3.49	4.47	5.72
100,000	2.67	3.39	4.32	5.51
200,000	2.40	3.04	3.84	4.85
400,000	2.17	2.73	3.39	4.23

DOCK HEIGHT FLOORS: Add $2.39 to $9.03 per square foot to base cost of first floor.

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.885	20	1.133
10	.921	22	1.181
12	.960	24	1.231
14	1.000 (base)	26	1.281
16	1.041	28	1.331
18	1.086	30	1.382

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	300	400	500	600	800	1000	1200	1400	1600	1800	2000	2200	2400	3000	Sq. Ft./Story
5,000	1.083	1.168	1.252	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	.996	1.040	1.083	1.168	-----	-----	-----	-----	-----	-----	-----	-----	-----	**10,000**
14,000	-----	.945	.977	1.008	1.071	1.132	-----	-----	-----	-----	-----	-----	-----	-----	**14,000**
20,000	-----	-----	.926	.949	.996	1.040	1.083	-----	-----	-----	-----	-----	-----	-----	**20,000**
25,000	-----	-----	.907	.924	.959	.996	1.032	1.066	-----	-----	-----	-----	-----	-----	**25,000**
30,000	-----	-----	-----	.907	.935	.965	.995	1.025	-----	-----	-----	-----	-----	-----	**30,000**
40,000	-----	-----	-----	-----	.907	.926	.949	.972	.995	1.019	-----	-----	-----	-----	**40,000**
50,000	-----	-----	-----	-----	.891	.907	.924	.942	.959	.977	.996	1.015	-----	-----	**50,000**
80,000	-----	-----	-----	-----	-----	.875	.887	.898	.907	.916	.926	.937	.949	.984	**80,000**
100,000	-----	-----	-----	-----	-----	.863	.872	.882	.891	.899	.907	.916	.924	.950	**100,000**
200,000	-----	-----	-----	-----	-----	-----	.846	.850	.855	.859	.863	.868	.873	.887	**200,000**
400,000	-----	-----	-----	-----	-----	-----	-----	-----	.835	.838	.841	.843	.846	.853	**400,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

AUDITORIUMS



EXCELLENT CLASS A

OCCUPANCY DESCRIPTION: These buildings are designed for mass seating for visual and voice presentations. They include a stage or arena, basic floor, lobby or foyer at the main entrance and necessary lighting. The better qualities include special lighting, sound systems and high-cost plumbing fixtures and restrooms.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Stage area, special lighting and sound system.

NOT INCLUDED IN COSTS: Elevators, sprinklers, movable floors and lights, seating, special equipment or kitchen equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$ 553.00	Special architecture and trim, best materials, highly ornamented	Best ornamental plaster and detail, carpeting, marble, vinyl	Special lighting and sound system, good plumbing	Hot and chilled water (zoned)
	Good	391.00	Good masonry, metal or concrete panels, good architecture	Plaster, good ornamental detail, carpeting, vinyl, terrazzo lobby	Good lighting and sound system, good plumbing	Warm and cool air (zoned)
	Average	288.00	Face brick, concrete panels with trim, plain architecture	Drywall, vinyl finishes, some ornamentation, carpeting	Adequate lighting and plumbing, sound system	Warm and cool air (zoned)
B	Excellent	491.00	Special architecture and rim, best materials, highly ornamented	Best ornamental plaster and detail, carpeting, marble, vinyl	Special lighting and sound system, good plumbing	Hot and chilled water (zoned)
	Good	349.00	Good masonry, metal or concrete panels, good architecture	Plaster, good ornamental detail, carpeting, vinyl, terrazzo lobby	Good lighting and sound system, good plumbing	Warm and cool air (zoned)
	Average	260.50	Face brick, concrete panels with trim, plain architecture	Drywall, vinyl finishes, some ornamentation, carpeting	Adequate lighting and plumbing, sound system	Warm and cool air (zoned)
A-B	Finished basement	158.50	Concrete masonry, partly finished interior	Masonry partitions, utility, repair, storage and dressing rooms	Adequate lighting and plumbing, some extras	Hot water
	Semifin. basement	141.50	Low-cost finishes	Finished lounge/restrooms, some utility and storage	Minimum lighting, adequate plumbing	Hot water
C	Excellent	361.50	Special architecture and trim, steel frame, best masonry	Best ornamental plaster and detail, carpeting, marble, vinyl	Special lighting and sound system, good plumbing	Warm and cool air (zoned)
	Good	266.00	Face brick, concrete and glass panels, good architecture	Plaster, good ornamental detail, carpeting, vinyl, terrazzo lobby	Good lighting and sound system, good plumbing	Warm and cool air (zoned)
	Average	185.00	Brick, block, concrete panels, little trim, good high school type	Drywall, some ornamentation, vinyl composition, terrazzo lobby	Adequate lighting and plumbing, sound system	Package A.C.
	Low-cost	128.50	Low-cost brick, block, tilt-up	Painted, acoustic and asphalt tile	Minimum lighting and plumbing	Forced air
D	Good	254.00	Brick veneer, best stucco, good trim, ornamental front	Plaster, good ornamental detail, carpeting, vinyl, terrazzo lobby	Good lighting and sound system, good plumbing	Warm and cool air (zoned)
	Average	176.00	Good stucco, some trim, good high school type	Drywall, some ornamentation, vinyl composition, terrazzo lobby	Adequate lighting and plumbing, sound system	Package A.C.
	Low-cost	121.00	Low-cost stucco or siding, very plain, low-cost school type	Drywall, plywood, acoustic tile, wood or asphalt tile floors	Minimum lighting and plumbing	Forced air
D POLE	Low-cost	113.50	Metal panels on wood pole frame	Few partitions, acoustic tile, wood or asphalt tile floors	Minimum lighting and plumbing	Forced air
S	Average	173.00	Metal sandwich panels	Drywall partitions, some ornament, acoustic tile, terrazzo lobby	Adequate lighting and plumbing, sound system	Package A.C.
	Low-cost	118.00	Steel or aluminum panels	Few partitions, acoustic tile	Minimum lighting and plumbing	Forced air
CDS†	Finished basement	110.00	Painted interior	Utility, workshops, storage and dressing rooms	Adequate lighting and plumbing	Forced air
	Semifin. basement	94.50	Low-cost finishes	Minimum lounge area, restrooms, some utility and storage	Minimum lighting, adequate plumbing	Forced air

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $ 8.52 per square foot.
For balconies, see Page CAL 382.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

AUDITORIUMS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 65,000 to $106,000.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 33.00	$ 42.00	$ 54.50	$ 70.00
Steel	31.00	41.75	56.00	76.00
Wood	26.00	35.00	46.75	62.50
Add for ornate finishes, balustrades	27.50	34.25	42.00	52.50
Add for roofs or awnings	15.20	20.10	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93
150,000	3.04	3.69	4.49	5.47
200,000	2.93	3.55	4.30	5.21

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.776	24	1.210
12	.889	26	1.262
14	.945	28	1.313
16	1.000 (base)	30	1.364
18	1.054	34	1.463
20	1.106	38	1.561
22	1.158	42	1.658

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	175	200	250	300	400	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.117	1.147	1.205	1.264	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
5,000	.999	1.011	1.034	1.056	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	-----	-----	-----	1.011	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	10,000
14,000	-----	-----	-----	-----	.982	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	14,000
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	25,000
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	40,000
45,000	-----	-----	-----	-----	-----	-----	.934	.939	.946	.954	.962	.976	.989	1.001	45,000
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	50,000
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	75,000
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	100,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

AUTO DEALERSHIPS – COMPLETE



GOOD CLASS C



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These structures include showroom/office and parts/service facilities. Because of the wide range in mix of facilities (15% to 55% showroom) and qualities, it is best to price each area individually, using the appropriate showroom and service repair garage cost. The large open areas used for display typically have storefronts. There are also some office and storage areas next to the sales cubicles. The service area is designed primarily for vehicular repair and maintenance. Better qualities will have more showroom space.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.
NOT INCLUDED IN COSTS: Service equipment, hoists, office furnishings and equipment or special signage.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 202.00	Brick, concrete or metal and glass, good showroom front	Plaster, acoustic tile, terrazzo display floor, adequate offices, garage area	Good display, adequate office and service lighting, restrooms	Warm and cool air (zoned)
C	Excellent	257.00	Masonry, metal or concrete, highly ornamental, over 30% sales	Plaster, good acoustic panel, best display floors, sealed work floors	Special lighting, good fixtures and plumbing throughout	Warm and cool air (zoned)
	Good	179.50	Brick, concrete, good showroom front, good sales and service	Drywall, acoustic tile, terrazzo display floor, good office area, garage finish	Good display, office and service lighting, restrooms	Package A.C.
	Average	131.50	Brick, block, concrete, storefront, average sales and service	Drywall, acoustic tile, vinyl composition, office, sales cubicles	Store and office lighting, parts and garage lighting in balance	Package A.C.
	Low cost	88.00	Block, tilt-up, simple front, 15% – 25% sales-office area	Minimum store finish in sales, garage finish in balance	Adequate lighting/plumbing, minimum services	Forced air
D	Excellent	246.50	Masonry veneer, EIFS, highly ornamental, over 30% sales	Plaster, good acoustic panel, best display floors, sealed work floors	Special lighting, good fixtures and plumbing throughout	Warm and cool air (zoned)
	Good	170.50	Masonry veneer, good front and trim, good sales and service	Drywall, acoustic tile, terrazzo display floor, good office area, garage finish	Good display, office and service lighting, restrooms	Package A.C.
	Average	123.50	Siding, veneer trim, showroom front, average sales and service	Drywall, acoustic tile, vinyl composition, office, sales cubicles	Store and office lighting, parts and garage lighting in balance	Package A.C.
	Low cost	81.50	Stucco or siding, simple front, 15% – 25% sales-office area	Minimum store finish in sales, garage finish in balance	Adequate lighting/plumbing, minimum services	Forced air
D POLE	Average	117.00	Pole frame, metal siding, storefront, average sales and service	Drywall, acoustic tile, vinyl composition, office, sales cubicles	Store and office lighting, parts and garage lighting in balance	Package A.C.
	Low cost	76.50	Metal on pole frame, simple storefront, 15% – 25% showroom	Minimum store finish in sales, garage finish in balance	Adequate lighting/plumbing, minimum services	Forced air
S	Good	172.50	Sandwich panels, good front, good sales and service	Drywall, acoustic tile, terrazzo display floor, good office area, garage finish	Good display, office and service lighting, restrooms	Package A.C.
	Average	124.00	Sandwich panels, showroom front, average sales and service	Drywall, acoustic tile, vinyl composition, office, sales cubicles	Store and office lighting, parts and garage lighting in balance	Package A.C.
	Low cost	81.50	Single wall, simple storefront, 15% – 25% sales-office area	Minimum store finish in sales, garage finish in balance	Adequate lighting/plumbing, minimum services	Forced air

For load-bearing parking roofs, add $8.81 per square foot. Access ramps cost $31.00 to $55.50 per square foot.
For office mezzanines, see Page CAL 22; storage mezzanines, see Page CAL 24.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

AUTO DEALERSHIPS – COMPLETE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Small two- or three-passenger elevators with simple call systems and push button control, and two or three stops, costs $66,500 to $109,000.

HOISTS: Automobile hoists cost $12,400 to $19,300 each.
Truck hoists, $16,900 to $32,100. See Section UIP 14 for greater detail.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.91	$ 6.57	$ 8.82	$ 11.74
2,500	4.63	6.17	8.24	10.95
5,000	4.16	5.51	7.28	9.63
10,000	3.78	4.95	6.48	8.49
15,000	3.54	4.62	6.03	7.88
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
50,000	2.96	3.79	4.89	6.27

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.921	20	1.133
12	.960	22	1.181
14	1.000 (base)	24	1.231
16	1.041	26	1.281
18	1.086	28	1.331

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	150	200	250	300	350	400	450	500	600	800	1000	1200	1500	Sq. Ft./Story
1,000	1.252	1.468	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	-----	1.147	1.252	1.360	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	-----	.996	1.040	1.083	1.125	1.168	1.210	1.252	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.984	1.013	1.040	1.068	1.094	1.147	1.252	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.972	.996	1.019	1.040	1.083	1.168	-----	-----	-----	**10,000**
14,000	-----	-----	-----	-----	-----	-----	.945	.961	.977	1.008	1.071	1.132	-----	-----	**14,000**
18,000	-----	-----	-----	-----	-----	-----	-----	.929	.942	.967	1.016	1.065	-----	-----	**18,000**
20,000	-----	-----	-----	-----	-----	-----	-----	-----	.926	.949	.996	1.040	1.083	-----	**20,000**
25,000	-----	-----	-----	-----	-----	-----	-----	-----	.907	.924	.959	.996	1.032	-----	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.907	.935	.965	.995	1.040	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.907	.926	.949	.984	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.891	.907	.924	.950	**50,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

AUTOMOBILE SHOWROOMS



GOOD CLASS C



GOOD CLASS S

OCCUPANCY DESCRIPTION: Primarily sales and showrooms for dealerships, whether automobile, boat or farm implement. The large open areas used for display typically have storefronts. There is also some office and storage area next to the sales cubicles. Most are finished with drywall and plaster. Floors are finished with a combination of resilient floor covering and some terrazzo. Ceilings in the offices may be tile panels on a suspended system. Lighting is usually very similar to store and office lighting and the better qualities have special display spotlights. Plumbing and restrooms are adequate to service the sales, clerical and managerial personnel using the building. The higher-quality showrooms may also have kitchen and/or lounge support facilities.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, special signage, furnishings or kitchen equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 228.50	Masonry, concrete or metal and glass, good ornamentation	Plaster, acoustic tile, terrazzo display floor, adequate office area	Good lighting and restrooms, some special fixtures	Warm and cool air (zoned)
C	Excellent	283.00	Face brick or stone, good metal or concrete and glass panels	Plaster, good acoustic tile, good terrazzo, stone, rubber tile, carpet	Special lighting, good fixtures and plumbing throughout	Warm and cool air (zoned)
	Good	200.00	Brick, concrete, good storefront, good ornamentation	Plaster, acoustic tile, terrazzo display floor, good office area	Good display and office lighting, restrooms	Package A.C.
	Average	147.50	Brick, block, concrete, good storefront, some ornamentation	Plaster or drywall, acoustic tile, vinyl composition, office, sales cubicles	Store and office lighting, small restrooms	Package A.C.
	Low cost	100.00	Brick, block, tilt-up, simple storefront, low-cost entrance	Painted walls, few drywall partitions, asphalt tile	Adequate lighting, minimum plumbing	Forced air
D	Excellent	273.50	Face brick or stone veneer, good EIFS, metal and glass panels	Plaster, good acoustic tile, good terrazzo, stone, rubber tile, carpet	Special lighting, good fixtures and plumbing throughout	Warm and cool air (zoned)
	Good	191.00	Masonry veneer, best stucco or siding, good front and trim	Plaster, acoustic tile, terrazzo display floor, good office area	Good display and office lighting, restrooms	Package A.C.
	Average	138.50	Siding, veneer trim, storefront, some ornamentation	Plaster or drywall, acoustic tile, vinyl composition, office, sales cubicles	Store-type lighting, small restrooms	Package A.C.
	Low cost	93.50	Stucco or siding, simple front, low-cost entrance	Drywall, few partitions or extras	Adequate lighting, minimum plumbing	Forced air
D POLE	Average	131.00	Pole frame, metal siding, storefront, some ornamentation	Fully lined and insulated, tile, vinyl composition, small office area	Store-type lighting, small restrooms	Package A.C.
	Low cost	86.00	Metal on pole frame, simple storefront, low-cost entrance	Some finish, few partitions, asphalt tile, few extras	Adequate lighting, minimum plumbing	Forced air
S	Good	193.00	Sandwich panels, good storefront, good ornamentation	Plaster, acoustic tile, terrazzo display floor, good office area	Good display and office lighting, restrooms	Package A.C.
	Average	138.50	Sandwich panels, storefront, some ornamentation	Plaster or drywall, acoustic tile, vinyl composition, small office area	Store-type lighting, small restrooms	Package A.C.
	Low cost	92.00	Single wall, simple storefront, low-cost entrance	Drywall, few partitions or extras	Adequate lighting, minimum plumbing	Forced air
CDS	Office mezzanine	68.50	In building cost	Enclosed, average office finish, acoustic tile soffit	Average office lighting and plumbing	Included in building cost

For load-bearing parking roofs, add $8.81 per square foot. Access ramps cost $31.00 to $55.50 per square foot.

NOTE: Vehicular showrooms are sales rooms. Where a sales room and service garage or warehouse constitute one building, the cost for each portion should be modified by its area/perimeter multiplier, considering half of the common wall to belong to each of the portions.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

AUTOMOBILE SHOWROOMS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Small two- or three-passenger elevators with simple call systems and push button control, and two or three stops, costs $66,500 to $109,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.91	$ 6.57	$ 8.82	$ 11.74
2,500	4.63	6.17	8.24	10.95
5,000	4.16	5.51	7.28	9.63
10,000	3.78	4.95	6.48	8.49
15,000	3.54	4.62	6.03	7.88
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
50,000	2.96	3.79	4.89	6.27

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.921	20	1.133
12	.960	22	1.181
14	1.000 (base)	24	1.231
16	1.041	26	1.281
18	1.086	28	1.331

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	150	200	250	300	350	400	450	500	600	800	1000	1200	1500	Sq. Ft./Story
1,000	1.252	1.468	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	-----	1.147	1.252	1.360	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
5,000	-----	-----	.996	1.040	1.083	1.125	1.168	1.210	1.252	-----	-----	-----	-----	-----	5,000
8,000	-----	-----	-----	-----	.984	1.013	1.040	1.068	1.094	1.147	1.252	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.972	.996	1.019	1.040	1.083	1.168	-----	-----	-----	10,000
14,000	-----	-----	-----	-----	-----	-----	.945	.961	.977	1.008	1.071	1.132	-----	-----	14,000
18,000	-----	-----	-----	-----	-----	-----	-----	.929	.942	.967	1.016	1.065	-----	-----	18,000
20,000	-----	-----	-----	-----	-----	-----	-----	-----	.926	.949	.996	1.040	1.083	-----	20,000
25,000	-----	-----	-----	-----	-----	-----	-----	-----	.907	.924	.959	.996	1.032	-----	25,000
30,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.907	.935	.965	.995	1.040	30,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.907	.926	.949	.984	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.891	.907	.924	.950	50,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

AUTOMOTIVE CENTERS



AVERAGE/GOOD CLASS C



LOW COST CLASS S

OCCUPANCY DESCRIPTION: These buildings are designed for both sales and service, with display rooms, office, storage and repair space commensurate with the quality. The better qualities are a combination retail store (with storefronts and finish) and garage. Average quality contains sales area of between 20% and 30% of the total floor area. The lighting in the sales area is similar to store lighting in both quantity and types of fixtures, with industrial fluorescent fixtures in the service areas. Plumbing is adequate to service the personnel.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, hoists or service equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 132.00	Brick, block, good front, 30% or more sales area	Good store finish in sales, good garage finish in balance	Good store illumination, good restrooms	Space heaters
	Average	107.00	Block, typical storefront, 20% – 30% sales area	Store finish in sales, garage finish in balance	Average store illumination and restrooms	Space heaters
	Low cost	86.50	Block, simple storefront, 15% – 25% finished sales area	Minimum store finish in sales, garage finish in balance	Minimum lighting, outlets and plumbing fixtures	Space heaters
D	Good	123.50	Siding, veneer, good storefront, 30% or more sales area	Good store finish in sales, good garage finish in balance	Good store illumination, good restrooms	Space heaters
	Average	99.50	Siding, storefront, 20% – 30% finished sales area	Store finish in sales, garage finish in balance	Average store illumination and restrooms	Space heaters
D POLE	Low cost	74.50	15% – 25% finished sales area, storefront, steel on wood pole frame	Minimum store finish in sales, garage finish in balance	Minimum lighting, outlets and plumbing fixtures	Space heaters
S	Average	99.00	20% – 30% sales area, storefront, some trim, sandwich panels	Store finish in sales, garage finish in balance	Average store illumination and restrooms	Space heaters
	Low cost	79.50	Single wall, simple storefront, 15% – 25% finished sales area	Minimum store finish in sales, garage finish in balance	Minimum lighting, outlets and plumbing fixtures	Space heaters
CDS	Storage basement	44.75	Reinforced concrete, unfinished interior	Unfinished storage area	Minimum lighting and drains	None
	Storage mezzanine	30.50	In building cost	Light storage on plywood, minimum supports, no soffit	Minimum lighting	Included in building cost

MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

AUTOMOTIVE CENTERS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

HOISTS: Automobile and light truck hoists cost $12,400 to $19,300 each. See Section UIP 14 for greater detail.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.91	$ 6.57	$ 8.82	$ 11.74
2,500	4.63	6.17	8.24	10.95
5,000	4.16	5.51	7.28	9.63
10,000	3.78	4.95	6.48	8.49
15,000	3.54	4.62	6.03	7.88
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
50,000	2.96	3.79	4.89	6.27

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.921	16	1.041
12	.960	18	1.086
14	1.000 (base)	20	1.133

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	150	200	250	300	350	400	450	500	600	800	1000	1200	1500	Sq. Ft./Story
1,000	1.252	1.468	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	-----	1.147	1.252	1.360	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
5,000	-----	-----	.996	1.040	1.083	1.125	1.168	1.210	1.252	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.984	1.013	1.040	1.068	1.094	1.147	1.252	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.972	.996	1.019	1.040	1.083	1.168	-----	-----	-----	**10,000**
14,000	-----	-----	-----	-----	-----	-----	.945	.961	.977	1.008	1.071	1.132	-----	-----	**14,000**
18,000	-----	-----	-----	-----	-----	-----	-----	.929	.942	.967	1.016	1.065	-----	-----	**18,000**
20,000	-----	-----	-----	-----	-----	-----	-----	-----	.926	.949	.996	1.040	1.083	-----	**20,000**
25,000	-----	-----	-----	-----	-----	-----	-----	-----	.907	.924	.959	.996	1.032	-----	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.907	.935	.965	.995	1.040	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.907	.926	.949	.984	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.891	.907	.924	.950	**50,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.