DAIRIES (MILKING PARLORS)



GOOD CLASS S

OCCUPANCY DESCRIPTION: These buildings are designed for the milking of cows and first-stage milk processing. Most, except for the lower quality units, offer short-term storage. The structures are built to comply with state health and sanitation codes. Usually of masonry or wood frame construction, they have contoured concrete floors with epoxy or tile finishes. The better qualities have high-level lighting, cow washes, restrooms, showers, pipe stanchions and milk piping. These units are generally not heated. Permanently installed piping and electrical circuits are included.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Piping and electrical circuits for milking equipment.

NOT INCLUDED IN COSTS: Sprinklers, milking equipment or milk storage and processing equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 104.50	Brick or stucco on block, insulated heavy roof structure	Ceramic and epoxy finishes, contoured concrete floor, plaster ceiling	High-level lighting, hot water, cow wash, restrooms and showers	None
	Good	78.50	Brick, concrete block, insulated roof	Plaster walls in cooler/storage room, contoured concrete floor with drains	Good lighting and plumbing, pipe stanchions, milk piping	None
	Average	59.00	Brick, concrete block or clay tile, light wood trusses	Plaster wainscot in cooler and washroom, good concrete floor	Adequate lighting and plumbing, pipe stanchions	None
	Low cost	45.00	Clay tile, concrete block, half walls, wood shutters and rafters	Painted walls, concrete milking floor, milking parlor only, no storage	Minimum electrical and plumbing service, wood stanchions	None
D	Excellent	97.00	Best sidings or veneer, good roof structure, fully insulated	Ceramic and epoxy finishes, contoured concrete floors, plaster ceiling	High-level lighting, hot water, cow wash, restrooms and showers	None
	Good	70.00	Good stucco or siding, some trim, wood or steel frame	Plaster walls, cooler and storage, contoured concrete floor	Good lighting and plumbing, pipe stanchions, milk piping	None
	Average	50.50	Stucco or siding, wood frame and rafters, windows or shutters	Plaster wainscot, cooler and washroom, good concrete floor	Adequate lighting and plumbing, pipe stanchions	None
	Low cost	36.50	Wood siding or plywood on light wood frame, shutters	Some wainscot, concrete floor, milking barn only, no storage	Minimum electrical and plumbing services, wood stanchions	None
D POLE	Excellent	89.00	Best metal siding on pole frame, fully insulated, sheathed	Ceramic and epoxy finishes, contoured concrete floors, plaster ceiling	High-level lighting, hot water, cow wash, restrooms and showers	None
	Good	64.50	Pole frame, good metal siding and sheathing, insulated	Plaster or gypsum board, cooler and storage, contoured concrete floor	Good lighting and plumbing, pipe stanchions, milk piping	None
	Average	47.00	Pole frame, metal siding, windows or good shutters	Gypsum board or plaster, wainscot in cooler and washroom	Adequate lighting and plumbing, pipe stanchions	None
	Low cost	34.00	Pole frame, metal siding, some wainscot, shutters	Little interior finish, concrete milking floor, milking barn only	Minimum electrical and plumbing services, wood stanchions	None
S	Excellent	96.50	Good steel siding and sheathing, fully insulated	Ceramic and epoxy finishes, contoured floors, plaster ceiling	High-level lighting, hot water, cow wash, restrooms and showers	None
	Good	71.00	Good steel siding, full sheathing, insulated	Plaster or gypsum board, cooler and storage, contoured concrete floor	Good lighting and plumbing, pipe stanchions, milk piping	None
	Average	52.00	Steel siding, windows or good shutters	Gypsum board or plaster, wainscot in cooler and washroom	Adequate lighting and plumbing, pipe stanchions	None
	Low cost	38.00	Steel siding, light frame, some wainscot, shutters	Little interior finish, concrete milking floor, milking barn only	Minimum electrical and plumbing wood stanchions	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

DAIRIES (MILKING PARLORS)

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

MILKING EQUIPMENT: Stalls, fully automatic system

	COST RANGE		
Double 6, Double 8	$ 8,600	–	$ 12,600
Double 10	11,600	–	17,700
Double 12	15,500	–	19,700
Double 16, Double 20	17,700	–	24,100
Stall, manual system	5,200	–	7,150

for feed system, add $1,120 - $1,430, plus $1,120 for auger, per stall;
for computerized automation, add $2,525 - $5,050 plus $64 - $87 for each I.D. tag

Bulk tanks, refrigerated, per gallon	$ 11.15	–	$ 21.50
Bulk tanks, unrefrigerated, per gallon	8.74	–	19.95
Compressor, each	6,250	–	20,500
Floor-mounted plate cooler, each	5,600	–	16,400
Chillers, each	5,200	–	8,200
Water heater, gas, each	3,725	–	4,250
Automatic wash systems, each	3,775	–	5,050

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.94	$ 6.42	$ 8.34	$ 10.85
2,500	4.27	5.50	7.04	9.03
5,000	3.87	4.92	6.28	7.99
7,500	3.62	4.58	5.79	7.32
10,000	3.45	4.35	5.50	6.92
15,000	3.21	4.05	5.14	6.51
20,000	3.12	3.90	4.88	6.08

Holding pen/wash area, block wall, slab floor, pipe dividers, cost per square foot: $11.15 - $15.50
add for roof: $9.16 - $9.94
add for power crowd gate: $10.00 - $19.95
add for cow wash: $4.12 - $6.37

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 6.36	Package A.C. (short ductwork)	$ 14.05	Central refrigeration (zoned)	$ 12.00
Electric wall heaters	2.71			package (short ductwork)	9.20
Forced air furnace	7.13			Evaporative coolers	5.48
Hot water, baseboard/convector	12.70				
Space heaters, with fan	3.49				
radiant	4.09				
Steam (including boiler)	11.30				
without boiler	4.78			**VENTILATION ONLY**	
Wall or floor furnace	3.23			Vent. (blowers/ducts)	$ 2.01

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.058
9	.981	14	1.077
10	1.000 (base)	16	1.115
11	1.019	18	1.154

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	75	125	150	200	250	300	350	400	500	600	700	800	900	1000	Sq. Ft./Story
1,000	.980	1.110	1.178	1.311	1.444	1.577	1.711	1.844	-----	-----	-----	-----	-----	-----	**1,000**
2,000	.878	.945	.977	1.044	1.110	1.178	1.245	1.311	-----	-----	-----	-----	-----	-----	**2,000**
3,000	.843	.889	.911	.955	1.000	1.044	1.088	1.133	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	.860	.878	.911	.945	.977	1.010	1.044	1.110	1.178	-----	-----	-----	-----	**4,000**
5,000	-----	.844	.857	.884	.911	.938	.960	.991	1.044	1.097	1.150	-----	-----	-----	**5,000**
6,000	-----	-----	.843	.865	.888	.911	.934	.955	1.000	1.044	1.088	1.133	-----	-----	**6,000**
7,000	-----	-----	.835	.854	.873	.892	.911	.931	.967	1.006	1.044	1.080	-----	-----	**7,000**
8,000	-----	-----	-----	.844	.860	.877	.894	.911	.945	.977	1.010	1.044	1.076	-----	**8,000**
9,000	-----	-----	-----	.836	.852	.867	.881	.896	.926	.955	.985	1.014	1.044	-----	**9,000**
10,000	-----	-----	-----	-----	.844	.858	.871	.884	.911	.938	.960	.991	1.018	1.044	**10,000**
12,000	-----	-----	-----	-----	.833	.843	.855	.867	.888	.911	.934	.955	.977	1.000	**12,000**
14,000	-----	-----	-----	-----	.825	.835	.844	.854	.873	.892	.911	.931	.949	.967	**14,000**
16,000	-----	-----	-----	-----	-----	.827	.836	.844	.861	.877	.894	.911	.928	.945	**16,000**
20,000	-----	-----	-----	-----	-----	.818	.824	.831	.844	.858	.871	.884	.898	.911	**20,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

DAY CARE CENTERS



GOOD CLASS C



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These structures are child and handicapped care centers and include nursery or children's pre-schools. They have light kitchen facilities, activity rooms, multiple restrooms and are more residential style in character than schools. Generally, the better centers may have reception, office, conference, lunch, shower and changing facilities, as well as classrooms.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, kitchen equipment, balconies, lockers, therapy or recreational equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 245.50	Brick, concrete or metal panels, formed concrete	Plaster or drywall, carpet, hardwood and vinyl	Good restrooms and kitchen, adequate lighting/plumbing	Heat pump system
C	Excellent	306.50	Face brick, glass panels, stone, top quality	Plaster, tile pavers, hardwood, carpet	Tiled restrooms, full kitchen, good lighting, extra features	Heat pump system
	Good	231.50	Face brick, concrete or metal panels, ornamentation	Plaster or drywall, carpet, hardwood and vinyl	Good restrooms and kitchen, adequate lighting/plumbing	Package A.C.
	Average	181.00	Brick, block, concrete panels, some trim	Plaster or drywall, acoustic tile, vinyl composition, carpet	Adequate lighting/plumbing, average restrooms/kitchen	Forced air
	Low cost	128.50	Brick or block, tilt-up, no trim	Painted walls, asphalt tile	Minimum lighting/plumbing	Wall furnace
D	Excellent	297.50	Face brick veneer, best siding, good ornamentation	Plaster, tile pavers, hardwood, carpet	Tiled restrooms, full kitchen, good lighting, extra features	Heat pump system
	Good	223.50	Brick veneer, good stucco or siding with good trim	Plaster or drywall, carpet, hardwood and vinyl	Good restrooms and kitchen, adequate lighting/plumbing	Package A.C
	Average	171.50	Brick veneer, stucco or siding, little trim	Plaster or drywall, acoustic tile, carpet, vinyl composition	Adequate lighting/plumbing, average restrooms/kitchen	Forced air
	Low cost	122.00	Stucco or siding, very plain	Drywall, asphalt tile	Minimum lighting and plumbing	Wall furnace
D POLE	Average	166.00	Pole frame, good metal panels, finished inside, little trim	Plaster or drywall, acoustic tile, carpet, vinyl composition	Adequate lighting/plumbing, average restrooms/kitchen	Forced air
	Low cost	116.00	Pole frame, metal siding	Drywall, asphalt tile	Minimum lighting and plumbing	Wall furnace
S	Average	167.00	Insulated sandwich panels, pre-engineered frame	Drywall, acoustic tile, carpet, vinyl composition	Adequate lighting/plumbing, average restrooms/kitchen	Forced air
	Low cost	118.50	Light steel frame, siding	Drywall, asphalt tile	Minimum lighting and plumbing	Wall furnace
CDS†	Classroom basement	127.50	Reinforced concrete, plaster or drywall interior	Classrooms, school finishes, some utility and storage	Adequate lighting and plumbing	Forced air
	Parking basement	59.50	Unfinished interior	Finished ceiling, concrete floor with hardener	Exposed lighting, adequate drains	Ventilation
	Unfinished basement	48.25	Unfinished interior	Unfinished storage and utility	Minimum lighting, drains	None
	Classroom mezzanine	92.50	Not included	Classroom and office, typical finishes	Adequate school lighting and plumbing	In building cost
	Open mezzanine	53.00	Not included	Finished floors and soffit, open play area	Average lighting, no plumbing	In building cost

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.59 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

DAY CARE CENTERS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055
9	.981	14	1.073
10	1.000 (base)	15	1.092
11	1.018	16	1.110
12	1.037		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	10,000
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	12,000
14,000	-----	-----	-----	-----	-----	-----	.923	.939	.955	.984	1.015	1.048	1.110	1.173	14,000
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	16,000
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	20,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

DORMITORIES



EXCELLENT CLASS B

OCCUPANCY DESCRIPTION: These buildings include college and boarding school residence halls, interns' or nurses' quarters, and military service quarters. They generally have lounges and frequently have dining facilities. In the better qualities, the rooms are soundproof, furniture is built in, baths are tiled and painted, halls, lounges and rooms are carpeted. Plaster and drywall are the most common wall finishes used. The amount of detail on the interior is commensurate with the overall quality.



GOOD CLASS B

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Built-in cabinetry, desks, etc., which are normally included in the general building contract. Elevators are included in costs designated with an (*) asterisk.

NOT INCLUDED IN COSTS: Sprinklers, balconies, kitchen equipment, swimming pools or recreation room equipment systems.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$ 438.50	Stone, best brick, good metal panels, best designs	Soundproofed rooms, carpeting, built-in furniture, fine lounges	*Tiled bathrooms, paired baths, good electrical and plumbing	Hot and chilled water (zoned)
	Good	301.00	Face brick, metal or concrete panels, ornamental fronts	Soundproofed rooms, carpeted halls and lounges, good detail	*Good bathrooms, good electrical/ plumbing fixtures	Hot and chilled water (zoned)
	Average	236.00	Brick, steel or concrete panels, some ornamentation	Drywall or plaster walls/ceiling, vinyl composition, carpeting	*One bath for three students, average electrical service	Warm and cool air (zoned)
	Low cost	186.00	Brick or concrete panels, very plain, painted interior	Drywall, acoustic tile, vinyl composition floors	*Painted shower rooms, half baths in living units	Hot water
B	Excellent	396.00	Stone, best brick, good metal panels, best designs	Soundproofed rooms, carpeting, built-in furniture, fine lounges	*Tiled bathrooms, paired baths, good electrical and plumbing	Hot and chilled water (zoned)
	Good	272.50	Face brick, metal or concrete panels, ornamental fronts	Soundproofed rooms, carpeted halls and lounges, good detail	*Good bathrooms, good electrical/ plumbing fixtures	Hot and chilled water (zoned)
	Average	213.00	Brick, steel or concrete panels, some ornamentation	Drywall or plaster walls/ceiling, vinyl composition, carpeting	*One bath for three students, average electrical service	Warm and cool air (zoned)
	Low cost	167.50	Brick or concrete panels, very plain, painted interior	Drywall, acoustic tile, vinyl composition floors	*Painted shower rooms, half baths in living units	Hot water
A-B	Basements dorm units	182.00	Half exposed, good fenestration	Average-quality dormitory units	Average electrical/plumbing	Hot water
	Finished basement	139.00	Finished interior	Finished, service, social functions	Adequate lighting/plumbing	Hot water
	Util. bsmt.	74.00	Painted concrete	Utility and storage units	Utility lighting/plumbing	None
C	Excellent	366.50	Stone, best brick, good metal panels, best designs	Soundproofed rooms, carpeting, built-in furniture, fine lounges	*Tiled bathrooms, paired baths, good electrical and plumbing	Hot and chilled water (zoned)
	Good	223.00	Face brick, metal or concrete panels, good design	Carpeted halls and lounges, good detail, plaster or drywall	*Good bathrooms, good electrical/ plumbing fixtures	Warm and cool air (zoned)
	Average	166.00	Brick, steel or concrete panels, little trim	Plaster or drywall, carpeted halls, acoustic tile	Standard electrical/plumbing fixtures, some tile and extras	Hot water
	Low cost	127.00	Brick, block, precast concrete, very plain	Exposed block, drywall, acoustic tile, vinyl composition	Minimum number and quality of fixtures	Forced air
D	Excellent	358.00	Stone or brick veneer, metal and glass, individual design	Carpeting, built-in furniture, good lounge and decoration	*Tiled bathrooms, paired baths, good electrical and plumbing	Hot and chilled water (zoned)
	Good	209.00	Brick veneer or best stucco with trim, good ornamentation	Carpeted halls and lounges, plaster or drywall, good detail	Good bathrooms, good electrical service	Warm and cool air (zoned)
	Average	157.00	Brick veneer or stucco with some trim	Plaster or drywall, carpeted halls, acoustic tile	Standard electrical/plumbing fixtures, some tile and extras	Hot water
	Low cost	119.00	Stucco or siding, very plain, simple entrance	Drywall, vinyl composition, minimum finish	Minimum number and quality of fixtures	Forced air
S	Average	152.50	Sandwich panels, some trim	Drywall, carpet and vinyl composition, acoustic tile ceilings	Standard electrical and plumbing fixtures	Hot water
CDS	Basement dorm units	133.50	Half exposed, good fenestration	Average-quality dormitory units	Average electrical/plumbing	Forced air
	Finished basement	99.50	Finished interior	Finished, service, social functions	Adequate lighting/plumbing	Forced air
	Util. bsmt.	45.75	Unfinished concrete	Unfinished floor and ceiling	Minimum lighting/plumbing	None

For parking basements, see Page CAL 2.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

DORMITORIES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Classes C/D/S	Sq. Ft. Costs
Excellent	$10.75	Excellent	$6.63
Good	8.04	Good	5.10
Average	6.16		
Low Cost	4.69		

ELEVATOR STOPS: For basement stops, add $9,550 to $14,400 per stop.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL,
3,000	$ 5.14	$ 6.63	$ 8.55	$11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
50,000	3.36	4.20	5.24	6.50
100,000	3.00	3.73	4.59	5.71

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL,
Concrete	$ 34.00	$ 43.50	$ 55.00	$ 71.00
Steel	31.75	42.50	56.50	75.50
Wood	29.75	39.50	52.50	68.50
Add for ornate finishes, balustrades	29.50	36.00	44.25	54.00
Add for roofs or awnings	15.35	20.40	27.00	36.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork)	$21.90	Central refrigeration (zoned)	$16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector	20.75	Heat pump system	25.50	Pkg. refrig.	$2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers.	$331 to $535 per MCFM capacity
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$3.18

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	12	1.055
9	.973	13	1.084
10	1.000 (base)	14	1.114
11	1.027		

4

Average Floor Area	AVERAGE PERIMETER													Average Floor Area
Sq. Ft./Story	200	250	300	350	400	450	500	600	700	800	1000	1200	1400	Sq. Ft./Story
2,000	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	.959	.989	1.021	1.052	1.083	1.113	1.143	1.206	1.268	1.329	-----	-----	-----	**4,000**
6,000	.917	.938	.959	.980	1.000	1.021	1.042	1.083	1.123	1.165	-----	-----	-----	**6,000**
8,000	-----	.913	.929	.944	.959	.974	.989	1.021	1.052	1.083	1.143	1.206	1.268	**8,000**
10,000	-----	-----	.910	.922	.935	.947	.959	.984	1.009	1.034	1.083	1.133	1.181	**10,000**
12,000	-----	-----	-----	.907	.917	.928	.938	.959	.980	1.000	1.042	1.083	1.123	**12,000**
14,000	-----	-----	-----	-----	.906	.915	.924	.942	.959	.977	1.011	1.047	1.083	**14,000**
20,000	-----	-----	-----	-----	.885	.892	.898	.910	.922	.935	.959	.984	1.009	**20,000**
24,000	-----	-----	-----	-----	-----	-----	.886	.896	.907	.917	.938	.959	.980	**24,000**
28,000	-----	-----	-----	-----	-----	-----	.880	.888	.898	.906	.924	.942	.959	**28,000**
32,000	-----	-----	-----	-----	-----	-----	.874	.882	.889	.898	.913	.928	.944	**32,000**
36,000	-----	-----	-----	-----	-----	-----	.870	.877	.883	.890	.904	.917	.932	**36,000**
40,000	-----	-----	-----	-----	-----	-----	.866	.873	.879	.885	.898	.910	.922	**40,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.