FIELDHOUSES



EXCELLENT CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: Fieldhouses are large gymnasium-type structures designed for indoor and outdoor sports and practice facilities. The better quality structures will include complete spectator and team facilities commensurate with the quality.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers, lockers, therapy or recreational equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 352.00	Good frame, face brick, stone, concrete or metal panels, solar glass	Good exhibition floor, varied sports and spectator facilities	Good lighting and outlets, good plumbing, extra features	Hot and chilled water (zoned)
	Average	231.00	Steel columns and girders, face brick, best ornamental block	Intramural and competitive sports venues, good support facilities	Good lighting and outlets, showers and restrooms	Warm and cool air (zoned)
A-B	Finished Basement	179.50	Reinforced concrete, plaster interior	Utility, classroom and dressing room finishes	Adequate lighting and plumbing, tiled showers and restrooms	Package A.C.
C	Excellent	336.00	Heavy frame, best masonry walls, spectator entrance and lobby	Good exhibition floor, some arena finishes and spectator facilities	Good lighting and outlets, good plumbing, extra features	Warm and cool air (zoned)
	Good	226.50	Steel columns and girders, face brick, best ornamental block	Intramural and competitive sports venues, good support facilities	Good lighting and outlets, showers and restrooms	Heat pump system
	Average	145.00	Steel or Glulam, trusses or girders, brick, block or tilt-up	Multisport fields, some courts, co-recreation/sports activities	Adequate lighting and plumbing, locker rooms	Package A.C.
	Low cost	84.50	Light frame, block or tilt-up, very plain	Low-cost finishes, minimal support facilities, synthetic flooring	Minimum sports lighting and plumbing	Space heaters
D	Excellent	326.00	Heavy frame, masonry veneer walls, spectator entrance and lobby	Good exhibition floor, some arena finishes and spectator facilities	Good lighting and outlets, good plumbing, extra features	Warm and cool air (zoned)
	Good	217.50	Steel or Glulam frame, trusses and girders, brick veneer, best stucco	Intramural and competitive sports venues, good support facilities	Good lighting and outlets, showers and restrooms	Heat pump system
	Average	137.50	Heavy frame, trusses or girders, good stucco or siding, little trim	Multisport fields, some courts co-recreation/sports activities	Adequate lighting and plumbing, locker rooms	Package A.C.
	Low cost	78.00	Light frame, stucco or siding, very plain	Low-cost finishes, minimal support facilities, synthetic flooring	Minimum sports lighting and plumbing	Space heaters
D POLE	Average	129.50	Pole frame, good metal panels, finished inside, little trim	Multisport fields, some courts, co-recreation/sports activities	Adequate lighting and plumbing, locker rooms	Package A.C.
	Low cost	72.50	Pole frame, metal siding, partly finished interior, insulation	Low-cost finishes, minimal support facilities, synthetic flooring	Minimum sports lighting and plumbing	Space heaters
	Cheap	56.50	Pole frame, metal single wall, very plain	Little or none, no dressing rooms or showers, practice field only	Minimum lighting and restrooms	Ventilation
S	Good	213.00	Pre-engineered, good sandwich panels, some brick or stone trim	Intramural and competitive sports venues, good support facilities	Good lighting and outlets, showers and restrooms	Heat pump system
	Average	133.00	Pre-engineered, finished interior, insulation, little trim	Multisport fields, some courts, co-recreation/sports activities	Adequate lighting and plumbing, locker rooms	Package A.C.
	Low cost	74.00	Pre-engineered, partly finished interior, some insulation	Low-cost finishes, minimal support facilities, synthetic flooring	Minimum sports lighting and plumbing	Space heaters
	Cheap	58.00	Single wall, very plain	Little or none, no dressing rooms or showers, practice field only	Minimum lighting and restrooms	Ventilation
CDS	Finished Basement	125.50	Reinforced concrete, plaster or drywall interior	Utility, classroom and dressing room finishes	Adequate lighting and plumbing, showers and restrooms	Forced air

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.59 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

FIELDHOUSES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 70,750 to $ 116,000.

Vertical wheelchair lifts cost $19,100 to $37,100.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 32.25	$ 42.00	$ 54.50	$ 71.00
Steel	29.75	40.25	54.00	73.00
Wood	27.75	37.25	49.75	66.00
Add for ornate finishes, balustrades	28.00	34.75	43.00	53.00
Add for roofs or awnings	15.20	20.15	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 5.92	$ 7.89	$ 10.57	$ 14.72
2,500	5.80	7.58	9.87	13.04
5,000	5.20	6.60	8.38	10.65
10,000	4.67	5.87	7.42	9.32
15,000	4.39	5.50	6.89	8.63
20,000	4.17	5.22	6.52	8.17
50,000	3.65	4.51	5.56	6.87
80,000	3.36	4.08	4.99	6.13
100,000	3.31	4.02	4.91	6.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.963	13	1.055	20	1.183
9	.981	14	1.073	22	1.220
10	1.000 (base)	15	1.092	24	1.257
11	1.018	16	1.110	30	1.367
12	1.037	18	1.147	36	1.476

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	800	1000	1200	1600	2000	Sq. Ft./Story
1,000	1.134	1.189	1.244	1.298	1.407	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.043	1.079	1.116	1.153	1.227	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	.996	1.024	1.052	1.079	1.134	1.189	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
3,000	-----	.968	.985	1.006	1.043	1.079	1.153	-----	-----	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	.957	.968	.995	1.024	1.079	1.134	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	.949	.968	.991	1.036	1.079	1.123	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	.934	.952	.968	1.006	1.043	1.079	-----	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	-----	.929	.942	.968	.996	1.024	1.079	1.134	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.927	.949	.968	.991	1.036	1.079	1.123	-----	-----	**10,000**
12,000	-----	-----	-----	-----	-----	.915	.934	.959	.968	1.006	1.043	1.079	1.153	-----	**12,000**
16,000	-----	-----	-----	-----	-----	-----	.915	.929	.942	.968	.996	1.024	1.079	1.134	**16,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.915	.927	.949	.968	.991	1.036	1.079	**20,000**

NOTE: For larger buildings, enter the table by taking half the area and half the perimeter. For very small structures, reverse the process (i.e., for a 10' x 10' or 100-square-foot building, multiply both the area and the perimeter by a factor of 5 to enter the table where the wall-to-floor ratio remains the same at 4:1 with a 10' height).

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

FITNESS CENTERS



EXCELLENT CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: These buildings are complete multisport recreational complexes distinguished by large gymnasium/auditorium-type structures that include both the private membership and public community center facilities. These multipurpose buildings will include gym/basketball, handball/racquetball/bowling and other sport courts, rinks, varied swimming/natatorium facilities, running tracks, as well as exercise, craft, game and other social/multipurpose exercise rooms. The number of varied amenities and support facilities (locker room, sauna, snack bars, etc.) will vary with the level of quality.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Suitable office areas and lounge facilities.

NOT INCLUDED IN COSTS: Elevators, sprinklers, lockers, pools, exercise equipment, kitchen equipment or furnishings. Equipment and trade fixtures associated with the various amenities.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 310.50	Special architecture, good materials, good entrance and lobby	Top sports finish, elaborate finishes, many extra facilities and rooms	Best sports lighting, plumbing, many extras	Hot and chilled water (zoned)
	Average	227.50	Heavy frame, metal or concrete panels, good architecture	Good main gym or rink, multisports courts, natatorium, many extras	Good sports lighting, restrooms, sauna, shower and locker rooms	Warm and cool air (zoned)
A-B	Finished basement	193.50	Reinforced concrete, plaster interior	Exercise and dressing room finishes, some utility and storage	Adequate lighting and plumbing, showers and restrooms	Package A.C.
	Good mezzanine	65.50	Not included	Open, finished running track, plaster or drywall soffit	Average lighting, no plumbing	In building cost
	Average mezzanine	48.00	Not included	Open, finished floors and soffit, add for spectator seating	Average lighting, no plumbing	In building cost
C	Excellent	300.00	Best masonry, good curtain walls, good entrance and lobby	Top sports finish, elaborate finishes, many extra facilities and rooms	Best sports lighting, plumbing, many extras	Hot and chilled water (zoned)
	Good	216.50	Brick, best block, metal and glass, good entrance	Good main gym or rink, multisports courts, natatorium, many extras	Good sports lighting, restrooms, sauna, shower and locker rooms	Warm and cool air (zoned)
	Average	152.50	Brick, block, tilt-up, some ornamentation, small front	Basketball floor, swim pools, good multipurpose rooms	Adequate lighting, restrooms, sauna, shower and locker rooms	Package A.C.
D	Good	206.50	Brick veneer or best stucco on heavy frame, good entrance	Good main gym or rink, multisports courts, natatorium, many extras	Good sports lighting, restrooms, sauna, shower and locker rooms	Warm and cool air (zoned)
	Average	145.50	Stucco or siding on Glulam frame with girders or trusses	Basketball floor, swim pools, good multipurpose rooms	Adequate lighting, restrooms, sauna, shower and locker rooms	Package A.C.
S	Good	208.50	Insulated metal sandwich panels, good frame, entrance	Good main gym or rink, multisports courts, natatorium, many extras	Good sports lighting, restrooms, sauna, shower and locker rooms	Warm and cool air (zoned)
	Average	144.50	Good metal panels and roof, little ornamentation, small front	Basketball floor, swim pools, good multipurpose rooms	Adequate lighting, restrooms, sauna, shower and locker rooms	Package A.C.
CDS	Finished basement	128.00	Reinforced concrete, plaster or drywall interior	Exercise and dressing room finishes, some utility and storage	Adequate lighting and plumbing, showers and restrooms	Forced air
	Good mezzanine	50.50	Not included	Open, finished running track, drywall soffit	Average lighting, no plumbing	In building cost
	Average mezzanine	34.25	Not included	Open, finished floors and soffit, add for spectator seating	Average lighting, no plumbing	In building cost

MEZZANINES: Do not use story height or area/perimeter multipliers with mezzanine costs.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

FITNESS CENTERS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

LOCKERS: per opening:

	COST RANGE		
Single Tier	$ 194.00	–	$ 374.00
Double	127.00	–	240.00
Triple	91.50	–	202.00
Box Type	66.00	–	123.00

SWIMMING POOLS: For lack of swimming pool, deduct $12.00 per square foot.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
12	.889	20	1.106
14	.945	22	1.158
16	1.000 (base)	24	1.210
18	1.054		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	250	300	350	400	450	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
5,000	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	-----	.999	1.011	1.023	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	**10,000**
12,000	-----	-----	-----	.995	1.005	1.015	1.034	1.052	1.071	1.089	-----	-----	-----	-----	**12,000**
14,000	-----	-----	-----	.982	.992	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	**14,000**
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	**25,000**
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	**30,000**
35,000	-----	-----	-----	-----	-----	.936	.945	.954	.964	.973	.982	.997	1.011	-----	**35,000**
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	**40,000**
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	**50,000**
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	**75,000**
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	**100,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

FRATERNAL BUILDINGS



AVERAGE CLASS C



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These large multipurpose buildings are designed for use by fraternal organizations and generally have an auditorium, kitchen, dining room, game rooms and offices. They also often have large meeting rooms with movable partitions.

Those consisting primarily of a small auditorium with few additional rooms would be classified as clubhouses. If the facility has many sleeping rooms or apartments it would be considered a city club for costing purposes.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, furnishings, kitchen equipment, lockers or athletic equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Average	$ 282.00	Brick, concrete, metal and glass, some ornamentation	Drywall, asphalt tile, hardwood, auditorium, kitchen and game rooms	Adequate lighting and plumbing	Warm and cool air (zoned)
B	Average	253.50	Brick, concrete, metal and glass, some ornamentation	Drywall, asphalt tile, hardwood, auditorium, kitchen and game rooms	Adequate lighting and plumbing	Warm and cool air (zoned)
A-B	Finished basement	168.50	Plaster interior	Finished rooms, asphalt tile	Adequate lighting and plumbing	Hot water
	Semifin. basement	120.00	Low cost finishing	Minimum social functions, kitchenette	Minimum lighting and plumbing	Forced air
	Unfinished basement	87.00	Unfinished interior	Unfinished storage and utility	Minimum lighting, drains	None
C	Excellent	333.50	Marble, stone, metal and glass, very decorative	Excellent finish and detail, carpet, terrazzo, vinyl, fine kitchen	Best lighting and sound systems, good plumbing	Warm and cool air (zoned)
	Good	254.00	Face brick, ornamental trim, good entrance, lobby	Good finish and detail, carpeting and tile, auditorium, good kitchen	Good fluorescent lighting, good plumbing and restrooms	Warm and cool air (zoned)
	Average	183.50	Brick, block, concrete panels, some ornamentation	Drywall, acoustic tile, hardwood and asphalt tile, kitchen	Adequate lighting and plumbing	Package A.C.
	Low-cost	131.50	Low-cost brick, block, concrete	Painted, acoustic and asphalt tile	Minimum lighting and plumbing	Forced air
D	Good	244.00	Brick veneer or best stucco with trim, good entrance	Good finish and detail, carpet, vinyl, auditorium, good kitchen	Good fluorescent lighting, good plumbing and restrooms	Warm and cool air (zoned)
	Average	173.50	Stucco, some brick or stone trim, small entrance	Drywall, acoustic tile, asphalt tile, kitchen and game rooms	Adequate lighting and plumbing	Package A.C.
	Low-cost	123.50	Low-cost wood or stucco	Drywall, acoustic and asphalt tile	Minimum lighting and plumbing	Forced air
D POLE	Low-cost	117.00	Metal skin on pole frame and truss, finished interior	Drywall, acoustic and resilient tile, small kitchen and game rooms	Minimum lighting and plumbing	Forced air
S	Average	170.00	Metal sandwich panels	Drywall, acoustic tile, asphalt tile, kitchen and game rooms	Adequate lighting and plumbing	Package A.C.
	Low-cost	121.50	Steel or aluminum panels	Drywall, acoustic and asphalt tile	Minimum lighting and plumbing	Forced air
CDS	Finished basement	124.00	Plaster or drywall interior	Finished rooms, asphalt tile	Adequate lighting and plumbing	Forced air
	Semifin. basement	72.50	Low-cost finishes	Minimum social functions	Minimum lighting and plumbing	Space heaters
	Unfinished basement	53.00	Unfinished interior	Unfinished storage and utility	Minimum lighting, drains	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

FRATERNAL BUILDINGS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger or freight elevator with simple call system and push button control and two or three stops, costs $65,000 to $106,000.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 33.00	$ 42.00	$ 54.50	$ 70.00
Steel	31.00	41.75	56.00	76.00
Wood	26.00	35.00	46.75	62.50
Add for ornate finishes, balustrades	27.50	34.25	42.00	52.50
Add for roofs or awnings	15.20	20.10	26.75	35.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 5.18	$ 6.54	$ 8.28	$ 10.45
10,000	4.66	5.83	7.30	9.12
15,000	4.35	5.43	6.81	8.51
20,000	4.17	5.19	6.47	8.05
30,000	3.90	4.85	6.03	7.50
40,000	3.74	4.63	5.73	7.08
60,000	3.53	4.33	5.31	6.54
80,000	3.38	4.14	5.06	6.21
100,000	3.25	3.98	4.85	5.93
150,000	3.04	3.69	4.49	5.47
200,000	2.93	3.55	4.30	5.21

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 13.40	Package A.C. (short ductwork)	$ 28.75	Central refrigeration (zoned)	$ 20.50
Electric wall heaters	4.90	Warm and cool air (zoned)	43.25	package (short ductwork)	14.30
Forced air furnace	18.20	Hot/chilled water (zoned)	58.00	Central evaporative	8.01
Hot water, baseboard/convector	24.60	Heat pump system	36.25	Pkg. refrig.	$ 2,875 to $ 3,725 per ton capacity
Space heaters, with fan	5.62			Evap. coolers.	$ 427 to $ 700 per MCFM capacity
radiant	6.45				
Steam (including boiler)	22.35				
without boiler	20.20	Small indiv. heat pumps cost	$ 2,525 to $ 3,525	**VENTILATION ONLY**	
Wall or floor furnace	5.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.59

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.833	20	1.106
12	.889	22	1.158
14	.945	24	1.210
16	1.000 (base)	26	1.262
18	1.054	28	1.313

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	175	200	250	300	400	500	600	700	800	900	1000	1200	1400	1600	Sq. Ft./Story
2,000	1.117	1.147	1.205	1.264	1.381	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
5,000	.999	1.011	1.034	1.056	1.100	-----	-----	-----	-----	-----	-----	-----	-----	-----	5,000
10,000	-----	-----	-----	-----	1.011	1.034	1.056	1.078	1.100	-----	-----	-----	-----	-----	10,000
14,000	-----	-----	-----	-----	.982	1.001	1.018	1.034	1.049	1.063	-----	-----	-----	-----	14,000
20,000	-----	-----	-----	-----	-----	.971	.986	.999	1.011	1.023	1.034	1.056	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	.954	.967	.980	.992	1.003	1.011	1.027	-----	-----	25,000
30,000	-----	-----	-----	-----	-----	.943	.954	.965	.976	.986	.995	1.011	1.026	-----	30,000
40,000	-----	-----	-----	-----	-----	-----	.938	.945	.954	.963	.971	.986	.999	1.011	40,000
45,000	-----	-----	-----	-----	-----	-----	.934	.939	.946	.954	.962	.976	.989	1.001	45,000
50,000	-----	-----	-----	-----	-----	-----	.930	.935	.941	.947	.954	.967	.980	.992	50,000
75,000	-----	-----	-----	-----	-----	-----	.920	.923	.926	.930	.934	.941	.949	.958	75,000
100,000	-----	-----	-----	-----	-----	-----	.914	.917	.920	.922	.925	.930	.935	.941	100,000

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

FRATERNITY HOUSES



GOOD/EXCELLENT CLASS D



AVERAGE CLASS D

OCCUPANCY DESCRIPTION: These structures are very similar in design to residential structures. The family-style nature of the kitchens, dining areas and lounge rooms differs from Dormitories. The distinguishing characteristics are the multiple sleeping units and the expanded plumbing to service more than one student per bath.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Elevators, sprinklers, balconies, fireplaces or kitchen equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$263.00	Stone, best brick and design, ornamental front	Soundproofed rooms, extra features, good lounge	Paired baths, tiled, good electrical and plumbing	Warm and cool air (zoned)
	Good	209.00	Face brick, stone trim, good fenestration and design	Plaster or drywall, hardwood, carpet, vinyl composition, good detail	Good electrical/plumbing fixtures, three students per bath	Warm and cool air (zoned)
	Average	159.00	Brick or block, little trim, good fenestration	Plaster or drywall, painted block, carpet, vinyl composition	Adequate, shower rooms, residential lighting circuits	Hot water
D	Excellent	256.00	Face brick or stone veneer, fine windows, ornamental front	Fine interior detail, ceramic tile, carpet, paneling, fine hardwood	Good fixtures, many outlets, one full bath per bedroom	Warm and cool air (zoned)
	Good	202.50	Good stucco or siding with trim, brick veneer, ornamentation	Plaster or drywall, hardwood, carpet, vinyl composition, good detail	Good electrical/plumbing fixtures, three students per bath	Warm and cool air (zoned)
	Average	151.00	Stucco or siding, little trim	Plaster or drywall, some carpet	Adequate lighting/plumbing	Hot water
C-D	Finished basement	53.50	Finished interior, add for saunas, bars, and equipment	Gypsum board ceiling, vinyl composition tile or sheet vinyl	Adequate lighting/plumbing	None
	Unfinished basement	43.25	Few partitions, little or no finish	Unfin. ceiling, slab, storage only	Minimum lighting and drain	None

For basement apartments use 75% of costs of comparable above ground units. For semi-basement apartments, use 85%.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

FRATERNITY HOUSES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

FIREPLACES: For each additional opening using the same chimney, add 30% to 50%. Fraternity Houses with basements, add 40% to extend the foundation to the basement level.

TYPE	COST RANGE
One-story	$3,850 – $12,400
Two-stories	4,890 – 14,890
Three-stories	5,930 – 17,380

RESIDENTIAL ELEVATORS: The small residential-style two or three passenger elevators found in rectories cost $28,600 to $57,500 for two stops plus $3,900 to $6,150 for each additional stop.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 5.14	$ 6.63	$ 8.55	$ 11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
50,000	3.36	4.20	5.24	6.50

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

	LOW	AVG.	GOOD	EXCL
Concrete	$ 34.00	$ 43.50	$ 55.00	$ 71.00
Steel	31.75	42.50	56.50	75.50
Wood	29.75	39.50	52.50	68.50
Add for ornate finishes, balustrades	29.50	36.00	44.25	54.00
Add for roofs or awnings	15.35	20.40	27.00	36.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork)	$ 21.90	Central refrigeration (zoned)	$ 16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector	20.75	Heat pump system	25.50	Pkg. refrig.	$2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers.	$331 to $535 per MCFM capacity
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 3.18

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	11	1.027
9	.973	12	1.055
10	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	150	200	250	300	350	400	450	500	550	600	650	700	750	800	Sq. Ft./Story
1,000	1.150	1.310	1.370	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	1.120	1.083	1.143	1.206	1.267	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
3,000	.970	1.000	1.042	1.083	1.123	1.165	1.206	-----	-----	-----	-----	-----	-----	-----	3,000
4,000	-----	.959	.989	1.021	1.052	1.083	1.113	1.143	1.175	1.206	1.237	-----	-----	-----	4,000
5,000	-----	-----	.959	.984	.922	1.034	1.059	1.083	1.108	1.133	1.157	1.181	-----	-----	5,000
7,000	-----	-----	.924	.942	.959	.977	.994	1.011	1.029	1.047	1.065	1.083	1.101	-----	7,000
10,000	-----	-----	-----	-----	.922	.935	.947	.959	.972	.984	.997	1.009	1.022	1.034	10,000
12,000	-----	-----	-----	-----	.907	.917	.928	.938	.949	.959	.970	.980	.990	1.000	12,000
14,000	-----	-----	-----	-----	-----	.906	.915	.924	.933	.942	.951	.959	.968	.977	14,000
18,000	-----	-----	-----	-----	-----	-----	.897	.904	.911	.917	.925	.932	.939	.945	18,000
22,000	-----	-----	-----	-----	-----	-----	-----	-----	.898	.903	.909	.915	.920	.926	22,000
30,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.885	.889	.894	.898	.902	30,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.