GARAGES: EMERGENCY RESPONSE, STAFFED



VERY GOOD CLASS C



GOOD CLASS C

OCCUPANCY DESCRIPTION: This occupancy is used by a full-time fire department. The buildings are designed for engine storage, dormitory and light kitchen facilities. The better quality fire stations are able to serve as a command post for major fire control.

Average quality fire stations are similar to company size fire units in city areas and are also equipped for 24-hour watch.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers or hoists.

GARAGES; EMERGENCY RESPONSE, STAFFED

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Good	$ 406.00	Good metal and glass, concrete, some good stone, good entrance	Fully equipped, kitchen, tile showers, offices, major command post	Good lighting and outlets, good plumbing	Warm and cool air (zoned)
	Average	292.00	Precast concrete, brick, limestone trim, some ornamentation	Kitchen, showers, offices, plaster, acoustic tile, vinyl tile	Adequate lighting and plumbing	Hot water
C	Excellent	384.50	Special design, face brick, stone, architectural concrete, good entrance	Individual sleeping rooms, tile showers/ decontamination room, good offices	Best lighting and outlets, good plumbing and kitchen	Warm and cool air (zoned)
	Very good	320.50	Face brick, stone, architectural concrete, good entrance	Fully equipped, kitchen, tile showers, offices, major command post	Good lighting and outlets, good plumbing	Heat pump system
	Good	264.00	Face brick, stone, metal and glass, ornamental trim	Kitchen, showers, offices, plaster, acoustic tile, vinyl tile	Good lighting and outlets, good plumbing	Package A.C.
	Average	184.50	Brick, block, concrete, some ornamentation	Small living and administrative areas, drywall and asphalt tile	Adequate lighting and plumbing	Forced air
	Low cost	121.50	Brick, block, tilt-up, very plain	Minimum watch type or emergency medical service, small finished areas	Minimum lighting and plumbing	Wall furnace
D	Excellent	369.00	Special design, face brick or stone veneer, good entrance	Individual sleeping rooms, tile showers/ decontamination room, good offices	Best lighting and outlets, good plumbing and kitchen	Warm and cool air (zoned)
	Very good	305.00	Face brick or stone veneer, good entrance	Fully equipped, kitchen, tile showers, offices, major command post	Good lighting and outlets, good plumbing	Heat pump system
	Good	248.50	Brick veneer, best stucco or siding with good trim	Kitchen, showers, offices, drywall or plaster, vinyl tile	Good lighting and plumbing	Package A.C.
	Average	170.50	Brick veneer, good stucco or siding with brick trim	Drywall and acoustic tile, small living and administrative areas	Adequate lighting and plumbing	Forced air
	Low cost	109.00	Stucco or siding, little trim	Drywall, small finished areas, minimum watch type or EMS	Minimum lighting and plumbing	Wall furnace
D POLE	Average	146.50	Pole frame, good metal panels, finished inside, little trim	Drywall and acoustic tile, some living and office area	Adequate lighting and plumbing	Forced air
	Low cost	92.50	Pole frame, metal siding, some interior finish and insulation	Minimum watch type, drywall, small finished areas	Minimum lighting and plumbing	Wall furnace
S	Good	219.00	Good sandwich panels, good entrance and trim	Kitchen, showers, offices, paneling, acoustic tile, carpet, vinyl tile	Good lighting and outlets, good plumbing	Package A.C.
	Average	152.00	Sandwich panels, or finished interior, some ornamentation	Drywall and acoustic tile, some living and office area	Adequate lighting and plumbing	Forced air
	Low cost	97.00	Metal exterior, some interior finish and insulation	Minimum watch type, drywall, small finished areas	Minimum lighting and plumbing	Wall furnace

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES: EMERGENCY RESPONSE, STAFFED

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

TRAINING TOWERS: Masonry towers or burn structures cost $15.00 to $25.25 per cubic foot of tower structure. For structures with thermal insulated. tiles, add 45%

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$2,950 to $3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	14	1.046
10	.953	16	1.092
12	1.000 (base)	18	1.138

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	700	800	1000	1200	1600	Sq. Ft./Story
1,000	1.168	1.235	1.299	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	1.007	1.040	1.072	1.105	1.168	1.235	1.364	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	-----	-----	.958	.975	1.007	1.040	1.105	1.168	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.936	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.926	.942	.975	1.007	1.040	1.072	1.105	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	1.105	1.155	-----	**10,000**
14,000	-----	-----	-----	-----	-----	.900	.920	.938	.956	.975	.993	1.030	1.067	1.140	**14,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.910	.923	.936	.949	.975	1.000	1.052	**20,000**
25,000	-----	-----	-----	-----	-----	-----	-----	.897	.908	.918	.928	.948	.969	1.011	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	-----	.897	.906	.915	.932	.949	.983	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.890	.897	.910	.923	.949	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.928	**50,000**

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES: EMERGENCY RESPONSE, VOLUNTEER



GOOD CLASS S

OCCUPANCY DESCRIPTION: Emergency Response Garages typically include vehicle storage, small offices, a classroom and min- imal plumbing. They have only partially finished floors and ceil- ings. Better than average garages may have kitchenettes, drywall and acoustical tile.



AVERAGE CLASS C

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers or hoists.

GARAGES: EMERGENCY RESPONSE, VOLUNTEER

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 170.50	Brick, ornamented block, concrete, some ornamentation	Office, classroom, kitchenette, drywall and acoustic tile	Good lighting, adequate plumbing and restrooms	Package A.C.
	Low cost	134.00	Brick, block, tilt-up, some trim	Painted walls, few small offices, some finished floor and ceiling	Adequate electrical, minimum plumbing	Forced air
C	Good	146.00	Brick, ornamented block, concrete, some trim	Office, classroom, kitchenette, drywall and acoustic tile	Good lighting, adequate plumbing and restrooms	Forced air
	Average	101.00	Brick, block, tilt-up, wall bearing or frame	Painted walls, few small offices, some finished floor and ceiling	Adequate electrical, minimum plumbing	Space heaters
	Low cost	77.50	Block, cheap brick, tilt-up, light shell structure	Some partitions, little finish, minimum garage type	Minimum electrical and water	Space heaters
D	Good	133.00	Brick veneer, good stucco or siding with brick trim	Office, classroom, kitchenette, drywall and acoustic tile	Good lighting, adequate plumbing and restrooms	Forced air
	Average	91.50	Studs or light frame, siding or stucco, some trim or veneer	Few small offices, some finished floor and ceiling	Adequate electrical, minimum plumbing	Space heaters
	Low cost	69.50	Cheap frame, stucco or siding, very plain	Minimum apparatus facility, few partitions, little finish	Minimum electrical and water	Space heaters
D POLE	Average	83.00	Pole frame and truss, metal siding, lined, insulated	Small finished offices, some drywall, vinyl composition	Adequate electrical, minimum plumbing	Space heaters
	Low cost	62.00	Pole frame, metal, primarily exposed	Some partitions, finish, garage type	Minimum electrical and water	Space heaters
S	Good	130.50	Sandwich panels, or finished interior, some trim	Office, classroom, kitchenette, drywall and acoustic tile	Good lighting, adequate outlets, plumbing, restrooms	Forced air
	Average	87.50	Single wall, some interior finish and insulation	Small finished offices, some drywall, vinyl composition	Adequate electrical, minimum plumbing	Space heaters
	Low cost	66.00	Metal on light frame, primarily exposed	Some partitions, little finish, minimum apparatus facility	Minimum electrical and water	Space heaters

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES: EMERGENCY RESPONSE, VOLUNTEER

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

TRAINING TOWERS: Masonry towers or burn structures cost $15.00 to $25.25 per cubic foot of tower structure. For structures with thermal insulated. tiles, add 45%

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$2,950 to $3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	14	1.046
10	.953	16	1.092
12	1.000 (base)	18	1.138

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	175	200	250	300	400	500	600	700	800	1000	1200	1600	Sq. Ft./Story
1,000	1.168	1.235	1.299	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	1.007	1.040	1.072	1.105	1.168	1.235	1.364	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	-----	-----	.958	.975	1.007	1.040	1.105	1.168	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.936	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.926	.942	.975	1.007	1.040	1.072	1.105	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	1.105	1.155	-----	**10,000**
14,000	-----	-----	-----	-----	-----	.900	.920	.938	.956	.975	.993	1.030	1.067	1.140	**14,000**
20,000	-----	-----	-----	-----	-----	-----	-----	.910	.923	.936	.949	.975	1.000	1.052	**20,000**
25,000	-----	-----	-----	-----	-----	-----	-----	.897	.908	.918	.928	.948	.969	1.011	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	-----	.897	.906	.915	.932	.949	.983	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.890	.897	.910	.923	.949	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.928	**50,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES: MINI-LUBE AND SERVICE/REPAIR SHEDS



GOOD CLASS C



LOW CLASS C

OCCUPANCY DESCRIPTION: Mini-lube garages are designed for quick-maintenance lube and oil changes and may have drive-thru bays. There is usually adequate lighting and adequate plumbing using commercial plumbing fixtures. The floor is concrete, with office areas having resilient floor covering. The size or amount of office area is commensurate with the overall quality. Exterior walls generally have some large openings for overhead doors and minimal fenestration.

Service garages/repair sheds are buildings designed primarily for vehicular repair and maintenance. They are characterized by their low-cost, open fronts (no doors), unfinished interiors, concrete or asphalt floors, with adequate lighting and outlets. These buildings are typically found in car dealerships and large fleet operations.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Sufficient heating to protect materials and personnel from freezing. Some shop cabinets and work space are included in the better-quality service/repair sheds.

NOT INCLUDED IN COSTS: Sprinklers, hoists or service equipment.

GARAGE – MINI-LUBE

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 242.00	Best block, entry, 20% or more finished sales area	Good store type finish in sales, good lobby, waiting room, restrooms	Good retail illumination, good garage in balance	Package A.C.
	Good	184.50	Good ornamental block and parapet, storefront lobby	Good drywall, acoustic tile, pavers, VCT, carpet, good office/waiting room	Good lighting and plumbing, service outlets	Forced air
	Average	142.00	Masonry bearing walls or frame, roll-up doors	Painted walls, slab, some partitions, floor and ceiling finish, waiting area	Adequate lighting and plumbing, service outlets	Space heaters
	Low cost	113.00	Block, cheap brick, tilt-up, light construction	Painted wall, slab, few partitions, small office area	Minimum lighting and plumbing, service outlets	Space heaters
D	Excellent	231.00	Best masonry veneer, entry, 20% or more finished sales area	Good store type finish in sales, good lobby, waiting room, restrooms	Good retail illumination, good garage in balance	Package A.C.
	Good	174.50	Good masonry veneer, EIFS, decorative parapet, storefront lobby	Good drywall, acoustic tile, pavers, VCT, carpet, good office/waiting room	Good lighting and plumbing, service outlets	Forced air
	Average	134.00	Frame and stucco, siding, masonry veneer, some trim, roll-up doors	Some gypsum walls and ceiling, slab, some finished floor, waiting area	Adequate lighting and plumbing, service outlets	Space heaters
	Low cost	105.50	Stucco or siding on wood or steel	Some gypsum walls and ceiling, slab, small office area	Minimum lighting and plumbing, service outlets	Space heaters
S	Average	134.00	Pre-engineered, steel studs or frame, good panels, roll-up doors	Some gypsum walls, acoustic tile, slab, some finished floor, waiting area	Adequate lighting and plumbing, service outlets	Space heaters
	Low cost	106.50	Pre-engineered frame, metal siding	Some gypsum walls, acoustic tile, slab, small office area	Minimum lighting and plumbing, service outlets	Space heaters
CDS	Average basement	59.50	Reinforced concrete or block, unfinished interior	Unfinished, storage areas, some partitions, service walkways	Minimum lighting and plumbing, drains	None

SERVICE/REPAIR SHED†

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Good	$ 51.50	Open front, block or low-cost brick, good roof	Unfinished, concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	35.00	Open front, tilt-up, block, steel or wood truss, average cover	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	None
	Low cost	26.50	End walls only, concrete block, shed or flat roof	Unfinished, concrete or asphalt floor	Adequate electrical and water service and outlets	None
D POLE	Good	41.50	Open front, good metal siding on pole frame	Unfinished, concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	28.00	Open front, metal or board on light pole frame	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	None
	Low cost	21.50	End walls only, low-cost siding on wood pole frame	Unfinished, concrete or asphalt floor	Adequate electrical and water service and outlets	None
S	Good	45.50	Open front, good metal and steel frame	Unfinished, concrete floor, shop area and cabinets	Good lighting and outlets, adequate plumbing	Space heaters
	Average	31.00	Open front, enameled siding on light frame	Unfinished, concrete or asphalt floor, some cabinets, work area	Adequate electrical and water service and outlets	None
	Low cost	24.00	End walls only, low-cost siding on steel frame	Unfinished, concrete or asphalt floor	Adequate electrical and water service and outlets	None

†**NOTE:** Use total length of walled sides as the perimeter in the floor area/perimeter table. For repair buildings, see Page CAL 88.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES: MINI-LUBE AND SERVICE/REPAIR SHEDS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

HOISTS: Automobile hoists cost $12,400 to $19,300 each.
Truck hoists, $16,900 to $32,100. See Section UIP 14 for greater detail.

Walk in service pits cost $3,475 to $7,450 per bay.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.91	$ 6.57	$ 8.82	$ 11.74
2,500	4.63	6.17	8.24	10.95
5,000	4.16	5.51	7.28	9.63
10,000	3.78	4.95	6.48	8.49

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$2.96

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.921	18	1.086
12	.960	20	1.133
14	1.000 (base)	22	1.181
16	1.041	24	1.231

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	125	150	175	200	250	300	350	400	450	500	600	700	800	Sq. Ft./Story
1,000	1.252	1.360	1.468	1.576	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
1,500	1.112	1.182	1.252	1.323	1.395	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,500**
2,000	-----	1.095	1.147	1.199	1.252	1.360	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
2,500	-----	-----	1.083	1.125	1.168	1.252	1.340	1.430	-----	-----	-----	-----	-----	-----	**2,500**
3,000	-----	-----	-----	1.077	1.112	1.182	1.252	1.323	1.395	-----	-----	-----	-----	-----	**3,000**
4,000	-----	-----	-----	1.013	1.040	1.094	1.147	1.199	1.252	1.306	-----	-----	-----	-----	**4,000**
5,000	-----	-----	-----	-----	.996	1.040	1.083	1.125	1.168	1.210	1.252	-----	-----	-----	**5,000**
6,000	-----	-----	-----	-----	-----	1.004	1.040	1.077	1.112	1.147	1.182	1.252	-----	-----	**6,000**
7,000	-----	-----	-----	-----	-----	-----	1.008	1.040	1.071	1.102	1.132	1.192	1.252	-----	**7,000**
8,000	-----	-----	-----	-----	-----	-----	.984	1.013	1.040	1.068	1.094	1.147	1.199	1.252	**8,000**
10,000	-----	-----	-----	-----	-----	-----	-----	.972	.996	1.019	1.040	1.083	1.125	1.168	**10,000**
12,000	-----	-----	-----	-----	-----	-----	-----	-----	.965	.984	1.003	1.040	1.077	1.112	**12,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – PARKING LEVELS



GOOD CLASS B PARKING LEVEL

OCCUPANCY DESCRIPTION: The intermediate and ground level parking levels are found underneath elevated buildings and include all framing, ramps and stairs necessary.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, landscaping on roof of below grade structures, ticketing equipment or hoists.

PARKING LEVELS (INTERMEDIATE/UNDER BUILDING)

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Excellent	$ 153.50	Best curtain wall panels, matching spandrel and louvers, fully enclosed	Unfinished except good office, service and lobby areas	*Reading-level lighting, restrooms and service plumbing	Ventilation
	Good	118.50	Good curtain panels, masonry, partial louvers, natural ventilation	Concrete with hardener, lines and stops, small office, few extras	*Adequate lighting and drains	None
	Average	94.00	Partial walls, brick, concrete, metal panels, some trim or louvers	Unfinished, concrete floor, lines, low-cost elevator lobbies	*Low-level lighting, drains	None
	Low cost†	72.00	Under building, grade level only, blind wall panels, some trim, gates	Concrete paving, lines and stops, plaster soffit, lobby not included	Low-level lighting, drains	None
	Cheap†	46.00	Under building, grade level only, no walls, covered columns	Asphalt paving, lines, painted soffit, vestibule/lobby not included	Minimum lighting, drains	None
CDS	Good	96.50	Good panels, masonry, partial louvers, open ventilation	Concrete with hardener, lines and stops, few extras	*Adequate lighting and drains	None
	Average	75.50	Partial walls, brick, masonry or stucco panels, some trim or louvers	Unfinished, concrete floor, lines, low-cost elevator lobbies	*Low-level lighting, drains	None
	Low cost†	56.50	Under building, grade level only, some blind walls, trim and gates	Concrete or asphalt, lines, plaster soffit, vestibule/lobby not included	Low-level lighting, drains	None
	Cheap†	34.00	Under building, grade level only, open, no walls, exposed columns	Asphalt paving, lines, finished building soffit, lobby not included	Minimum lighting, drains	None

†Ground-level vestibule entry lobbies for elevated buildings must be added separately. See Page CAL 232.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – PARKING LEVELS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked.

For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs	Classes C/D/S	Sq. Ft. Costs
Good	$ 5.61	Good	$ 3.34
Average	4.54	Average	2.86
Low cost	3.59		

NOTE: Do not use floor area/perimeter multipliers with open grade level parking under elevated buildings.

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,500	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$ 2,950 to $ 3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$ 2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)	20	1.184

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	200	250	300	400	500	600	700	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
3,000	-----	.975	1.018	1.061	1.105	1.191	-----	-----	-----	-----	-----	-----	-----	-----	**3,000**
5,000	-----	-----	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	.926	.942	.975	1.007	1.040	1.072	1.105	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	1.105	1.155	-----	-----	**10,000**
14,000	-----	-----	-----	-----	.900	.920	.938	.956	.975	.993	1.030	1.067	1.105	1.140	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.910	.923	.936	.949	.975	1.000	1.027	1.052	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.897	.908	.918	.928	.948	.969	.990	1.011	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.897	.906	.915	.932	.949	.965	.983	**30,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	.928	**50,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – PARKING STRUCTURES



GOOD CLASS B PARKING STRUCTURE



GOOD CLASS B PARKING STRUCTURE

OCCUPANCY DESCRIPTION: Built above and below grade, these structures are designed for live-load storage of autos. Independent above grade structures commonly have either no exterior walls or partial exterior walls. The independent above grade structure is priced by the number of stories and will always have one more level (ground or roof) of parking than stories, while the underground structure will have a load bearing roof for a park or plaza at grade level. While the lower quality structures do not have office area, the better qualities have some small office and service areas. There is low level lighting and adequate plumbing for restrooms and service areas.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, landscaping on roof of below grade structures, ticketing equipment or hoists.

ABOVE GROUND STRUCTURES

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Good	$ 110.00	Partial walls, brick or concrete, ornamentation	Unfinished, except good office and service area	*Reading-level lighting, restrooms and service plumbing	None
	Average	84.50	Partial walls, brick, block, concrete, little trim	Unfinished, small office and service area	*Low-level lighting, drains, minimum restroom for office	None
B	Good	97.00	Partial walls, brick or concrete, ornamentation	Unfinished, except good office and service area	*Reading-level lighting, restrooms and service plumbing	None
	Average	75.00	Partial walls, brick, block, concrete, plain finish	Unfinished, small office and service area	*Low-level lighting, drains, minimum restroom for office	None
	Low cost	58.50	Low parapets, precast frame and floors, minimum finish	Unfinished, minimum extras	*Minimum lighting and plumbing	None
S	Low cost	55.50	Demountable type, exposed steel frame	Unfinished, some masonry shear walls, minimum extras	Low-level lighting, drains, minimum personnel plumbing	None
	Cheap	43.50	Demountable type, exposed steel frame, cable rails	Unfinished, no extras	Minimum lighting, drains only	None

UNDERGROUND STRUCTURES

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 143.50	Unfinished concrete, water proofed walls and load-bearing roof at grade level	Unfinished, some office and service areas	Good lighting, restrooms and service plumbing	Package A.C.

†Ground-level vestibule entry lobbies for elevated buildings must be added separately. See Page CAL 232.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – PARKING STRUCTURES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Good	$ 4.03
Average	2.70
Low cost	1.97

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
5,000	$ 4.16	$ 5.51	$ 7.28	$ 9.63
10,000	3.78	4.95	6.48	8.49
15,000	3.54	4.62	6.03	7.88
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
50,000	2.96	3.79	4.89	6.27
80,000	2.75	3.49	4.47	5.72
100,000	2.67	3.39	4.32	5.51
150,000	2.49	3.17	4.02	5.11
200,000	2.40	3.04	3.84	4.85
250,000	2.32	2.91	3.68	4.63
400,000	2.17	2.73	3.39	4.23

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $ 560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.885	14	1.000 (base)
10	.921	16	1.041
12	.960	18	1.086

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	250	300	350	400	450	500	600	700	800	900	1000	1200	1500	2000	Sq. Ft./Story
5,000	1.040	1.083	1.125	1.168	1.210	1.252	-----	-----	-----	-----	-----	-----	-----	-----	**5,000**
10,000	-----	-----	.972	.996	1.019	1.040	1.083	1.125	1.168	1.210	-----	-----	-----	-----	**10,000**
14,000	-----	-----	-----	.945	.961	.977	1.008	1.040	1.071	1.102	1.132	-----	-----	-----	**14,000**
20,000	-----	-----	-----	-----	-----	.926	.949	.972	.996	1.019	1.040	1.083	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	.907	.924	.942	.959	.977	.996	1.032	-----	-----	**25,000**
30,000	-----	-----	-----	-----	-----	-----	.907	.921	.935	.949	.965	.995	1.040	-----	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	.899	.907	.916	.926	.949	.984	-----	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	.891	.898	.907	.924	.950	.996	**50,000**
60,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.889	.895	.907	.928	.965	**60,000**
70,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.877	.884	.896	.913	.945	**70,000**
80,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.869	.875	.887	.903	.926	**80,000**
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	.863	.872	.887	.907	**100,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – RESIDENTIAL



GOOD CLASS D



LOW COST D-POLE

OCCUPANCY DESCRIPTION:
For attached garages, deduct the cost of the common wall. For built-in garages, deduct the cost of the common wall and the roof cost. For open carports use roof and wall costs as required, add supports from Section UIP 1. Costs do not include interior finish or electric door operators, except as specifically mentioned; add from Sections UIP 2 and UIP 5 if necessary.

CLASS	TYPE	COST PER SQUARE FOOT						WALL COST (Lin. Ft.)	ROOF COST (Sq. Ft.)	DESCRIPTION
		200 Sq. Ft.	400 Sq. Ft.	600 Sq. Ft.	800 Sq. Ft.	1,000 Sq. Ft.	1,400 Sq. Ft.			
C	Excellent	$ 147.00	$ 111.00	$ 99.50	$ 93.00	$ 87.50	$ 81.00	$ 26.75	$ 347.00	Face brick or cut stone walls, heavy roof, slate, tile, lightweight concrete, heavy reinforced slab, plaster interior, good windows and lighting
	Very good	126.00	93.00	84.00	78.00	73.50	68.00	22.25	298.00	Good brick, adobe stone, heavy roof structure, tile heavy shake, finished interior, good overhead and pedestrian doors, good windows and lighting
	Good	99.50	73.50	66.00	61.50	58.50	52.50	18.50	247.00	Brick, ornamental block, adobe, good roof structure and roofing, good reinforced slab, overhead door, window, pedestrian door, good lighting
	Average	74.50	54.00	48.50	45.25	42.50	38.25	12.75	183.00	8” brick or block, 2 x 4 rafters, gable roof, wood or good asphalt shingles, reinforced slab, overhead door, window, pedestrian door, lighting
	Low cost	56.50	40.50	36.25	33.25	31.50	28.25	8.72	137.00	Concrete block, low-cost brick, structural tile, asphalt shingles or composition roofing, unreinforced slab, low cost overhead or hinged doors
D MASONRY VENEER	Excellent	142.00	107.00	96.50	91.00	85.50	79.00	26.50	325.00	Best face brick or cut stone veneer, heavy roof, slate, tile, good reinforced slab, plaster interior, good windows and lighting
	Very good	121.00	90.50	81.50	77.00	71.50	66.50	22.15	280.00	Good brick or stone veneer, heavy roof structure, tile, heavy shake, finished interior, good overhead and pedestrian doors, good windows and lighting
	Good	96.50	71.50	65.00	60.50	57.50	51.50	18.30	236.00	Face brick veneer, good roof, shakes, tile, etc., reinforced slab, good overhead doors, good windows, pedestrian door, good lighting
	Average	72.50	53.00	48.25	44.50	42.00	37.75	12.55	178.00	Brick veneer, 2 x 4 rafters, gable roof, wood or good asphalt shingles, reinforced slab, overhead door, window, pedestrian door, lighting
	Low cost	55.50	39.50	35.50	32.75	31.00	27.75	8.72	134.00	Low-cost brick or block veneer, composition or asphalt shingle roof, unreinforced slab, low-cost overhead or hinged doors, one window or light
D	Excellent	120.00	93.50	85.50	81.00	75.50	70.00	26.50	244.00	Best stucco, stone or brick trim, heavy rafters or steep roof, heavy slab, finished interior, good doors, good lighting and windows
	Very good	103.00	79.50	72.50	68.50	64.00	59.50	22.00	211.00	Good sidings, stone trim, heavy roof, tile, heavy shake, finished interior, good overhead and pedestrian doors, good fenestration and lighting
	Good	81.00	62.00	57.00	53.50	50.00	46.25	18.20	175.00	Good stucco or siding, good roof, shakes, tile, etc., reinforced slab, good overhead doors, good windows, pedestrian door, good lighting
	Average	61.00	46.00	41.75	39.25	37.25	33.75	12.45	134.00	Stucco or siding, 2 x 4 rafters, gable roof, wood or good asphalt shingles, reinforced slab, overhead door, window, pedestrian door, lighting
	Low cost	46.25	34.50	31.00	29.00	27.75	24.85	8.55	103.00	Low-cost stucco or siding, light studs, composition or asphalt shingle roof, unreinforced slab, low-cost overhead or hinged door, one window or light
	Cheap	37.00	26.50	23.95	22.05	-----	-----	7.90	87.00	Cheap siding, vertical boards, hardboard, no floor, windows or lighting
D POLE	Low cost	39.00	29.75	26.75	25.25	-----	-----	6.40	75.00	Single wall, enameled metal on wood pole frame, concrete slab
S	Average	68.50	52.00	48.50	44.75	43.00	-----	12.55	158.00	Insulated sandwich panels on pre-engineered frame, reinforced slab, pedestrian door, windows, electric light and outlet
	Low cost	40.75	31.00	28.25	26.25	-----	-----	6.61	81.50	Single wall, enameled metal on low-cost pre-engineered frame, concrete slab

NOTE: Residential-type garages usually found with single-family residences should be priced from Volume I.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – RESIDENTIAL

MULTIPLE GARAGES OR CARPORTS

Costs per square foot include back wall, end wall and roof with necessary supports and girders. Add $795 to $1,380 per single space for doors. Average and Good costs include lockers and partitions commensurate with the quality. Concrete floors included: deduct $2.01 to $3.00 for asphalt. Open carport covers with concrete floors will cost $12.50 to $24.95 per square foot.

SQUARE FOOT COST TABLE

CLASS	QUALITY	4-CAR	8-CAR	12-CAR	16-CAR	20-CAR
C	Good	$51.50	$47.25	$45.50	$45.00	$44.75
	Average	39.50	36.50	34.75	34.25	34.00
	Low cost	30.75	27.75	26.75	26.50	26.00
D MASONRY VENEER	Good	$43.75	$41.00	$39.75	$39.25	$38.75
	Average	32.25	29.75	29.00	28.50	28.25
	Low cost	23.70	21.75	21.20	20.85	20.70

BASEMENT GARAGES

Lump sums to be added to the total basement costs, including garage finish.

	SINGLE	DOUBLE	3-CAR
Unfinished basements	$2,800.00 - $3,950.00	$3,775.00 - $5,650.00	$5,200.00 - $7,700.00
Finished basements	$2,210.00 - $3,125.00	$2,600.00 - $3,725.00	$3,250.00 - $4,800.00

BUILT-IN GARAGES FOR TOWN HOUSES

Costs per square foot of garage area, including interior finish.

CLASS	QUALITY	SINGLE		DOUBLE		3-CAR	
		End Unit	Inside	End Unit	Inside	End Unit	Inside
C	Excellent	84.50	50.00	63.00	47.75	57.50	46.25
	Good	64.50	38.25	48.25	36.25	43.50	35.25
	Average	49.00	29.25	36.50	27.25	33.00	26.75
	Low cost	37.50	22.35	28.00	20.45	24.95	20.15
D MASONRY VENEER	Excellent	81.50	48.25	61.50	46.50	56.50	45.00
	Good	62.50	37.50	46.75	35.25	42.75	34.25
	Average	48.00	28.50	36.00	26.50	32.75	26.00
	Low cost	37.00	21.95	27.50	20.15	24.80	19.70
D	Excellent	68.00	43.00	51.50	41.25	48.25	39.75
	Good	52.50	33.25	40.25	31.50	37.25	30.50
	Average	40.50	25.75	31.00	23.85	27.75	23.35
	Low cost	31.50	19.95	24.20	18.25	22.20	17.95

NOTE: Residential-type garages usually found with single-family residences should be priced from Volume I.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – SERVICE STATIONS



AVERAGE/GOOD CLASS S-C SERVICE STATION



AVERAGE CLASS S-C SERVICE STATION

OCCUPANCY DESCRIPTION: Service stations are complete stations, including areas for office storage, sales, restrooms, and lube areas for service bay stations.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Base electric and interior circuits. Sufficient heating to protect materials and personnel from freezing.

NOT INCLUDED IN COSTS: Sprinklers, hoists, compressors, exterior electrical circuits, carwashes, food service or display fixtures, exterior equipment and improvements.

STATIONS WITH SERVICE BAYS

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
S-C	Excellent	$ 282.50	Best steel or brick, masonry trim, good fenestration, garage doors	Good finish, best workmanship, many built-in features, tire racks, etc.	Six to eight good commercial plumbing fixtures, good electrical	Package A.C.
	Good	222.00	Good steel or brick, sectional doors, good sash, large overhangs	Ranch or suburban style, tiled restrooms, good office	Average commercial fixtures, adequate interior circuits	Space heaters
	Average	184.50	Average painted steel or block, little trim, small overhangs	Present-day station, small office, storage, restrooms	Five to six low-cost commercial plumbing fixtures, standard electrical	Space heaters
	Low cost	153.00	Painted steel, inexpensive sash and doors or gates	Older station, minimum finishes, few built-in items	Four residential-type fixtures, minimum interior electrical	Space heaters
D	Good	181.00	Good sidings, sectional doors, good sash, large overhangs	Ranch or suburban style, tiled restroom, good office	Average commercial fixtures, adequate interior circuits	Space heaters
	Average	152.00	Siding or metal on wood frame, little trim, small overhangs	Present-day station, small office, storage, restrooms	Five to six low-cost commercial plumbing fixtures, std. electrical	Space heaters
	Low cost	127.50	Siding or stucco, inexpensive sash and doors or gates	Older station, minimum finishes, few built-in items	Two to three low-cost fixtures, minimum interior circuits	Space heaters
	Cheap	102.00	Low-cost siding or stucco, cheap sash and gates	Substandard, older station, minimal finishes	Two cheap plumbing fixtures, minimum incandescent lighting	None

PREFABRICATED FOOD BOOTHS

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
S	Good	$ 356.00	Good enameled prefinished steel, good front, masonry trim	Good acoustic, ceramic tile, security partitioning, walk-in box	Good lighting and outlets, restroom, standard fixtures	Package A.C.
	Average	313.00	Sandwich panels, small front, some trim or mansard	Typical food booth, some extras, adequate support, cooler areas	Adequate electrical, approx. one plumbing fixture each 175 sq. ft.	Package A.C.
	Low cost	275.00	Painted steel panels, low cost sash and fascia	Acoustic tile, vinyl composition, limited partitions, built-in cooler	Minimum display wiring and plumbing	Package A.C.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – SERVICE STATIONS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

HOISTS: Automobile hoists cost $12,400 to $19,300 each.
Truck hoists, $16,900 to $32,100. See Section UIP 14 for greater detail.

For cashier booths, gasoline pumps, see Section UIP 14.

CANOPIES: Costs per square foot of covered area including light fixtures and supports. Add 10% for gable or ranch style, 25% for round.
Individually designed or highly ornamented canopies can cost 100% more.

	LOW	AVG.	GOOD	EXCL.
Concrete tees	$ 35.50	$ 40.75	$ 48.75	$ 57.00
Steel	30.50	39.25	50.00	63.00
Wood frame	26.75	33.75	41.00	52.50

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.91	$ 6.57	$ 8.82	$ 11.74
2,500	4.63	6.17	8.24	10.95
5,000	4.16	5.51	7.28	9.63
10,000	3.78	4.95	6.48	8.49

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$ 2,420 to $ 3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $ 560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$ 2,330 to $ 3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.885	16	1.041
10	.921	18	1.086
12	.960	20	1.133
14	1.000 (base)	22	1.181

4

FLOOR AREA MULTIPLIERS

FLOOR AREA PER UNIT Sq. Ft.	MULTIPLIER Food Booths	MULTIPLIER Service Bay Stations	FLOOR AREA PER UNIT Sq. Ft.	MULTIPLIER Food Booths	MULTIPLIER Service Bay Stations
400	1.118	1.525	**2,600**	.891	.812
600	1.064	1.330	**2,800**	.883	.792
800	1.027	1.207	**3,200**	.869	.757
1,000	1.000	1.120	**3,600**	.856	.728
1,200	.978	1.053	**4,000**	.846	.702
1,400	.960	1.000	**4,400**	.836	.680
1,600	.945	.956	**4,800**	.827	.660
1,800	.932	.919	**5,200**	.819	.642
2,000	.920	.887	**5,600**	.812	.627
2,200	.909	.859	**6,000**	.805	-----
2,400	.900	.834	**8,000**	.775	-----

5 **USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.**

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – SERVICE/FLEET SERVICE FACILITIES



LOW COST/AVERAGE CLASS S SERVICE

OCCUPANCY DESCRIPTION: Service garages are designed primarily for vehicular repair and maintenance. They are built in all classes of construction and include small office areas with plaster or drywall finish. There is usually good lighting and adequate plumbing using commercial plumbing fixtures. The floor is concrete, with office areas having resilient floor covering. The size or amount of office area is commensurate with the overall quality. Exterior walls generally have some large openings for overhead doors and minimal fenestration.



GOOD CLASS S FLEET SERVICE FACILITY

Fleet service facilities include several subdivisions for offices, stores and shops to support major vehicular maintenance and repair facilities. Exterior walls will have some office fenestration and numerous openings for overhead doors.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Sufficient heating to protect materials and personnel from freezing. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, hoists or service equipment.

GARAGES – SERVICE (REPAIR)

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 124.00	Brick, reinforced concrete, good fenestration	Some plaster and glazed surfaces, offices, masonry partitions	*Good level of lighting, adequate plumbing	Space heaters
C	Excellent	159.00	Steel or concrete frame, brick, decorative block or concrete panels	Some good offices and supply rooms,	Good electrical, lighting and service outlets, good restrooms	Forced air
	Good	111.50	Steel, concrete or glulam frame, masonry curtain or bearing walls	Finished office, painted walls, some partitions	Adequate lighting and service outlets, adequate restrooms	Space heaters
	Average	81.00	Masonry bearing walls with pilasters, light trusses	Unfinished, small finished office area, some supply area	Adequate lighting and service outlets, small restroom	Space heaters
	Low cost	60.00	Light masonry bearing walls, light rafters	Unfinished, small partitioned office area, concrete floor	Minimum electrical and plumbing	Space heaters
D	Good	98.00	Wood frame, good siding, brick veneer or stucco and fenestration	Partially finished, finished office area, some partitions	Adequate lighting and service outlets, adequate restrooms	Space heaters
	Average	72.00	Light wood frame, siding or stucco	Unfinished, small finished office area, some supply area	Adequate lighting and service outlets, small restroom	Space heaters
	Low cost	53.50	Cheap frame, stucco or siding	Unfinished, small office area, concrete floor	Minimum lighting and plumbing	Space heaters
D POLE	Average	64.00	Pole frame, metal siding, lined and insulated	Small finished office area, some supply area	Adequate lighting and service outlets, small restroom	Space heaters
	Low cost	47.00	Pole frame and truss, metal siding	Small partitioned office area, concrete floor, utility type	Minimum lighting and plumbing	Space heaters
S	Good	95.50	Sandwich panels or metal with interior finish	Partially finished, finished office area, some partitions	Adequate lighting and service outlets, adequate restrooms	Space heaters
	Average	70.00	Single wall with some interior finish	Unfinished, small finished office area, some supply area	Adequate lighting and service outlets, small restroom	Space heaters
	Low cost	51.50	Light, pre-engineered, utility-type building	Unfinished, small office area, concrete floor	Minimum lighting and plumbing	Space heaters

FLEET SERVICE FACILITIES

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 249.00	Good masonry or concrete, some ornamentation, heavy frame	Plaster, acoustic tile, finished floors, good offices, shops, supply rooms	Many power outlets, good lighting and plumbing	Package A.C.
	Good	179.50	Steel or concrete frame, brick, or concrete panels	Some good offices and interior finish, supply rooms and shops	Good electrical, lighting and service outlets, good restrooms	Package A.C.
	Average	121.00	Steel, concrete or glulam frame, masonry curtain or bearing walls	Finished office, painted walls, some partitions, supply areas and shops	Adequate lighting and service outlets, adequate restrooms	Forced air
D	Average	108.00	Stucco or brick veneer, some frame or bearing, finished interior	Finished office, some partitions, supply areas and shops	Adequate lighting and service outlets, adequate restrooms	Forced air
S	Excellent	218.00	Good sandwich panels, some ornamentation, heavy frame	Finished walls & floor, acoustic tile, good offices, shops, supply rooms	Many power outlets, good lighting and plumbing	Package A.C.
	Good	158.50	Good steel frame, siding and fenestration	Some good offices and interior finish, supply rooms and shops	Good electrical, lighting and service outlets, good restrooms	Package A.C.
	Average	108.00	Sandwich panels or metal with interior finish	Partially finished, finished office area, some partitions, supply and shop areas	Adequate lighting and service outlets, adequate restrooms	Forced air

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – SERVICE/FLEET SERVICE FACILITIES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Average	$ 3.13

HOISTS: Automobile hoists cost $12,400 to $19,300 each. Truck hoists cost, $16,900 to $32,100 each. See Section UIP 14 for greater detail.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.91	$ 6.57	$ 8.82	$ 11.74
2,500	4.63	6.17	8.24	10.95
5,000	4.16	5.51	7.28	9.63
10,000	3.78	4.95	6.48	8.49
15,000	3.54	4.62	6.03	7.88
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
50,000	2.96	3.79	4.89	6.27

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $ 560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
10	.921	18	1.086
12	.960	20	1.133
14	1.000 (base)	22	1.181
16	1.041	24	1.231

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Sq. Ft./Story
1,000	1.252	1.468	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	-----	1.147	1.252	1.360	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
4,000	-----	-----	1.040	1.094	1.147	1.252	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	.996	1.040	1.083	1.168	1.252	-----	-----	-----	-----	-----	-----	-----	5,000
8,000	-----	-----	-----	-----	.984	1.040	1.094	1.147	1.199	1.252	-----	-----	-----	-----	8,000
10,000	-----	-----	-----	-----	-----	.996	1.040	1.083	1.125	1.168	1.210	-----	-----	-----	10,000
14,000	-----	-----	-----	-----	-----	.945	.977	1.008	1.040	1.071	1.102	1.132	-----	-----	14,000
20,000	-----	-----	-----	-----	-----	-----	.926	.949	.972	.996	1.019	1.040	1.083	-----	20,000
25,000	-----	-----	-----	-----	-----	-----	.907	.924	.942	.959	.977	.996	1.032	-----	25,000
30,000	-----	-----	-----	-----	-----	-----	-----	.907	.921	.935	.949	.965	.995	1.040	30,000
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.899	.907	.916	.926	.949	.984	40,000
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.891	.898	.907	.924	.950	50,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – STORAGE



AVERAGE C MILL STORAGE

OCCUPANCY DESCRIPTION: Storage garages are designed for live and dead load storage of automobiles. Built in all classes of construction, they have some unfinished partitioned office areas using masonry or wood frame walls with minimum lighting and plumbing.



AVERAGE CLASS C

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers or hoists.

STORAGE GARAGES

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 111.50	Brick, reinforced concrete, little ornamentation	Plaster or drywall, masonry partitions, small office and service area	*Low lighting levels, minimum plumbing	Space heaters
A-B	Parking basement	89.00	Unfinished concrete, waterproofed walls	Unfinished, concrete floor, striped	Minimum lighting, drains	Ventilation
C	Average	80.50	Brick, block, tilt-up, plain facade	Unfinished, small partitioned office area, concrete floors	Low-level lighting, minimum plumbing	Space heaters
C MILL	Average	95.50	Mill-type frame, brick, plain facade	Painted walls, mill-type floors, masonry partitions	*Minimum electrical and plumbing	Space heaters
D	Average	73.00	Wood frame, stucco or siding, plain facade	Unfinished, small partitioned office area, concrete floors	Minimum electrical and plumbing	Space heaters
S	Average	71.00	Single-wall construction, enameled steel or aluminum	Unfinished, small partitioned office area, concrete floors	Low-level lighting, minimum plumbing	Space heaters
CDS	Avg. parking bsmt.	57.00	Unfinished concrete, waterproofed walls	Plaster or drywall ceiling, concrete floor, striped	Minimum lighting, adequate drains	Ventilation
	Low parking bsmt.	48.50	Partially exposed, some ornamentation, unfinished interior	Finished ceiling, concrete slab, striping	Minimum lighting, adequate drains	None

NOTE: For parking structures, see Page CAL 82.

MEZZANINES: Do not use story height or area/perimeter multipliers with industrial type mezzanine costs shown above. For fully finish office type mezzanines, see Page CAL 140.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GARAGES – STORAGE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B/C MILL	Sq. Ft. Costs
Average	$ 3.13

ELEVATOR STOPS: For basement or mezzanine elevator stops, add $9,700 to $14,600 per stop.

A small passenger elevator with simple call system and push button control, four passenger cab, and two or three stops,costs $66,500 to $109,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,000	$ 4.91	$ 6.57	$ 8.82	$ 11.74
2,500	4.63	6.17	8.24	10.95
5,000	4.16	5.51	7.28	9.63
10,000	3.78	4.95	6.48	8.49
15,000	3.54	4.62	6.03	7.88
20,000	3.37	4.37	5.70	7.43
30,000	3.18	4.12	5.34	6.89
50,000	2.96	3.79	4.89	6.27

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 8.96	Package A.C. (short ductwork)	$ 19.75	Central refrigeration (zoned)	$ 16.70
Electric wall heaters	3.65	Warm and cool air (zoned)	27.00	package (short ductwork)	11.00
Forced air furnace	10.15	Hot/chilled water (zoned)	45.50	Central evaporative	6.89
Hot water, baseboard/convector	17.95	Heat pump system	24.85	Pkg. refrig.	$2,420 to $3,200 per ton capacity
Space heaters, with fan	5.11			Evap. coolers.	$ 341 to $560 per MCFM capacity
radiant	5.72				
Steam (including boiler)	15.65	Small indiv. heat pumps cost	$2,330 to $3,150	**VENTILATION ONLY**	
without boiler	13.65	per ton of rated capacity.		Vent. (blowers/ducts)	$ 2.96

3

HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.885	14	1.000 (base)
10	.921	16	1.041
12	.960	18	1.086

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	100	150	200	250	300	400	500	600	700	800	900	1000	1200	1500	Sq. Ft./Story
1,000	1.252	1.468	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	-----	1.147	1.252	1.360	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	-----	-----	1.040	1.094	1.147	1.252	-----	-----	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	.996	1.040	1.083	1.168	1.252	-----	-----	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	-----	.984	1.040	1.094	1.147	1.199	1.252	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	-----	-----	.996	1.040	1.083	1.125	1.168	1.210	-----	-----	-----	**10,000**
14,000	-----	-----	-----	-----	-----	.945	.977	1.008	1.040	1.071	1.102	1.132	-----	-----	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.926	.949	.972	.996	1.019	1.040	1.083	-----	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.907	.924	.942	.959	.977	.996	1.032	-----	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.907	.921	.935	.949	.965	.995	1.040	**30,000**
40,000	-----	-----	-----	-----	-----	-----	-----	-----	.899	.907	.916	.926	.949	.984	**40,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.891	.898	.907	.924	.950	**50,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GOVERNMENTAL BUILDINGS



AVERAGE CLASS C



GOOD CLASS B

OCCUPANCY DESCRIPTION: These buildings include city halls, courthouses, etc., but do not include typical office or service buildings. They may be massive buildings or buildings utilizing modern exterior curtain walls. The better qualities have well-finished chambers and hearing rooms, as well as executive offices, while average quality governmental buildings have only a few decorative features.

These buildings are built using all classes of construction. Exteriors vary with the building class; typical finishes include marble, granite, concrete, metal and glass panels, concrete block and various types of masonry veneer.

Interiors commonly utilize high use floor covers such as terrazzo, marble, carpet, ceramic tile and, in some cases, resilient flooring. Most, except the low quality governmental buildings, have combined heating and cooling systems.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, parking or balconies.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A	Excellent	$ 519.50	Highly ornamental, marble, granite, best metal and glass	Plaster, marble trim, ornate detail, terrazzo, carpet, vinyl floors	*Best lighting and outlets, tiled restrooms, many fixtures	Hot and chilled water (zoned)
	Good	401.50	Good metal and glass, concrete, some good stone, good entrance	Plaster or drywall, some paneled offices, vinyl and carpet	*Good lighting and outlets, good tiled restrooms	Hot and chilled water (zoned)
	Average	297.00	Brick, concrete panels, metal and glass, little ornamentation	Plaster or drywall, little paneling, vinyl composition, some carpet	*Adequate lighting and outlets, some tiled restrooms	Warm and cool air (zoned)
B	Excellent	469.50	Highly ornamental, marble, granite, best metal and glass	Plaster, marble trim, ornate detail, terrazzo, carpet, vinyl floors	*Best lighting and outlets, tiled restrooms, many fixtures	Hot and chilled water (zoned)
	Good	366.50	Good metal and glass, concrete, some good stone, good entrance	Plaster or drywall, some paneled offices, vinyl and carpet	*Good lighting and outlets, good tiled restrooms	Hot and chilled water (zoned)
	Average	272.00	Brick, concrete panels, metal and glass, little ornamentation	Plaster or drywall, little paneling, vinyl composition, some carpet	*Adequate lighting and outlets, some tiled restrooms	Warm and cool air (zoned)
	Low cost	209.50	Precast concrete, block, little trim	Plaster or drywall, few paneled offices, vinyl composition	Adequate lighting and outlets, adequate plumbing	Warm and cool air (zoned)
A-B	Office basement	222.00	Reinforced concrete, plaster interior	Office partitions, acoustic tile, some paneling, vinyl composition	Office lighting and outlets, adequate plumbing	Warm and cool air (zoned)
	Parking basement	100.50	Painted interior	Parking, storage and service, lines and stops	Adequate lighting and plumbing	Ventilation
C	Excellent	403.00	Marble or granite, best metal and glass, highly decorative	Plaster, marble trim, paneling, terrazzo, carpet, vinyl floors	Best lighting and outlets, tiled restrooms, many fixtures	Hot and chilled water (zoned)
	Good	292.00	Best ornamental masonry, good metal and glass	Plaster or drywall, good detail and paneling, terrazzo, vinyl tile	Good lighting and outlets, good tiled restrooms	Warm and cool air (zoned)
	Average	224.50	Brick, block, concrete, metal and glass, good entrance	Plaster or drywall, some paneled offices, vinyl composition	Adequate lighting and outlets, adequate plumbing	Warm and cool air (zoned)
	Low cost	158.50	Brick, block, tilt-up, very plain	Plaster or drywall, acoustic tile	Adequate lighting and plumbing	Package A.C.
D	Excellent	388.50	Best masonry veneer, metal and glass, fine fenestration	Plaster, marble trim, paneling, terrazzo, carpet, vinyl floors	Best lighting and outlets, tiled restrooms, many fixtures	Hot and chilled water (zoned)
	Good	279.50	Face brick or stone veneer, fine fenestration	Plaster or drywall, vinyl, paneling, carpet, vinyl composition	Good lighting and outlets, good tiled restrooms	Warm and cool air (zoned)
	Average	197.00	Brick veneer, ornamental stucco, EIFS, metal and glass	Plaster or drywall, acoustic tile, some paneling, vinyl composition	Adequate lighting and outlets, adequate plumbing	Package A.C.
	Low cost	143.00	Stucco or siding, very plain	Drywall, acoustic tile, asphalt tile	Adequate lighting and plumbing	Forced air
S	Average	196.00	Sandwich panels, good fenestration, some brick or stone	Plaster or drywall, some paneled offices, vinyl composition	Adequate lighting and outlets, adequate plumbing	Package A.C.
	Low Cost	142.00	Insulated wall or sandwich panels, adequate fenestration	Drywall, acoustic tile, asphalt tile	Adequate lighting and plumbing	Forced air
CDS	Office basement	140.00	Plaster or drywall interior	Office partitions, acoustic tile and vinyl composition	Office lighting and outlets, adequate plumbing	Forced air
	Parking basement	67.00	Unfinished interior	Parking, storage and service, lines and stops	Adequate lighting and plumbing	Ventilation

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.54 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GOVERNMENTAL BUILDINGS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: Buildings whose base costs include service elevators are marked with an asterisk (*). If the building under consideration has no elevators, deduct the following from the base costs so marked. For detailed costs, see Section UIP 8.

Classes A/B	Sq. Ft. Costs
Excellent	$ 17.95
Good	12.45
Average	8.64

ELEVATOR STOPS: For basements stops, add $9,400 to $14,400 per stop. A small passenger elevator with simple call system and push button control four passenger cab and two or three stops, costs $68,000 to $112,000.

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99
75,000	3.39	4.20	5.22	6.46
100,000	3.27	4.01	4.96	6.13

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 41.00	$ 53.00	$ 69.00
Steel	29.75	40.50	55.00	75.50
Wood	25.25	33.75	45.00	60.00
Add for ornate finishes, balustrades	27.50	34.00	41.75	51.00
Add for roofs or awnings	15.20	20.15	26.75	35.75

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$2,950 to $3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Up to 30 stories, add .5% (1/2%) for each story over three, above ground, to all base costs; over 30, add .4% (4/10%) for each additional story.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	200	250	300	400	500	600	700	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
3,000	-----	.975	1.018	1.061	1.105	1.191	-----	-----	-----	-----	-----	-----	-----	-----	**3,000**
5,000	-----	-----	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	.926	.942	.975	1.007	1.040	1.072	1.105	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	1.105	1.155	-----	-----	**10,000**
14,000	-----	-----	-----	-----	.900	.920	.938	.956	.975	.993	1.030	1.067	1.105	1.140	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.910	.923	.936	.949	.975	1.000	1.027	1.052	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.897	.908	.918	.928	.948	.969	.990	1.011	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.897	.906	.915	.932	.949	.965	.983	**30,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	.928	**50,000**
75,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.873	.879	.885	.892	.900	**75,000**
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.866	.871	.876	.881	.887	**100,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GOVERNMENTAL - COMMUNITY SERVICE BUILDINGS



AVERAGE CLASS C

OCCUPANCY DESCRIPTION: These public buildings are designed as mixed-use structures, typically found in rural communities, and are generally smaller and utilitarian in scope. The lower qualities are generally composed of public safety facilities, volunteer fire, limited office and council meeting rooms and/or small libraries, etc.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit. Elevators are included in costs designated with an asterisk (*).

NOT INCLUDED IN COSTS: Sprinklers, parking or balconies.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
A-B	Average	$ 239.50	Brick, precast concrete, block, some trim, good lobby	Plaster or drywall, good detail, terrazzo, carpet, vinyl tile	Good lighting and outlets, adequate restrooms	Warm and cool air (zoned)
	Low cost	184.50	Precast concrete, block, very plain lobby	Plaster or drywall, vinyl composition, some carpet and pavers	Adequate administrative lighting, restroom facilities, some extras	Heat pump system
A-B	Finished basement	222.00	Reinforced concrete, plaster interior	Office partitions, acoustic tile, some paneling, vinyl composition	Office lighting and outlets, adequate plumbing	Warm and cool air (zoned)
C	Excellent	330.00	Steel frame, masonry and glass, stone ornamentation, top quality	Plaster, paneling, carpet and terrazzo, suspended ceilings, best mixed-use	Best fluorescent ceiling panels, tiled restrooms, good fixtures	Warm and cool air (zoned)
	Good	246.50	Steel columns, web or bar joists, ornamental block or face brick	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	Good fluorescent lighting, good restrooms and fixtures	Heat pump system
	Average	181.50	Steel frame or bearing wall, brick, block, concrete panels, some trim	Paint, drywall partitions, acoustic tile, vinyl composition, typical mixed-use	Fluorescent lighting, adequate outlets and plumbing	Package A.C.
	Low cost	132.50	Brick, block, tilt-up panels, bearing walls, wood joists, little trim	Paint, few low-cost partitions, acoustic tile, public safety, few offices	Minimum administrative lighting and plumbing	Forced air
D	Excellent	317.50	Steel or wood frame, brick or stone veneer, metal and glass, ornamental	Plaster, paneling, carpet and terrazzo, suspended ceilings, best mixed-use	Best fluorescent ceiling panels, tiled restrooms, good fixtures	Warm and cool air (zoned)
	Good	235.50	Steel or glulam frame and joists, brick veneer, glass, best stucco	Plaster or drywall, good partitions, acoustic tile, carpet and vinyl	Good fluorescent lighting, good restrooms and fixtures	Heat pump system
	Average	172.50	Wood frame or pipe columns, good stucco or siding with some trim	Paint, drywall partitions, acoustic tile, vinyl composition, typical mixed-use	Fluorescent lighting, adequate outlets and plumbing	Package A.C.
	Low cost	126.00	Wood frame, stucco or siding, some ornamentation	Paint, few low-cost partitions, acoustic tile, public safety, few offices	Minimum administrative lighting and plumbing	Forced air
D POLE	Average	164.50	Pole frame, insulated metal panels, some ornamentation	Plaster or drywall, good hardwood, low-cost terrazzo, vinyl composition	Adequate lighting and outlets, adequate restrooms	Package A.C.
	Low cost	119.50	Pole frame, finished interior, insulation, little trim	Drywall, acoustic tile, few partitions, public safety, some town offices	Minimum administrative lighting and plumbing	Forced air
S	Good	231.50	Pre-engineered, good sandwich panels, some brick or stone trim	Drywall, some trim, carpet, vinyl, acoustic tile, good mixed-use	Good lighting and plumbing, tiled restrooms	Heat pump system
	Average	169.00	Pre-engineered, sandwich panels, some ornamentation	Drywall, acoustic, vinyl composition, some pavers or ceramic	Adequate lighting and outlets, adequate restrooms	Package A.C.
	Low cost	123.50	Pre-engineered, finished interior, insulation, little trim	Drywall, acoustic tile, few partitions, public safety, some town offices	Minimum administrative lighting and plumbing	Forced air
CDS†	Finished basement	140.00	Plaster or drywall interior	Office partitions, acoustic tile and vinyl composition	Office lighting and outlets, adequate plumbing	Forced air

†For fire-resistant Type I basements, with concrete slab separation under Class C, D or S units, add $8.54 per square foot.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GOVERNMENTAL - COMMUNITY SERVICE BUILDINGS

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops, costs $ 68,000 to $ 112,000.

ELEVATOR STOPS: For basements stops, add $9,400 to $14,400 per stop.

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the balcony area.

	LOW	AVG.	GOOD	EXCL.
Concrete	$ 31.75	$ 41.00	$ 53.00	$ 69.00
Steel	29.75	40.50	55.00	75.50
Wood	25.25	33.75	45.00	60.00
Add for ornate finishes, balustrades	27.50	34.00	41.75	51.00
Add for roofs or awnings	15.20	20.15	26.75	35.75

SPRINKLERS: Apply to sprinklered area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
1,500	$ 6.26	$ 8.11	$ 10.50	$ 13.60
2,000	5.95	7.69	9.94	12.85
5,000	5.19	6.60	8.45	10.75
10,000	4.66	5.90	7.49	9.48
15,000	4.33	5.48	6.95	8.77
20,000	4.15	5.24	6.60	8.32
30,000	3.92	4.90	6.13	7.68
50,000	3.62	4.49	5.59	6.99
75,000	3.39	4.20	5.22	6.46
100,000	3.27	4.01	4.96	6.13

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 17.20	Package A.C. (short ductwork)	$ 27.25	Central refrigeration (zoned)	$ 21.15
Electric wall heaters	5.15	Warm and cool air (zoned)	44.50	package (short ductwork)	14.90
Forced air furnace	19.35	Hot/chilled water (zoned)	63.00	Central evaporative	8.19
Hot water, baseboard/convector	29.75	Heat pump system	37.25	Pkg. refrig.	$ 2,950 to $ 3,800 per ton capacity
Space heaters, with fan	6.34			Evap. coolers.	$ 424 to $ 745 per MCFM capacity
radiant	7.28				
Steam (including boiler)	28.00				
without boiler	25.75	Small indiv. heat pumps cost	$ 2,600 to $ 3,475	**VENTILATION ONLY**	
Wall or floor furnace	5.62	per ton of rated capacity.		Vent. (blowers/ducts)	$ 5.04

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Up to 30 stories, add .5% (1/2%) for each story over three, above ground, to all base costs; over 30, add .4% (4/10%) for each additional story.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.900	13	1.023
9	.928	14	1.046
10	.953	15	1.069
11	.977	16	1.092
12	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER														Average Floor Area
Sq. Ft./Story	125	150	200	250	300	400	500	600	700	800	1000	1200	1400	1600	Sq. Ft./Story
1,000	1.168	1.235	1.364	1.494	1.624	1.884	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
3,000	-----	.975	1.018	1.061	1.105	1.191	-----	-----	-----	-----	-----	-----	-----	-----	**3,000**
5,000	-----	-----	.949	.975	1.000	1.052	1.105	1.155	-----	-----	-----	-----	-----	-----	**5,000**
8,000	-----	-----	-----	.926	.942	.975	1.007	1.040	1.072	1.105	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	.910	.923	.949	.975	1.000	1.027	1.052	1.105	1.155	-----	-----	**10,000**
14,000	-----	-----	-----	-----	.900	.920	.938	.956	.975	.993	1.030	1.067	1.105	1.140	**14,000**
20,000	-----	-----	-----	-----	-----	-----	.910	.923	.936	.949	.975	1.000	1.027	1.052	**20,000**
25,000	-----	-----	-----	-----	-----	-----	.897	.908	.918	.928	.948	.969	.990	1.011	**25,000**
30,000	-----	-----	-----	-----	-----	-----	-----	.897	.906	.915	.932	.949	.965	.983	**30,000**
50,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.887	.897	.908	.918	.928	**50,000**
75,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.873	.879	.885	.892	.900	**75,000**
100,000	-----	-----	-----	-----	-----	-----	-----	-----	-----	.866	.871	.876	.881	.887	**100,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREENHOUSES – COMMERCIAL



AVERAGE CLASS S



CHEAP CLASS S

OCCUPANCY DESCRIPTION: Enclosures used to regulate the climatic conditions for the display, sales and research of various plants and vegetables.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Heating or automated watering systems, shade curtains and planting benches are not included.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING & PLUMBING	HEAT
D	Fair	$ 68.00	Best redwood or laminated frame, glass or sandwich panels	Concrete floor, good working classroom house or nursery sales	Adequate electrical, lighting, water and drains	None
	Low cost	54.50	Wood frame, glass or fiberglass covering, some vents	Dirt floor, some gravel or concrete walks, typical display nursery house	Minimum equipment outlets and hose bibs	None
S	Excellent	197.50	Structural mullions, architectural embellishments, very ornate	Concrete, pavers, some partitions and extras, good conservatory type	Best lighting, electrical and plumbing	None
	Very good	161.00	Best aluminum frame, gutters, metal sandwich or masonry knee wall	Sealed concrete, research modules, glazed corridors	Good lighting and plumbing	None
	Good	131.00	Shed or gable, good glass and masonry knee wall	Good concrete floor, good display science greenhouse	Good lighting and water, good drains	None
	Average	86.50	Tubular or structural frame, good glazing, some knee wall	Concrete floor, best display or horticulture house	Adequate electrical and water service, drains	None
	Fair	70.50	Good metal frame, glass or translucent sandwich panels	Concrete floor, good display house or nursery sales	Adequate electrical, lighting, water and drains	None
	Cheap	57.50	Metal frame, glass or fiberglass covering, some vents	Dirt floor, some gravel or concrete walks, typical display nursery house	Minimum equipment outlets and hose bibs	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREENHOUSES – COMMERCIAL

REFINEMENTS: On this page are the means of making major adjustments to the base costs. Follow Steps 1 through 5 to attain final costs, adjusted for lump sums, heating and cooling, story height, floor area/perimeter ratio, and locality.

1 ADJUSTMENTS

	COST RANGE		
Humidifiers, each	$ 660.00	–	$ 3,075.00
Exhaust fan cooling assembly, per unit	1,070.00	–	2,925.00
Water-drip humidity pad assembly, per square foot of pad	19.35	–	31.25
Automatic vent and/or environmental controls, per unit	1,070.00	–	2,750.00
Automatic chemical injectors (excluding tanks), per unit	3,575.00	–	6,400.00
Automatic water controls, per unit	412.00	–	1,030.00
Traveling boom sprayer, per linear foot of rail	82.00	–	123.00
Roof shade curtains, per square foot of cover, manual (automated, add 100%)	1.08	–	1.31
Hinged vents, manual, per linear foot (automatic, add 20%)	44.50	–	54.50
Automatic sidewall curtain assembly, per linear foot	18.30	–	23.50
Concrete curb, per linear foot	3.96	–	8.72
Stem, knee walls, per linear foot	16.90	–	21.05

MISCELLANEOUS SQUARE FOOT COSTS

Electrical: Low cost, $.33; Average, $1.02; Good, $.2.07; Excellent, $3.59
Floors or walks: Dirt, $.33 – $.52; Gravel, $.73 – $1.06; Asphalt, $2.80 – $4.57; Concrete, $4.12 – $6.03
Water system, plastic: Spray, $.27 – $.44; Mist, $.38 – $.68; Drip tube, $.50 – $.81
Planting benches, per square foot of bench: Plastic, $5.20 – $8.22; Wood slat, $8.13– $9.32; Solid propagating, $8.59 – $15.35

2 HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$17.40	Package A.C. (short ductwork)	$ 22.85	Central refrigeration (zoned)	$ 20.75
Electric wall heaters	5.20	Warm and cool air (zoned)	36.00	package (short ductwork)	14.45
Forced air furnace	19.85	Hot/chilled water (zoned)	56.50	Central evaporative	7.77
Hot water, baseboard/convector	28.75	Heat pump system	34.25	Pkg. refrig.	$ 2,950 to $ 3,775 per ton capacity
Space heaters, with fan	5.87			Evap. coolers.	$ 434 to $ 735 per MCFM capacity
radiant	6.79				
Steam (including boiler)	26.00				
without boiler	23.60	Small indiv. heat pumps cost	$2,550 to $3,625	**VENTILATION ONLY**	
Wall or floor furnace	5.38	per ton of rated capacity.		Vent. (blowers/ducts)	$ 4.77

3 HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.983	14	1.036
9	.991	16	1.055
10	1.000 (base)	18	1.074
11	1.009	20	1.090
12	1.018		

4

Average Floor Area	AVERAGE PERIMETER													Average Floor Area
Sq. Ft./Story	90	120	200	300	500	600	800	1000	1200	1400	1600	1800	2000	Sq. Ft./Story
500	1.710	1.750	1.840	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	**500**
1,000	1.650	1.670	1.720	1.780	-----	-----	-----	-----	-----	-----	-----	-----	-----	**1,000**
2,000	1.360	1.370	1.410	1.450	-----	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	-----	1.170	1.200	1.240	1.320	-----	-----	-----	-----	-----	-----	-----	-----	**4,000**
5,000	-----	-----	1.150	1.160	1.180	1.190	-----	-----	-----	-----	-----	-----	-----	**5,000**
6,000	-----	-----	-----	1.110	1.130	1.140	-----	-----	-----	-----	-----	-----	-----	**6,000**
8,000	-----	-----	-----	1.040	1.060	1.070	1.080	-----	-----	-----	-----	-----	-----	**8,000**
10,000	-----	-----	-----	.950	.990	1.000	1.020	1.040	-----	-----	-----	-----	-----	**10,000**
20,000	-----	-----	-----	-----	.830	.840	.860	.880	-----	-----	-----	-----	-----	**20,000**
25,000	-----	-----	-----	-----	-----	.800	.820	.840	.860	-----	-----	-----	-----	**25,000**
50,000	-----	-----	-----	-----	-----	-----	.680	.700	.720	.740	-----	-----	-----	**50,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREENHOUSES - SHADE



AVERAGE CLASS S

OCCUPANCY DESCRIPTION: These light structures are open (non-walled) shelters designed as sun shades for various plants and vegetables. They have shade netting roofs on either wood posts or steel pipe column and cable supports. The floor is dirt and there is minimum hose bibs and no electrical. The better qualities will have light pipe or post girders instead of cable and some gravel floor covering.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Heating or automated watering systems, shade curtains and planting benches are not included.

SQUARE FOOT COST TABLE

GREENHOUSE SHADE SHELTERS

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
D	Average	$ 3.50	Light wood posts and girders, shade netting cover	Some gravel	No electrical, hose bibs only	None
	Low cost	2.50	No walls, wood posts and cable, flat shade netting roof	Dirt floor	Hose bibs only	None
S	Average	3.50	Light pipe columns and girders, shade netting cover	Some gravel	No electrical, hose bibs only	None
	Low cost	3.00	No walls, steel pipe and cable, flat shade netting roof	Dirt floor	Hose bibs only	None

LATH SHADE HOUSES

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
D	Average	$ 7.50	Wood skeleton frame, spaced wood lath	Gravel, some concrete walks	Equipment outlets and hose bibs	None
S	Average	12.50	Metal skeleton frame, spaced aluminum lath	Gravel, some concrete walks	Equipment outlets and hose bibs	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREENHOUSES - SHADE

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 ADJUSTMENTS

	COST RANGE		
Humidifiers, each	$ 615.00	–	$ 3,050.00
Exhaust fan cooling assembly, per unit	1,070.00	–	2,875.00
Water-drip humidity pad assembly, per square foot of pad	19.40	–	31.00
Automatic vent and/or environmental controls, per unit	1,070.00	–	2,750.00
Automatic chemical injectors (excluding tanks), per unit	3,575.00	–	6,350.00
Automatic water controls, per unit	403.00	–	1,020.00
Traveling boom sprayer, per linear foot of rail	65.50	–	137.00
Roof shade curtains, per square foot of cover, manual (automated, add 100%)	1.05	–	1.30
Hinged vents, manual, per linear foot (automatic, add 20%)	44.25	–	53.00
Automatic sidewall curtain assembly, per linear foot	18.15	–	23.85
Concrete curb, per linear foot	3.96	–	8.72
Stem, knee walls, per linear foot	16.90	–	21.05

MISCELLANEOUS SQUARE FOOT COSTS

Electrical: Low cost, $.33; Average, $1.02; Good, $.2.07; Excellent, $3.59
Floors or walks: Dirt, $.33 – $.52; Gravel, $.73 – $1.06; Asphalt, $2.80 – $4.57; Concrete, $4.12 – $6.03
Water system, plastic: Spray, $.27 – $.44; Mist, $.40 – $.68; Drip tube, $.47 – $.78
Planting benches, per square foot of bench: Plastic, $5.11 – $8.15; Wood slat, $8.08 – $9.21; Solid propagating, $8.59 – $15.35

2 HEATING AND COOLING

These costs are averages of total installed costs of the entire heating or cooling installation, including its prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Unit-in-Place costs.

HEATING & COOLING	Sq. Ft. Costs
Hot water or steam	$ 7.13
Gas furnaces	4.78
Suspended gas heaters	4.09
add for fan-jet duct distribution	1.44

VENTILATION ONLY	Sq. Ft. Costs
Ventilation (fans only)	$ 0.82

3 HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.973	12	1.018
8	.983	13	1.027
9	.991	14	1.036
10	1.000 (base)	16	1.055
11	1.009	18	1.074

4

Average Floor Area	AVERAGE PERIMETER													Average Floor Area
Sq. Ft./Story	90	120	200	300	500	600	800	1000	1200	1400	1600	1800	2000	Sq. Ft./Story
500	1.710	1.750	1.840	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	500
1,000	1.650	1.670	1.720	1.780	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	1.360	1.370	1.410	1.450	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
4,000	-----	1.170	1.200	1.240	1.320	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	1.150	1.160	1.180	1.190	-----	-----	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	1.110	1.130	1.140	-----	-----	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	1.040	1.060	1.070	1.080	-----	-----	-----	-----	-----	-----	8,000
10,000	-----	-----	-----	.950	.990	1.000	1.020	1.040	-----	-----	-----	-----	-----	10,000
20,000	-----	-----	-----	-----	.830	.840	.860	.880	-----	-----	-----	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	.800	.820	.840	.860	-----	-----	-----	-----	25,000
50,000	-----	-----	-----	-----	-----	-----	.680	.700	.720	.740	-----	-----	-----	50,000
100,000	-----	-----	-----	-----	-----	-----	-----	.580	.590	.600	.610	-----	-----	100,000
200,000	-----	-----	-----	-----	-----	-----	-----	-----	.550	.560	.570	.580	.590	200,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREENHOUSES - STRUCTURES



GOOD CLASS S HOOP (ARCH RIB)

OCCUPANCY DESCRIPTION: Enclosures used to regulate the climatic conditions for germinating and growing various plants and vegetables.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Heating or automated watering systems, shade curtains and planting benches are not included.

SQUARE FOOT COST TABLE

STRAIGHT-WALL STRUCTURES

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
D	Average	$ 14.50	Wood frame, glass or fiberglass covering, some vents	Gravel, some concrete	Adequate electrical and hose bibs	None
	Fair	9.50	Wood frame, fiberglass walls, double polyethylene roof cover	Gravel floor	Minimum electrical, lighting and water	None
	Low cost	6.00	Post frame, fiberglass end walls, double polyethylene cover	Dirt floor	Minimum equipment outlet and hose bibs	None
	Cheap	5.50	Light post frame, wide spacing, polyethylene cover	Dirt floor	No electrical, hose bib only	None
S	Excellent	46.00	Best frame, translucent sandwich panels and venting	Concrete floor, drains	Good lighting and plumbing	None
	Very good	38.00	Heavy frame, good sandwich panels, good wall and roof vents	Good concrete walks	Adequate electrical, good fixtures and water service	None
	Good	31.50	Good metal frame, tempered glass, polycarbonate/acrylic, good vents	Concrete walks	Adequate electrical and water service	None
	Average	14.50	Metal frame, glass or fiberglass covering, some vents	Gravel, some concrete	Adequate electrical and hose bibs	None
	Fair	10.00	Metal frame, double polyethylene arch roof, fiberglass walls	Gravel floor	Minimum electrical, lighting and water	None
	Low cost	7.00	Metal frame, fiberglass end walls, double polyethylene cover	Dirt floor	Minimum equipment outlet and hose bib	None
	Cheap	6.00	Light tubular frame, gable or arch roof, polyethylene cover	Dirt floor	No electrical, hose bib only	None

HOOP (ARCH-RIB/QUONSET) STRUCTURES

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
D	Low cost	$ 6.00	Light built-up wood arch, fiberglass ends, double polyethylene cover	Dirt floor	Minimum equipment outlet and hose bibs	None
S	Very good	26.50	Good translucent sandwich panels, heavy frame, pitched peak, vents	Good concrete walks	Adequate electrical, good fixtures and water service	None
	Good	22.00	Good polycarbonate or acrylic cover, roof and wall vents	Concrete walks	Adequate electrical and water service	None
	Average	10.50	Fiberglass panels on light arch frame, some vents	Gravel, some concrete	Adequate electrical and hose bibs	None
	Fair	7.00	Pipe or light tubular arch, double poly., fiberglass ends & knee walls	Gravel floor	Minimum electrical, lighting and water	None
	Low cost	5.00	Trussed pipe arch, double polyethylene cover, fiberglass end walls	Dirt floor	Minimum equipment outlet and hose bibs	None
	Cheap	4.50	Light pipe arch, wide spacing, polyethylene cover	Dirt floor	No electrical, hose bib only	None

For modified hoop structures (3' straight side wall), add 5%.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GREENHOUSES - STRUCTURES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1 ADJUSTMENTS

	COST RANGE		
Humidifiers, each	$ 615.00	–	$ 3,050.00
Exhaust fan cooling assembly, per unit	1,070.00	–	2,875.00
Water-drip humidity pad assembly, per square foot of pad	19.40	–	31.00
Automatic vent and/or environmental controls, per unit	1,070.00	–	2,750.00
Automatic chemical injectors (excluding tanks), per unit	3,575.00	–	6,350.00
Automatic water controls, per unit	403.00	–	1,020.00
Traveling boom sprayer, per linear foot of rail	65.50	–	137.00
Roof shade curtains, per square foot of cover, manual (automated, add 100%)	1.05	–	1.30
Hinged vents, manual, per linear foot (automatic, add 20%)	44.25	–	53.00
Automatic sidewall curtain assembly, per linear foot	18.15	–	23.85
Concrete curb, per linear foot	3.96	–	8.72
Stem, knee walls, per linear foot	16.90	–	21.05

MISCELLANEOUS SQUARE FOOT COSTS

Electrical: Low cost, $.33; Average, $1.02; Good, $.2.07; Excellent, $3.59
Floors or walks: Dirt, $.33 – $.52; Gravel, $.73 – $1.06; Asphalt, $2.80 – $4.57; Concrete, $4.12 – $6.03
Water system, plastic: Spray, $.27 – $.44; Mist, $.40 – $.68; Drip tube, $.47 – $.78
Planting benches, per square foot of bench: Plastic, $5.11 – $8.15; Wood slat, $8.08 – $9.21; Solid propagating, $8.59 – $15.35

2 HEATING AND COOLING

These costs are averages of total installed costs of the entire heating or cooling installation, including its prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Unit-in-Place costs.

HEATING & COOLING	Sq. Ft. Costs
Hot water or steam	$ 7.13
Gas furnaces	4.78
Suspended gas heaters	4.09
add for fan-jet duct distribution	1.44

VENTILATION ONLY	Sq. Ft. Costs
Ventilation (fans only)	$ 0.82

3 HEIGHT REFINEMENTS

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
7	.973	12	1.018
8	.983	13	1.027
9	.991	14	1.036
10	1.000 (base)	16	1.055
11	1.009	18	1.074

4

Average Floor Area	AVERAGE PERIMETER													Average Floor Area
Sq. Ft./Story	90	120	200	300	500	600	800	1000	1200	1400	1600	1800	2000	Sq. Ft./Story
500	1.710	1.750	1.840	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	500
1,000	1.650	1.670	1.720	1.780	-----	-----	-----	-----	-----	-----	-----	-----	-----	1,000
2,000	1.360	1.370	1.410	1.450	-----	-----	-----	-----	-----	-----	-----	-----	-----	2,000
4,000	-----	1.170	1.200	1.240	1.320	-----	-----	-----	-----	-----	-----	-----	-----	4,000
5,000	-----	-----	1.150	1.160	1.180	1.190	-----	-----	-----	-----	-----	-----	-----	5,000
6,000	-----	-----	-----	1.110	1.130	1.140	-----	-----	-----	-----	-----	-----	-----	6,000
8,000	-----	-----	-----	1.040	1.060	1.070	1.080	-----	-----	-----	-----	-----	-----	8,000
10,000	-----	-----	-----	.950	.990	1.000	1.020	1.040	-----	-----	-----	-----	-----	10,000
20,000	-----	-----	-----	-----	.830	.840	.860	.880	-----	-----	-----	-----	-----	20,000
25,000	-----	-----	-----	-----	-----	.800	.820	.840	.860	-----	-----	-----	-----	25,000
50,000	-----	-----	-----	-----	-----	-----	.680	.700	.720	.740	-----	-----	-----	50,000
100,000	-----	-----	-----	-----	-----	-----	-----	.580	.590	.600	.610	-----	-----	100,000
200,000	-----	-----	-----	-----	-----	-----	-----	-----	.550	.560	.570	.580	.590	200,000

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GROUP CARE HOMES



AVERAGE CLASS D

OCCUPANCY DESCRIPTION: These structures are small congregate care or special needs buildings that are more family or residential style in character than convalescent hospitals. Therapy or lounge and administrative rooms commensurate with the quality are included.

INCLUDED IN COSTS: Architects' fees and contractors' overhead and profit.

NOT INCLUDED IN COSTS: Sprinklers, kitchen equipment, balconies, therapy or recreational equipment.

SQUARE FOOT COST TABLE

CLASS	TYPE	COST/ SQ. FT.	EXTERIOR WALLS	INTERIOR FINISH	LIGHTING, PLUMBING AND MECHANICAL	HEAT
C	Excellent	$ 307.00	Face brick, stone, best windows, shakes or shingles on good structure	Plaster or drywall, enamel or vinyl walls, vinyl floor, carpet and ceramic	Signal system, therapy facilities, good lighting and plumbing	Warm and cool air (zoned)
	Very good	248.50	Brick or good block and stucco, good fenestration and roof	Good plaster or drywall, some detail, carpet and ceramic	Special fixtures, more than one bath per bedroom	Warm and cool air (zoned)
	Good	196.50	Brick or block, wood or good asphalt shingle roof	Plaster or drywall, good ceilings and floor covering	Individual baths, large kitchen, good electrical fixtures	Heat pump system
	Average	157.00	Brick or block, some trim	Plaster or drywall, carpet, vinyl	Adequate lighting/plumbing	Package A.C.
	Low cost	121.00	Concrete block, very plain	Painted block, low-cost flooring	Minimum quantity/quality	Forced air
D	Excellent	297.00	Best siding or stucco, brick veneer, stone trim, shakes, shingles	Plaster or drywall, enamel or vinyl walls, vinyl floor, carpet and ceramic	Signal system, therapy facilities, good lighting and plumbing	Warm and cool air (zoned)
	Very good	239.50	Good siding or stucco, good trim, light shakes or good shingles	Good plaster or drywall, some detail, carpet and ceramic	Special fixtures, more than one bath per bedroom	Warm and cool air (zoned)
	Good	188.50	Siding or stucco, some trim, wood or good asphalt shingles	Plaster or drywall, good ceilings and floor covering	Individual baths, large kitchen, good electrical fixtures	Heat pump system
	Average	149.00	Siding or stucco, standard sash, asphalt shingles or built-up	Drywall, carpet, some ceramic tile, vinyl composition	Adequate lighting/plumbing, minimum extra facilities	Package A.C.
	Low cost	114.50	Low-cost siding or stucco	Drywall, low-cost carpet, asphalt	Minimum quantity/quality	Forced air
C-D	Finished basement	53.50	Finished interior, add for recreation equipment	Gypsum board ceiling, vinyl composition tile or sheet vinyl	Adequate lighting/plumbing	None
	Unfinished basement	43.25	Few partitions, little or no finish	Unfinished ceiling, slab, storage only	Minimum lighting and drains	None

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.

GROUP CARE HOMES

REFINEMENTS: On this page are adjustments to the base costs from the previous page. Follow steps 1 through 5 to obtain final costs.

1

BUILT-IN APPLIANCES: For individual listing, see Segregated Cost, Section SEG 1.

	LOW	AVG.	GOOD	EXCL.
Allowance (if not itemized)	$1,820	$4,150	$7,550	$12,800

ELEVATORS: A small passenger elevator with simple call system and push-button control, four-passenger cab, and two or three stops costs $64,750 to $106,000 .

SPRINKLERS: Apply to area covered by sprinklers.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
3,000	$ 5.14	$ 6.63	$ 8.55	$ 11.05
5,000	4.75	6.09	7.80	10.00
10,000	4.28	5.44	6.91	8.77
20,000	3.87	4.87	6.10	7.69
50,000	3.36	4.20	5.24	6.50

BALCONIES: Balcony costs include the supporting structure, decking and rails. Apply costs to the sq.ft. of the balcony area.

Sq. Ft.	LOW	AVG.	GOOD	EXCL.
Concrete . .	$ 34.00	$ 43.50	$ 55.00	$ 71.00
Steel	31.75	42.50	56.50	75.50
Wood	29.75	39.50	52.50	68.50
Add for ornate finishes, balustrades . . .	29.50	36.00	44.25	54.00
Add for roofs or awnings.	15.35	20.40	27.00	36.00

2

HEATING AND COOLING

These costs are averages of the total installed cost of the entire heating or cooling system including a prorated share of contractors' overhead and profit and architects' fees. If the heating found in the building being assessed is different from that indicated, take the difference between the costs of the two and add to or subtract from the base square foot cost. For other types or system adjustments, see Segregated Costs.

HEATING ONLY	Sq. Ft. Costs	HEATING & COOLING	Sq. Ft. Costs	COOLING ONLY	Sq. Ft. Costs
Electric cable or baseboard	$ 10.50	Package A.C. (short ductwork). . .	$ 21.90	Central refrigeration (zoned)	$ 16.00
Electric wall heaters	3.84	Warm and cool air (zoned)	30.50	package (short ductwork)	10.65
Forced air furnace	15.15	Hot/chilled water (zoned)	45.50	Central evaporative	7.04
Hot water, baseboard/convector. .	20.75	Heat pump system	25.50	Pkg. refrig. . .	$2,750 to $3,425 per ton capacity
radiant floor/ceiling	22.55	Ind. thru-wall heat pumps	10.75	Evap. coolers.	$331 to $535 per MCFM capacity
Steam (including boiler)	19.20				
without boiler	16.85	Small indiv. heat pumps cost $2,280 to $3,125		**VENTILATION ONLY**	
Wall or floor furnace	4.43	per ton of rated capacity.		Vent. (blowers/ducts)	$ 3.18

3

HEIGHT REFINEMENTS

MULTISTORY BUILDINGS: Add .5% (1/2%) for each story over three, above ground, to all base costs.

STORY HEIGHT MULTIPLIERS: Multiply base cost by the following multipliers for any variation from the average story height.

Average Wall Height	Square Foot Multiplier	Average Wall Height	Square Foot Multiplier
8	.947	11	1.027
9	.973	12	1.055
10	1.000 (base)		

4

Average Floor Area	AVERAGE PERIMETER													Average Floor Area
Sq. Ft./Story	200	250	300	350	400	450	500	600	700	800	1000	1200	1400	Sq. Ft./Story
2,000	1.083	1.143	1.206	1.267	1.329	-----	-----	-----	-----	-----	-----	-----	-----	**2,000**
4,000	.959	.989	1.021	1.052	1.083	1.113	1.143	1.206	1.268	1.329	-----	-----	-----	**4,000**
6,000	.917	.938	.959	.980	1.000	1.021	1.042	1.083	1.123	1.165	-----	-----	-----	**6,000**
8,000	-----	.913	.929	.944	.959	.974	.989	1.021	1.052	1.083	1.143	1.206	1.268	**8,000**
10,000	-----	-----	.910	.922	.935	.947	.959	.984	1.009	1.034	1.083	1.133	1.181	**10,000**
12,000	-----	-----	-----	.907	.917	.928	.938	.959	.980	1.000	1.042	1.083	1.123	**12,000**
14,000	-----	-----	-----	-----	.906	.915	.924	.942	.959	.977	1.011	1.047	1.083	**14,000**
20,000	-----	-----	-----	-----	.885	.892	.898	.910	.922	.935	.959	.984	1.009	**20,000**
24,000	-----	-----	-----	-----	-----	-----	.886	.896	.907	.917	.938	.959	.980	**24,000**
28,000	-----	-----	-----	-----	-----	-----	.880	.888	.898	.906	.924	.942	.959	**28,000**
32,000	-----	-----	-----	-----	-----	-----	.874	.882	.889	.898	.913	.928	.944	**32,000**
36,000	-----	-----	-----	-----	-----	-----	.870	.877	.883	.890	.904	.917	.932	**36,000**
40,000	-----	-----	-----	-----	-----	-----	.866	.873	.879	.885	.898	.910	.922	**40,000**

5 USE COUNTY MULTIPLIERS IN MULTIPLIER SECTION.

© 2025 Marshall & Swift/Boeckh, LLC, all rights reserved.
Any reprinting, distribution, modification, reverse engineering, or creation of derivative works, is strictly prohibited.